



1 DEMOLITION FLOOR PLAN

SCALE 1/16"= 1'-0"



- GENERAL PLAN NOTES:**
- G1. INSTALL PROTECTIVE BARRIERS TO DIRECT PUBLIC TRAFFIC AROUND CONSTRUCTION AREA. DO NOT ALLOW GENERAL PUBLIC DIRECT ACCESS INTO CONSTRUCTION AREA.
  - G2. COORDINATE CONSTRUCTION STAGING, PARKING AND PERSONNEL WITH SCHOOL ADMINISTRATION.
  - G3. MAINTAIN EXIT PATHWAYS AND PROVIDE FOR DAILY FOOT TRAFFIC. BARRICADE AREAS AS REQUIRED TO KEEP POPULATION SAFE.
  - G4. MAINTAIN FIRE ALARM AND ELECTRICAL SERVICE WHENEVER DISRUPTION OF SERVICES ARE REQUIRED. GIVE THE PRINCIPAL 48 HOURS NOTICE IF AT ALL POSSIBLE.

**LEGEND:**

CAREFULLY REMOVE EXISTING CARPET, TRANSITIONS, AND RUBBER BASE. CAREFULLY REMOVE RUBBER BASE TO NOT DAMAGE EXISTING WALLS. DISPOSE OF DEMOLISHED MATERIAL. PREP SLAB AS REQUIRED TO INSTALL NEW LVT.

**DEMO PLAN NOTES**

IN BUILDING C MULTIPURPOSE ROOM, REMOVE EXISTING SCOREBOARD AND PRESENT TO OWNER.

IMPROVEMENTS TO  
J.I. BARRON ELEMENTARY SCHOOL  
PINEVILLE, LA

Owner : Rapides Parish School Board

Pineville, Louisiana

DEMOLITION FLOOR PLAN

REVISIONS:

DATE: SEPTEMBER 2025

JOB NUMBER: 2025-02

A200

2 OF 10A



YEAGER, WATSON & ASSOCIATES, LLC

ARCHITECTS

148 SOUTH CREATION STREET  
RUSTON, LOUISIANA 71270

TELEPHONE: (337) 265-5789  
FACSIMILE: (337) 265-5722

