



GENERAL NOTE:
REFER TO A202 AND A203 FOR NEW FLOORING AND BASE AS SCHEDULED.
FOR NEW RETRO-FIT ROOF INSTALLATION, PROVIDE 10,000 SQ. FT. CEILING TILE AND 5,000 SQ. FT. CEILING GRID AS SPECIFIED.

- GENERAL PLAN NOTES:**
- G1. INSTALL PROTECTIVE BARRIERS TO DIRECT PUBLIC TRAFFIC AROUND CONSTRUCTION AREA. DO NOT ALLOW GENERAL PUBLIC DIRECT ACCESS INTO CONSTRUCTION AREA.
 - G2. COORDINATE CONSTRUCTION STAGING, PARKING AND PERSONNEL WITH SCHOOL ADMINISTRATION.
 - G3. MAINTAIN EXIT PATHWAYS AND PROVIDE FOR DAILY FOOT TRAFFIC. BARRICADE AREAS AS REQUIRED TO KEEP POPULATION SAFE.
 - G4. MAINTAIN FIRE ALARM AND ELECTRICAL SERVICE WHENEVER DISRUPTION OF SERVICES ARE REQUIRED. GIVE THE PRINCIPAL 48 HOURS NOTICE IF AT ALL POSSIBLE.
 - G5. ALLOW REPLACEMENT OF CEILING TILE UP TO 1,000 SQUARE FEET. ALLOW REPLACEMENT OF CEILING GRID UP TO 500 LINEAR FEET.

- PLAN NOTES**
- 1 IN BUILDING C MULTIPURPOSE ROOM, NEW SCOREBOARDS AS SPECIFIED. REFER TO ELECTRICAL.
 - 2 NEW SPLASH BLOCKS AT DOWNSPOUTS. REFER TO CIVIL.
 - 3 NEW INLINE DRAINAGE CONNECTION. REFER TO CIVIL.

- DRAINAGE LEDGEND**
- DS DOWNSPOUT WITH SPLASH BLOCK REFER TO CIVIL.
 - DS DOWNSPOUT WITH INLINE DRAIN. AT EXISTING CONCRETE. CUT AND REPLACE CONCRETE AS REQUIRED. REFER TO CIVIL.
 - DS-C AT EXISTING WALKWAY COVER, RUN DOWNSPOUT OUT OVER COVER AND DOWN EXISTING COLUMN.

1 PARTIAL FLOOR PLAN - BUILDINGS A & B
SCALE 3/32" = 1'-0"

