



GENERAL NOTE:
REFER TO A202 AND A203 FOR NEW FLOORING AND BASE AS SCHEDULED.
FOR NEW RETRO-FIT ROOF INSTALLATION, PROVIDE 10,000 SQ. FT. CEILING TILE AND 5,000 SQ. FT. CEILING GRID AS SPECIFIED.

- GENERAL PLAN NOTES:**
- G1. INSTALL PROTECTIVE BARRIERS TO DIRECT PUBLIC TRAFFIC AROUND CONSTRUCTION AREA. DO NOT ALLOW GENERAL PUBLIC DIRECT ACCESS INTO CONSTRUCTION AREA.
 - G2. COORDINATE CONSTRUCTION STAGING, PARKING AND PERSONNEL WITH SCHOOL ADMINISTRATION.
 - G3. MAINTAIN EXIT PATHWAYS AND PROVIDE FOR DAILY FOOT TRAFFIC. BARRICADE AREAS AS REQUIRED TO KEEP POPULATION SAFE.
 - G4. MAINTAIN FIRE ALARM AND ELECTRICAL SERVICE WHENEVER DISRUPTION OF SERVICES ARE REQUIRED. GIVE THE PRINCIPAL 48 HOURS NOTICE IF AT ALL POSSIBLE.

NEW LVT AS SPECIFIED. PROVIDE TRANSITION STRIPS AS REQUIRED.

- TRANSITIONS:**
- PROVIDE RUBBER TRANSITION, LVT TO EXISTING CERAMIC TILE.
 - PROVIDE RUBBER TRANSITION, LVT TO EXISTING VINYL WOOD FLOORING.
 - AS REQUIRED FROM DAMAGED VCT EDGES: PROVIDE RUBBER TRANSITION STRIP AT JUNCTION OF NEW LVT AND EXISTING VCT.

- FINISH SCHEDULE:**
- FINISH LEGEND : BLANK SPACES = NO WORK**
- FLOOR TYPES**
1 LVT
- BASE TYPES**
20 Rubber Cove 4" High
- WALLS**
30 Paint on Existing Gyp. Bd.
- REMARKS**
1 TRANSITION - EXISTING CERAMIC TILE TO NEW LVT
2 TRANSITION - EXISTING WOOD FLOORING TO NEW LVT
3 TRANSITION - EXISTING QUARRY TILE TO NEW LVT
- GENERAL:**
Shaded area denotes changes by ADDENDUM No.

RM. #	DESIGNATION	FLOOR	BASE	WALLS	REMARKS
BUILDING A					
A 114	CLASSROOM	1	20		1
A 115	EQUIPMENT	1	20		
A 116	CLASSROOM	1	20		1
A 122	CLASSROOM	1	20		1
A 123	EQUIPMENT	1	20		
A 124	CLASSROOM	1	20		1
1-D	HALLWAY				
1-E	HALLWAY				
BUILDING B					
2-B	HALLWAY	1	20		2
2-C	HALLWAY	1	20		3
B 110	WORK ROOM	1	20		
B 111	BOOKS	1	20		
B 112	OFFICE	1	20		
B 113	CLOSET	1	20		
B 114	STORAGE	1	20		3
B 115	BARRON CAFE	1	20		3
B 116	CLASSROOM	1	20		
B 117	CLASSROOM	1	20		
B 118	CLASSROOM	1	20		
B 119	CLASSROOM	1	20		
1-C	HALLWAY	1	20		
1-E	HALLWAY	1	20		
B 120	LIBRARY	1	20		
B 121	WORK ROOM	1	20		
B 122	OFFICE	1	20		
B 123	LUNCHROOM	1	20		
1-A	HALLWAY	1	20		
B 131	CLASSROOM	1	20		
B 132	CLASSROOM	1	20		
B 133	CLASSROOM	1	20		
B 134	CLASSROOM	1	20		
B 135	RECEPTION	1	20		
B 136	WORK ROOM	1	20		
B 137	CONFERENCE	1	20		
B 138	OFFICE	1	20		
B 139	OFFICE	1	20		
B 140	VESTIBULE	1	20		
2-A	HALLWAY	1			1
2-B	HALLWAY	1			2
2-C	HALLWAY	1			
3-A	HALLWAY	1			2
3-B	HALLWAY	1	20		
B 148	CLASSROOM	1	20		2
B 149	CLASSROOM	1	20		
B 150	CLASSROOM	1	20		
B 151	CLASSROOM	1	20		
4-A	HALLWAY	1	20		
4-B	HALLWAY	1	20		
B 153	CLASSROOM	1	20		
B 154	CLASSROOM	1	20		
B 155	CLASSROOM	1	20		
B 156	CLASSROOM	1	20		
5-A	HALLWAY	1	20	30	
5-B	HALLWAY	1	20	30	
B 157	CLASSROOM	1	20		
B 158	CLASSROOM	1	20		
B 159	CLASSROOM	1	20		
5-C	HALLWAY	1	20	30	
B 160	CLASSROOM	1	20		
B 161	CLASSROOM	1	20		
B 162	CLASSROOM	1	20		
B 163	HEALTH UNIT	1	20		1
B 164	EXAM ROOM	1	20		
B 165	EXAM ROOM	1	20		
B 170	CLASSROOM	1	20		
B 171	CLASSROOM	1	20		
B 172	CLASSROOM	1	20		
B 173	CLASSROOM	1	20		

1 ENLARGED
PARTIAL FLOOR PLAN - BUILDINGS A & B
SCALE 3/32" = 1'-0"



YEAGER, WATSON & ASSOCIATES, LLC
ARCHITECTS
118 SOUTH TRENTON STREET
RUSTON, LOUISIANA 71270
TELEPHONE (337) 262-5789
FACSIMILE (337) 262-5772

IMPROVEMENTS TO
J.I. BARRON ELEMENTARY SCHOOL
PINEVILLE, LA
RPSB# 52-26-01
Owner : Rapides Parish School Board



ENLARGED FLOOR PLANS
REVISIONS:
DATE: SEPTEMBER 2025
JOB NUMBER: 2025-02

A202
4 OF 10A