



PLUMBING NOTES	
1	PLUG AND SEAL EXISTING ROOF DRAIN/PIPING.
2	PLUG AND SEAL EXISTING OVERFLOW ROOF DRAIN/PIPING.
3	NEW ROOF DRAIN AND NEW OVERFLOW ROOF DRAIN TO REPLACE EXISTING. CONTRACTOR TO VERIFY AND MATCH EXISTING SIZES IN FIELD. PROVIDE WITH NEW FLASHING.
4	REPLACE EXISTING FLUE VENT THROUGH ROOF WITH NEW FLUE VENT. CONTRACTOR TO VERIFY AND MATCH EXISTING SIZE AND MATERIAL IN FIELD PRIOR TO STARTING WORK. CONTRACTOR SHALL EXTEND NEW FLUE VENT HIGHER TO PENETRATE THROUGH NEW ROOF.
5	EXISTING SANITARY VENT THROUGH ROOF LOCATED IN THIS VICINITY. EXTEND EXISTING VENT HIGHER TO VENT THROUGH NEW ROOF. VERIFY AND MATCH EXISTING PIPE SIZE AND MATERIAL IN FIELD PRIOR TO STARTING WORK.
6	EXISTING CAPPED SANITARY VENT THROUGH ROOF IN THIS VICINITY TO REMAIN.
7	NEW ROOF DRAIN TO REPLACE EXISTING ROOF DRAIN. CONTRACTOR TO VERIFY AND MATCH EXACT SIZE AND LOCATION OF EXISTING ROOF DRAINS. PROVIDE NEW ROOF DRAIN AND FLASHING, ETC. TO BE INSTALLED WHEN NEW ROOFING APPLIED TO EXISTING DECK (AS DIRECTED BY ARCHITECT). MAKE ALL NECESSARY EXTENSIONS, ADJUSTMENTS, ECT. TO CONNECT NEW ROOF DRAINS TO EXISTING DOWNSPOUTS.
8	NEW OVERFLOW ROOF DRAIN TO REPLACE EXISTING. CONTRACTOR TO VERIFY AND MATCH SIZE AND LOCATION OF EXISTING OVERFLOW ROOF DRAINS. NEW ROOF DRAIN AND FLASHING, ETC. TO BE INSTALLED WHEN NEW ROOFING APPLIED TO EXISTING DECK (AS DIRECTED BY ARCHITECT). MAKE ALL NECESSARY EXTENSIONS, ADJUSTMENTS, ECT. TO CONNECT NEW ROOF DRAINS TO EXISTING DOWNSPOUTS.
9	EXISTING SANITARY VENT THROUGH ROOF TO REMAIN. PROVIDE NEW FLASHING, ETC. TO BE INSTALLED WHEN NEW ROOFING APPLIED TO EXISTING DECK (AS DIRECTED BY ARCHITECT).
10	EXISTING ROOFTOP NATURAL GAS PIPING TO BE REPLACED WITH NEW NATURAL GAS PIPING. CONTRACTOR SHALL VERIFY AND MATCH EXISTING PIPE SIZES IN FIELD PRIOR TO STARTING WORK.

1 PLUMBING ROOF PLAN - DEMOLITION
3/32" = 1'-0" Refer to Architectural Drawings for All Dimensions



1304 Bertrand Dr. Suite F7, Lafayette, LA 70506
13201 Northwest Hwy. Ste 633, Houston, TX 77040
(504) 484-7474
Mechanical Contact: Gabrielle Wehrer
Email: gabrielle@meconsulting.com
General Contact: Terry Kitch
Email: Terry@meconsulting.com
PROJECT NO. 25051.00



PLUMBING ROOF PLAN - DEMO

REVISIONS:

DATE: SEPTEMBER 2025
JOB NUMBER: 2025-02

P101 OF 1

IMPROVEMENTS TO
J.I. BARRON ELEMENTARY SCHOOL
PINEVILLE, LA
RPSB# 52-26-01

Pineville, Louisiana

Owner : Rapides Parish School Board

YEAGER, WATSON & ASSOCIATES, LLC
ARCHITECTS
118 SOUTH TRENTON STREET
HOUSTON, LOUISIANA 71270
TELEPHONE: (518) 202-2708
FACSIMILE: (518) 202-2722