



- PLUMBING NOTES**
- 1 EXISTING SANITARY VENT THROUGH ROOF LOCATED IN THIS VICINITY. EXTEND EXISTING VENT HIGHER TO VENT THROUGH NEW ROOF. VERIFY AND MATCH EXISTING PIPE SIZE AND MATERIAL IN FIELD PRIOR TO STARTING WORK.
  - 2 FLUE VENT UP THOUGH NEW ROOF.
  - 3 NEW ROOF DRAIN AND FLASHING, ETC. TO BE INSTALLED WHEN NEW ROOFING APPLIED TO EXISTING DECK (AS DIRECTED BY ARCHITECT). MAKE ALL NECESSARY EXTENSIONS, ADJUSTMENTS, ECT. TO CONNECT NEW ROOF DRAINS TO EXISTING DOWNSPOUTS.
  - 4 NEW OVERFLOW ROOF DRAIN AND FLASHING, ETC. TO BE INSTALLED WHEN NEW ROOFING APPLIED TO EXISTING DECK (AS DIRECTED BY ARCHITECT). MAKE ALL NECESSARY EXTENSIONS, ADJUSTMENTS, ECT. TO CONNECT NEW ROOF DRAINS TO EXISTING DOWNSPOUTS.

**1 PLUMBING ROOF PLAN - NEW**  
3/32" = 1'-0" Refer to Architectural Drawings for All Dimensions



**M&E CONSULTING**  
1304 Bertrand Dr. Suite F7, Lafayette, LA 70506  
13201 Northwest Fwy. Ste 633, Houston, TX 77040  
(504) 484-7474  
Mechanical Contact: Gabrielle Wehrer  
Email: gabrielle@meconsulting.com  
Electrical Contact: Terry Kitch  
Email: Terry@meconsulting.com  
PROJECT NO. 25051.00



PLUMBING ROOF PLAN - NEW

REVISIONS:

DATE: SEPTEMBER 2025  
JOB NUMBER: 2025-02

P201

**J.I. BARRON ELEMENTARY SCHOOL**  
PINEVILLE, LA  
RPSB# 52-26-01

Pineville, Louisiana

Owner : Rapides Parish School Board

**YEAGER, WATSON & ASSOCIATES, LLC**  
ARCHITECTS  
118 SOUTH TRENTON STREET  
HOUSTON, LOUISIANA 71270  
TELEPHONE: (518) 202-5708  
FACSIMILE: (518) 202-5722