



EXISTING CARPET AND WALL BASE TO BE DEMOLISHED BY OTHERS. PLUMBING CONTRACTOR SHALL LOCATE AND INSPECT EXISTING FLOOR CLEANOUTS. REPLACE DAMAGED CLEANOUTS OR CLEANOUT COVERS WITH NEW. ADJUST ALL CLEANOUTS FOR TOP OF CLEANOUT TO FINISH FLUSH WITH NEW VINYL TILE FLOORING. PROVIDE NEW FLOOR CLEANOUT SEALS. ALL NEW CLEANOUTS AND COVERS SHALL MATCH EXISTING. COORDINATE IN FIELD.



1/16" = 1'-0" Refer to Architectural Drawings for All Dimensions

