

## **DIVISION 23 – HEATING, VENTILATION AND AIR CONDITIONING**

230000	MECHANICAL GENERAL PROVISIONS
230513	COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT
230523.13	BUTTERFLY VALVES FOR HVAC PIPING
230529	HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT
230553	IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT
230593	TESTING, ADJUSTING, AND BALANCING FOR HVAC
230713	DUCT INSULATION
230719	HVAC PIPING INSULATION
232113	HYDRONIC PIPING
232114	HVAC CONDENSATE PIPING
233113	METAL DUCTS
233300	AIR DUCT ACCESSORIES
233423	HVAC POWER VENTILATORS
233713	DIFFUSERS, REGISTERS, GRILLES AND LOUVERS

## SECTION 23 00 00 – MECHANICAL GENERAL PROVISIONS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. The General Conditions of the Architectural Specifications, along with the supplementary conditions, special conditions, information to bidders, and any other pertinent information and documents shall apply the same as if repeated herein.

#### 1.2 SCOPE OF WORK

- A. Furnish all labor and material necessary to provide and install the complete mechanical portion of this Contract, including HVAC systems as called for herein and on accompanying drawings. Parts of the mechanical division may be bid separately or in combination, at the Contractor's option; however, it shall be the responsibility of the General Contractor to assure himself that all items covered in this Division have been included if he chooses to accept separate bids.
- B. This Contractor shall refer to the Architectural and Structural drawings and install equipment, piping, etc. to meet building and space requirements. No equipment shall be bid on or submitted for approval if it will not fit in the space provided.
- C. It is the intention of these Specifications that all mechanical systems shall be furnished complete with all necessary valves, controls, insulation, piping, devices, equipment, etc. necessary to provide a satisfactory installation in working order.
- D. Contractor shall visit the site and acquaint himself thoroughly with all existing facilities and conditions that would affect his portion of the work. Failure to do so shall not relieve the Contractor from the responsibility of installing his work to meet the conditions.
- E. This Contractor shall protect the entire system and all parts thereof from injury throughout the project and up to acceptance of the work. Failure to do so shall be sufficient cause for the Architect to reject any piece of equipment.

#### 1.3 DEMOLITION

- A. The contractor shall visit the site prior to bid to determine the extent of work required to complete the project.
- B. Contractor shall coordinate demolition with owner. The Owner shall have "First Right of Refusal" regarding salvage of all equipment and materials to be removed. Locate equipment as directed by owner. All equipment and materials not salvaged by the owner shall be removed from the site and discarded at the contractor's expense.



- C. Contractor shall coordinate all work with general contractor and phase work as required by project.
- D. All equipment piping, etc. required to be removed to accommodate the modifications shall be removed.
- E. Contractor shall maintain services to existing facilities which shall remain during and after construction is complete.
- F. Contractor shall coordinate any shutdown of services with the owner. It is intended that the building will remain occupied during construction. Contractor shall schedule shut down of services with the owner in order to prevent disruption of building occupancy.
- G. Contractor shall be responsible for draining down of existing systems to complete demolition. All work shall be scheduled with the owner. Contractor shall also be responsible for refilling system and removing all air in order to return the systems to proper operating conditions.
- H. All shut down of services shall be done at night or during a time period approved by the owner. The systems shall be required to be back up and running each morning unless otherwise approved by the owner.

#### 1.4 GROUND AND CHASES

- A. This Contractor shall see that all required chases, grounds, holes and accessories necessary for the installation of his work are properly built in as the work progresses; otherwise, he shall bear the cost of providing them.

#### 1.5 CUTTING AND PATCHING

- A. Initial cutting and patching shall be the responsibility of the General Contractor, with the Mechanical Contractor being responsible for laying out and marking any and all holes required for the reception of his work. No structural beams or joists shall be cut or thimble without first receiving the approval of the Architect. After initial surfacing has been done, any further cutting, patching and painting shall be done at this Contractor's expense.

#### 1.6 FILL AND CHARGES FOR EQUIPMENT

- A. Fill and charge with materials or chemicals all those devices or equipment as required to comply with the manufacturer's guarantee or as required for proper operation of the equipment.

#### 1.7 MACHINERY GUARDS

- A. This Contractor shall provide v-belt guards for each v-belt drive or other hazardous drive. The guard shall enclose the drive entirely and shall have a hole for taking a tachometer reading.
- B. Provide protective guard for belts, pulleys, gears, couplings, projecting set screws, keys and other rotating parts which are located such that a person might come in close proximity. Construct protective guard around angle iron frame, securely bolted to apparatus; comply with safety requirements. Install guard to completely enclose drives and pulleys and not interfere

with lubrication of equipment. Provide 2 inch minimum diameter opening in fan belt guards housing for tachometer.

#### 1.8 REPAIRING ROADWAYS AND WALKS

- A. Where this Contractor cuts or breaks roadways or walks, in order to lay piping, he shall repair or replace these sections to meet the Architect's approval.

#### 1.9 WELDING

- A. Weld piping and above grade steel tanks in accordance with qualified procedures using performance qualified welders and welding operators. Qualified procedures and welders in accordance with ASME Section IX. Welding procedures qualified by others and welders and welding operators qualified by another employer may be accepted as permitted by ANSI B31.1. Notify the A/E 24 hours in advance of tests, and perform the tests at the work site if practicable. Furnish A/E with a copy of qualified procedures and a list of names and identification symbols of qualified welders and welding operators. Apply welders or welding operators assigned symbols near each weld they make as permanent record.

#### 1.10 NOISE AND VIBRATION

- A. Provide the plumbing system and its associated components, items, piping, and equipment free of objectionable vibration or noise. Statically and dynamically balance rotating equipment and mount or fasten so that no vibration is transmitted to or through the building structure by equipment, piping, ducts or other parts of work, rectify such conditions at no additional compensation.

#### 1.11 CLEANING AND ADJUSTING

- A. Upon completion of his work, the Contractor shall clean and adjust all equipment, controls, valves, etc.; clean all piping, ductwork, etc.; and leave the entire installation in good working order.

#### 1.12 OPERATING AND MAINTENANCE INSTRUCTIONS

- A. Provide the Owner with three (3) copies of printed instructions indicating various pieces of equipment by name and model number, complete with parts lists, maintenance and repair instructions and test and balance report.
- B. COPIES OF SHOP DRAWINGS WILL NOT BE ACCEPTABLE AS OPERATION AND MAINTENANCE INSTRUCTIONS BUT MUST BE INCLUDED IN SUBMITTAL PACKAGE.
- C. This information shall be bound in plastic hardbound notebooks with the job name permanently embossed on the cover. Rigid board dividers with labeled tabs shall be provided for different pieces of equipment. Submit manuals to the Architect for approval.

- D. In addition to the operation and maintenance brochure, the Contractor shall provide a separate brochure which shall include registered warranty certificates on all equipment, especially any pieces of equipment which carry warranties exceeding one (1) year.
- E. The operation and maintenance brochure shall be furnished with a detailed list of all equipment furnished to the project, including the serial number and all pertinent nameplate data such as voltage, amperage draw, recommended fuse size, rpm, etc. The Contractor shall include this data on each piece of equipment furnished under this contract.

#### 1.13 GUARANTEE

- A. The Contractor shall guarantee all materials, equipment and workmanship for a period of one (1) year from the date of final acceptance of the project. This guarantee shall include furnishing of all labor and material necessary to make any repairs, adjustments or replacement of any equipment, parts, etc. necessary to restore the project to first class condition. This guarantee shall exclude only the changing or cleaning of filters. Warranties exceeding one (1) year are hereinafter specified with individual pieces of equipment.

#### 1.14 LOCAL CONDITIONS

- A. The location and elevation of all utility services is based on available surveys and utility maps and are reasonably accurate; however, these shall serve as a general guide only, and the Contractor shall visit the site and verify the location and elevation of all services to his satisfaction in order to determine the amount of work required for the execution of the Contract.
- B. The Contractor shall contact the various utility companies, determine the extent of their requirements and he shall include in his bid all lawful fees and payments required by these companies for complete connection and services to the building, including meters, connection charges, street patching, extensions from meters to main, etc.
- C. In case major changes are required, this fact, together with the reasons therefor, shall be submitted to the Architect, in writing, not less than seven (7) days before the date of bidding. Failure to comply with this requirement will make the Contractor liable for any changes, additions and expenses necessary for the successful completion of the project.

#### 1.15 PERMITS, INSPECTIONS AND TESTS

- A. All permits, fees, etc. for the installation, inspections, plan review, service connections locations, and/or construction of the work which are required by any authority and/or agencies having jurisdiction, shall be obtained and paid for by the Contractor. This shall be verified during the bidding process.
- B. The Contractor shall make all tests required by the Architect, Engineer or other governing authorities at no additional cost to the Owner.
- C. The Contractor shall notify the Architect and local governing authorities before any tests are made, and the tests are not to be drawn off a line covered or insulated until examined and approved by the authorities. In event defects are found, these shall be corrected and the work shall be retested.

- D. Prior to requesting final inspection by the Architect, the Contractor shall have a complete coordination and adjustment meeting of all of his sub-contractors directly responsible for the operation of any portion of the system. At the time of this meeting, each and every sequence of operation shall be checked to assure proper operation. Notify the Architect in writing ten (10) days prior to this meeting, instructing him of the time, date and whom you are requesting to be present.
- E. This project shall not be accepted until the above provisions are met to the satisfaction of the Architect.

#### 1.16 CODES AND STANDARDS

- A. The entire mechanical work shall comply with the rules and regulations of the City, Parish, County and State in which this project is being constructed, including the State Fire Marshal and the State Board of Health. All modifications required by these authorities shall be made without additional charge to the Owners. The Mechanical Contractor shall report these changes to the Architect and secure his approval before work is started.
- B. In addition to the codes heretofore mentioned, all mechanical work and equipment shall conform to the applicable portions of the following specifications, codes and/or regulations:
  - 1. American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
  - 2. National Electrical Code (NEC)
  - 3. National Fire Protection Association (NFPA)
  - 4. American Society of Mechanical Engineers (ASME)
  - 5. American Gas Association (AGA)
  - 6. International Building Code (IBC)
  - 7. International Mechanical Code (IMC)
  - 8. International Plumbing Code (IPC)
  - 9. International Fuel Gas Code (IFGC)
  - 10. Underwriters Laboratories (UL)
  - 11. Life Safety Code (NFPA 101)
  - 12. State Sanitary Code
  - 13. Louisiana State Uniform Construction Code Council (LSUCCC)
- C. All materials, equipment and accessories installed under this Contract shall conform to all rules, codes, etc. as recommended by National Associations governing the manufacturer, rating and testing of such materials, equipment and accessories. All materials shall be new and of the best quality and first class in every respect. Whenever directed by the Architect, the Contractor shall submit a sample for approval before proceeding.
- D. Where laws or local regulations provide that certain accessories such as gauges, thermometers, relief valves and parts be installed on equipment, it shall be understood that such equipment be furnished complete with the necessary accessories, whether or not called for in these Specifications.
- E. All unfired pressure vessels shall be built in accordance with the A.S.M.E. Code and so stamped. Furnish shop certificates for each vessel.

#### 1.17 REVIEW OF MATERIALS

- A. Whenever manufacturers or trade names are mentioned in these Plans or Specifications, the words "or approved equivalent" shall be assumed to follow whether or not so stated. Manufacturers or trade names are used to establish a standard of quality only, and should not be construed to infer a preference. Equivalent products which meet the Architect's approval will be accepted; however, these products must be submitted to the Architect a minimum of seven (7) days prior to the Bid Date.
- B. Submission shall include the manufacturer's name, model number, rating table and construction features.
- C. Upon receipt and checking of this submittal, the Architect will issue an addendum listing items which are approved as equivalent to those specified. THE CONTRACTOR SHALL BASE HIS BID SOLELY ON THOSE ITEMS SPECIFIED OR INCLUDED IN THE "PRIOR APPROVAL ADDENDUM", AS NO OTHER ITEM WILL BE ACCEPTABLE.
- D. Prior approval of a particular piece of equipment does not mean automatic final acceptance and will not relieve the Contractor of the responsibility of assuring himself that this equipment is in complete accord with the Plans and Specifications and that it will fit into the space provided. Shop drawings must be submitted on all items of equipment for approval as hereinafter specified.
- E. Before proceeding with work and/or within thirty (30) days after the award of the General Contract for this work, the Mechanical Contractor shall furnish to the Architect complete shop and working drawings of such apparatus, equipment, controls, insulation, etc. to be provided in this project. These drawings shall give dimensions, weights, mounting data, performance curves and other pertinent information.
- F. The Architect's approval of shop drawings shall not relieve the Contractor from the responsibility of incorrectly figured dimensions or any other errors which may be contained in these drawings. Any omission from the shop drawings or specifications, even though approved by the Architect, shall not relieve the Contractor from furnishing and erecting same.
- G. If contractor submits hard copies, Six (6) sets of shop drawings shall be submitted to the Architect for approval. These submittals shall be supplied as part of this Contractor's contract.
- H. This information shall be bound in plastic hardbound notebooks with the job name on the cover. Rigid board dividers with labeled tabs shall be provided for different pieces of materials and equipment. Submit shop drawings to the Architect for approval. Faxed copies shall not be acceptable. We prefer electronic submissions sent via E-Mail.
- I. Required shop drawing submittals shall include but are not limited to the following:
  - 1. Grilles, registers, diffusers and louvers.
  - 2. Ductwork and duct sealer.
  - 3. Duct insulation and accessories.
  - 4. Exhaust fans.
  - 5. Manual Dampers, Motorized Dampers and Control Dampers.
  - 6. Actuators.
  - 7. Valves
  - 8. Chilled Water Piping.
  - 9. Test and Balancing Agency (including forms).

#### 1.18 COORDINATION DRAWINGS

- A. Submit three (3) black line prints of all mechanical room layouts showing locations of all equipment, piping, etc. to insure all will fit in space provided. Submit drawings at 1/4" scale. Layouts shall include equipment submitted on project to scale on plans.
- B. Submit coordination drawings with the respective equipment shop drawings.

#### 1.19 MINOR DEVIATIONS

- A. Plans and detail sketches are submitted to limit, explain and define conditions, specified requirements, pipe sizes and manner of erecting work. Structural or other conditions may require certain modifications from the manner of installation shown, and such deviations are permissible and shall be made as required. However, specified sizes and requirements necessary for satisfactory operation shall remain unchanged. It may be necessary to shift ducts or pipes, or to change the shape of ducts, and these changes shall be made as required. All such changes shall be referred to the Architect and Engineer for approval before proceeding. Extra charges shall not be allowed for these changes. The contractor shall obtain a full set of plans and specifications for the coordination of his work prior to bidding this project. Items which are unclear to the bidding contractor shall be brought to the Architect and Engineers attention prior to bidding the project. An interpretation shall be clarified by the Architect and/or the Engineer prior to bidding.
- B. The Contractor shall realize that the drawings could delve into every step, sequence or operation necessary for the completion of the project, without drawing on the Contractor's experience or ingenuity. However, only typical details are shown on the Plans. In cases where the Contractor is not certain about the method of installation of his work, he shall ask for details. Lack of details will not be an excuse for improper installation.
- C. In general, the drawings are diagrammatic and the Contractor shall install his work in a manner so that interferences between the various trades are avoided. In cases where interferences do occur, the Architect is to state which item was first installed.

#### 1.20 AS-BUILT RECORD DRAWINGS

- A. The Contractor shall obtain at his cost, two sets of blackline prints of the original bid documents by the Architect. One set shall be kept on the site with all information as referenced below, and shall update same as the work progresses. The other set will be utilized to record all field changes to a permanent record copy for the Owner.
- B. If the Contractor elects to vary from the Contract Documents and secures prior approval from the Architect for any phase of the work, he shall record in a neat and readable manner, ALL such variances on the blackline print in red. The original blackline prints shall be returned to the Architect for documentation.
- C. All deviations from sizes, locations, and from all other features of the installations shown in the Contract Documents shall be recorded.
- D. In addition, it shall be possible using these drawings to correctly and easily locate, identify and establish sizes of all piping, directions and the like, as well as other features of the work which will be concealed underground and/or in the finished building.



- E. For work concealed in the building, sufficient information shall be given so it can be located with reasonable accuracy and ease. In some cases this may be by dimension. In others, it may be sufficient to illustrate the work on the drawings in relation to the spaces in the building near which it was actually installed. The Architect's/Engineer's decision in this matter will be final.
- F. The following requirements apply to all "As-Built" drawings:
  - 1. They shall be maintained at the Contractor's expense.
  - 2. All such drawings shall be done carefully and neatly, and in a form approved by the Architect/Engineer.
  - 3. Additional drawings shall be provided as necessary for clarifications.
  - 4. These drawings shall be kept up-to-date during the entire course of the work and shall be available upon request for examination by the Architect/Engineer; and when necessary, to establish clearances for other parts of the work.
  - 5. "As-built" drawings shall be returned to the Architect upon completion of the work and are subject to approval of the Architect/Engineer.

## **PART 2 - PRODUCTS**

### **2.1 HVAC SYSTEM PRODUCTS**

- A. Refer to individual Division 23 sections for mechanical products, controls, fans, pipe, tube and fitting materials and joining methods.

## **PART 3 - EXECUTION**

### **3.1 MANUFACTURER'S DIRECTION**

- A. The contractor shall install and operate all equipment and material in accordance with the manufacturer's installation and operating instructions. The manufacturer's instructions of installation and operation shall become part of the Contract Documents and shall supplement the Drawings and Specifications.

### **3.2 EQUIPMENT LABELS**

- A. Provide equipment labels for HVAC Equipment. Labels shall have permanent laminated construction secured to equipment.

### **3.3 VALVE TAGS**

- A. Secure metal tags to all valves. Labeling on all valve tags shall include type of system the valve controls and the area of building, zone, or equipment number affected by valve operation. Tag shall be 2" minimum diameter brass, engraved with code number, service and size. A framed list of the valves, giving manufacturer's name, model number, type and location shall be mounted in the main equipment room.

### **3.4 ACCESS DOORS:**

- A. Provide access doors in walls, floors and ceilings to permit access to equipment and piping requiring service or adjustment.
  - 1. Valves.
  - 2. Manual balancing dampers and automatic control dampers.
  - 3. Air terminal units and VRF indoor units.
  - 4. Duct mounted filters and coils.
  - 5. Drainage cleanouts.
  - 6. Kitchen Hood exhaust ductwork in accordance with NFPA requirements.
  - 7. Equipment shutoff protection devices such as disconnects, motor rated switches, etc.
  - 8. Other mechanical equipment indicated in schedules or specifications which are requiring maintenance, adjustment or operation.
- B. Provide hinged access doors and frames as follows:
  - 1. Drywall Construction:
    - a. Provide with concealed spring hinges and flush screwdriver operated cam locks in sufficient number of the size of the panel.
    - b. Provide prime paintable surface (not galvanized).
    - c. Product: Milcor "Style M" (Karp DSC-214M).
  - 2. Visible Masonry and Ceramic Tile:
    - a. Milcor "Style M" (Karp DSC-214M).
  - 3. Cement Plaster:
    - a. Milcor "Style K" (KarpDSC-214 PL).
  - 4. Acoustical Plaster:
    - a. Reinforced panel as required to prevent sagging. Provide continuous steel piano type hinge for the length of the panel, and sufficient number for the size of the panel. Provide factory prime paint surface (not galvanized).
    - b. Product: Milcor "Style AP" (Karp 214 PL).
  - 5. Acoustical Tile:
    - a. Milcor "Style AT" (Larsen L-CPA).
- C. Provide continuous concealed hinges and cam locks.
- D. Provide UL listed 1-1/2 hour label "B" access doors with automatic self-closing latching mechanism where required.
- E. Provide removable ceiling access tile section immediately adjacent to each mechanical or electrical device located in the ceiling plenum above removable tile ceiling.
- F. Coordinate approval of type, color and location of access doors & frames with Architect.

### 3.5 CLEANING AND SERVICE

- A. Upon Completion of this work, the contractor shall clean and adjust equipment, controls, valves, etc.;
- B. Inspect, clean and service air filters and strainers immediately prior to final acceptance of project.
- C. Provide complete and working charge of proper refrigerant, free of contaminants, into each refrigerant system. After each system has been in operation long enough to ensure completely balanced condition, check the charge and modify it for proper operation as required.

- D. Place mechanical systems in complete working order. Clean equipment and piping materials thoroughly returning to “as new” condition prior to request for substantial completion.
- E. Remove excess materials and debris from mechanical rooms and drain pans. Broom clean areas. Thoroughly clean ductwork inside and outside before air devices (diffusers, grilles, etc.) are installed.

### 3.6 TEMPORARY HEATING AND AIR CONDITIONING DURING CONSTRUCTION PHASE

- A. Permanent building air conditioning equipment or systems are not designed to control building temperature and humidity levels during construction of the building. The building’s HVAC system is not designed nor is it well suited for the proper drying of building/construction materials, and should not be used for such purposes.
- B. At all times, during construction phases, provide temporary ventilation both for comfort and protection of workers, for proper drying of wet work, and for proper curing of installed materials. Follow material manufacturer’s published instructions with regard to installation of building materials.
- C. Provide temporary heat both for the comfort and protection of workers and as necessary to ensure suitable working conditions for construction operations of construction trades, and also as necessary for storage of products and materials. Refer to material manufacturer’s literature for environmental operational temperature and humidity requirements.
- D. Provide temporary heat by use of self-contained, vented portable heating units, employing tanked gas or other approved heat source.
- E. Use only heating apparatus and fuels labeled or listed by a “National Recognized Testing Laboratory” recognized by OSHA. Keep equipment and surroundings in clean, safe conditions.
- F. Use flame resistant tarpaulins other material for temporary enclosures of space.
- G. Provide temporary humidity control by the use of small incremental de-humidifiers, packaged desiccant type de-humidifiers, and/or packaged DX type air conditioners.
- H. Do not permit space temperatures to reach or fall to a level which will cause damage to work. Coordinate the temperature and humidity requirements with the manufacturer of the finishes being provided.
- I. Replace interior or exterior surfaces damaged by the use of temporary heaters with new materials or refinish at no additional expense to the owner.
- J. As soon as practical after permanent heating, ventilation, and air conditioning systems are in place and operable, the contractor at his option, may provide heat from the permanent building heating system, until such time that the building is complete. It is recommended that the building’s permanent heating and air conditioning systems not be utilized to maintain temperature and humidity conditions within the building during the construction phase. Small space heaters and portable de-humidifiers are suggested as sources of temperature and humidity control. It is the intent that the permanent HVAC systems should not be used to condition or control humidity during construction.

- K. The use of permanent HVAC systems will require that the systems be complete and fully controllable by the Building Automation System (BAS) including the ability to remotely alarm proper maintenance personnel in the event of any and all system failure(s) or inability to maintain setpoint temperatures and humidity levels. Should the contractor elect to utilize the building's permanent HVAC system, the contractor shall bring the HVAC systems and ductwork back to an original unused condition or state by thoroughly cleaning and/or repairing both equipment and ductwork including repair and refinishing scrapes, tears, scratches and dents, cleaning ductwork, cleaning AHU coils, etc.
- L. All dust, dirt, fungal growth, and debris in duct work shall be cleaned.
- M. All disposable or wearable parts such as belts, filters, etc., shall be replaced without option or cause.
- N. Contractor's Use of Permanent HVAC Systems:
  - 1. Heating System:
    - a. Should the contractor (at his option and at his own risk), utilize the building's permanent heating systems provided under this contract to provide space heating prior to project completion date subject to the restraints stated herein.
    - b. The fuel for such space heating and for required tests of heating equipment shall be provided by contractor.
    - c. The start up of equipment for use by the contractor shall not commence any warranty period.
    - d. The heating system shall be operated only by qualified personnel, and shall be operated with all auxiliaries, safeties, and in accordance with manufacturer's instructions and good operating practice.
    - e. If at any time the Owner's Representative determines that the equipment is being improperly operated or maintained, contractor will be directed to disconnect its use.
    - f. Heating systems shall be operated and controlled to prevent temperature in any room or space in any building from exceeding 90 deg. F.
    - g. Temperature controls shall be functional to the extent that the operating temperatures of equipment, ductwork piping, etc., shall not either fall or be elevated above or below normal operating limits. The contractor shall demonstrate to the owner or his representative the ability of the system to be controlled, including limit alarms installed and the ability to monitor the systems off-site.
    - h. Systems shall not be operated unattended such as on holidays, weekends, nights, etc, nor shall personnel unfamiliar with the operation of the HVAC Systems be employed to "monitor or attend to" the systems such as security personnel, or janitorial staff. The heating system, when in operation, shall be continuously monitored by the mechanical contractor's approved personnel.
    - i. Systems when activated, may be placed into operation without diffusers and registers in place, but filters capable of filtering gypsum dust or other associated construction dust and debris shall be provided both in air handling equipment and at return air grille locations. Filter all return air entering duct work, to prevent return air ductwork from accumulating dust or otherwise becoming dirty.
    - j. Prior to final acceptance of the work, the contractor shall place heating systems and related equipment in a condition equal to new in that contractor shall clean all ductwork, coils, equipment, etc.
    - k. All disposable or wearable parts such as belts, filters, etc., shall be replaced without option or cause.
  - 2. Preliminary Heating Test, Adjusting and Balancing Report:
    - a. Provide a TAB report at the time the heating system(s) start-up which shall indicate the following conditions:

- 1) Air pressure drop across the unit filters
  - 2) Air pressure drop across the unit's cooling coil(s)
  - 3) Air pressure drop across the unit's heating coil(s)
  - 4) Total static pressure produced by the unit
  - 5) Discharge air static pressure
  - 6) Fan RPM
  - 7) Suction air pressure
  - 8) Provide a unit pressure graph
  - 9) Discharge air temperature (each air moving device)
  - 10) Return air temperature (each air moving device)
  - 11) Entering water temperatures (hot & chilled)
  - 12) Leaving water temperatures (hot & chilled)
  - 13) Water flow quantity (gpm) through the coil(s)(hot & chilled)
3. Air Conditioning System:
- a. Should the contractor (at his option and at his own risk), utilize the building's permanent air conditioning systems provided under this contract to provide space cooling and de-humidification prior to the project completion date. As such, any damages, loss of performance, wear, and other detrimental effects caused by the operational performance characteristics of the A/C system such as condensation, sweating of grilles, registers, diffusers, ducts, equipment, walls, floors, ceilings, and other conditions which may cause damage to building components or which cause mold, mildew, etc., shall be the total responsibility of the contractor.
  - b. The fuel, electricity or other energy required for space cooling and for any subsequent operation or testing shall be provided by the Contractor.
  - c. The cooling system(s) shall be operated only by fully qualified personnel and shall be operated with all safety auxiliaries, and in accordance with manufacturer's instructions and good operating practice.
  - d. Start-up of equipment for use by the Contractor shall not commence any warranty period.
  - e. If at any time the Owner's Representative determines that the equipment is being improperly operated or maintained, the contractor will be directed to discontinue and disconnect its use and the contractor will be required to provide portable units to maintain space temperatures.
  - f. Temporary cooling and/or de-humidification systems shall be operated and controlled to prevent temperature and humidity in any room or space in any portion of the building from falling below 75 deg. F or above 65% relative humidity.
  - g. Temperature controls shall be functional to the extent that the operating temperatures of equipment, ductwork, piping, etc., shall not fall below the normal stated "design" operating limits. The contractor shall demonstrate to the owner or his representative the ability of the system to be controlled, including limit alarms installed and the ability to monitor the systems off-site.
  - h. Insulation systems for all piping, ductwork, etc., shall be completely installed prior to use of the permanent systems.
  - i. Systems shall not be operated unattended such as on holidays, weekends, nights, etc., nor shall personnel unfamiliar with the operation of the HVAC Systems be employed to "monitor or attend to" the systems such as security personnel, or janitorial staff. The air conditioning system when in operation, shall be continuously monitored by the mechanical contractor's approved personnel.
  - j. Systems when activated, may be placed into operation without diffusers and registers in place, but filters capable of filtering gypsum dust or other associated construction dust and debris shall be provided both in air handling equipment and at return air grille locations. Filter all return air entering duct work, to prevent return air duct work from accumulating dust or otherwise becoming dirty.

- k. Contractor shall, prior to final acceptance of the work, place cooling systems and related equipment in a condition equal to new in that contractor shall clean all ductwork, coils, equipment, etc.
- l. All disposable or wearable parts such as belts, filters, etc., shall be replaced without option or cause.
- 4. Preliminary Air Conditioning Test, Adjusting and Balancing Report:
  - a. Provide a TAB report at the time the heating system(s) start-up which shall indicate the following conditions:
    - 1) Air pressure drop across the unit filters
    - 2) Air pressure drop across the unit's cooling coil(s)
    - 3) Air pressure drop across the unit's heating coil(s)
    - 4) Total static pressure produced by the unit
    - 5) Discharge air static pressure
    - 6) Fan RPM
    - 7) Suction air pressure
    - 8) Provide a unit pressure graph
    - 9) Discharge air temperature (each air moving device)
    - 10) Return air temperature (each air moving device)
    - 11) Entering water temperatures (hot & chilled)
    - 12) Leaving water temperatures (hot & chilled)
    - 13) Water flow quantity (gpm) through the coil(s)(hot & chilled)

END OF SECTION 23 00 00

## **SECTION 23 05 13 – COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section includes general requirements for single-phase and polyphase, general-purpose, horizontal, small and medium, squirrel-cage induction motors for use on ac power systems up to 600 V and installed at equipment manufacturer's factory or shipped separately by equipment manufacturer for field installation.

#### **1.3 COORDINATION**

- A. Coordinate features of motors, installed units, and accessory devices to be compatible with the following:
  - 1. Motor controllers.
  - 2. Torque, speed, and horsepower requirements of the load.
  - 3. Ratings and characteristics of supply circuit and required control sequence.
  - 4. Ambient and environmental conditions of installation location.

### **PART 2 - PRODUCTS**

#### **2.1 GENERAL MOTOR REQUIREMENTS**

- A. Comply with NEMA MG 1 unless otherwise indicated.

#### **2.2 MOTOR CHARACTERISTICS**

- A. Duty: Continuous duty at ambient temperature of 40 deg C and at altitude of 3300 feet above sea level.
- B. Capacity and Torque Characteristics: Sufficient to start, accelerate, and operate connected loads at designated speeds, at installed altitude and environment, with indicated operating sequence, and without exceeding nameplate ratings or considering service factor.

#### **2.3 POLYPHASE MOTORS**

- A. Description: NEMA MG 1, Design B, medium induction motor.

- B. Efficiency: Energy efficient, as defined in NEMA MG 1.
- C. Service Factor: 1.15.
- D. Multispeed Motors: Variable torque.
  - 1. For motors with 2:1 speed ratio, consequent pole, single winding.
  - 2. For motors with other than 2:1 speed ratio, separate winding for each speed.
- E. Rotor: Random-wound, squirrel cage.
- F. Bearings: Regreasable, shielded, antifriction ball bearings suitable for radial and thrust loading.
- G. Temperature Rise: Match insulation rating.
- H. Insulation: Class F.
- I. Code Letter Designation:
  - 1. Motors 15 HP and Larger: NEMA starting Code F or Code G.
  - 2. Motors Smaller than 15 HP: Manufacturer's standard starting characteristic.
- J. Enclosure Material: Cast iron for motor frame sizes 324T and larger; rolled steel for motor frame sizes smaller than 324T.

#### 2.4 SINGLE-PHASE MOTORS

- A. Motors larger than 1/20 hp shall be one of the following, to suit starting torque and requirements of specific motor application:
  - 1. Permanent-split capacitor.
  - 2. Split phase.
  - 3. Capacitor start, inductor run.
  - 4. Capacitor start, capacitor run.
- B. Multispeed Motors: Variable-torque, permanent-split-capacitor type.
- C. Bearings: Prelubricated, antifriction ball bearings or sleeve bearings suitable for radial and thrust loading.
- D. Motors 1/20 HP and Smaller: Shaded-pole type.
- E. Thermal Protection: Internal protection to automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature rating of motor insulation. Thermal-protection device shall automatically reset when motor temperature returns to normal range.

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. All materials and equipment shall be installed in accordance with Manufacturer's recommended installation methods for obtaining conformance with the Contract Documents.



- B. Alignment of all motors, factory coupled or mounted, and all motors field coupled and mounted, shall be rechecked after all connections have been made and after 48 hours of operation in designed service.
- C. Verify the voltage characteristics of each motor prior to ordering.
- D. Verify the correct wire connections and rotation of equipment by “bumping” motor after wiring.
- E. Confirm voltage imbalance on 3-phase motors is less than 2%.

3.2 APPLICATION: Except as specifically indicated, motors shall be selected as follows:

- A. Phase:
  - 1. Less than 1.0 HP: Single-Phase.
  - 2. 1 HP and Larger: Three-phase.
- B. Single Phase Starting:
  - 1. 1/8 HP and Less: Split phase or permanent split capacitor.
  - 2. Greater than 1/8 HP: Capacitor start.
- C. Enclosure:
  - 1. Totally enclosed fan-cooled (TEFC) for all motors located outside above roof, in wet areas, in mechanical rooms, or elsewhere as indicated.
  - 2. Open drip-proof (ODP) for motors located elsewhere, in a clean, dry environment.

END OF SECTION 23 05 13

## **SECTION 23 05 23.13 – BUTTERFLY VALVES FOR HVAC PIPING**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:
  - 1. High-performance butterfly valves.

#### **1.3 DEFINITIONS**

- A. CWP: Cold working pressure.
- B. EPDM: Ethylene propylene copolymer rubber.
- C. NBR: Acrylonitrile-butadiene, Buna-N, or nitrile rubber.
- D. SWP: Steam working pressure.

#### **1.4 ACTION SUBMITTALS**

- A. Product Data: For each type of valve.

#### **1.5 DELIVERY, STORAGE, AND HANDLING**

- A. Prepare valves for shipping as follows:
  - 1. Protect internal parts against rust and corrosion.
  - 2. Protect threads, flange faces, grooves, and weld ends.
  - 3. Set butterfly valves closed or slightly open.
- B. Use the following precautions during storage:
  - 1. Maintain valve end protection.
  - 2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.
- C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use handwheels or stems as lifting or rigging points.

## PART 2 - PRODUCTS

### 2.1 GENERAL REQUIREMENTS FOR VALVES

- A. Source Limitations for Valves: Obtain each type of valve from single source from single manufacturer.
- B. ASME Compliance:
  - 1. ASME B16.1 for flanges on iron valves.
  - 2. ASME B16.5 for pipe flanges and flanged fittings, NPS 1/2 through NPS 24.
  - 3. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
  - 4. ASME B31.1 for power piping valves.
  - 5. ASME B31.9 for building services piping valves.
- C. AWWA Compliance: Comply with AWWA C606 for grooved-end connections.
- D. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.
- E. Valve Sizes: Same as upstream piping unless otherwise indicated.
- F. Valve Actuator Types:
  - 1. Gear Actuator: For valves **NPS 8 (DN 200)** and larger.
  - 2. Handlever: For valves **NPS 6 (DN 150)** and smaller.
  - 3. Chainwheel: Device for attachment to gear, stem, or other actuator of size and with chain for mounting height, according to "Valve Installation" Article.
- G. Valves in Insulated Piping: With **2-inch (50-mm)** stem extensions with extended necks.

### 2.2 HIGH-PERFORMANCE BUTTERFLY VALVES

- A. Class 150, Single-Flange, High-Performance Butterfly Valves:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Apollo Flow Controls; Conbraco Industries, Inc.
    - b. Milwaukee Valve Company.
    - c. NIBCO INC.
  - 2. Description:
    - a. Standard: MSS SP-68.
    - b. CWP Rating: **285 psig (1965 kPa)** at **100 deg F (38 deg C)**.
    - c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
    - d. Body Material: Carbon steel, cast iron, ductile iron, or stainless steel.

- e. Seat: Reinforced PTFE or metal.
- f. Stem: Stainless steel; offset from seat plane.
- g. Disc: Carbon steel.
- h. Service: Bidirectional.

B. Class 300, Single-Flange, High-Performance Butterfly Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Apollo Flow Controls; Conbraco Industries, Inc.
  - b. Milwaukee Valve Company.
  - c. NIBCO INC.
2. Description:
  - a. Standard: MSS SP-68.
  - b. CWP Rating: **720 psig** (4965 kPa) at **100 deg F** (38 deg C).
  - c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
  - d. Body Material: Carbon steel, cast iron, or ductile iron.
  - e. Seat: Reinforced PTFE or metal.
  - f. Stem: Stainless steel; offset from seat plane.
  - g. Disc: Carbon steel.
  - h. Service: Bidirectional.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.
- C. Examine mating flange faces for damage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.
- D. Do not attempt to repair defective valves; replace with new valves.

#### 3.2 VALVE INSTALLATION

- A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.

- B. Locate valves for easy access and provide separate support where necessary.
- C. Install valves in horizontal piping with stem at or above center of pipe.
- D. Install valves in position to allow full stem movement.
- E. Install chainwheels on operators for butterfly valves **NPS 4 (DN 100)** and larger and more than **96 inches (2400 mm)** above floor. Extend chains to **60 inches (1520 mm)** above finished floor.
- F. Install valve tags. Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for valve tags and schedules.

### 3.3 ADJUSTING

- A. Adjust or replace valve packing after piping systems have been tested and put into service but before final adjusting and balancing. Replace valves if persistent leaking occurs.

### 3.4 CHILLED-WATER VALVE SCHEDULE

- A. Pipe **NPS 2-1/2 (DN 65)** and Larger:
  - 1. High-Performance Butterfly Valves: Class 300, single flange.

END OF SECTION 23 05 23.13

## **SECTION 23 05 29 – HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:
  - 1. Metal pipe hangers and supports.
  - 2. Trapeze pipe hangers.
  - 3. Metal framing systems.
  - 4. Thermal-hanger shield inserts.
  - 5. Fastener systems.
  - 6. Pipe stands.
  - 7. Equipment supports.

#### **1.3 DEFINITIONS**

- A. MSS: Manufacturers Standardization Society of the Valve and Fittings Industry Inc.

#### **1.4 PERFORMANCE REQUIREMENTS**

- A. Delegated Design: Design trapeze pipe hangers and equipment supports, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.
- B. Structural Performance: Hangers and supports for HVAC piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
  - 1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
  - 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

#### **1.5 ACTION SUBMITTALS**

- A. Product Data: For each type of product indicated.

1.6 INFORMATIONAL SUBMITTALS

- A. Welding certificates.

1.7 QUALITY ASSURANCE

- A. Structural Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- B. Pipe Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code.

**PART 2 - PRODUCTS**

2.1 METAL PIPE HANGERS AND SUPPORTS

- A. Carbon-Steel Pipe Hangers and Supports:
  - 1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
  - 2. Galvanized Metallic Coatings: Pregalvanized or hot dipped.
  - 3. Nonmetallic Coatings: Plastic coating, jacket, or liner.
  - 4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
  - 5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

2.2 TRAPEZE PIPE HANGERS

- A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural carbon-steel shapes with MSS SP-58 carbon-steel hanger rods, nuts, saddles, and U-bolts.

2.3 METAL FRAMING SYSTEMS

- A. MFMA Manufacturer Metal Framing Systems:
  - 1.
  - 2. Manufacturers:
    - a. Cooper B-Line, Inc.; a division of Cooper Industries.
    - b. Flex-Strut Inc.
    - c. Thomas & Betts Corporation, A Member of the ABB Group.
    - d. Unistrut; an Atkore International company.
    - e. Wesanco, Inc.
  - 3. Standard: MFMA-4.
  - 4. Channels: Continuous slotted steel channel with intumed lips.
  - 5. Channel Nuts: Formed or stamped steel nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
  - 6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
  - 7. Metallic Coating: Electroplated zinc.

## 2.4 FASTENER SYSTEMS

- A. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened Portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
- B. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel anchors, for use in hardened Portland cement concrete; with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

## 2.5 EQUIPMENT SUPPORTS

- A. Description: Welded, shop- or field-fabricated equipment support made from structural carbon-steel shapes.
- B. Roof Sleepers for VRF outdoor condensing units: Pate Model ES-2 or equal, equipment rail supports, 18 ga. Galvanized steel, unitized construction with integral base plate, continuous welded corner seams, pressure treated wood nailer, counterflashing with screws. Height of support shall be a minimum of 16 inches. Coordinate layout of supports with the equipment manufacturer's representative and equipment point loading requirements. Coordinate flashing and exterior insulation with the roofing installer and Architect.

## 2.6 MISCELLANEOUS MATERIALS

- A. Structural Steel: ASTM A 36/A 36M, carbon-steel plates, shapes, and bars; black and galvanized.
- B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
  - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
  - 2. Design Mix: 5000-psi, 28-day compressive strength.

# PART 3 - EXECUTION

## 3.1 HANGER AND SUPPORT INSTALLATION

- A. Metal Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from the building structure.
- B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.
  - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified for individual pipe hangers.



2. Field fabricate from ASTM A 36/A 36M, carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1/D1.1M.
- C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal framing systems.
- D. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.
- E. Fastener System Installation:
1. Install powder-actuated fasteners for use in lightweight concrete or concrete slabs less than 4 inches thick in concrete after concrete is placed and completely cured. Use operators that are licensed by powder-actuated tool manufacturer. Install fasteners according to powder-actuated tool manufacturer's operating manual.
  2. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.
- F. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.
- G. Equipment Support Installation: Fabricate from welded-structural-steel shapes.
- H. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- I. Install lateral bracing with pipe hangers and supports to prevent swaying.
- J. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- K. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- L. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.
- M. Insulated Piping:
1. Attach clamps and spacers to piping.
    - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
    - b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
    - c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.
  2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
    - a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
  3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.

- a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
- 4. Shield Dimensions for Pipe: Not less than the following:
  - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
  - b. NPS 4: 12 inches long and 0.06 inch thick.
  - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
  - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
  - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
- 5. Pipes NPS 8 and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
- 6. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

### 3.2 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make bearing surface smooth.
- C. Provide lateral bracing, to prevent swaying, for equipment supports.

### 3.3 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:
  - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
  - 2. Obtain fusion without undercut or overlap.
  - 3. Remove welding flux immediately.
  - 4. Finish welds at exposed connections so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

### 3.4 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

### 3.5 PAINTING

- A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
  - 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

### 3.6 HANGER AND SUPPORT SCHEDULE

- A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-69 for pipe-hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finish.
- D. Use carbon-steel pipe hangers and supports metal trapeze pipe hangers and metal framing systems and attachments for general service applications.
- E. Use thermal-hanger shield inserts for insulated piping and tubing.
- F. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
  - 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F, pipes NPS 4 to NPS 24, requiring up to 4 inches of insulation.
  - 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes NPS 3/4 to NPS 36, requiring clamp flexibility and up to 4 inches of insulation.
  - 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes NPS 1/2 to NPS 24 if little or no insulation is required.
  - 5. Pipe Hangers (MSS Type 5): For suspension of pipes NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
  - 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes NPS 3/4 to NPS 8.
  - 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
  - 8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
  - 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
  - 10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8.
  - 11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3.
  - 12. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.

13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
  14. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
  15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
  16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
  17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction might occur.
  18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes NPS 2-1/2 to NPS 24, from single rod if horizontal movement caused by expansion and contraction might occur.
  19. Complete Pipe Rolls (MSS Type 44): For support of pipes NPS 2 to NPS 42 if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is not necessary.
  20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes NPS 2 to NPS 24 if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is not necessary.
  21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes NPS 2 to NPS 30 if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- G. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
  2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.
- H. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
  2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
  3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
  4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
  5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.
- I. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
  2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction, to attach to top flange of structural shape.
  3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
  4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
  5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.

6. C-Clamps (MSS Type 23): For structural shapes.
  7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
  8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
  9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
  10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
  11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
  12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:
    - a. Light (MSS Type 31): 750 lb.
    - b. Medium (MSS Type 32): 1500 lb.
    - c. Heavy (MSS Type 33): 3000 lb.
  13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
  14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
  15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- J. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
  2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
  3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.
- K. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
  2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
  3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41, roll hanger with springs.
  4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
  5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from hanger.
  6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from base support.
  7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from trapeze support.
  8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
    - a. Horizontal (MSS Type 54): Mounted horizontally.
    - b. Vertical (MSS Type 55): Mounted vertically.
    - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.

- L. Comply with MSS SP-69 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- M. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.

END OF SECTION 23 05 29

## **SECTION 23 05 53 – IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:
  - 1. Equipment Labels.

#### **1.3 ACTION SUBMITTALS**

- A. Product Data: For each type of product.
- B. Samples: For color, letter style, and graphic representation required for each identification material and device.
- C. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.

### **PART 2 - PRODUCTS**

#### **2.1 EQUIPMENT LABELS**

- A. Plastic Labels for Equipment:
  - 1. Manufacturer shall be one of the following:
    - a. Brady Corporation.
    - b. Brimar Industries, Inc.
    - c. Carlton Industries, LP.
    - d. Champion America.
    - e. Craftmark Pipe Markers.
    - f. Emedco.
    - g. Kolbi Pipe Marker Co.
    - h. LEM Products Inc.
    - i. Marking Services, Inc.
    - j. Seton Identification Products.
  - 2. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.
  - 3. Letter Color: White.
  - 4. Background Color: Black.

5. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
  6. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
  7. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
  8. Fasteners: Stainless-steel rivets.
  9. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- B. Label Content: Include equipment's Drawing designation or unique equipment number, drawing numbers where equipment is indicated (plans, details, and schedules).
- C. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number, and identify Drawing numbers where equipment is indicated (plans, details, and schedules) and the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

### **PART 3 - EXECUTION**

#### **3.1 PREPARATION**

- A. Clean equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulated.

#### **3.2 GENERAL INSTALLATION REQUIREMENTS**

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

#### **3.3 EQUIPMENT LABEL INSTALLATION**

- A. Install or permanently fasten labels on each major item of mechanical equipment.
- B. Locate equipment labels where accessible and visible.

END OF SECTION 23 05 53



## **SECTION 23 05 93 – TESTING, ADJUSTING, AND BALANCING FOR HVAC**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SCOPE OF WORK**

- A. The Contractor shall obtain the services of an independent Test and Balance (TAB) Company which specializes in the testing and balancing of heating, ventilating and air conditioning (HVAC) systems to test, adjust and balance all HVAC systems in the building(s).
- B. The work included in this section consists of furnishing labor, instruments, and tools required in testing, adjusting and balancing the HVAC systems as described in these specifications or shown on accompanying drawings. Services shall include checking equipment performance, taking the specified measurements, and recording and reporting the results. The testing, adjusting and balancing agency shall act as a reporting agency; that is, list and report each piece of equipment as to identification number, manufacturer, model number, serial number, proper location, specified performance, and report actual performance of all equipment as found during testing. The report is intended to be used during the life of the building as a ready reference indicating original conditions, equipment components, etc.
- C. Representatives of the Test and Balance Company shall visit the job site during installation of the HVAC equipment, piping and ductwork as required.
- D. Upon completion of the HVAC system installation, the Test and Balance Company shall perform all required testing and balancing with the full cooperation of the Contractor and his Sub-contractors. The Contractor shall make changes and/or adjustments to the HVAC system components that are required by the Test and Balance Company to accomplish proper balancing. The TAB agency shall not supply or install any materials or balancing devices such as pulleys, drives, belts, etc. All of this work is by the Contractor and shall be performed at no additional cost to the Owner.
- E. The test and balance report complete with a summary page listing all deficiencies shall be submitted to the Architect for review. If the Architect agrees with the report, he shall sign it and return it to the Contractor. The test and balance report must be complete and must be accepted by the Architect prior to acceptance of the project. Any outstanding test and balance items shall be placed on the punch list and a monetary value shall be assigned to them.
- F. After all deficiencies have been corrected the Architect shall sign the testing and balancing report, and the Test and Balance Company shall supply four (4) copies of the final and complete report to the Contractor for inclusion in the Operation and Maintenance Manuals.

- G. The Test and Balance Company shall obtain a copy of all HVAC related shop drawings from the contractor. The contractor shall provide a set of approved shop drawings to the TAB contractor within 30 days from receiving approved shop drawings.
- H. The items requiring testing, adjusting, and balancing include (but are not restricted to) the following:
  - 1. Air Systems:
    - a. Pre-Test RTUs prior to demolition to record unit total air flows (supply, return air and outside air) and unit static profile.
    - b. Supply Fan RTU.
    - c. Exhaust Fans
    - d. Zone Branch and main ducts
    - e. Diffusers, Registers, Grilles and Dampers
    - f. Coils (Air Temperatures)
    - g. Valves
    - h. Vibration Isolators
  - 2. Hydronic Systems:
    - a. Pre-test chilled water piping serving CW RTU prior to demolition to record flow and pressure for CWS/CWR.
    - b. System Branches to RTU.
    - c. Coils

### 1.3 DEFINITIONS

- A. AABC: Associated Air Balance Council.
- B. BAS: Building automation systems.
- C. NEBB: National Environmental Balancing Bureau.
- D. TAB: Testing, adjusting, and balancing.
- E. TABB: Testing, Adjusting, and Balancing Bureau.
- F. TAB Specialist: An independent entity meeting qualifications to perform TAB work.
- G. TDH: Total dynamic head.

### 1.4 INFORMATIONAL SUBMITTALS

- A. Certified TAB reports.
- B. Sample report forms.

1.5 QUALITY ASSURANCE

- A. TAB Specialists Qualifications: Certified by AABC NEBB or TABB.
- B. Instrumentation Type, Quantity, Accuracy, and Calibration: Comply with requirements in ASHRAE 111, Section 4, "Instrumentation."
- C. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 7.2.2 - "Air Balancing."
- D. ASHRAE/IESNA Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6.7.2.3 - "System Balancing."

**PART 2 - PRODUCTS** (Not Applicable)

**PART 3 - EXECUTION**

3.1 EXAMINATION

- A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems designs that may preclude proper TAB of systems and equipment.
- B. Examine installed systems for balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers. Verify that locations of these balancing devices are applicable for intended purpose and are accessible.
- C. Examine the approved submittals for HVAC systems and equipment.
- D. Examine design data including HVAC system descriptions, statements of design assumptions for environmental conditions and systems output, and statements of philosophies and assumptions about HVAC system and equipment controls.
- E. Examine ceiling plenums and underfloor air plenums used for supply, return, or relief air to verify that they are properly separated from adjacent areas. Verify that penetrations in plenum walls are sealed and fire-stopped if required.
- F. Examine equipment performance data including fan and pump curves.
  - 1. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
  - 2. Calculate system-effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from the conditions used to rate equipment performance. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," or in SMACNA's "HVAC Systems - Duct Design." Compare results with the design data and installed conditions.

- G. Examine system and equipment installations and verify that field quality-control testing, cleaning, and adjusting specified in individual Sections have been performed.
- H. Examine test reports specified in individual system and equipment Sections.
- I. Examine HVAC equipment and verify that bearings are greased, belts are aligned and tight, filters are clean, and equipment with functioning controls is ready for operation.
- J. Examine operating safety interlocks and controls on HVAC equipment.
- K. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

### 3.2 PREPARATION

- A. Prepare a TAB plan that includes the following:
  - 1. Equipment and systems to be tested.
  - 2. Strategies and step-by-step procedures for balancing the systems.
  - 3. Instrumentation to be used.
  - 4. Sample forms with specific identification for all equipment.
- B. Perform system-readiness checks of HVAC systems and equipment to verify system readiness for TAB work. Include, at a minimum, the following:
  - 1. Airside:
    - a. Verify that leakage and pressure tests on air distribution systems have been satisfactorily completed.
    - b. Duct systems are complete with terminals installed.
    - c. Volume, smoke, and fire dampers are open and functional.
    - d. Clean filters are installed.
    - e. Fans are operating, free of vibration, and rotating in correct direction.
    - f. Variable-frequency controllers' startup is complete and safeties are verified.
    - g. Automatic temperature-control systems are operational.
    - h. Ceilings are installed.
    - i. Windows and doors are installed.
    - j. Suitable access to balancing devices and equipment is provided.

### 3.3 GENERAL PROCEDURES FOR TESTING AND BALANCING

- A. Perform testing and balancing procedures on each system according to the procedures contained in AABC's "National Standards for Total System Balance" NEBB's "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems" and in this Section.
- B. Cut insulation, ducts, pipes, and equipment cabinets for installation of test probes to the minimum extent necessary for TAB procedures.
  - 1. After testing and balancing, patch probe holes in ducts with same material and thickness as used to construct ducts.
  - 2. After testing and balancing, install test ports and duct access doors.
  - 3. Install and join new insulation that matches removed materials. Restore insulation, coverings, vapor barrier, and finish.

- C. Mark equipment and balancing devices, including damper-control positions, valve position indicators, fan-speed-control levers, and similar controls and devices, with paint or other suitable, permanent identification material to show final settings.
- D. Take and report testing and balancing measurements in inch-pound (IP) units.

### 3.4 GENERAL PROCEDURES FOR BALANCING AIR SYSTEMS

- A. Prepare test reports for both fans and outlets. Obtain manufacturer's outlet factors and recommended testing procedures. Cross-check the summation of required outlet volumes with required fan volumes.
- B. Prepare schematic diagrams of systems' "as-built" duct layouts.
- C. Determine the best locations in main and branch ducts for accurate duct-airflow measurements.
- D. Check airflow patterns from the outdoor-air louvers and dampers and the return- and exhaust-air dampers through the supply-fan discharge and mixing dampers.
- E. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.
- F. Verify that motor starters are equipped with properly sized thermal protection.
- G. Check dampers for proper position to achieve desired airflow path.
- H. Check for airflow blockages.
- I. Check condensate drains for proper connections and functioning.
- J. Check for proper sealing of air-handling-unit components.
- K. Verify that air duct system is sealed as specified.

### 3.5 PROCEDURES FOR CONSTANT-VOLUME AIR SYSTEMS

- A. Adjust fans to deliver total indicated airflows within the maximum allowable fan speed listed by fan manufacturer.
  - 1. Measure total airflow.
    - a. Set outside-air, return-air, and relief-air dampers for proper position that simulates minimum outdoor-air conditions.
    - b. Where duct conditions allow, measure airflow by Pitot-tube traverse. If necessary, perform multiple Pitot-tube traverses to obtain total airflow.
    - c. Where duct conditions are not suitable for Pitot-tube traverse measurements, a coil traverse may be acceptable.
    - d. If a reliable Pitot-tube traverse or coil traverse is not possible, measure airflow at terminals and calculate the total airflow.
  - 2. Measure fan static pressures as follows:
    - a. Measure static pressure directly at the fan outlet or through the flexible connection.
    - b. Measure static pressure directly at the fan inlet or through the flexible connection.

- c. Measure static pressure across each component that makes up the air-handling system.
  - d. Report artificial loading of filters at the time static pressures are measured.
- 3. Review Record Documents to determine variations in design static pressures versus actual static pressures. Calculate actual system-effect factors. Recommend adjustments to accommodate actual conditions.
- 4. Obtain approval from Construction Manager for adjustment of fan speed higher or lower than indicated speed. Comply with requirements in HVAC Sections for air-handling units for adjustment of fans, belts, and pulley sizes to achieve indicated air-handling-unit performance.
- 5. Do not make fan-speed adjustments that result in motor overload. Consult equipment manufacturers about fan-speed safety factors. Modulate dampers and measure fan-motor amperage to ensure that no overload occurs. Measure amperage in full-cooling, full-heating, economizer, and any other operating mode to determine the maximum required brake horsepower.
- B. Adjust volume dampers for main duct, submain ducts, and major branch ducts to indicated airflows.
  - 1. Measure airflow of submain and branch ducts.
  - 2. Adjust submain and branch duct volume dampers for specified airflow.
  - 3. Re-measure each submain and branch duct after all have been adjusted.
- C. Adjust air inlets and outlets for each space to indicated airflows.
  - 1. Set airflow patterns of adjustable outlets for proper distribution without drafts.
  - 2. Measure inlets and outlets airflow.
  - 3. Adjust each inlet and outlet for specified airflow.
  - 4. Re-measure each inlet and outlet after they have been adjusted.
- D. Verify final system conditions.
  - 1. Re-measure and confirm that minimum outdoor, return, and relief airflows are within design. Readjust to design if necessary.
  - 2. Re-measure and confirm that total airflow is within design.
  - 3. Re-measure all final fan operating data, rpms, volts, amps, and static profile.
  - 4. Mark all final settings.
  - 5. Test system in economizer mode. Verify proper operation and adjust if necessary.
  - 6. Measure and record all operating data.
  - 7. Record final fan-performance data.

### 3.6 PROCEDURES FOR MOTORS

- A. Motors 1/2 HP and Larger: Test at final balanced conditions and record the following data:
  - 1. Manufacturer's name, model number, and serial number.
  - 2. Motor horsepower rating.
  - 3. Motor rpm.
  - 4. Phase and hertz.
  - 5. Nameplate and measured voltage, each phase.
  - 6. Nameplate and measured amperage, each phase.
  - 7. Starter size and thermal-protection-element rating.
  - 8. Service factor and frame size.

3.7 PROCEDURES FOR CONDENSING UNITS

- A. Verify proper rotation of fans.
- B. Measure entering- and leaving-air temperatures.
- C. Record fan and motor operating data.

3.8 TOLERANCES

- A. Set HVAC system's airflow rates and water flow rates within the following tolerances:
  - 1. Supply, Return, and Equipment with Fans: Plus or minus 10 percent.
  - 2. Exhaust Fans: Plus 10 percent.
  - 3. Outside Airflow: Plus 10 percent.
  - 4. Air Outlets and Inlets: Plus or minus 10 percent.
- B. Maintaining pressure relationships as designed shall have priority over the tolerances specified above.

3.9 FINAL REPORT

- A. General: Prepare a certified written report; tabulate and divide the report into separate sections for tested systems and balanced systems.
  - 1. Include a certification sheet at the front of the report's binder, signed and sealed by the certified testing and balancing engineer.
  - 2. Include a list of instruments used for procedures, along with proof of calibration.
  - 3. Certify validity and accuracy of field data.
- B. Final Report Contents: In addition to certified field-report data, include the following:
  - 1. Fan curves.
  - 2. Manufacturers' test data.
  - 3. Field test reports prepared by system and equipment installers.
  - 4. Other information relative to equipment performance; do not include Shop Drawings and Product Data.
- C. General Report Data: In addition to form titles and entries, include the following data:
  - 1. Title page.
  - 2. Name and address of the TAB specialist.
  - 3. Project name.
  - 4. Project location.
  - 5. Architect's name and address.
  - 6. Engineer's name and address.
  - 7. Contractor's name and address.
  - 8. Report date.
  - 9. Signature of TAB supervisor who certifies the report.
  - 10. Table of Contents with the total number of pages defined for each section of the report. Number each page in the report.
  - 11. Summary of contents including the following:
    - a. Indicated versus final performance.
    - b. Notable characteristics of systems.

- c. Description of system operation sequence if it varies from the Contract Documents.
  - 12. Nomenclature sheets for each item of equipment.
  - 13. Notes to explain why certain final data in the body of reports vary from indicated values.
  - 14. Test conditions for fans performance forms including the following:
    - a. Settings for outdoor-, return-, and exhaust-air dampers.
    - b. Conditions of filters.
    - c. Cooling coil, wet- and dry-bulb conditions.
    - d. Fan drive settings including settings and percentage of maximum pitch diameter.
    - e. Settings for supply-air, static-pressure controller.
    - f. Other system operating conditions that affect performance.
- D. Air-Handling-Unit Test Reports: For air-handling units with coils, include the following:
  - 1. Unit Data:
    - a. Unit identification.
    - b. Location.
    - c. Make and type.
    - d. Model number and unit size.
    - e. Manufacturer's serial number.
    - f. Unit arrangement and class.
    - g. Discharge arrangement.
    - h. Sheave make, size in inches, and bore.
    - i. Center-to-center dimensions of sheave and amount of adjustments in inches.
    - j. Number, make, and size of belts.
    - k. Number, type, and size of filters.
  - 2. Motor Data:
    - a. Motor make, and frame type and size.
    - b. Horsepower and rpm.
    - c. Volts, phase, and hertz.
    - d. Full-load amperage and service factor.
    - e. Sheave make, size in inches, and bore.
    - f. Center-to-center dimensions of sheave and amount of adjustments in inches.
  - 3. Test Data (Indicated and Actual Values):
    - a. Total airflow rate in cfm.
    - b. Total system static pressure in inches wg.
    - c. Fan rpm.
    - d. Discharge static pressure in inches wg.
    - e. Filter static-pressure differential in inches wg.
    - f. Preheat-coil static-pressure differential in inches wg.
    - g. Cooling-coil static-pressure differential in inches wg.
    - h. Heating-coil static-pressure differential in inches wg.
    - i. Outdoor airflow in cfm.
    - j. Return airflow in cfm.
    - k. Outdoor-air damper position.
    - l. Return-air damper position.
    - m. Vortex damper position.
- E. Fan Test Reports: For supply, return, and exhaust fans, include the following:
  - 1. Fan Data:
    - a. System identification.
    - b. Location.
    - c. Make and type.



- d. Model number and size.
    - e. Manufacturer's serial number.
    - f. Arrangement and class.
    - g. Sheave make, size in inches, and bore.
    - h. Center-to-center dimensions of sheave and amount of adjustments in inches.
  - 2. Motor Data:
    - a. Motor make, and frame type and size.
    - b. Horsepower and rpm.
    - c. Volts, phase, and hertz.
    - d. Full-load amperage and service factor.
    - e. Sheave make, size in inches, and bore.
    - f. Center-to-center dimensions of sheave, and amount of adjustments in inches.
    - g. Number, make, and size of belts.
  - 3. Test Data (Indicated and Actual Values):
    - a. Total airflow rate in cfm.
    - b. Total system static pressure in inches wg.
    - c. Fan rpm.
    - d. Discharge static pressure in inches wg.
    - e. Suction static pressure in inches wg.
- F. Round, Flat-Oval, and Rectangular Duct Traverse Reports: Include a diagram with a grid representing the duct cross-section and record the following:
- 1. Report Data:
    - a. System and air-handling-unit number.
    - b. Location and zone.
    - c. Traverse air temperature in deg F.
    - d. Duct static pressure in inches wg.
    - e. Duct size in inches.
    - f. Duct area in sq. ft.
    - g. Indicated airflow rate in cfm.
    - h. Indicated velocity in fpm.
    - i. Actual airflow rate in cfm.
    - j. Actual average velocity in fpm.
    - k. Barometric pressure in psig.
- G. Instrument Calibration Reports:
- 1. Report Data:
    - a. Instrument type and make.
    - b. Serial number.
    - c. Application.
    - d. Dates of use.
    - e. Dates of calibration.
- 3.10 VERIFICATION OF TAB REPORT
- A. The TAB specialist's test and balance engineer shall conduct the inspection in the presence of Architect.
  - B. Architect may randomly select measurements, documented in the final report, to be rechecked. Rechecking shall be limited to either 10 percent of the total measurements recorded or the extent of measurements that can be accomplished in a normal 8-hour business day.
- TESTING, ADJUSTING, AND BALANCING FOR  
HVAC
- 23 05 93 - 9 OF 10

- C. If rechecks yield measurements that differ from the measurements documented in the final report by more than the tolerances allowed, the measurements shall be noted as "FAILED."
- D. If the number of "FAILED" measurements is greater than 10 percent of the total measurements checked during the final inspection, the testing and balancing shall be considered incomplete and shall be rejected.
- E. If TAB work fails, proceed as follows:
  - 1. TAB specialists shall recheck all measurements and make adjustments. Revise the final report and balancing device settings to include all changes; resubmit the final report and request a second final inspection.
  - 2. If the second final inspection also fails, Owner may contract the services of another TAB specialist to complete TAB work according to the Contract Documents and deduct the cost of the services from the original TAB specialist's final payment.
  - 3. If the second verification also fails, the design professional may contact AABC Headquarters regarding the AABC National Performance Guaranty.
- F. Prepare test and inspection reports.

### 3.11 ADDITIONAL TESTS

- A. Within 90 days of completing TAB, perform additional TAB to verify that balanced conditions are being maintained throughout and to correct unusual conditions.
- B. Seasonal Periods: If initial TAB procedures were not performed during near-peak summer and winter conditions, perform additional TAB during near-peak summer and winter conditions.

END OF SECTION 23 05 93

## **SECTION 23 07 13 – DUCT INSULATION**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section includes insulating the following duct services:

1. Indoor, concealed supply air.
2. Indoor, concealed return air.
3. Indoor, concealed exhaust air.
4. Indoor, concealed outdoor air.
5. Indoor, return air plenum boxes.
6. Indoor, tops of ceiling diffusers and grilles.

#### **1.3 ACTION SUBMITTALS**

- A. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance, thickness, and jackets (both factory- and field-applied if any).
- B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.
  1. Detail application of protective shields, saddles, and inserts at hangers for each type of insulation and hanger.
  2. Detail insulation application at elbows, fittings, dampers, specialties and flanges for each type of insulation.
  3. Detail application of field-applied jackets.
  4. Detail application at linkages of control devices.

#### **1.4 INFORMATIONAL SUBMITTALS**

- A. Qualification Data: For qualified Installer.
- B. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.
- C. Field quality-control reports.

1.5 QUALITY ASSURANCE

- A. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84, by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
  - 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
  - 2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.7 COORDINATION

- A. Coordinate sizes and locations of supports, hangers, and insulation shields as specified.
- B. Coordinate clearance requirements with duct Installer for duct insulation application. Before preparing ductwork Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.

1.8 SCHEDULING

- A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.
- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

**PART 2 - PRODUCTS**

2.1 INSULATION MATERIALS

- A. Comply with requirements in "Duct Insulation Schedule, General," "Indoor Duct and Plenum Insulation Schedule," articles for where insulating materials shall be applied.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.

- D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.
- E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- F. Fire Rated Insulation:
  - 1. Manufacturer shall be one of the following:
    - a. 3M FireMaster Fast Wrap 615+.
    - b. Thermal Ceramics FireMaster.
- G. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type II for sheet materials.
  - 1. Manufacturer shall be one of the following:
    - a. Aeroflex, USA, Inc.
    - b. Armacell LLC.
- H. Fiber-Glass Blanket Insulation: Fiber-Glass bonded with a thermosetting resin. Comply with ASTM C 553, Type II and ASTM C 1290, Type III with factory-applied FSK jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
  - 1. Manufacturer shall be one of the following:
    - a. Certainteed Corporation.
    - b. Johns Manville; a Berkshire Hathaway company.
    - c. Knauf Insulation.
    - d. Manson Insulation Inc.
    - e. Owens Corning.

## 2.2 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.
- B. Flexible Elastomeric Adhesive: Comply with MIL-A-24179A, Type II, Class I.
  - 1. Manufacture shall be one of the following:
    - a. Aeroflex USA, Inc.
    - b. Armacell LLC.
    - c. Foster Brand.
- C. Fiber-Glass Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.
  - 1. Manufacturer shall be one of the following:
    - a. Childers Brand.
    - b. Eagle Bridges – Marathon Industries.
    - c. Foster Brand.
    - d. Mon-Eco Industries, Inc.

## 2.3 MASTICS

- A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.

1. For indoor applications, use mastics that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

B. Vapor-Barrier Mastic: Water based; suitable for indoor use on below ambient services.

1. Manufacturer:
  - a. Foster Brand.
  - b. Knauf Insulation.
  - c. Vimasco Corporation.
  - d. Childers.
2. Water-Vapor Permeance: ASTM E 96/E 96M, Procedure B, 0.013 perm at 43-mil dry film thickness.
3. Service Temperature Range: Minus 20 to plus 180 deg F.
4. Solids Content: ASTM D 1644, 58 percent by volume and 70 percent by weight.
5. Color: White.

## 2.4 SEALANTS

- A. FSK and Metal Jacket Flashing Sealants:
1. Materials shall be compatible with insulation materials, jackets, and substrates.
  2. Fire- and water-resistant, flexible, elastomeric sealant.
  3. Service Temperature Range: Minus 40 to plus 250 deg F.
  4. Color: Aluminum.
  5. For indoor applications, sealants shall have a VOC content of 420 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  6. Sealants shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

## 2.5 FACTORY-APPLIED JACKETS

- A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
1. FSK Jacket: Aluminum-foil, fiberglass-reinforced scrim with kraft-paper backing; complying with ASTM C 1136, Type II.

## 2.6 TAPES

- A. FSK Tape: Foil-face, vapor-retarder tape matching factory-applied jacket with acrylic adhesive; complying with ASTM C 1136.
1. Width: 3 inches.
  2. Thickness: 6.5 mils.
  3. Adhesion: 90 ounces force/inch in width.
  4. Elongation: 2 percent.
  5. Tensile Strength: 40 lbf/inch in width.
  6. FSK Tape Disks and Squares: Precut disks or squares of FSK tape.

## 2.7 SECUREMENTS

### A. Bands:

1. Aluminum: ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, 3/4 inch wide with wing seal or closed seal.

### B. Insulation Pins and Hangers:

1. Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.135-inch- diameter shank, length to suit depth of insulation indicated.
2. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.135-inch- diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
3. Metal, Adhesively Attached, Perforated-Base Insulation Hangers: Baseplate welded to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
  - a. Baseplate: Perforated, galvanized carbon-steel sheet, 0.030 inch thick by 2 inches square.
  - b. Spindle: Copper- or zinc-coated, low-carbon steel, fully annealed, 0.106-inch-diameter shank, length to suit depth of insulation indicated.
  - c. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.
  - d. Baseplate: Perforated, nylon sheet, 0.030 inch thick by 1-1/2 inches in diameter.
  - e. Spindle: Nylon, 0.106-inch- diameter shank, length to suit depth of insulation indicated, up to 2-1/2 inches.
  - f. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.

### C. Staples: Outward-clinching insulation staples, nominal 3/4-inch- wide, stainless steel or Monel.

## 2.8 WALL LINER

### A. Fibrous-Glass Duct Liner: Comply with ASTM C 1071, NFPA 90A, or NFPA 90B; and with NAIMA AH124, "Fibrous Glass Duct Liner Standard."

#### 1. Manufacturers shall be as follows:

- a. Certainteed
- b. Owens Corning
- c. Johns Manville
- d. Knauf

#### 2. Maximum Thermal Conductivity:

- a. Type I, Flexible: 0.27 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.

3. Antimicrobial Erosion-Resistant Coating: Apply to the surface of the liner that will form the interior surface of the duct to act as a moisture repellent and erosion-resistant coating. Antimicrobial compound shall be tested for efficacy by an NRTL and registered by the EPA for use in HVAC systems.
4. Water-Based Liner Adhesive: Comply with NFPA 90A or NFPA 90B and with ASTM C 916.
  - a. For indoor applications, adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

B. Insulation Pins and Washers:

1. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
2. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick galvanized steel; with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.

### **PART 3 - EXECUTION**

#### **3.1 EXAMINATION**

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
  1. Verify that systems to be insulated have been tested and are free of defects.
  2. Verify that surfaces to be insulated are clean and dry.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

#### **3.2 PREPARATION**

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

#### **3.3 GENERAL INSTALLATION REQUIREMENTS**

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of ducts and fittings.
- B. Install insulation materials, vapor barriers or retarders, jackets, and thicknesses required for each item of duct system as specified in insulation system schedules.



- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.
- F. Keep insulation materials dry during application and finishing.
- G. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- H. Install insulation with least number of joints practical.
- I. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
  - 1. Install insulation continuously through hangers and around anchor attachments.
  - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
  - 3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
- J. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- K. Install insulation with factory-applied jackets as follows:
  - 1. Draw jacket tight and smooth.
  - 2. Cover circumferential joints with 3-inch- wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
  - 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 4 inches o.c.
    - a. For below ambient services, apply vapor-barrier mastic over staples.
  - 4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
  - 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to duct flanges and fittings.
- L. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- M. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.

- N. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.

### 3.4 PENETRATIONS

- A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
  - 1. Seal penetrations with flashing sealant.
  - 2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  - 3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
  - 4. Seal jacket to roof flashing with flashing sealant.
- B. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
  - 1. Seal penetrations with flashing sealant.
  - 2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  - 3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
  - 4. Seal jacket to wall flashing with flashing sealant.
- C. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- D. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Terminate insulation at fire damper sleeves for fire-rated wall and partition penetrations. Externally insulate damper sleeves to match adjacent insulation and overlap duct insulation at least 2 inches.
- E. Insulation Installation at Floor Penetrations:
  - 1. Duct: For penetrations through fire-rated assemblies, terminate insulation at fire damper sleeves and externally insulate damper sleeve beyond floor to match adjacent duct insulation. Overlap damper sleeve and duct insulation at least 2 inches.
  - 2. Seal penetrations through fire-rated assemblies.

### 3.5 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

- A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

### 3.6 INSTALLATION OF FIBER-GLASS INSULATION

- A. Blanket Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.
1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of duct and plenum surfaces.
  2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
  3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
    - a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
    - b. On duct sides with dimensions larger than 18 inches, place pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
    - c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
    - d. Do not overcompress insulation during installation.
    - e. Impale insulation over pins and attach speed washers.
    - f. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.
  4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
    - a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
    - b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.
  5. Overlap unfaced blankets a minimum of 2 inches on longitudinal seams and end joints. At end joints, secure with steel bands spaced a maximum of 18 inches o.c.
  6. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
  7. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch- wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

### 3.7 WALL LINER

- A. Apply on all mechanical room walls from floor to ceiling / deck.
  - 1. Adhere a single layer of indicated thickness of duct liner with at least 90 percent adhesive coverage at liner contact surface area. Attaining indicated thickness with multiple layers of duct liner is prohibited.
  - 2. Apply adhesive to transverse edges of liner facing upstream that do not receive metal nosing.
  - 3. Butt transverse joints without gaps, and coat joint with adhesive.
  - 4. Fold and compress liner in corners or cut and fit to ensure butted-edge overlapping.
  - 5. Secure liner with mechanical fasteners 4 inches from corners and at intervals not exceeding 12 inches transversely; at 3 inches from transverse joints and at intervals not exceeding 18 inches longitudinally.

### 3.8 FIELD-APPLIED JACKET INSTALLATION

- A. Where FSK jackets are indicated, install as follows:
  - 1. Draw jacket material smooth and tight.
  - 2. Install lap or joint strips with same material as jacket.
  - 3. Secure jacket to insulation with manufacturer's recommended adhesive.
  - 4. Install jacket with 1-1/2-inch laps at longitudinal seams and 3-inch- wide joint strips at end joints.
  - 5. Seal openings, punctures, and breaks in vapor-retarder jackets and exposed insulation with vapor-barrier mastic.

### 3.9 FIRE-RATED INSULATION SYSTEM INSTALLATION

- A. Where fire-rated insulation system is indicated, secure system to ducts and duct hangers and supports to maintain a continuous fire rating.
- B. Insulate duct access panels and doors to achieve same fire rating as duct.
- C. Install firestopping at penetrations through fire-rated assemblies.

### 3.10 FINISHES

- A. Insulation with ASJ, Glass-Cloth, or Other Paintable Jacket Material: Paint jacket with paint system identified below and as specified.
  - 1. Flat Acrylic Finish: Two finish coats over a primer that is compatible with jacket material and finish coat paint. Add fungicidal agent to render fabric mildew proof.
    - a. Finish Coat Material: Interior, flat, latex-emulsion size.
- B. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.

- C. Color: Final color as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.
- D. Do not field paint aluminum or stainless-steel jackets.

3.11 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Perform tests and inspections.
- C. Tests and Inspections:
  - 1. Inspect ductwork, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one location(s) for each duct system defined in the "Duct Insulation Schedule, General" Article.
- D. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

3.12 DUCT INSULATION SCHEDULE, GENERAL

- A. Plenums and Ducts Requiring Insulation:
  - 1. Indoor, concealed supply air.
  - 2. Indoor, concealed return air.
  - 3. Indoor, concealed exhaust air.
  - 4. Indoor, concealed outdoor air.
  - 5. Indoor, return air plenum boxes.
  - 6. Indoor, tops of ceiling diffusers and grilles.
- B. Items Not Insulated:
  - 1. Metal ducts with duct liner of sufficient thickness to comply with energy code and ASHRAE/IESNA 90.1.
  - 2. Factory-insulated flexible ducts.
  - 3. Factory-insulated plenums and casings.
  - 4. Flexible connectors.
  - 5. Vibration-control devices.
  - 6. Factory-insulated access panels and doors.

3.13 DUCT AND PLENUM INSULATION SCHEDULE

- A. Concealed, round and flat-oval, supply-air duct insulation shall be the following:
  - 1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
  - 2. Minimum installed R-value shall be R-6.0.
- B. Concealed, round and flat-oval, return-air duct insulation shall be the following:

1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
  2. Minimum installed R-value shall be R-6.0.
- C. Concealed, round and flat-oval, outdoor-air duct insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
  2. Minimum installed R-value shall be R-6.0.
- D. Concealed, round and flat-oval, exhaust-air duct insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
  2. Minimum installed R-value shall be R-6.0.
- E. Concealed, rectangular, supply-air duct insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
  2. Minimum installed R-value shall be R-6.0.
- F. Concealed, rectangular, return-air duct insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
  2. Minimum installed R-value shall be R-6.0.
- G. Concealed, rectangular, outdoor-air duct insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
  2. Minimum installed R-value shall be R-6.0.
- H. Concealed, rectangular, exhaust-air duct shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
  2. Minimum installed R-value shall be R-6.0.
- I. Concealed, supply-air plenum insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
  2. Minimum installed R-value shall be R-6.0.
- J. Return air plenum boxes installation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
  2. Minimum installed R-value shall be R-6.0.
- K. Tops of supply air diffusers and grilles insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
  2. Minimum installed R-value shall be R-6.0.

END OF SECTION 23 07 13

## **SECTION 23 07 19 – HVAC PIPING INSULATION**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section includes insulating the following HVAC piping systems:
  - 1. Condensate drain piping, indoors
  - 2. Chilled-water and brine piping, indoors
  - 3. Refrigerant suction and hot-gas piping, indoors

#### **1.3 ACTION SUBMITTALS**

- A. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory and field applied if any).

#### **1.4 INFORMATIONAL SUBMITTALS**

- A. Qualification Data: For qualified Installer.
- B. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.
- C. Field quality-control reports.

#### **1.5 QUALITY ASSURANCE**

- A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.
- B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84, by a testing and inspecting agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.

1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.7 COORDINATION

- A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Section 230529 "Hangers and Supports for HVAC Piping and Equipment."
- B. Coordinate clearance requirements with piping Installer for piping insulation application. Before preparing piping Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.
- C. Coordinate installation and testing of heat tracing.

1.8 SCHEDULING

- A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.
- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

**PART 2 - PRODUCTS**

2.1 INSULATION MATERIALS

- A. Comply with requirements in "Piping Insulation Schedule, General," "Indoor Piping Insulation Schedule," "Outdoor, Aboveground Piping Insulation Schedule," and "Outdoor, Underground Piping Insulation Schedule" articles for where insulating materials shall be applied.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.
- D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.
- E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.



- F. Cellular Glass: Inorganic, incombustible, foamed or cellulated glass with annealed, rigid, hermetically sealed cells. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Owens Corning.
    - b. Knauf Insulation
    - c. Or Prior Approved Equal.
  2. Block Insulation: ASTM C 552, Type I.
  3. Special-Shaped Insulation: ASTM C 552, Type III.
  4. Board Insulation: ASTM C 552, Type IV.
  5. Preformed Pipe Insulation without Jacket: Comply with ASTM C 552, Type II, Class 1.
  6. Preformed Pipe Insulation with Factory-Applied ASJ: Comply with ASTM C 552, Type II, Class 2.
  7. Factory fabricate shapes according to ASTM C 450 and ASTM C 585.
- G. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Aeroflex USA.
    - b. Armacell LLC.
    - c. K-Flex USA.
    - d. Or Prior Approved Equal
- H. Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 553, Type II and ASTM C 1290, Type II with factory-applied vinyl jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. CertainTeed Corporation; Saint-Gobain North America.
    - b. Johns Manville; a Berkshire Hathaway company.
    - c. Knauf Insulation.
    - d. Manson Insulation Inc.
    - e. Owens Corning.
    - f. Or Prior Approved Equal
- I. Mineral-Fiber, Preformed Pipe Insulation:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Johns Manville; a Berkshire Hathaway company.
    - b. Knauf Insulation.
    - c. Manson Insulation Inc.
    - d. Owens Corning.

- e. Or Prior Approved Equal.
- 2. Type I, **850 deg F (454 deg C)** Materials: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 547, Type I, Grade A, with factory-applied ASJ. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
- J. Mineral-Fiber, Pipe and Tank Insulation: Mineral or glass fibers bonded with a thermosetting resin. Semirigid board material with factory-applied ASJ complying with ASTM C 1393, Type II or Type IIIA Category 2, or with properties similar to ASTM C 612, Type IB. Nominal density is **2.5 lb/cu. ft. (40 kg/cu. m)** or more. Thermal conductivity (k-value) at **100 deg F (55 deg C)** is **0.29 Btu x in./h x sq. ft. x deg F (0.042 W/m x K)** or less. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. CertainTeed Corporation; Saint-Gobain North America.
    - b. Johns Manville; a Berkshire Hathaway company.
    - c. Knauf Insulation.
    - d. Manson Insulation Inc.
    - e. Owens Corning.
    - f. Or Prior Approved Equal.

## 2.2 INSULATING CEMENTS

- A. Mineral-Fiber Insulating Cement: Comply with ASTM C 195.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Ramco Insulation, Inc
    - b. Rutland.
    - c. Or Prior Approved Equal
- B. Expanded or Exfoliated Vermiculite Insulating Cement: Comply with ASTM C 196.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Ramco Insulation, Inc.
    - b. Rutland
    - c. Or Prior Approved Equal
- C. Mineral-Fiber, Hydraulic-Setting Insulating and Finishing Cement: Comply with ASTM C 449.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

- a. Ramco Insulation, Inc.
- b. Rutland
- c. Or Prior Approved Equal

## 2.3 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.
- B. Flexible Elastomeric and Polyolefin Adhesive: Comply with MIL-A-24179A, Type II, Class I.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Aeroflex USA.
    - b. Armacell LLC.
    - c. K-Flex USA.
    - d. Or Prior Approved Equal
  - 2. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 3. Adhesive shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- C. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Childers Brand; H. B. Fuller Construction Products.
    - b. Foster Brand; H. B. Fuller Construction Products.
    - c. Mon-Eco Industries, Inc.
    - d. Or Prior Approved Equal
  - 2. For indoor applications, adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 3. Adhesive shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- D. ASJ Adhesive, and FSK and PVDC Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Childers Brand; H. B. Fuller Construction Products.
    - b. Foster Brand; H. B. Fuller Construction Products.
    - c. Mon-Eco Industries, Inc.
    - d. Or Prior Approved Equal

2. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
3. Adhesive shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

E. PVC Jacket Adhesive: Compatible with PVC jacket.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Johns Manville; a Berkshire Hathaway company.
  - b. The Dow Chemical Company.
  - c. Voltek; a division of Sekisui America Corp.
  - d. Or Prior Approved Equal
2. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
3. Adhesive shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

## 2.4 MASTICS

A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.

1. For indoor applications, use mastics that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

B. Vapor-Barrier Mastic: Water based; suitable for indoor use on below-ambient services.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Childers Brand; H. B. Fuller Construction Products.
  - b. Foster Brand; H. B. Fuller Construction Products.
  - c. Knauf Insulation.
  - d. Mon-Eco Industries, Inc.
  - e. Vimasco Corporation.
  - f. Or Prior Approved Equal
2. Water-Vapor Permeance: ASTM E 96/E 96M, Procedure B, 0.013 perm (0.009 metric perm) at 43-mil (1.09-mm) dry film thickness.
3. Service Temperature Range: Minus 20 to plus 180 deg F (Minus 29 to plus 82 deg C).
4. Solids Content: ASTM D 1644, 58 percent by volume and 70 percent by weight.
5. Color: White.
- 6.

## 2.5 SEALANTS

A. Joint Sealants:

1. Joint Sealants for Cellular-Glass, Phenolic, and Polyisocyanurate Products: Subject to compliance with requirements, provide one of the following:
  2. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Childers Brand; H. B. Fuller Construction Products.
    - b. Foster Brand; H. B. Fuller Construction Products.
    - c. Mon-Eco Industries, Inc.
    - d. Owens Corning.
    - e. Or Prior Approved Equal
  3. Joint Sealants for Polystyrene Products: Subject to compliance with requirements, provide one of the following:
  4. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Childers Brand; H. B. Fuller Construction Products.
    - b. Foster Brand; H. B. Fuller Construction Products.
    - c. Eagle Bridges - Marathon Industries.
    - d. Or Prior Approved Equal
  5. Materials shall be compatible with insulation materials, jackets, and substrates.
  6. Permanently flexible, elastomeric sealant.
  7. Service Temperature Range: **Minus 100 to plus 300 deg F (Minus 73 to plus 149 deg C).**
  8. Color: White or gray.
- B. FSK and Metal Jacket Flashing Sealants:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Childers Brand; H. B. Fuller Construction Products.
    - b. Foster Brand; H. B. Fuller Construction Products.
    - c. Mon-Eco Industries, Inc.
    - d. Or Prior Approved Equal
  2. Materials shall be compatible with insulation materials, jackets, and substrates.
  3. Fire- and water-resistant, flexible, elastomeric sealant.
  4. Service Temperature Range: **Minus 40 to plus 250 deg F (Minus 40 to plus 121 deg C).**
  5. Color: Aluminum.
  6. For indoor applications, sealants shall have a VOC content of 420 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  7. Sealants shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- C. ASJ Flashing Sealants, and Vinyl, PVDC, and PVC Jacket Flashing Sealants:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Childers Brand; H. B. Fuller Construction Products.

- b. Foster Brand; H. B. Fuller Construction Products.
- c. Or Prior Approved Equal
- 2. Materials shall be compatible with insulation materials, jackets, and substrates.
- 3. Fire- and water-resistant, flexible, elastomeric sealant.
- 4. Service Temperature Range: **Minus 40 to plus 250 deg F (Minus 40 to plus 121 deg C).**
- 5. Color: White.
- 6. For indoor applications, sealants shall have a VOC content of 420 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- 7. Sealants shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

## 2.6 FACTORY-APPLIED JACKETS

- A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
  - 1. ASJ: White, kraft-paper, fiberglass-reinforced scrim with aluminum-foil backing; complying with ASTM C 1136, Type I.
  - 2. ASJ-SSL: ASJ with self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip; complying with ASTM C 1136, Type I.
  - 3. FSK Jacket: Aluminum-foil, fiberglass-reinforced scrim with kraft-paper backing; complying with ASTM C 1136, Type II.
  - 4. FSP Jacket: Aluminum-foil, fiberglass-reinforced scrim with polyethylene backing; complying with ASTM C 1136, Type II.
  - 5. PVDC Jacket for Indoor Applications: **4-mil- (0.10-mm-)** thick, white PVDC biaxially oriented barrier film with a permeance at **0.02 perm (0.013 metric perm)** when tested according to ASTM E 96/E 96M and with a flame-spread index of 5 and a smoke-developed index of 20 when tested according to ASTM E 84.
    - a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
      - 1) ITW Insulation Systems; Illinois Tool Works, Inc.
      - 2) Johns Manville; a Berkshire Hathaway company.
      - 3) Or Prior Approved Equal
  - 6. PVDC-SSL Jacket: PVDC jacket with a self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip.
    - a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
      - 1) ITW Insulation Systems; Illinois Tool Works, Inc.
      - 2) Johns Manville; a Berkshire Hathaway company.
      - 3) Or Prior Approved Equal
  - 7. Vinyl Jacket: White vinyl with a permeance of **1.3 perms (0.86 metric perms)** when tested according to ASTM E 96/E 96M, Procedure A, and complying with NFPA 90A and NFPA 90B.

## 2.7 FIELD-APPLIED JACKETS

- A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.
- B. FSK Jacket: Aluminum-foil-face, fiberglass-reinforced scrim with kraft-paper backing.
- C. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Airex Manufacturing.
    - b. Johns Manville; a Berkshire Hathaway company.
    - c. P.I.C. Plastics, Inc.
    - d. Proto Corporation.
    - e. Speedline Corporation.
    - f. Or Prior Approved Equal
  - 2. Adhesive: As recommended by jacket material manufacturer.
  - 3. Color: White
  - 4. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.
    - a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.
- D. Metal Jacket:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Johns Manville; a Berkshire Hathaway company.
    - b. RPR Products, Inc.
    - c. Or Prior Approved Equal
  - 2. Aluminum Jacket: Comply with **ASTM B 209 (ASTM B 209M)**, Alloy 3003, 3005, 3105, or 5005, Temper H-14.
    - a. Sheet and roll stock ready for shop or field sizing
    - b. Finish and thickness are indicated in field-applied jacket schedules.
    - c. Moisture Barrier for Indoor Applications: **1-mil- (0.025-mm-)** thick, heat-bonded polyethylene and kraft paper
    - d. Moisture Barrier for Outdoor Applications: **3-mil- (0.075-mm-)** thick, heat-bonded polyethylene and kraft paper
    - e. Factory-Fabricated Fitting Covers:
      - 1) Same material, finish, and thickness as jacket.
      - 2) Preformed 2-piece or gore, 45- and 90-degree, short- and long-radius elbows.
      - 3) Tee covers.
      - 4) Flange and union covers.
      - 5) End caps.
      - 6) Beveled collars.

- 7) Valve covers.
- 8) Field fabricate fitting covers only if factory-fabricated fitting covers are not available.

## 2.8 TAPES

- A. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive, complying with ASTM C 1136.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. 3M Industrial Adhesives and Tapes Division.
  - b. Avery Dennison Corporation, Specialty Tapes Division.
  - c. Ideal Tape Co., Inc., an American Biltrite Company.
  - d. Knauf Insulation.
  - e. Or Prior Approved Equal
2. Width: **3 inches** (75 mm).
3. Thickness: **11.5 mils** (0.29 mm).
4. Adhesion: **90 ounces force/inch** (1.0 N/mm) in width.
5. Elongation: 2 percent.
6. Tensile Strength: **40 lbf/inch** (7.2 N/mm) in width.
7. ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape.

- B. FSK Tape: Foil-face, vapor-retarder tape matching factory-applied jacket with acrylic adhesive; complying with ASTM C 1136.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. 3M Industrial Adhesives and Tapes Division.
  - b. Avery Dennison Corporation, Specialty Tapes Division.
  - c. Ideal Tape Co., Inc., an American Biltrite Company.
  - d. Knauf Insulation.
  - e. Or Prior Approved Equal
2. Width: **3 inches** (75 mm).
3. Thickness: **6.5 mils** (0.16 mm).
4. Adhesion: **90 ounces force/inch** (1.0 N/mm) in width.
5. Elongation: 2 percent.
6. Tensile Strength: **40 lbf/inch** (7.2 N/mm) in width.
7. FSK Tape Disks and Squares: Precut disks or squares of FSK tape.

- C. PVC Tape: White vapor-retarder tape matching field-applied PVC jacket with acrylic adhesive; suitable for indoor and outdoor applications.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. 3M Industrial Adhesives and Tapes Division.
  - b. Ideal Tape Co., Inc., an American Biltrite Company.
  - c. Or Prior Approved Equal
2. Width: **2 inches** (50 mm).



3. Thickness: 6 mils (0.15 mm).
4. Adhesion: 64 ounces force/inch (0.7 N/mm) in width.
5. Elongation: 500 percent.
6. Tensile Strength: 18 lbf/inch (3.3 N/mm) in width.

D. Aluminum-Foil Tape: Vapor-retarder tape with acrylic adhesive.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. 3M Industrial Adhesives and Tapes Division.
  - b. Avery Dennison Corporation, Specialty Tapes Division.
  - c. Ideal Tape Co., Inc., an American Biltrite Company.
  - d. Knauf Insulation.
  - e. Or Prior Approved Equal
2. Width: 2 inches (50 mm).
3. Thickness: 3.7 mils (0.093 mm).
4. Adhesion: 100 ounces force/inch (1.1 N/mm) in width.
5. Elongation: 5 percent.
6. Tensile Strength: 34 lbf/inch (6.2 N/mm) in width.

E. PVDC Tape for Indoor Applications: White vapor-retarder PVDC tape with acrylic adhesive.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - a. Johns Manville; a Berkshire Hathaway company.
  - b. ITW Insulation Systems; Illinois Tool Works, Inc.
  - c. Or Prior Approved Equal
2. Width: 3 inches (75 mm).
3. Film Thickness: 4 mils (0.10 mm).
4. Adhesive Thickness: 1.5 mils (0.04 mm).
5. Elongation at Break: 145 percent.
6. Tensile Strength: 55 lbf/inch (10.1 N/mm) in width.

## 2.9 SECUREMENTS

A. Bands:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Johns Manville; a Berkshire Hathaway company.
  - b. RPR Products, Inc.
  - c. Or Prior Approved Equal
2. Aluminum: ASTM B 209 (ASTM B 209M), Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch (0.51 mm) thick, 3/4 inch (19 mm) wide with closed seal.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
  - 1. Verify that systems to be insulated have been tested and are free of defects.
  - 2. Verify that surfaces to be insulated are clean and dry.
  - 3. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.
- B. Surface Preparation: Clean and prepare surfaces to be insulated. Before insulating, apply a corrosion coating to insulated surfaces as follows:
  - 1. Stainless Steel: Coat 300 series stainless steel with an epoxy primer **5 mils (0.127 mm)** thick and an epoxy finish **5 mils (0.127 mm)** thick if operating in a temperature range between **140 and 300 deg F (60 and 149 deg C)**. Consult coating manufacturer for appropriate coating materials and application methods for operating temperature range.
  - 2. Carbon Steel: Coat carbon steel operating at a service temperature between **32 and 300 deg F (0 and 149 deg C)** with an epoxy coating. Consult coating manufacturer for appropriate coating materials and application methods for operating temperature range.
- C. Coordinate insulation installation with the trade installing heat tracing. Comply with requirements for heat tracing that apply to insulation.
- D. Mix insulating cements with clean potable water; if insulating cements are to be in contact with stainless-steel surfaces, use demineralized water.

### 3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping including fittings, valves, and specialties.
- B. Install insulation materials, forms, vapor barriers or retarders, jackets, and thicknesses required for each item of pipe system as specified in insulation system schedules.
- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.
- F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.

- G. Keep insulation materials dry during application and finishing.
- H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- I. Install insulation with least number of joints practical.
- J. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
  - 1. Install insulation continuously through hangers and around anchor attachments.
  - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
  - 3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
  - 4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.
- K. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- L. Install insulation with factory-applied jackets as follows:
  - 1. Draw jacket tight and smooth.
  - 2. Cover circumferential joints with **3-inch- (75-mm-)** wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced **4 inches (100 mm)** o.c.
  - 3. Overlap jacket longitudinal seams at least **1-1/2 inches (38 mm)**. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at [**2 inches (50 mm)**] [**4 inches (100 mm)**] o.c.
    - a. For below-ambient services, apply vapor-barrier mastic over staples.
  - 4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
  - 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to pipe flanges and fittings.
- M. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- N. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.
- O. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least **4 inches (100 mm)** beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.
- P. For above-ambient services, do not install insulation to the following:

1. Vibration-control devices.
2. Testing agency labels and stamps.
3. Nameplates and data plates.
4. Manholes.
5. Handholes.
6. Cleanouts.

### 3.4 PENETRATIONS

- A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
  1. Seal penetrations with flashing sealant.
  2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  3. Extend jacket of outdoor insulation outside roof flashing at least **2 inches (50 mm)** below top of roof flashing.
  4. Seal jacket to roof flashing with flashing sealant.
- B. Insulation Installation at Underground Exterior Wall Penetrations: Terminate insulation flush with sleeve seal. Seal terminations with flashing sealant.
- C. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
  1. Seal penetrations with flashing sealant.
  2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least **2 inches (50 mm)**.
  4. Seal jacket to wall flashing with flashing sealant.
- D. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- E. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions.
  1. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping and fire-resistive joint sealers.
- F. Insulation Installation at Floor Penetrations:
  1. Pipe: Install insulation continuously through floor penetrations.
  2. Seal penetrations through fire-rated assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

### 3.5 GENERAL PIPE INSULATION INSTALLATION

- A. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.
- B. Insulation Installation on Fittings, Valves, Strainers, Flanges, and Unions:
  - 1. Install insulation over fittings, valves, strainers, flanges, unions, and other specialties with continuous thermal and vapor-retarder integrity unless otherwise indicated.
  - 2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
  - 3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
  - 4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts. Fill joints, seams, and irregular surfaces with insulating cement.
  - 5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below-ambient services, provide a design that maintains vapor barrier.
  - 6. Insulate flanges and unions using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker.
  - 7. Cover segmented insulated surfaces with a layer of finishing cement and coat with a mastic. Install vapor-barrier mastic for below-ambient services and a breather mastic for above-ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.
  - 8. For services not specified to receive a field-applied jacket except for flexible elastomeric and polyolefin, install fitted PVC cover over elbows, tees, strainers, valves, flanges, and unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing using PVC tape.
  - 9. Stencil or label the outside insulation jacket of each union with the word "union." Match size and color of pipe labels.
- C. Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, test connections, flow meters, sensors, switches, and transmitters on insulated pipes. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.
- D. Install removable insulation covers at locations indicated. Installation shall conform to the following:

1. Make removable flange and union insulation from sectional pipe insulation of same thickness as that on adjoining pipe. Install same insulation jacket as adjoining pipe insulation.
2. When flange and union covers are made from sectional pipe insulation, extend insulation from flanges or union long at least two times the insulation thickness over adjacent pipe insulation on each side of flange or union. Secure flange cover in place with stainless-steel or aluminum bands. Select band material compatible with insulation and jacket.
3. Construct removable valve insulation covers in same manner as for flanges, except divide the two-part section on the vertical center line of valve body.
4. When covers are made from block insulation, make two halves, each consisting of mitered blocks wired to stainless-steel fabric. Secure this wire frame, with its attached insulation, to flanges with tie wire. Extend insulation at least 2 inches (50 mm) over adjacent pipe insulation on each side of valve. Fill space between flange or union cover and pipe insulation with insulating cement. Finish cover assembly with insulating cement applied in two coats. After first coat is dry, apply and trowel second coat to a smooth finish.
5. Unless a PVC jacket is indicated in field-applied jacket schedules, finish exposed surfaces with a metal jacket.

### 3.6 INSTALLATION OF CELLULAR-GLASS INSULATION

#### A. Insulation Installation on Straight Pipes and Tubes:

1. Secure each layer of insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
3. For insulation with factory-applied jackets on above-ambient services, secure laps with outward-clinched staples at 6 inches (150 mm) o.c.
4. For insulation with factory-applied jackets on below-ambient services, do not staple longitudinal tabs. Instead, secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.

#### B. Insulation Installation on Pipe Flanges:

1. Install preformed pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of cellular-glass block insulation of same thickness as pipe insulation.
4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch (25 mm), and seal joints with flashing sealant.

#### C. Insulation Installation on Pipe Fittings and Elbows:

1. Install preformed sections of same material as straight segments of pipe insulation when available. Secure according to manufacturer's written instructions.
2. When preformed sections of insulation are not available, install mitered sections of cellular-glass insulation. Secure insulation materials with wire or bands.

#### D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed sections of cellular-glass insulation to valve body.
2. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
3. Install insulation to flanges as specified for flange insulation application.

### 3.7 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

- A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- B. Insulation Installation on Pipe Flanges:
  1. Install pipe insulation to outer diameter of pipe flange.
  2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
  3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of sheet insulation of same thickness as pipe insulation.
  4. Secure insulation to flanges and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- C. Insulation Installation on Pipe Fittings and Elbows:
  1. Install mitered sections of pipe insulation.
  2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- D. Insulation Installation on Valves and Pipe Specialties:
  1. Install preformed valve covers manufactured of same material as pipe insulation when available.
  2. When preformed valve covers are not available, install cut sections of pipe and sheet insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
  3. Install insulation to flanges as specified for flange insulation application.
  4. Secure insulation to valves and specialties and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

### 3.8 INSTALLATION OF MINERAL-FIBER INSULATION

- A. Insulation Installation on Straight Pipes and Tubes:
  1. Secure each layer of preformed pipe insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
  2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
  3. For insulation with factory-applied jackets on above-ambient surfaces, secure laps with outward-clinched staples at **6 inches (150 mm)** o.c.

4. For insulation with factory-applied jackets on below-ambient surfaces, do not staple longitudinal tabs. Instead, secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.

B. Insulation Installation on Pipe Flanges:

1. Install preformed pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least **1 inch (25 mm)**, and seal joints with flashing sealant.

C. Insulation Installation on Pipe Fittings and Elbows:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.
3. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
4. Install insulation to flanges as specified for flange insulation application.

### 3.9 FIELD-APPLIED JACKET INSTALLATION

A. Where glass-cloth jackets are indicated, install directly over bare insulation or insulation with factory-applied jackets.

1. Draw jacket smooth and tight to surface with **2-inch (50-mm)** overlap at seams and joints.
2. Embed glass cloth between two **0.062-inch- (1.6-mm-)** thick coats of lagging adhesive.
3. Completely encapsulate insulation with coating, leaving no exposed insulation.

B. Where FSK jackets are indicated, install as follows:

1. Draw jacket material smooth and tight.
2. Install lap or joint strips with same material as jacket.
3. Secure jacket to insulation with manufacturer's recommended adhesive.
4. Install jacket with **1-1/2-inch (38-mm)** laps at longitudinal seams and **3-inch- (75-mm-)** wide joint strips at end joints.
5. Seal openings, punctures, and breaks in vapor-retarder jackets and exposed insulation with vapor-barrier mastic.



- C. Where PVC jackets are indicated, install with **1-inch (25-mm)** overlap at longitudinal seams and end joints; for horizontal applications. Seal with manufacturer's recommended adhesive.
  - 1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.
- D. Where metal jackets are indicated, install with **2-inch (50-mm)** overlap at longitudinal seams and end joints. Overlap longitudinal seams arranged to shed water. Seal end joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless-steel bands **12 inches (300 mm)** o.c. and at end joints.
- E. Where PVDC jackets are indicated, install as follows:
  - 1. Apply three separate wraps of filament tape per insulation section to secure pipe insulation to pipe prior to installation of PVDC jacket.
  - 2. Wrap factory-presizes jackets around individual pipe insulation sections with one end overlapping the previously installed sheet. Install presized jacket with an approximate overlap at butt joint of **2 inches (50 mm)** over the previous section. Adhere lap seal using adhesive or SSL, and then apply 1-1/4 circumferences of appropriate PVDC tape around overlapped butt joint.
  - 3. Continuous jacket can be spiral-wrapped around a length of pipe insulation. Apply adhesive or PVDC tape at overlapped spiral edge. When electing to use adhesives, refer to manufacturer's written instructions for application of adhesives along this spiral edge to maintain a permanent bond.
  - 4. Jacket can be wrapped in cigarette fashion along length of roll for insulation systems with an outer circumference of **33-1/2 inches (850 mm)** or less. The **33-1/2-inch- (850-mm-)** circumference limit allows for **2-inch- (50-mm-)** overlap seal. Using the length of roll allows for longer sections of jacket to be installed at one time. Use adhesive on the lap seal. Visually inspect lap seal for "fishmouthing," and use PVDC tape along lap seal to secure joint.
  - 5. Repair holes or tears in PVDC jacket by placing PVDC tape over the hole or tear and wrapping a minimum of 1-1/4 circumferences to avoid damage to tape edges.

### 3.10 FINISHES

- A. Pipe Insulation with ASJ, Glass-Cloth, or Other Paintable Jacket Material: Paint jacket with paint system identified below and as specified in Section 099113 "Exterior Painting" and Section 099123 "Interior Painting."
  - 1. Flat Acrylic Finish: **[Two] <Insert number>** finish coats over a primer that is compatible with jacket material and finish coat paint. Add fungicidal agent to render fabric mildew proof.
    - a. Finish Coat Material: Interior, flat, latex-emulsion size.
- B. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.
- C. Color: Final color as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.
- D. Do not field paint aluminum or stainless-steel jackets.

### 3.11 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Perform tests and inspections.
- C. Tests and Inspections:
  - 1. Inspect pipe, fittings, strainers, and valves, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to three locations of straight pipe, three locations of threaded fittings, three locations of welded fittings, two locations of threaded strainers, two locations of welded strainers, three locations of threaded valves, and three locations of flanged valves for each pipe service defined in the "Piping Insulation Schedule, General" Article.
- D. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

### 3.12 PIPING INSULATION SCHEDULE, GENERAL

- A. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.
- B. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:
  - 1. Drainage piping located in crawl spaces.
  - 2. Underground piping.
  - 3. Chrome-plated pipes and fittings unless there is a potential for personnel injury.

### 3.13 INDOOR PIPING INSULATION SCHEDULE

- A. Condensate and Equipment Drain Water below 60 Deg F (16 Deg C):
  - 1. All Pipe Sizes: Insulation shall be the following:
    - a. Flexible Elastomeric: 3/4 inch (19 mm) thick.
- B. Chilled Water and Brine, above 40 Deg F (5 Deg C):
  - 1. NPS 12 (DN 300) and Smaller: Insulation shall be the following:
    - a. Cellular Glass: 2 inches (50 mm) thick.
- C. Refrigerant Suction and Hot-Gas Piping:
  - 1. All Pipe Sizes: Insulation shall be the following:
    - a. Flexible Elastomeric: 1 inch (25 mm) thick.
- D. Refrigerant Suction and Hot-Gas Flexible Tubing:

1. All Pipe Sizes: Insulation shall be the following:
  - a. Flexible Elastomeric: 1 inch (25 mm) thick.

3.14 INDOOR, FIELD-APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Piping, Concealed:
  1. None.
- D. Piping, Exposed:
  1. PVC: 20 mils (0.5 mm) thick.

END OF SECTION 230719

## **SECTION 23 21 13 – HYDRONIC PIPING**

### **PART 1 - GENERAL**

#### **1.1 SUMMARY**

- A. Section includes pipe and fitting materials and joining methods for the following:

1. Chilled-water piping.
2. Air-vent piping.
3. Safety-valve-inlet and -outlet piping.

#### **1.2 ACTION SUBMITTALS**

- A. Delegated-Design Submittal:

1. Design calculations and detailed fabrication and assembly of pipe anchors and alignment guides, hangers and supports for multiple pipes, expansion joints and loops, and attachments of the same to the building structure.
2. Locations of pipe anchors and alignment guides and expansion joints and loops.
3. Locations of and details for penetrations, including sleeves and sleeve seals for exterior walls, floors, basement, and foundation walls.
4. Locations of and details for penetration and firestopping for fire- and smoke-rated wall and floor and ceiling assemblies.

#### **1.3 INFORMATIONAL SUBMITTALS**

- A. Field quality-control reports.

#### **1.4 QUALITY ASSURANCE**

- A. ASME Compliance: Comply with ASME B31.9, "Building Services Piping," for materials, products, and installation.

### **PART 2 - PRODUCTS**

#### **2.1 PERFORMANCE REQUIREMENTS**

- A. Hydronic piping components and installation shall be capable of withstanding the following minimum working pressure and temperature unless otherwise indicated:

1. Chilled-Water Piping: 150 psig at 200 deg F.
2. Air-Vent Piping: 200 deg F.

3. Safety-Valve-Inlet and -Outlet Piping: Equal to the pressure of the piping system to which it is attached.

## 2.2 STEEL PIPE AND FITTINGS

- A. Steel Pipe: ASTM A 53/A 53M, black steel with plain ends; welded and seamless, Grade B, and wall thickness as indicated in "Piping Applications" Article.
- B. Cast-Iron Threaded Fittings: ASME B16.4; Classes 125 and 250 as indicated in "Piping Applications" Article.
- C. Malleable-Iron Threaded Fittings: ASME B16.3, Classes 150 and 300 as indicated in "Piping Applications" Article.
- D. Malleable-Iron Unions: ASME B16.39; Classes 150, 250, and 300 as indicated in "Piping Applications" Article.
- E. Cast-Iron Pipe Flanges and Flanged Fittings: ASME B16.1, Classes 25, 125, and 250; raised ground face, and bolt holes spot faced as indicated in "Piping Applications" Article.
- F. Wrought Cast- and Forged-Steel Flanges and Flanged Fittings: ASME B16.5, including bolts, nuts, and gaskets of the following material group, end connections, and facings:
  1. Material Group: 1.1.
  2. End Connections: Butt welding.
  3. Facings: Raised face.

## 2.3 JOINING MATERIALS

- A. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions of piping system contents.
  1. ASME B16.21, nonmetallic, flat, asbestos free, 1/8-inch maximum thickness unless otherwise indicated.
    - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
    - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.
- B. Flange Bolts and Nuts: ASME B18.2.1, carbon steel, unless otherwise indicated.
- C. Welding Filler Metals: Comply with AWS D10.12M/D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.
- D. Solvent Cements for Joining Plastic Piping:
  1. CPVC Piping: ASTM F 493.
    - a. CPVC solvent cement shall have a VOC content of 490 g/L or less.
    - b. Adhesive primer shall have a VOC content of 550 g/L or less.

- c. Solvent cement and adhesive primer shall comply with the testing and product requirements of the California Department of Public Health's (formerly, the California Health Services') "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
  - 2. PVC Piping: ASTM D 2564. Include primer according to ASTM F 656.
    - a. PVC solvent cement shall have a VOC content of 510 g/L or less.
    - b. Adhesive primer shall have a VOC content of 550 g/L or less.
    - c. Solvent cement and adhesive primer shall comply with the testing and product requirements of the California Department of Public Health's (formerly, the California Health Services') "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- E. Gasket Material: Thickness, material, and type suitable for fluid to be handled and working temperatures and pressures.

## 2.4 DIELECTRIC FITTINGS

- A. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.
- B. Dielectric Unions:
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. WATTS; A Watts Water Technologies Company.
    - b. Wilkins.
    - c. Zurn Industries, LLC.
    - d. Or Prior Approved Equal
  - 2. Description:
    - a. Standard: ASSE 1079.
    - b. Pressure Rating: 150 psig.
    - c. End Connections: Solder-joint copper alloy and threaded ferrous.

## PART 3 - EXECUTION

### 3.1 PIPING APPLICATIONS

- A. Chilled-water piping, aboveground, NPS 2 and smaller shall be any of the following:
  - 1. Schedule 40 steel pipe; Class 150, malleable-iron fittings; cast-iron flanges and flange fittings; and threaded joints.

- B. Chilled-water piping, aboveground, NPS 2-1/2 and larger, shall be any of the following:
  - 1. Schedule 40 steel pipe; grooved, mechanical joint coupling and fittings; and grooved, mechanical joints.
- C. Blowdown-Drain Piping: Same materials and joining methods as for piping specified for the service in which blowdown drain is installed.
- D. Air-Vent Piping:
  - 1. Inlet: Same as service where installed with metal-to-plastic transition fittings for plastic piping systems according to piping manufacturer's written instructions.
  - 2. Outlet: Type K, annealed-temper copper tubing with soldered or flared joints.
- E. Safety-Valve-Inlet and -Outlet Piping for Hot-Water Piping: Same materials and joining methods as for piping specified for the service in which safety valve is installed with metal-to-plastic transition fittings for plastic piping systems according to piping manufacturer's written instructions.

### 3.2 PIPING INSTALLATIONS

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- E. Install piping to permit valve servicing.
- F. Install piping at indicated slopes.
- G. Install piping free of sags and bends.
- H. Install fittings for changes in direction and branch connections.
- I. Install piping to allow application of insulation.
- J. Select system components with pressure rating equal to or greater than system operating pressure.
- K. Install groups of pipes parallel to each other, spaced to permit applying insulation and servicing of valves.
- L. Install drains, consisting of a tee fitting, NPS 3/4 ball valve, and short NPS 3/4 threaded nipple with cap, at low points in piping system mains and elsewhere as required for system drainage.

- M. Install piping at a uniform grade of 0.2 percent upward in direction of flow.
- N. Reduce pipe sizes using eccentric reducer fitting installed with level side up.
- O. Install branch connections to mains using [**mechanically formed**] tee fittings in main pipe, with the branch connected to the bottom of the main pipe. For up-feed risers, connect the branch to the top of the main pipe.
- P. Install valves according to Section 230523.11 "Globe Valves for HVAC Piping," Section 230523.12 "Ball Valves for HVAC Piping," Section 230523.13 "Butterfly Valves for HVAC Piping," Section 230523.14 "Check Valves for HVAC Piping," and Section 230523.15 "Gate Valves for HVAC Piping."
- Q. Install unions in piping, [**NPS 2**] and smaller, adjacent to valves, at final connections of equipment, and elsewhere as indicated.
- R. Install flanges in piping, [**NPS 2-1/2**] and larger, at final connections of equipment and elsewhere as indicated.
- S. Install shutoff valve immediately upstream of each dielectric fitting.
- T. Comply with requirements in Section 230516 "Expansion Fittings and Loops for HVAC Piping" for installation of expansion loops, expansion joints, anchors, and pipe alignment guides.
- U. Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for identifying piping.
- V. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 230517 "Sleeves and Sleeve Seals for HVAC Piping."
- W. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 230517 "Sleeves and Sleeve Seals for HVAC Piping."
- X. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 230518 "Escutcheons for HVAC Piping."

### 3.3 DIELECTRIC FITTING INSTALLATION

- A. Install dielectric fittings in piping at connections of dissimilar metal piping and tubing.
- B. Dielectric Fittings for NPS 2 and Smaller: Use dielectric unions.
- C. Dielectric Fittings for NPS 2-1/2 to NPS 4: Use dielectric flanges.

### 3.4 HANGERS AND SUPPORTS

- A. Comply with requirements in Section 230529 "Hangers and Supports for HVAC Piping and Equipment" for hanger, support, and anchor devices. Comply with the following requirements for maximum spacing of supports.



B. Install the following pipe attachments:

1. Adjustable steel clevis hangers for individual horizontal piping less than 20 feet long.
2. Adjustable roller hangers and spring hangers for individual horizontal piping 20 feet or longer.
3. Pipe Roller: MSS SP-58, Type 44 for multiple horizontal piping 20 feet or longer, supported on a trapeze.
4. Spring hangers to support vertical runs.
5. Provide copper-clad hangers and supports for hangers and supports in direct contact with copper pipe.
6. On plastic pipe, install pads or cushions on bearing surfaces to prevent hanger from scratching pipe.

C. Install hangers for steel piping with the following maximum spacing and minimum rod sizes:

1. NPS 3/4: Maximum span, 7 feet.
2. NPS 1: Maximum span, 7 feet.
3. NPS 1-1/2: Maximum span, 9 feet.
4. NPS 2: Maximum span, 10 feet.
5. NPS 2-1/2: Maximum span, 11 feet.
6. NPS 3 and Larger: Maximum span, 12 feet.

D. Install hangers for drawn-temper copper piping with the following maximum spacing and minimum rod sizes:

1. NPS 3/4: Maximum span, 5 feet; minimum rod size, 1/4 inch.
2. NPS 1: Maximum span, 6 feet; minimum rod size, 1/4 inch.
3. NPS 1-1/4: Maximum span, 7 feet; minimum rod size, 3/8 inch.
4. NPS 1-1/2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
5. NPS 2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
6. NPS 2-1/2: Maximum span, 9 feet; minimum rod size, 3/8 inch.
7. NPS 3 and Larger: Maximum span, 10 feet; minimum rod size, 3/8 inch.

E. Plastic Piping Hanger Spacing: Space hangers according to pipe manufacturer's written instructions for service conditions. Avoid point loading. Space and install hangers with the fewest practical rigid anchor points.

F. Support vertical runs at roof, at each floor, and at 10-foot intervals between floors.

### 3.5 PIPE JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- C. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.

- D. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8/A5.8M.
- E. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
  - 1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
  - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- F. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.

### 3.6 TERMINAL EQUIPMENT CONNECTIONS

- A. Sizes for supply and return piping connections shall be the same as or larger than equipment connections.
- B. Install control valves in accessible locations close to connected equipment.
- C. Install bypass piping with globe valve around control valve. If parallel control valves are installed, only one bypass is required.
- D. Install ports for pressure gages and thermometers at coil inlet and outlet connections. Comply with requirements in Section 230519 "Meters and Gages for HVAC Piping."

### 3.7 FIELD QUALITY CONTROL

- A. Prepare hydronic piping according to ASME B31.9 and as follows:
  - 1. Leave joints, including welds, uninsulated and exposed for examination during test.
  - 2. Provide temporary restraints for expansion joints that cannot sustain reactions due to test pressure. If temporary restraints are impractical, isolate expansion joints from testing.
  - 3. Flush hydronic piping systems with clean water; then remove and clean or replace strainer screens.
  - 4. Isolate equipment from piping. If a valve is used to isolate equipment, its closure shall be capable of sealing against test pressure without damage to valve. Install blinds in flanged joints to isolate equipment.
  - 5. Install safety valve, set at a pressure no more than one-third higher than test pressure, to protect against damage by expanding liquid or other source of overpressure during test.
- B. Perform the following tests on hydronic piping:
  - 1. Use ambient temperature water as a testing medium unless there is risk of damage due to freezing. Another liquid that is safe for workers and compatible with piping may be used.
  - 2. While filling system, use vents installed at high points of system to release air. Use drains installed at low points for complete draining of test liquid.

3. Isolate expansion tanks and determine that hydronic system is full of water.
  4. Subject piping system to hydrostatic test pressure that is not less than 1.5 times the system's working pressure. Test pressure shall not exceed maximum pressure for any vessel, pump, valve, or other component in system under test. Verify that stress due to pressure at bottom of vertical runs does not exceed 90 percent of specified minimum yield strength or 1.7 times the "SE" value in Appendix A in ASME B31.9, "Building Services Piping."
  5. After hydrostatic test pressure has been applied for at least 10 minutes, examine piping, joints, and connections for leakage. Eliminate leaks by tightening, repairing, or replacing components, and repeat hydrostatic test until there are no leaks.
  6. Prepare written report of testing.
- C. Perform the following before operating the system:
1. Open manual valves fully.
  2. Inspect pumps for proper rotation.
  3. Set makeup pressure-reducing valves for required system pressure.
  4. Inspect air vents at high points of system and determine if all are installed and operating freely (automatic type), or bleed air completely (manual type).
  5. Set temperature controls so all coils are calling for full flow.
  6. Inspect and set operating temperatures of hydronic equipment, such as boilers, chillers, cooling towers, to specified values.
  7. Verify lubrication of motors and bearings.

END OF SECTION 23 21 13

## **SECTION 23 21 14 – HVAC CONDENSATE PIPING**

### **PART 1 - GENERAL**

#### **1.1 SUMMARY**

- A. Section includes pipe and fitting materials and joining methods for the following:
  - 1. Condensate-drain piping.

#### **1.2 ACTION SUBMITTALS**

- A. Product Data: For each type of the following:
  - 1. Copper Tube.
- B. Delegated-Design Submittal:
  - 1. Design calculations and detailed fabrication and assembly of pipe anchors and alignment guides, hangers and supports for multiple pipes, expansion joints and loops, and attachments of the same to the building structure.
  - 2. Locations of pipe anchors and alignment guides and expansion joints and loops.
  - 3. Locations of and details for penetrations, including sleeves and sleeve seals for exterior walls, floors, basement, and foundation walls.
  - 4. Locations of and details for penetration and firestopping for fire- and smoke-rated wall and floor and ceiling assemblies.

#### **1.3 INFORMATIONAL SUBMITTALS**

- A. Field quality-control reports.

#### **1.4 QUALITY ASSURANCE**

- A. ASME Compliance: Comply with ASME B31.9, "Building Services Piping," for materials, products, and installation.

### **PART 2 - PRODUCTS**

#### **2.1 PERFORMANCE REQUIREMENTS**

- A. Hydronic piping components and installation shall be capable of withstanding the following minimum working pressure and temperature unless otherwise indicated:
  - 1. Condensate-Drain Piping: 140 deg F.

2.2 COPPER TUBE AND FITTINGS

- A. DWV Copper Tubing: ASTM B 306, Type DWV.

2.3 JOINING MATERIALS

- A. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- B. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys for joining copper with copper; or BAg-1, silver alloy for joining copper with bronze or steel.
- C. Gasket Material: Thickness, material, and type suitable for fluid to be handled and working temperatures and pressures.

2.4 TRANSITION FITTINGS

- A. Plastic-to-Metal Transition Fittings:
  - 1. One-piece fitting with one threaded brass or copper insert and one solvent-cement-joint end of material and wall thickness to match plastic pipe material.
- B. Plastic-to-Metal Transition Unions:
  - 1. Brass or copper end, solvent-cement-joint end of material and wall thickness to match plastic pipe material, rubber gasket, and threaded union.

2.5 DIELECTRIC FITTINGS

- A. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.

**PART 3 - EXECUTION**

3.1 PIPING APPLICATIONS

- A. Condensate-Drain Piping: Type DWV, drawn-temper copper tubing, wrought-copper fittings, and soldered joints.

3.2 PIPING INSTALLATIONS

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.

- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- E. Install piping to permit valve servicing.
- F. Install piping at indicated slopes.
- G. Install piping free of sags and bends.
- H. Install fittings for changes in direction and branch connections.
- I. Install piping to allow application of insulation.
- J. Select system components with pressure rating equal to or greater than system operating pressure.
- K. Install groups of pipes parallel to each other, spaced to permit applying insulation and servicing of valves.
- L. Reduce pipe sizes using eccentric reducer fitting installed with level side up.
- M. Install shutoff valve immediately upstream of each dielectric fitting.
- N. Comply with requirements specified for identifying piping.

### 3.3 DIELECTRIC FITTING INSTALLATION

- A. Install dielectric fittings in piping at connections of dissimilar metal piping and tubing.
- B. Dielectric Fittings for NPS 2 and Smaller: Use dielectric nipples.
- C. Dielectric Fittings for NPS 2-1/2 to NPS 4: Use dielectric nipples.

### 3.4 HANGERS AND SUPPORTS

- A. Comply with requirements specified for hanger, support, and anchor devices. Comply with the following requirements for maximum spacing of supports.
- B. Install the following pipe attachments:
  - 1. Adjustable steel clevis hangers for individual horizontal piping less than 20 feet long.
  - 2. Adjustable roller hangers and spring hangers for individual horizontal piping 20 feet or longer.
  - 3. Pipe Roller: MSS SP-58, Type 44 for multiple horizontal piping 20 feet or longer, supported on a trapeze.
  - 4. Spring hangers to support vertical runs.
  - 5. Provide copper-clad hangers and supports for hangers and supports in direct contact with copper pipe.

C. Install hangers for copper piping with the following maximum spacing and minimum rod sizes:

1. NPS 3/4: Maximum span, 5 feet; minimum rod size, 1/4 inch.
2. NPS 1: Maximum span, 6 feet; minimum rod size, 1/4 inch.
3. NPS 1-1/4: Maximum span, 7 feet; minimum rod size, 3/8 inch.
4. NPS 1-1/2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
5. NPS 2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
6. NPS 2-1/2: Maximum span, 9 feet; minimum rod size, 3/8 inch.
7. NPS 3 and Larger: Maximum span, 10 feet; minimum rod size, 3/8 inch.

D. Support vertical runs at roof, at each floor, and at 10-foot intervals between floors.

### 3.5 PIPE JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- C. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.
- D. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8/A5.8M.
- E. Mechanically Formed, Copper-Tube-Outlet Joints: Use manufacturer-recommended tool and procedure, and brazed joints.

END OF SECTION 23 21 14

## **SECTION 23 31 13 – METAL DUCTS**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:
  - 1. Single-wall rectangular ducts and fittings.
  - 2. Single-wall round ducts and fittings.
  - 3. Sheet metal materials.
  - 4. Sealants and gaskets.
  - 5. Hangers and supports.

#### **1.3 PERFORMANCE REQUIREMENTS**

- A. Delegated Duct Design: Duct construction, including sheet metal thicknesses, seam and joint construction, reinforcements, and hangers and supports, shall comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" and performance requirements and design criteria indicated in "Duct Schedule" Article.
- B. Structural Performance: Duct hangers and supports shall withstand the effects of gravity loads and stresses within limits and under conditions described in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"
- C. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.

#### **1.4 ACTION SUBMITTALS**

- A. Product Data: For each type of the following products:
  - 1. Adhesives.
  - 2. Sealants and gaskets.

### **PART 2 - PRODUCTS**

#### **2.1 SINGLE-WALL RECTANGULAR DUCTS AND FITTINGS**

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" based on indicated static-pressure class unless otherwise indicated.



- B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-1, "Rectangular Duct/Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-2, "Rectangular Duct/Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- D. Elbows, Transitions, Offsets, Branch Connections, and Other Duct Construction: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 4, "Fittings and Other Construction," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

## 2.2 SINGLE-WALL ROUND DUCTS AND FITTINGS

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 3, "Round, Oval, and Flexible Duct," based on indicated static-pressure class unless otherwise indicated.
- B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-1, "Round Duct Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
  - 1. Transverse Joints in Ducts Larger Than 60 Inches in Diameter: Flanged.
- C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-2, "Round Duct Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
  - 1. Fabricate round ducts larger than 90 inches in diameter with butt-welded longitudinal seams.
  - 2. Fabricate flat-oval ducts larger than 72 inches in width (major dimension) with butt-welded longitudinal seams.
- D. Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

## 2.3 SHEET METAL MATERIALS

- A. General Material Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction

methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

- B. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.
  - 1. Duct Galvanized Coating Designation: G90.
  - 2. Finishes for Surfaces Exposed to View: Mill phosphatized.
- C. Galvanized sheet metal for rectangular and round ductwork shall have a minimum gauge of 26.

## 2.4 DUCT LINER

- A. Fibrous-Glass Duct Liner: Comply with ASTM C 1071, NFPA 90A, or NFPA 90B; and with NAIMA AH124, "Fibrous Glass Duct Liner Standard."
  - 1. Manufacturers shall be as follows:
    - a. Certaineed
    - b. Owens Corning
    - c. Johns Manville
    - d. Knauf
  - 2. Maximum Thermal Conductivity:
    - a. Type I, Flexible: 0.27 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
  - 3. Antimicrobial Erosion-Resistant Coating: Apply to the surface of the liner that will form the interior surface of the duct to act as a moisture repellent and erosion-resistant coating. Antimicrobial compound shall be tested for efficacy by an NRTL and registered by the EPA for use in HVAC systems.
  - 4. Water-Based Liner Adhesive: Comply with NFPA 90A or NFPA 90B and with ASTM C 916.
    - a. For indoor applications, adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- B. Insulation Pins and Washers:
  - 1. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
  - 2. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick galvanized steel; with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.
- C. Shop Application of Duct Liner: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 7-11, "Flexible Duct Liner Installation."
  - 1. Adhere a single layer of indicated thickness of duct liner with at least 90 percent adhesive coverage at liner contact surface area. Attaining indicated thickness with multiple layers of duct liner is prohibited.
  - 2. Apply adhesive to transverse edges of liner facing upstream that do not receive metal nosing.

3. Butt transverse joints without gaps, and coat joint with adhesive.
4. Fold and compress liner in corners of rectangular ducts or cut and fit to ensure butted-edge overlapping.
5. Do not apply liner in rectangular ducts with longitudinal joints, except at corners of ducts, unless duct size and dimensions of standard liner make longitudinal joints necessary.
6. Apply adhesive coating on longitudinal seams in ducts with air velocity of 2500 fpm.
7. Secure liner with mechanical fasteners 4 inches from corners and at intervals not exceeding 12 inches transversely; at 3 inches from transverse joints and at intervals not exceeding 18 inches longitudinally.
8. Secure transversely oriented liner edges facing the airstream with metal nosings that have either channel or "Z" profiles or are integrally formed from duct wall. Fabricate edge facings at the following locations:
  - a. Fan discharges.
  - b. Intervals of lined duct preceding unlined duct.
  - c. Upstream edges of transverse joints in ducts where air velocities are higher than 2500 fpm or where indicated.
9. Secure insulation between perforated sheet metal inner duct of same thickness as specified for outer shell. Use mechanical fasteners that maintain inner duct at uniform distance from outer shell without compressing insulation.
  - a. Sheet Metal Inner Duct Perforations: 3/32-inch diameter, with an overall open area of 23 percent.
10. Terminate inner ducts with buildouts attached to fire-damper sleeves, dampers, turning vane assemblies, or other devices. Fabricated buildouts (metal hat sections) or other buildout means are optional; when used, secure buildouts to duct walls with bolts, screws, rivets, or welds.

## 2.5 SEALANT AND GASKETS

- A. General Sealant and Gasket Requirements: Surface-burning characteristics for sealants and gaskets shall be a maximum flame-spread index of 25 and a maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.
- B. Two-Part Tape Sealing System:
  1. Tape: Woven cotton fiber impregnated with mineral gypsum and modified acrylic/silicone activator to react exothermically with tape to form hard, durable, airtight seal.
  2. Tape Width: 4 inches.
  3. Sealant: Modified styrene acrylic.
  4. Water resistant.
  5. Mold and mildew resistant.
  6. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
  7. Service: Indoor and outdoor.
  8. Service Temperature: Minus 40 to plus 200 deg F.
  9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum.
  10. For indoor applications, sealant shall have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  11. Sealant shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

- C. Water-Based Joint and Seam Sealant:
  - 1. Application Method: Brush on.
  - 2. Solids Content: Minimum 65 percent.
  - 3. Shore A Hardness: Minimum 20.
  - 4. Water resistant.
  - 5. Mold and mildew resistant.
  - 6. VOC: Maximum 75 g/L (less water).
  - 7. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
  - 8. Service: Indoor or outdoor.
  - 9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.
- D. Solvent-Based Joint and Seam Sealant:
  - 1. Application Method: Brush on.
  - 2. Base: Synthetic rubber resin.
  - 3. Solvent: Toluene and heptane.
  - 4. Solids Content: Minimum 60 percent.
  - 5. Shore A Hardness: Minimum 60.
  - 6. Water resistant.
  - 7. Mold and mildew resistant.
  - 8. Service: Indoor or outdoor.
  - 9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.
- E. Flanged Joint Sealant: Comply with ASTM C 920.
  - 1. General: Single-component, acid-curing, silicone, elastomeric.
  - 2. Type: S.
  - 3. Grade: NS.
  - 4. Class: 25.
  - 5. Use: O.
- F. Flange Gaskets: Butyl rubber, neoprene, or EPDM polymer with polyisobutylene plasticizer.
- G. Round Duct Joint O-Ring Seals:
  - 1. Seal shall provide maximum 3 cfm/100 sq. ft. at 1-inch wg and shall be rated for 10-inch wg static-pressure class, positive or negative.
  - 2. EPDM O-ring to seal in concave bead in coupling or fitting spigot.
  - 3. Double-lipped, EPDM O-ring seal, mechanically fastened to factory-fabricated couplings and fitting spigots.

## 2.6 HANGERS AND SUPPORTS

- A. Hanger Rods for Noncorrosive Environments: Cadmium-plated steel rods and nuts.
- B. Hanger Rods for Corrosive Environments: Electrogalvanized, all-thread rods or galvanized rods with threads painted with zinc-chromate primer after installation.
- C. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct."
- D. Steel Cables for Galvanized-Steel Ducts: Galvanized steel complying with ASTM A 603.

- E. Steel Cables for Stainless-Steel Ducts: Stainless steel complying with ASTM A 492.
- F. Steel Cable End Connections: Cadmium-plated steel assemblies with brackets, swivel, and bolts designed for duct hanger service; with an automatic-locking and clamping device.
- G. Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.
- H. Trapeze and Riser Supports:
  - 1. Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates.
  - 2. Supports for Stainless-Steel Ducts: Stainless-steel shapes and plates.
  - 3. Supports for Aluminum Ducts: Aluminum or galvanized steel coated with zinc chromate.

### **PART 3 - EXECUTION**

#### **3.1 DUCT INSTALLATION**

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of duct system. Indicated duct locations, configurations, and arrangements were used to size ducts and calculate friction loss for air-handling equipment sizing and for other design considerations. Install duct systems as indicated unless deviations to layout are approved on Shop Drawings and Coordination Drawings.
- B. Install ducts according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" unless otherwise indicated.
- C. Install round ducts in maximum practical lengths.
- D. Install ducts with fewest possible joints.
- E. Install factory- or shop-fabricated fittings for changes in direction, size, and shape and for branch connections.
- F. Unless otherwise indicated, install ducts vertically and horizontally, and parallel and perpendicular to building lines.
- G. Install ducts close to walls, overhead construction, columns, and other structural and permanent enclosure elements of building.
- H. Install ducts with a clearance of 1 inch, plus allowance for insulation thickness.
- I. Route ducts to avoid passing through transformer vaults and electrical equipment rooms and enclosures.
- J. Where ducts pass through non-fire-rated interior partitions and exterior walls and are exposed to view, cover the opening between the partition and duct or duct insulation with sheet metal flanges of same metal thickness as the duct. Overlap openings on four sides by at least 1-1/2 inches.
- K. Where ducts pass through fire-rated interior partitions and exterior walls, install fire dampers. Comply with requirements as specified for fire and smoke dampers.

- L. Protect duct interiors from moisture, construction debris and dust, and other foreign materials.

### 3.2 INSTALLATION OF EXPOSED DUCTWORK

- A. Protect ducts exposed in finished spaces from being dented, scratched, or damaged.
- B. Trim duct sealants flush with metal. Create a smooth and uniform exposed bead. Do not use two-part tape sealing system.
- C. Grind welds to provide smooth surface free of burrs, sharp edges, and weld splatter. When welding stainless steel with a No. 3 or 4 finish, grind the welds flush, polish the exposed welds, and treat the welds to remove discoloration caused by welding.
- D. Maintain consistency, symmetry, and uniformity in the arrangement and fabrication of fittings, hangers and supports, duct accessories, and air outlets.
- E. Repair or replace damaged sections and finished work that does not comply with these requirements.

### 3.3 DUCT SEALING

- A. Seal ducts for duct static-pressure, seal classes, and leakage classes specified in "Duct Schedule" Article."
- B. If ducts are not listed in the "Duct Schedule" Article then seal unlisted ducts to the following seal classes according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible":
  - 1. Ducts:
    - a. Pressure Class: Positive 2-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 6.
    - d. SMACNA Leakage Class for Round and Flat Oval: 3.

### 3.4 HANGER AND SUPPORT INSTALLATION

- A. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 5, "Hangers and Supports."
- B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
  - 1. Where practical, install concrete inserts before placing concrete.
  - 2. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
  - 3. Use powder-actuated concrete fasteners for standard-weight aggregate concretes or for slabs more than 4 inches thick.
  - 4. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes or for slabs less than 4 inches thick.
- C. Hanger Spacing: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct," for maximum hanger spacing; install hangers and supports within 24 inches of each elbow and within 48 inches of each branch intersection.

- D. Hangers Exposed to View: Threaded rod and angle or channel supports.
- E. Support vertical ducts with steel angles or channel secured to the sides of the duct with welds, bolts, sheet metal screws, or blind rivets; support at each floor and at a maximum intervals of 16 feet.
- F. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

### 3.5 CONNECTIONS

- A. Make connections to equipment with flexible connectors.
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for branch, outlet and inlet, and terminal unit connections.

### 3.6 PAINTING

- A. Paint interior of metal ducts that are visible through registers and grilles and that do not have duct liner. Apply one coat of flat, black, latex paint over a compatible galvanized-steel primer.

### 3.7 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Leakage Tests:
  - 1. Comply with SMACNA's "HVAC Air Duct Leakage Test Manual." Submit a test report for each test.
  - 2. Test the following systems:
    - a. Ducts with a Pressure Class Higher Than **3-Inch wg**:
      - 1) Test representative duct sections totaling no less than **25 percent** of total installed duct area for each designated pressure class.
    - b. Exhaust Ducts with a Pressure Class of **2-Inch wg or Higher**:
      - 1) Test representative duct sections totaling no less than **50 percent** of total installed duct area for each designated pressure class.
    - c. Outdoor Air Ducts with a Pressure Class of **2-Inch wg or Higher**:
      - 1) Test representative duct sections totaling no less than **50 percent** of total installed duct area for each designated pressure class.
  - 3. Disassemble, reassemble, and seal segments of systems to accommodate leakage testing and for compliance with test requirements.
  - 4. Test for leaks before applying external insulation.
  - 5. Conduct tests at static pressures equal to maximum design pressure of system or section being tested. If static-pressure classes are not indicated, test system at maximum system design pressure. Do not pressurize systems above maximum design operating pressure.
  - 6. Give seven days' advance notice for testing.

C. Duct System Cleanliness Tests:

1. Visually inspect duct system to ensure that no visible contaminants are present.
2. Test sections of metal duct system, chosen randomly by Owner, for cleanliness according to "Vacuum Test" in NADCA ACR, "Assessment, Cleaning and Restoration of HVAC Systems."
  - a. Acceptable Cleanliness Level: Net weight of debris collected on the filter media shall not exceed 0.75 mg/100 sq. cm.

D. Duct system will be considered defective if it does not pass tests and inspections.

E. Prepare test and inspection reports.

3.8 DUCT CLEANING

A. Clean **[new]** **[and]** **[existing]** duct system(s) before testing, adjusting, and balancing.

B. Use service openings for entry and inspection.

1. Create new openings and install access panels appropriate for duct static-pressure class if required for cleaning access. Provide insulated panels for insulated or lined duct. Patch insulation and liner as recommended by duct liner manufacturer.
2. Disconnect and reconnect flexible ducts as needed for cleaning and inspection.
3. Remove and reinstall ceiling to gain access during the cleaning process.

C. Particulate Collection and Odor Control:

1. When venting vacuuming system inside the building, use HEPA filtration with 99.97 percent collection efficiency for 0.3-micron-size (or larger) particles.
2. When venting vacuuming system to outdoors, use filter to collect debris removed from HVAC system, and locate exhaust downwind and away from air intakes and other points of entry into building.

D. Clean the following components by removing surface contaminants and deposits:

1. Air outlets and inlets (registers, grilles, and diffusers).
2. Supply, return, and exhaust fans including fan housings, plenums (except ceiling supply and return plenums), scrolls, blades or vanes, shafts, baffles, dampers, and drive assemblies.
3. Air-handling unit internal surfaces and components including mixing box, coil section, air wash systems, spray eliminators, condensate drain pans, humidifiers and dehumidifiers, filters and filter sections, and condensate collectors and drains.
4. Coils and related components.
5. Return-air ducts, dampers, actuators, and turning vanes except in ceiling plenums and mechanical equipment rooms.
6. Supply-air ducts, dampers, actuators, and turning vanes.
7. Dedicated exhaust and ventilation components and makeup air systems.

E. Mechanical Cleaning Methodology:



1. Clean metal duct systems using mechanical cleaning methods that extract contaminants from within duct systems and remove contaminants from building.
2. Use vacuum-collection devices that are operated continuously during cleaning. Connect vacuum device to downstream end of duct sections so areas being cleaned are under negative pressure.
3. Use mechanical agitation to dislodge debris adhered to interior duct surfaces without damaging integrity of metal ducts, duct liner, or duct accessories.
4. Clean fibrous-glass duct liner with HEPA vacuuming equipment; do not permit duct liner to get wet. Replace fibrous-glass duct liner that is damaged, deteriorated, or delaminated or that has friable material, mold, or fungus growth.
5. Clean coils and coil drain pans according to NADCA 1992. Keep drain pan operational. Rinse coils with clean water to remove latent residues and cleaning materials; comb and straighten fins.
6. Provide drainage and cleanup for wash-down procedures.
7. Antimicrobial Agents and Coatings: Apply EPA-registered antimicrobial agents if fungus is present. Apply antimicrobial agents according to manufacturer's written instructions after removal of surface deposits and debris.

### 3.9 START UP

- A. Air Balance: Comply with requirements as specified.

### 3.10 DUCT SCHEDULE

- A. Supply Ducts:
  1. Ducts Connected to Constant-Volume Units, VRF Outside Air Units and RTUs:
    - a. Pressure Class: Positive 2-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 6.
    - d. SMACNA Leakage Class for Round and Flat Oval: 3.
- B. Return Ducts:
  1. Ducts Connected to Constant-Volume Units, VRF Outside Air Units and RTUs:
    - a. Pressure Class: Positive or negative 2-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 6.
    - d. SMACNA Leakage Class for Round and Flat Oval: 3.
- C. Exhaust Ducts:
  1. Ducts Connected to Fans Exhausting (ASHRAE 62.1, Class 1 and 2) Air:
    - a. Pressure Class: Negative 2-inch wg.
    - b. Minimum SMACNA Seal Class: A if negative pressure, and A if positive pressure.
    - c. SMACNA Leakage Class for Rectangular: 12.
    - d. SMACNA Leakage Class for Round and Flat Oval: 6.
- D. Outdoor-Air (Not Filtered, Heated, or Cooled) Ducts:
  1. Ducts Connected to Constant-Volume Units, VRF Outside Air Units:
    - a. Pressure Class: Positive or negative 2-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 6.
    - d. SMACNA Leakage Class for Round and Flat Oval: 3.

END OF SECTION 23 31 13

## **SECTION 23 33 00 – AIR DUCT ACCESSORIES**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:
  - 1. Manual volume dampers.
  - 2. Spin Collars.
  - 3. Fire dampers.
  - 4. Turning vanes.
  - 5. Duct-mounted access doors.
  - 6. Duct Access Panel Assemblies.
  - 7. Flexible connectors.
  - 8. Flexible ducts.
  - 9. Duct accessory hardware.

#### **1.3 CLOSEOUT SUBMITTALS**

- A. Operation and Maintenance Data: For air duct accessories to include in operation and maintenance manuals.

### **PART 2 - PRODUCTS**

#### **2.1 ASSEMBLY DESCRIPTION**

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

#### **2.2 MATERIALS**

- A. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.
  - 1. Galvanized Coating Designation: G90.
  - 2. Exposed-Surface Finish: Mill phosphatized.

- B. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless-steel ducts.
- C. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

## 2.3 MANUAL VOLUME DAMPERS

- A. Low-Leakage, Steel, Manual Volume Dampers:
  - 1. Manufacturers:
    - a. Greenheck.
    - b. Dace Mfg.
    - c. Nailor Industries Inc.
    - d. Pottorff.
    - e. Ruskin Company.
  - 2. Comply with AMCA 500-D testing for damper rating.
  - 3. Low-leakage rating, with linkage outside airstream, and bearing AMCA's Certified Ratings Seal for both air performance and air leakage.
  - 4. Suitable for horizontal or vertical applications.
  - 5. Frames:
    - a. Hat Channel shaped.
    - b. 0.031-inch- thick, galvanized sheet steel.
    - c. Mitered and welded corners.
    - d. Flanges for attaching to walls and flangeless frames for installing in ducts.
  - 6. Blades:
    - a. Multiple blade.
    - b. Opposed-blade design.
    - c. Stiffen damper blades for stability.
    - d. Galvanized, roll-formed steel, 0.031 inch thick.
  - 7. Blade Axles: Galvanized steel.
  - 8. Bearings:
    - a. Molded synthetic.
    - b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
  - 9. Blade Seals: Neoprene.
  - 10. Jamb Seals: Stainless Steel.
  - 11. Tie Bars and Brackets: Galvanized steel.
  - 12. Accessories:
    - a. Include locking device to hold single-blade dampers in a fixed position without vibration.
- B. Jackshaft:
  - 1. Size: 0.5-inch diameter.
  - 2. Material: Galvanized-steel pipe rotating within pipe-bearing assembly mounted on supports at each mullion and at each end of multiple-damper assemblies.
  - 3. Length and Number of Mountings: As required to connect linkage of each damper in multiple-damper assembly.
- C. Damper Hardware:
  - 1. Zinc-plated, die-cast core with dial and handle made of 3/32-inch- thick zinc-plated steel, and a 3/4-inch hexagon locking nut.
  - 2. Include center hole to suit damper operating-rod size.
  - 3. Include elevated platform for insulated duct mounting.

## 2.4 SPIN COLLARS

- A. All round take-offs to round branch duct shall be made with factory fabricated spin-type collar fittings with balancing damper and constructed of minimum 26 ga galvanized steel. The damper shall have a raised 2" handle with a high quality locking quadrant. A 3/8" continuous rod with "U" bolts connects the damper to the rod. Nylon end bearing are required where the rod penetrates the spin collar barrel. These spin-collars shall be as manufactured by Flexmaster Model FLD-B03, Dace #26ga MSD-C03 or approved equal.

## 2.5 FIRE DAMPERS

- A. The contractor shall furnish and install UL555 rated 1-1/2 hour fire dampers at the locations indicated on the drawings in new ducts and sound attenuators. The contractor shall provide dampers with sleeves and angle frames necessary to comply with the manufacturer's UL installation requirements. Dampers for vertical or horizontal air flow shall be provided as required.
- B. Manufacturers:
  - 1. Greenheck.
  - 2. Flex-Tek Group.
  - 3. Nailor Industries Inc.
  - 4. Pottorff.
  - 5. Ruskin Company.
- C. Fire damper shall be 100% free area and installed in wall and floor openings utilizing steel sleeves, angles, other materials and practice required to provide an installation equivalent to that utilized by the manufacturer when dampers are tested by UL555. Installation shall be in accordance with the damper manufacturer's instructions.
- D. Fire damper for rectangular ductwork and transfer openings shall be Ruskin type DIBD-B, Greenheck Model DFD-150-B (Basis of Design).
- E. Fire dampers for round ductwork shall be Ruskin Model DIBD-CR, Greenheck DFD-150-CR (Basis of Design).
- F. All fire dampers shall be installed per N.F.P.A. and U.L. requirements. Install U.L. approved sealant around the perimeter of the angle iron support at the sleeve and the wall in accordance with U. L. recommendations.
- G. All fire dampers shall meet the latest Class 1 leakage requirements.

## 2.6 TURNING VANES

- A. Manufactured Turning Vanes for Metal Ducts: Curved blades of galvanized sheet steel; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
  - 1. Acoustic Turning Vanes: Fabricate airfoil-shaped aluminum extrusions with perforated faces and fibrous-glass fill.
- B. Manufactured Turning Vanes for Nonmetal Ducts: Fabricate curved blades of resin-bonded fiberglass with acrylic polymer coating; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.

- C. General Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 4-3, "Vanes and Vane Runners," and 4-4, "Vane Support in Elbows."
- D. Vane Construction: Single wall for ducts up to 48 inches wide and double wall for larger dimensions.

## 2.7 DUCT-MOUNTED ACCESS DOORS

- A. Duct-Mounted Access Doors: Fabricate access panels according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 7-2, "Duct Access Doors and Panels," and 7-3, "Access Doors - Round Duct."
  - 1. Door:
    - a. Double wall, rectangular.
    - b. Galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class.
    - c. Vision panel.
    - d. Hinges and Latches: 1-by-1-inch butt or piano hinge and cam latches.
    - e. Fabricate doors airtight and suitable for duct pressure class.
  - 2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
  - 3. Number of Hinges and Locks:
    - a. Access Doors Less Than 12 Inches Square: No hinges and two sash locks.
    - b. Access Doors up to 18 Inches Square: Continuous and two sash locks.
    - c. Access Doors up to 24 by 48 Inches: Continuous and two compression latches with outside and inside handles.
    - d. Access Doors Larger Than 24 by 48 Inches: Four hinges and two compression latches with outside and inside handles.

## 2.8 DUCT ACCESS PANEL ASSEMBLIES

- A. Labeled according to UL 1978 by an NRTL.
- B. Panel and Frame: Minimum thickness 0.0528-inch carbon steel.
- C. Fasteners: Carbon steel. Panel fasteners shall not penetrate duct wall.
- D. Gasket: Comply with NFPA 96; grease-tight, high-temperature ceramic fiber, rated for minimum 2000 deg F.
- E. Minimum Pressure Rating: 10-inch wg, positive or negative.

## 2.9 FLEXIBLE CONNECTORS

- A. Materials: Flame-retardant or noncombustible fabrics.
- B. Coatings and Adhesives: Comply with UL 181, Class 1.
- C. Metal-Edged Connectors: Factory fabricated with a fabric strip 3-1/2 inches wide attached to two strips of 2-3/4-inch- wide, 0.028-inch- thick, galvanized sheet steel or 0.032-inch- thick aluminum sheets. Provide metal compatible with connected ducts.

- D. Indoor System, Flexible Connector Fabric: Glass fabric double coated with neoprene.
  - 1. Minimum Weight: 26 oz./sq. yd.
  - 2. Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
  - 3. Service Temperature: Minus 40 to plus 200 deg F.
- E. Outdoor System, Flexible Connector Fabric: Glass fabric double coated with weatherproof, synthetic rubber resistant to UV rays and ozone.
  - 1. Minimum Weight: 24 oz./sq. yd..
  - 2. Tensile Strength: 530 lbf/inch in the warp and 440 lbf/inch in the filling.
  - 3. Service Temperature: Minus 50 to plus 250 deg F.
- F. Thrust Limits: Combination coil spring and elastomeric insert with spring and insert in compression, and with a load stop. Include rod and angle-iron brackets for attaching to fan discharge and duct.
  - 1. Frame: Steel, fabricated for connection to threaded rods and to allow for a maximum of 30 degrees of angular rod misalignment without binding or reducing isolation efficiency.
  - 2. Outdoor Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
  - 3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
  - 4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
  - 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
  - 6. Elastomeric Element: Molded, oil-resistant rubber or neoprene.
  - 7. Coil Spring: Factory set and field adjustable for a maximum of 1/4-inch movement at start and stop.

## 2.10 FLEXIBLE DUCTS

- A. Manufacturers:
  - 1. Thermaflex Model M-KE
  - 2. Flexmaster 1M
- B. Insulated, Flexible Duct: UL 181, Class 1, 2-ply vinyl film supported by helically wound, spring-steel wire; fibrous-glass insulation; polyethylene vapor-barrier film.
  - 1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
  - 2. Maximum Air Velocity: 4000 fpm.
  - 3. Temperature Range: Minus 10 to plus 160 deg F.
  - 4. Insulation R-value: Comply with ASHRAE/IESNA 90.1. (R6)
- C. Flexible Duct Connectors:
  - 1. Clamps: Stainless-steel band with cadmium-plated hex screw to tighten band with a worm-gear action in sizes 3 through 18 inches, to suit duct size.
  - 2. Non-Clamp Connectors: Liquid adhesive plus tape.

## 2.11 DUCT ACCESSORY HARDWARE

- A. Instrument Test Holes: Cast iron or cast aluminum to suit duct material, including screw cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit duct-insulation thickness.
- B. Adhesives: High strength, quick setting, neoprene based, waterproof, and resistant to gasoline and grease.

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Install duct accessories according to applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.
- B. Install duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and fibrous-glass ducts, stainless-steel accessories in stainless-steel ducts, and aluminum accessories in aluminum ducts.
- C. Install backdraft dampers at inlet of exhaust fans or exhaust ducts as close as possible to exhaust fan unless otherwise indicated.
- D. Install volume dampers at points on supply, return, and exhaust systems where branches extend from larger ducts. Where dampers are installed in ducts having duct liner, install dampers with hat channels of same depth as liner, and terminate liner with nosing at hat channel.
  - 1. Install steel volume dampers in steel ducts.
  - 2. Install aluminum volume dampers in aluminum ducts.
- E. Set dampers to fully open position before testing, adjusting, and balancing.
- F. Install test holes at fan inlets and outlets and elsewhere as indicated.
- G. Install fire dampers according to UL listing.
- H. Install duct access doors on sides of ducts to allow for inspecting, adjusting, and maintaining accessories and equipment at the following locations:
  - 1. Upstream from duct filters.
  - 2. Downstream from manual volume dampers, control dampers, backdraft dampers, and equipment.
  - 3. Adjacent to and close enough to fire or smoke dampers, to reset or reinstall fusible links. Access doors for access to fire or smoke dampers having fusible links shall be pressure relief access doors and shall be outward operation for access doors installed upstream from dampers and inward operation for access doors installed downstream from dampers.
  - 4. At each change in direction and at maximum 50-foot spacing.
  - 5. Control devices requiring inspection.
  - 6. Elsewhere as indicated.
- I. Install access doors with swing against duct static pressure.
- J. Access Door Sizes:
  - 1. One-Hand or Inspection Access: 8 by 5 inches.
  - 2. Two-Hand Access: 12 by 6 inches.
  - 3. Head and Hand Access: 18 by 10 inches.
  - 4. Head and Shoulders Access: 21 by 14 inches.
  - 5. Body Access: 25 by 14 inches.
  - 6. Body plus Ladder Access: 25 by 17 inches.



- K. Label access doors according to Section 230553 "Identification for HVAC Piping and Equipment" to indicate the purpose of access door.
- L. Install flexible connectors to connect ducts to equipment.
- M. For fans developing static pressures of 5-inch wg and more, cover flexible connectors with loaded vinyl sheet held in place with metal straps.
- N. Connect diffusers or light troffer boots to ducts directly or with maximum 60-inch lengths of flexible duct clamped or strapped in place.
- O. Connect flexible ducts to metal ducts with draw bands.
- P. Install duct test holes where required for testing and balancing purposes.
- Q. Install thrust limits at centerline of thrust, symmetrical on both sides of equipment. Attach thrust limits at centerline of thrust and adjust to a maximum of 1/4-inch movement during start and stop of fans.

### 3.2 FIELD QUALITY CONTROL

- A. Tests and Inspections:
  - 1. Operate dampers to verify full range of movement.
  - 2. Inspect locations of access doors and verify that purpose of access door can be performed.
  - 3. Operate fire, smoke, and combination fire and smoke dampers to verify full range of movement and verify that proper heat-response device is installed.
  - 4. Inspect turning vanes for proper and secure installation.
  - 5. Operate remote damper operators to verify full range of movement of operator and damper.

END OF SECTION 23 33 00

## **SECTION 23 34 23 – HVAC POWER VENTILATORS**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:
  - 1. Inline exhaust fans.

#### **1.3 PERFORMANCE REQUIREMENTS**

- A. Operating Limits: Classify according to AMCA 99.

#### **1.4 ACTION SUBMITTALS**

- A. Product Data: For each type of product indicated. Include rated capacities, operating characteristics, and furnished specialties and accessories. Also include the following:
  - 1. Certified fan performance curves with system operating conditions indicated.
  - 2. Certified fan sound-power ratings.
  - 3. Motor ratings and electrical characteristics, plus motor and electrical accessories.
  - 4. Material thickness and finishes, including color charts.
  - 5. Dampers, including housings, linkages, and operators.
  - 6. Roof curbs.
  - 7. Fan speed controllers.

#### **1.5 CLOSEOUT SUBMITTALS**

- A. Operation and Maintenance Data: For power ventilators to include in emergency, operation, and maintenance manuals.

#### **1.6 QUALITY ASSURANCE**

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. AMCA Compliance: Fans shall have AMCA-Certified performance ratings and shall bear the AMCA-Certified Ratings Seal.
- C. UL Standards: Power ventilators shall comply with UL 705. Power ventilators for use for restaurant kitchen exhaust shall also comply with UL 762.

1.7 COORDINATION

- A. Coordinate size and location of structural-steel support members.
- B. Coordinate sizes and locations of roof curbs, equipment supports, and roof penetrations with actual equipment provided.

**PART 2 - PRODUCTS**

2.1 INLINE EXHAUST FANS

- A. Manufacturers:
  - 1. Cook.
  - 2. Greenheck.
  - 3. ACME
  - 4. Pen-Barry
  - 5. Twin City
- B. All exhaust fans shall be equipped with bird screen, automatic back-draft dampers, solid state speed controller (direct drive) and integral disconnect switch unless noted otherwise. Fan motors shall be of the 40 deg C ambient temperature rise type and shall be suitable for continuous duty operation.
- C. Direct drive fans shall be complete with solid state speed control switch mounted on unit for balancing. Interlock with remote on/off switch.
- D. Housing: Steel.
- E. Fan Wheel: Centrifugal wheels directly mounted on motor shaft. Fan shrouds, motor, and fan wheel shall be removable for service.
- F. Electrical Requirements: Junction box for electrical connection on housing and receptacle for motor plug-in.

**PART 3 - EXECUTION**

3.1 INSTALLATION

- A. Install power ventilators level and plumb.
- B. Install units with clearances for service and maintenance.
- C. Label units according to requirements specified.

3.2 CONNECTIONS

- A. Drawings indicate general arrangement of ducts and duct accessories. Make final duct connections with flexible connectors.
- B. Install ducts adjacent to power ventilators to allow service and maintenance.
- C. Ground equipment.

3.3 ADJUSTING

- A. Adjust damper linkages for proper damper operation.
- B. Adjust belt tension.
- C. Replace fan and motor pulleys as required to achieve design airflow.
- D. Lubricate bearings.

END OF SECTION 23 34 23

## SECTION 23 37 13 - DIFFUSERS, REGISTERS, GRILLES, AND LOUVERS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Fixed face registers and grilles.
- B. Related Sections:
  - 1. Section 233300 "Air Duct Accessories" for fire and smoke dampers and volume-control dampers not integral to diffusers, registers, and grilles.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated, include the following:
  - 1. Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static-pressure drop, and noise ratings.
  - 2. Diffuser, Register, and Grille Schedule: Indicate drawing designation, room location, quantity, model number, size, and accessories furnished.

### PART 2 - PRODUCTS

#### 2.1 REGISTERS AND GRILLES

- A. Louvered Grille:
  - 1. Manufacturers:
    - a. Titus.
    - b. Price Industries.
    - c. Nailor Industries.
    - d. Metalaire, Inc.
  - 2. Material: Aluminum.
  - 3. Finish: Baked enamel, Prime Aluminum.
  - 4. Core Construction: Integral.
  - 5. Frame: 1 inch wide.

**PART 3 - EXECUTION**

**3.1 EXAMINATION**

- A. Examine areas where diffusers, registers, and grilles are to be installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

**3.2 INSTALLATION**

- A. Install diffusers, registers, and grilles level and plumb.
- B. Install diffusers, registers, and grilles with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

**3.3 ADJUSTING**

- A. After installation, adjust diffusers, registers, and grilles to air patterns indicated, or as directed, before starting air balancing.

**END OF SECTION 23 37 13**