5-26 Lenwil Elementary Cafeteria Renovation

Ouachita Parish School Board

Project documents obtained from www.CentralBidding.com

06-Oct-2025 11:55:51 AM

PROJECT MANUAL:

Lenwil Elementary School Cafeteria Renovation

112 Arrant Road, West Monroe, LA 71292

Ouachita Parish School System

1600 N 7th Street West Monroe, LA. 71291

Owner's Project Number
5-26

Architect's Project Number
25-WM0015

Date
October, 2025

TBA

Exhibit B

PROJECT MANUAL

LENWIL ELEMENTARY SCHOOL CAFETERIA RENOVATION
112 Arrant Road West Monroe, LA. 71292

Ouachita Parish School System
1600 N 7th Street West Monroe, LA. 71291

TBA Studio

TABLE OF CONTENTS

DIVISION 0 – PROCUREMENT & CONTRACTING

REQUIREMENTS

SECTION 000101 - PROJECT MANUAL COVER
000102 - TABLE OF CONTENTS
001113 – NOTICE TO BIDDERS
001114 – SALES AND USE TAX
001115 - ATTESTATION AFFIDAVIT
001115A – NON-COLLUSION AFFIDAVIT
002113 – INSTRUCTION TO BIDDERS
002212 – A201-2017 GENERAL CONDITIONS
002213 – SUPPLEMENTARY CONDITIONS
002214 – A101 CONTRACT
002513 – PREBID MEETING
002600 – PROCUREMENT SUBSTITUTION
004113 - BID FORM
004313 – BID BOND

DIVISION 1 - GENERAL REQUIREMENTS

SECTION 011000 - SUMMARY
012500 - SUBSTITUTION PROCEDURES
012600 - CONTRACT MODIFICATION PROCEDURES
012900 - PAYMENT PROCEDURES
013100 - PROJECT MANAGEMENT & COORDINATION
013200 - CONSTRUCTION PROGRESS DOCUMENTATION
013233 - PHOTOGRAPHIC DOCUMENTATION
013300 - SUBMITTAL PROCEDURES
014000 - QUALITY REQUIREMENTS
014100 – TESTING LABORATORY SERVICES
014200 – REFERENCE

015000 - TEMPORARY FACILITES AND CONTROLS
015639 - TEMPORARY TREE AND PLANT PROTECTION
016000 – PRODUCT REQUIREMENTS
017300 - EXECUTION
017419 - CONSTRUCTION WASTE MANAGEMENT & DISPOSAL
017700 - CLOSEOUT PROCEDURE
017823 - OPERATION & MAINTENANCE DATA
017839 - PROJECT RECORD DOCUMENTS
017900 - DEMONSTRATION AND TRAINING

DIVISION 2 – EXISTING CONDITIONS

SECTION 023000 – EARTHWORK
024000 - GRADING
024100 - DEMOLITION
024119 - SELECTIVE DEMOLITION
027000 - CONCRETE

DIVISION 3 – CONCRETE

SECTION 031000 – CONCRETE FORMWORK
031521 – TERMITE BARRIER
032000 – CONCRETE REINFORCEMENT

DIVISION 4 - MASONRY

SECTION 040519 – MASONRY – ANCHORAGE & REINFORCING
041000 – MOTAR & MASONRY GROUT FOR MASONRY
042113 – BRICK MASONRY

DIVISION 6 – WOOD, PLASTICS & COMPOSITES

SECTION 061000 - ROUGH CARPENTRY
061600 - SHEATHING
062023 - INTERIOR FINISH CARPENTRY
064116 - PLASTIC-LAMINATE-FACED ARCHITECTURAL CABINETS
066400 – PLASTIC PANELING

DIVISION 7 - THERMAL AND MOISTURE PROTECTION

SECTION 071900 - WATER REPELLENTS
072100 - BUILDING INSULATION
072726 - FLUID-APPLIED AIR & WATER-RESISTIVE BARRIER SYSTEM
074213.13 – FORMED METAL WALL PANELS
076200 - SHEET METAL FLASHING AND TRIM
077100 - ROOF SPECIALTIES

077200 - ROOF ACCESSORIES
078413 - PENETRATION FIRESTOPPING
079200 - JOINT SEALANTS

DIVISION 8 - OPENINGS

SECTION 081113 - HOLLOW METAL DOORS AND FRAMES
083313 – COILING COUNTER DOORS
084113 - ALUMINUM-FRAMED ENTRANCES & STOREFRONT
087100 – DOOR HARDWARE
088000 – GLAZING

DIVISION 9 - FINISHES

SECTION 090561.13 – MOISTURE VAPOR EMISSION CONTROL
092216 - NON-STRUCTURAL METAL FRAMING
092900 - GYPSUM BOARD
093000 - TILING
095100 – ACOUSTICAL CEILING SOUND SCAPE BLADES
095113 – ACOUSTICAL PANEL CEILINGS
096513 - RESILIENT BASE AND ACCESSORIES
096519 - RESILIENT TILE FLOORING
097700 – SPECIAL WALL SURFACES
099000 – PAINTING & COATING
099600 – HIGH-PERFORMANCE COATINGS

DIVISION 10 - SPECIALTIES

SECTION 101416 - PLAQUES
101423 - PANEL SIGNAGE
102800 - TOILET, BATH, AND LAUNDRY ACCESSORIES
104413 - FIRE PROTECTION CABINETS
104413 – FIRST AID CABINETS
104416 - FIRE EXTINGUISHERS
105113 – METAL LOCKERS

DIVISION 11 – EQUIPMENT

SECTION 11400 – FOOD SERVICE EQUIPMENT

DIVISION 12 – FURNISHINGS

SECTION 123661 - SIMULATED STONE COUNTERTOPS

DIVISION 21 – FIRE SUPPRESSION

SECTION 211313 -WET-PIPE SPRINKLER SYSTEM

DIVISION 22 – PLUMBING

SECTION 220000 – PLUMBING GENERAL PROVISIONS
220523 – GENERAL DUTY VALVES FOR PLUMBING
220529 – HANGERS AND SUPPORTS FOR PLUMBING PIPING
220719 – PLUMBING PIPING INSULATION
221116 – DOMESTIC WATER PIPING
221119 – DOMESTIC WATER PIPING SPECIALTIES
221219 – NATURAL GAS DISTRIBUTION AND PIPING
221316 – SANITARY WASTE AND VENT PIPING
221319 – SANITARY WASTE PIPING SPECIALTIES
221323 – SANITARY WASTE INTERCEPTORS
223400 – FUEL-FIRED, DOMESTIC-WATER HEATERS
224200 – PLUMBING FIXTURES

DIVISION 23 – HEATING, VENTILATION & AIR CONDITIONING

SECTION 230000 – MECHANICAL GENERAL PROVISIONS
230513 – COMMON MOTOR REQ. FOR HVAC EQUIP.
230529 – HANGERS AND SUPPORTS FOR HVAC PIPING & EQUIP.
230553 – IDENTIFICATION FOR HVAC PIPING & EQUIP.
230593 – TESTING, ADJUSTING AND BALANCING FOR HVAC
230713 – DUCT INSULATION
230719 – HVAC PIPING INSULATION
232114 – HVAC CONDENSATE PIPING
232300 – REFRIGERANT PIPING
233113 – METAL DUCTS
233300 – AIR DUCT ACCESSORIES
233423 – HVAC POWER VENTILATORS
233713 – DIFFUSERS, REGISTERS, GRILLES AND LOUVERS
233713 – COMMERCIAL – TYPE 1 KITCHEN HOODS
233714 – COMMERCIAL – TYPE II KITCHEN HOODS
237030 – AIR PURIFICATION SYSTEM
237413 – PACKAGED, ROOFTOP A/C UNITS
237420 – PACKED 100% OUTSIDE AIR A/C UNITS
239020 – TEMPERATURE CONTROLS

DIVISION 26 – ELECTRICAL

SECTION 260500 – COMMON WORK RESULTS FOR ELECTRICAL
260519 – LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS & CABLES
260526 – GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS
260529 – HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS
260533 – RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS
260553 – IDENTIFICATION FOR ELECTRICAL SYSTEMS
260573 – OVERCURRENT PROTECTION DEVICE COORDINATION STUDY
260923 – LIGHTING CONTROL DEVICES
262416 – PANELBOARDS
262726 – WIRING DEVICES
262813 - FUSES

262816 – ENCLOSED SWITCHES AND CIRCUIT BREAKERS
264313 – SURGE PROTECTION DEVICES FOR SERVICE ENTERANCE AND BRANCH PANELS
265100 – INTERIOR LIGHTING

DIVISION 28 – FIRE ALARM

SECTION 283111 – FIRE ALARM SYSTEM WITH VOICE

DIVISION 31 – EARTHWORK

SECTION 312513 – EROSION AND SEDIMENTATION CONTROL

DIVISION 32 – EXTERIOR IMPROVEMENTS

SECTION 321216 – ASPHALT PAVING
321613 – CONCRETE CURBS AND SIDEWALKS
326113 – MISCELLANEOUS WORK AND CLEANUP
329200 – TURF AND GRASSES

DIVISION 33 - UTILITIES

SECTION 331113 – PUBLIC WATER UTILITY DISTRIBUTION PIPING
331113 – WATER UTILITY DISTRIBUTION VALVES
333100 – SANITARY UTILITY SEWERAGE PIPING
334000 – STORM DRAINAGE UTILITIES

NOTICE TO BIDDERS

Sealed Bids will be received by the Ouachita Parish School Board, 1600 N. 7th Street, West Monroe, Louisiana 71291 until **2:00 P.M. October 30, 2025.**

For: Lenwil Elementary School Cafeteria Renovation
112 Arrant Road West Monroe, LA. 71292
Ouachita Parish School System

BID NUMBER: 5-26
Complete Bidding Documents for this project are available in electronic form. They may be obtained from www.centralbidding.com Printed copies are not available from the Architect but arrangements can be made to obtain them through most reprographic firms. Plan holders are responsible for their own reproduction costs. Questions about this procedure shall be directed to the Architect at
TBA Studio 103 Cypress Street
West Monroe, Louisiana 71291
Telephone: (318) 340-1550
Facsimile: (318) 998-1315
E-mail: hterrell@tbastudio.com

All bids must be accompanied by bid security equal to five percent (5%) of the base bid and all additive alternates, and must be in the form of a certified check, cashier's check or bid bond written by a company licensed to do business in Louisiana, countersigned by a person who is under contract with the surety company or bond issuer as a licensed agent in this State and who is residing in this state. No Bid Bond indicating an obligation of less than five percent (5%) by any method is acceptable. Contractors have the option of submitting bids electronically at www.centralauctionhouse.com or www.centralbidding in lieu of sealed bids.

Bids shall be accepted from Contractors who are licensed under LA. R.S. 37:2150-2192 for the classification of **Building Construction.** Bidder is required to comply with provisions and requirements of LA R.S. 38:2212(B)(5). No bid may be withdrawn except under the provisions of LA. R.S. 38:2214.

The successful Bidder will be required to furnish a performance and payment bond written by a company licensed to do business in Louisiana, and shall be countersigned by a person who is contracted with the surety company or bond issuer as agent of the company or issuer, and who is licensed as an insurance agent in this State, and who is residing in this State, in an amount equal to the 100% of the contract amount.

A **Mandatory pre-bid conference** will be held **October 17**, **2025** at **10:00 AM** at the main entrance to LENWIL ELEMENTARY SCHOOL campus. Bids shall be accepted only from Contractors who attend the Pre-bid Conference in its entirety.

The Owner reserves the right to reject any and all bids for just cause. In accordance with La. R.S. 38:2212(B)(1), the provisions and requirements of this Section; and those stated in the bidding documents shall not be waived by any entity.

ANY PERSON REQUIRING SPECIAL ACCOMMODATIONS SHALL NOTIFY ARCHITECT OF THE TYPE(S) OF ACCOMMODATION REQUIRED NOT LESS THAN SEVEN (7) DAYS BEFORE THE BID OPENING.

ATTEST: _____
Todd Guice, Superintendent

OUACHITA PARISH SCHOOL BOARD

_____
Tommy Comeaux, President

Publications Dates: 10-02-25 / 10-09-25 / 10-16-25

STATE OF LOUISIANA

PARISH OF OUACHITA

SALES AND USE TAX EXEMPTION AGREEMENT

BE IT KNOWN that on the dates and at the places recited herein below, personally came and appeared:

THE OUACHITA PARISH SCHOOL BOARD ("OPSB"), a municipal corporation and body politic organized under the laws of the State of Louisiana, appearing herein through its duly authorized President, Tommy Comeaux, and its duly authorized Superintendent of Schools, Todd Guice.
.

-AND-

_____(“Contractor"), a corporation or business association authorized to do business in the State of Louisiana, appearing herein through its duly authorized representative, _____.

Jointly appearing here for the purpose of entering into the following agreement:

The OPSB is a public entity which is exempt from the payment of state and local sales and use taxes, by virtue of the authority of LSA-R.S. 47:301(8)(c) and other pertinent authorities.

The OPSB has let out for public bid, pursuant to LSA-R.S. 38:2211, et seq., public works projects to effect construction and capital improvements to facilities in the Ouachita Parish School District.

The OPSB desires, and Contractor agrees, that in all instances where Contractor purchases, materia1s or supplies for incorporation into a public work of the OPSB, or where equipment is rented by Contractor for the purpose of accomplishing such public work, Contractor shall act as the agent of the OPSB, shall purchase such supplies and materials, or rent such equipment, in the name and stead of the OPSB, with title and ownership being transferred directly from the vendor to the OPSB, and Contractor shall claim or otherwise assert the OPSB's exemption from the payment of sales and use taxes. In connection therewith, Contractor, as agent of the OPSB, shall be authorized to perform such acts as are necessary (consistent with the authorization granted herein) to claim and assert the OPSB sales and use tax exemption, and sha1l be provided with a sales and use tax exemption certificate ("certificate") by the OPSB for presentation to vendors to claim the exemption.

Both the OPSB and Contractor understand that this Agreement shall be an addendum to and a part of the bid specifications and terms that are applicable to any bid that is let for public work by the OPSB, and shall become a material term of any contractual agreement entered into by the OPSB with Contractor for any contract awarded to Contractor for public work.

DONE AND SIGNED on this_____ day of_____, 2025 in

_____(city), Louisiana , Parish of Ouachita.

OUACHITA PARISH SCHOOL BOARD

_____
Tommy Comeaux, President

_____
Todd Guice, Superintendent

DONE AND SIGNED on this_____ day of_____, 2025 in

West Monroe (city), Louisiana , Parish of Ouachita.

( )
CONTRACTOR

BY:_____

Duly Authorized

Name of Project
Lenwil Elementary School
Cafeteria Renovation
112 Arrant Rd, West Monroe, LA 71292

Project Numbers
Architect 25-WM0015
Owner 5-26

Ouachita Parish School Board

STATE OF LOUISIANA – PARISH OF OUACHITA

ATTESTATIONS AFFIDAVIT

Before me, the undersigned notary public, duly commissioned and qualified in and for the parish and state aforesaid, personally came and appeared Affiant, who after being duly sworn, attested as follows:

LA. R.S. 38:2227 PAST CRIMINAL CONVICTIONS OF BIDDERS

A. No sole proprietor or individual partner, incorporator, director, manager, officer, organizer, or member who has a minimum of a ten percent (10%) ownership in the bidding entity named below has been convicted of, or has entered a plea of guilty or nolo contendere to any of the following state crimes or equivalent federal crimes:

(a) Public bribery (R.S. 14:118)
(b) Corrupt influencing (R.S. 14:120)
(c) Extortion (R.S. 14:66)
(d) Money laundering (R.S. 14:230)

B. Within the past five years from the project bid date, no sole proprietor or individual partner, incorporator, director, manager, officer, organizer, or member who has a minimum of a ten percent (10%) ownership in the bidding entity named below has been convicted of, or has entered a plea of guilty or nolo contendere to any of the following state crimes or equivalent federal crimes, during the solicitation or execution of a contract or bid awarded pursuant to the provisions of Chapter 10 of Title 38 of the Louisiana Revised Statutes:

(a) Theft (R.S. 14:67)
(b) Identity Theft (R.S. 14:67.16)
(c) Theft of a business record (R.S.14:67.20)
(d) False accounting (R.S. 14:70)
(e) Issuing worthless checks (R.S. 14:71)
(f) Bank fraud (R.S. 14:71.1)
(g) Forgery (R.S. 14:72)
(h) Contractors; misapplication of payments (R.S. 14:202)
(i) Malfeasance in office (R.S. 14:134)

LA. R.S. 38:2212.10 Verification of Employees

A. At the time of bidding, Appearer is registered and participates in a status verification system to verify that all new hires in the state of Louisiana are legal citizens of the United States or are legal aliens.

B. If awarded the contract, Appearer shall continue, during the term of the contract, to utilize a status verification system to verify the legal status of all new employees in the state of Louisiana.

C. If awarded the contract, Appearer shall require all subcontractors to submit to it a sworn affidavit verifying compliance with Paragraphs (A) and (B) of this Subsection.

Name of Project
Lenwil Elementary School
Cafeteria Renovation
112 Arrant Rd, West Monroe, LA 71292

Project Numbers
Architect 25-WM0015
Owner 5-26

LA. R.S. 23:1726(B) Certification Regarding Unpaid Workers Compensation Insurance

A. R.S. 23:1726 prohibits any entity against whom an assessment under Part X of Chapter 11 of Title 23 of the Louisiana Revised Statutes of 1950 (Alternative Collection Procedures & Assessments) is in effect, and whose right to appeal that assessment is exhausted, from submitting a bid or proposal for or obtaining any contract pursuant to Chapter 10 of Title 38 of the Louisiana Revised Statutes of 1950 and Chapters 16 and 17 of Title 39 of the Louisiana Revised Statutes of 1950.

B. By signing this bid /proposal, Affiant certifies that no such assessment is in effect against the bidding / proposing entity.

_____ _____
NAME OF BIDDER **NAME OF AUTHORIZED SIGNATORY OF BIDDER**

_____ _____
DATE **TITLE OF AUTHORIZED SIGNATORY OF BIDDER**

_____
SIGNATURE OF AUTHORIZED
SIGNATORY OF BIDDER/AFFIANT

Sworn to and subscribed before me by Affiant on the _____ day of _____ , 20___ .

_____
Notary Public

NON-COLLUSION AFFIDAVIT

The undersigned bidder or' agent, being duly sworn on oath, says that he/she has not, nor has any other' member, representative, or agent of the firm, company, corporation or partnership represented by him, entered into any combination, collusion or agreement with any person relative to the price to be bid by anyone at such letting nor to prevent any person from bidding not to include anyone to refrain from bidding, and that this bid is made without reference to any other bid and without any agreement, understanding or combination with any other person in reference to such bidding.

He/She further says that no person or persons, firms, or corporation has, have or will receive directly or indirectly, any rebate, fee gift, commission or anything of value on account of such sale.

OATH AND AFFIRMATION

I HEREBY AFFIRM UNDER THE PENALTIES FOR PERJURY THAT THE FACTS AND INFORMATION CONTAINED IN THE FOREGOING BID FOR PUBLIC WORKS ARE TRUE AND CORRECT.

Dated this_____day of _____

_____
(Name of Organization)

_____
(Title of Person Signing)

_____
(Signature)

ACKNOWLEDGEMENT

STATE OF LOUISIANA)
) ss
COUNTY OF OUACHITA)

Before me, a Notary Public, personally appeared the above named and swore that the statements contained in the foregoing document are true and correct.

Subscribed and sworn to me this_____day of _____

_____
Notary Public Signature

My Commission Expires: _____

SECTION 002113 INSTRUCTIONS TO BIDDERS

COMPLETION TIME:

The Bidder shall agree to fully complete the contract within **(210)** consecutive calendar days, subject to such extensions as may be granted under Paragraph 8.3, in the General Conditions and the Supplementary Conditions, and acknowledges that this construction time will start on or before the date specified in the written "Notice to Proceed" from the Owner.

LIQUIDATED DAMAGES:

The Bidder shall agree to pay as Liquidated Damages the amount of **(seven hundred)** Dollars **($700.00)** for each consecutive calendar day for which the work is not complete, beginning with the first day beyond the contract completion date stated on the "Notice to Proceed" or as amended by change order.

ARTICLE 1

DEFINITIONS

1.1 The Bid Documents include the following:

Advertisement for Bids
Instructions to Bidders
Bid Form
Bid Bond
General Conditions of the Contract for Construction,
AlA Document A201, 2017 Edition
Supplementary Conditions
Contract Between Owner and Contractor and Performance and Payment Bond
Affidavit
User Agency Documents (if applicable)
Change Order Form
Partial Occupancy Form
Recommendation of Acceptance
Asbestos Abatement (if applicable)
Other Documents (if applicable)
Specifications & Drawings
Addenda issued during the bid period and acknowledged in the Bid Form

1.2 All definitions set forth in the General Conditions of the Contract for Construction, AlA Document A201 and the Supplementary Conditions are applicable to the Bid Documents.

1.3 Addenda are written and/or graphic instruments issued by the Architect prior to the opening of bids, which modify or interpret the Bid Documents by additions, deletions, clarifications, corrections and prior approvals.

1.4 A bid is a complete and properly signed proposal to do the work or designated portion thereof for the sums stipulated therein supported by data called for by the Bid Documents.

1.5 Base bid is the sum stated in the bid for which the Bidder offers to perform the work described as the base, to which work may be added, or deleted for sums stated in alternate bids.

1.6 An alternate bid (or alternate) is an amount stated in the bid to be added to the amount of the base bid if the corresponding change in project scope or materials or methods of construction described in the Bid Documents is accepted.

1.7 A Bidder is one who submits a bid for a prime Contract with the Owner for the work described in the Bid Documents.

1.8 A Sub-bidder is one who submits a bid to a Bidder for materials and/or labor for a portion of the work.

1.9 Where the word "Architect" is used in any of the documents, it shall refer to the Prime Designer of the project, regardless of discipline.

ARTICLE 2

PRE-BID CONFERENCE

2.1 A Pre-Bid Conference shall be held at least 10 days before the date for receipt for bids. The Architect shall coordinate the setting of the date, time and place for the Pre-Bid Conference with the User Agency and shall notify in writing the Owner and all who have received sets of the Bid Documents to attend. The purpose of the Pre-Bid Conference is to familiarize Bidders with the requirements of the Project and the intent of the Bid Documents, and to receive comments and information from interested Bidders. If the Pre-Bid Conference is stated in the Advertisement for Bids to be a Mandatory Pre-Bid Conference, bids shall be accepted only from those bidders who attend the Pre-Bid Conference. Contractors who are not in attendance for the **entire** Pre-Bid Conference will be considered to have not attended.

2.2 Any revision of the Bid Documents made as a result of the Pre-Bid Conference shall not be valid unless included in an addendum.

ARTICLE 3

BIDDER'S REPRESENTATION

3.1 Each Bidder by making his bid represents that:

3.1.1 He has read and understands the Bid Documents and his bid is made in accordance therewith.

3.1.2 He has visited the site and has familiarized himself with the local conditions under which the work is to be performed.

3.1.3 His bid is based solely upon the materials, systems and equipment described in the Bid Documents as advertised and as modified by addenda.

3.1.4 His bid is not based on any verbal instructions contrary to the Bid Documents and addenda.

3.1.5 He is familiar with Code of Governmental Ethics requirement that prohibits public servants and/or their immediate family members from bidding on or entering into contracts; he is aware that the Designer and its principal owners are considered Public Servants under the Code of Governmental Ethics for the limited purposes and scope of the Design Contract with the State on this Project (see Ethics Board Advisory Opinion, No. 2009-378 and 2010-128); and neither he nor any principal of the Bidder with a controlling interest therein has an immediate family relationship with the Designer or any principal within the Designer's firm (see La. R.S. 42:1113). Any Bidder submitting a bid in violation of this clause shall be disqualified and any contract entered into in violation of this clause shall be null and void.

3.2 The Bidder must be fully qualified under any State or local licensing law for Contractors in effect at the time and at the location of the work before submitting his bid. In the State of Louisiana, Revised Statutes 37:2150, et seq. will be considered, if applicable.

The Contractor shall be responsible for determining that all of his Sub-bidders or prospective Subcontractors are duly licensed in accordance with law.

ARTICLE 4

BID DOCUMENTS

4.1 Copies

4.1.1 Bid Documents may be obtained from the Architect for a deposit as stated in the Advertisement for Bids. The deposit will be refunded as stated in the Advertisement for Bids. No deposits will be refunded on Bid Documents returned later than ten days after receipt of bids.

4.1.1.2 As an alternative method of distribution, the Designer may provide the Bid Documents in electronic format. They may be obtained without charge and without deposit as stated in the Advertisement for Bids.

4.1.1.2.1 If electronic distribution is available, printed copies will not be available from the Designer, but arrangements can be made to obtain them through most reprographic firms and/or plan rooms.

4.1.1.2.2 If electronic distribution is available, the reproduction cost on the first paper plan set acquired by bona fide prime bidders will be fully refunded by the Designer upon delivery of the

documents to the Designer in good condition no later than ten days after receipt of bids.

4.1.1.2.3 If electronic distribution is available, all other plan holders are responsible for their own reproduction costs.

4.1.2 Complete sets of Bid Documents shall be used in preparing bids; neither the Owner nor the Architect assume any responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bid Documents.

4.1.3 The Owner or Architect in making copies of the Bid Documents available on the above terms, do so only for the purpose of obtaining bids on the work and do not confer a license or grant for any other use.

4.2 Interpretation or Correction of Bid Documents

4.2.1 Bidders shall promptly notify the Architect of any ambiguity, inconsistency or error which they may discover upon examination of the Bid Documents or of the site and local conditions.

4.2.2 Bidders requiring clarification or interpretation of the Bid Documents shall make a written request to the Architect, to reach him at least seven days prior to the date for receipt of bids.

4.2.3 Any interpretation, correction or change of the Bid Documents will be made by addendum. Interpretations, corrections or changes of the Bid Documents made in any other manner will not be binding and Bidders shall not rely upon such interpretations, corrections and changes.

4.3 Substitutions

4.3.1 The materials, products and equipment described in the Bid Documents establish a standard of required function, dimension, appearance and quality to be met by any proposed substitution. No substitutions shall be allowed after bids are received.

4.3.2 No substitution will be considered unless written request for approval has been submitted by the Proposer and **has been received by the Architect at least seven (7) working days prior to the opening of bids.** (La. R.S. 38:2295(C)) Each such request shall include the name of the material or equipment for which it is to be substituted and a complete description of the proposed substitute including model numbers, drawings, cuts, performance and test data and any other information necessary for an evaluation. A statement setting forth any changes in other materials, equipment or work that incorporation of the substitute would require shall be included. It shall be the responsibility of the proposer to include in his proposal all changes required of the Bid Documents if the proposed product is used. Prior approval, if given, is contingent upon supplier being responsible for any costs which may be necessary to modify the space or facilities needed to accommodate the materials and equipment approved.

4.3.3 If the Architect approves any proposed substitution, such approval shall be set forth in an addendum. Bidders shall not rely upon approvals made in any other manner.

4.4 Addenda

4.4.1 Addenda will be transmitted to all who are known by the Architect to have received a complete set of Bid Documents.

4.4.2 Copies of addenda will be made available for inspection wherever Bid Documents are on file for that purpose.

4.4.3 Except as described herein, addenda shall not be issued within a period of seventy-two (72) hours prior to the advertised time for the opening of bids, excluding Saturdays, Sundays, and any other legal holidays. If the necessity arises of issuing an addendum modifying plans and specifications within the seventy-two (72) hour period prior to the advertised time for the opening of bids, then the opening of bids shall be extended at least seven but no more than twenty-one (21) working days, without the requirement of re-advertising. Owner shall be consulted prior to issuance of such an addendum and shall approve such issuance. The revised time and date for the opening of bids shall be stated in the addendum.

4.4.4 Each Bidder shall ascertain from the Architect prior to submitting his bid that he has received all addenda issued, and he shall acknowledge their receipt on the Bid Form.

4.4.5 The Owner shall have the right to extend the bid date by up to (30) thirty days without the requirement of re-advertising. Any such extension shall be made by addendum issued by the Architect.

ARTICLE 5

BID PROCEDURE

5.1 Form and Style of Bids

5.1.1 Bids shall be submitted on the Louisiana Uniform Public Work Bid Form provided by the Architect for this project.

5.1.2 The Bidder shall ensure that all applicable blanks on the bid form are completely and accurately filled in.

5.1.3 Bid sums shall be expressed in both words and figures, and in case of discrepancy between the two, the written words shall govern.

5.1.4 Any interlineation, alteration or erasure must be initialed by the signer of the bid or his authorized representative.

5.1.5 Bidders are cautioned to complete all alternates should such be required in the Bid Form. Failure to submit alternate prices will render the bid non responsive and shall cause its rejection.

5.1.6 Bidders are cautioned to complete all unit prices should such be required in the Bid Form. Unit prices represent a price proposal to do a specified quantity and quality of work. Unit prices are incorporated into the base bid or alternates, as indicated on the Unit Price Form, but are not the sole components thereof.

5.1.7 Bidder shall make no additional stipulations on the Bid Form nor qualify his bid in any other manner.

5.1.8 Written evidence of the authority of the person signing the bid for the public work shall be submitted in accordance with La. R.S. 38:2212 (B)(5).

5.1.9 On any bid in excess of fifty thousand dollars ($50,000.00), the Contractor shall certify that he is licensed under La. R.S. 37: 2150-2173 and show his license number on the bid above his signature or his duly authorized representative.

5.2 Bid Security

5.2.1 No bid shall be considered or accepted unless the bid is accompanied by bid security in an amount of five percent (5.0%) of the base bid and all alternates.

The bid security shall be in the form of a certified check or cashier's check drawn on a bank insured by the Federal Deposit Insurance Corporation, or a Bid Bond written by a surety company licensed to do business in Louisiana and signed by the surety's agent or attorney-in-fact. The Bid Bond shall be written on the Bid Bond Form, and the surety for the bond must meet the qualifications stated thereon. The Bid Bond shall include the legal name of the bidder be in favor of the Owner and shall be accompanied by appropriate power of attorney. The Bid Bond must be signed by both the bidder/principal and the surety in the space provided on the Bid Bond Form. Failure by the bidder/principal or the surety to sign the bid bond shall result in the rejection of the bid.

Bid security furnished by the Contractor shall guarantee that the Contractor will, if awarded the work according to the terms of his proposal, enter into the Contract and furnish Performance and Payment Bonds as required by these Bid Documents, within fifteen (15) days after written notice that the instrument is ready for his signature.

Should the Bidder refuse to enter into such Contract or fail to furnish such bonds, the amount of the bid security shall be forfeited to the Owner as liquidated damages, not as penalty.

5.2.2 The Owner will have the right to retain the bid security of Bidders until either (a) the Contract has been executed and bonds have been furnished, or (b) the specified time has elapsed so that bids may be withdrawn, or (c) all bids have been rejected.

5.3 Submission of Bids

5.3.1 The Bid shall be sealed in an opaque envelope. The bid envelope shall be identified on the outside with the name of the project, and the name, address, **and license number** of the Bidder. The envelope shall not contain multiple bid forms, and will be received until the time specified and at

the place specified in the Advertisement for Bids. It shall be the specific responsibility of the Bidder to deliver his sealed bid to the Owner at the appointed place and prior to the announced time for the opening of bids. Late delivery of a bid for any reason, including late delivery by United States Mail, or express delivery, shall disqualify the bid.

If the bid is sent by mail, the sealed envelope shall be enclosed in a separate mailing envelope with the notation "Bid Enclosed" on the face thereof. Such bids shall be sent by Registered or Certified Mail, Return Receipt Requested, addressed to: Ouachita Parish School Board,
1600 N. 7th Street
West Monroe, Louisiana, 71291
Bids sent by express delivery shall be delivered to:
Ouachita Parish School Board
1600 N. 7th Street
West Monroe, Louisiana, 71291

5.3.2 Bids shall be deposited at the designated location prior to the time on the date for receipt of bids indicated in the Advertisement for Bids, or any extension thereof made by addendum. Bids received after the time and date for receipt of bids will be returned unopened.

5.3.3 Bidder shall assume full responsibility for timely delivery at location designated for receipt of bids.

5.3.4 Oral, telephonic or telegraphic bids are invalid and shall not receive consideration. Owner shall not consider notations written on outside of bid envelope which have the effect of amending the bid. Written modifications enclosed in the bid envelope, and signed or initialed by the Contractor or his representative, shall be accepted.

5.4 Modification or Withdrawal of Bid

5.4.1 A bid may not be modified, withdrawn or canceled by the Bidder during the time stipulated in the Advertisement for Bids, for the period following the time and bid date designated for the receipt of bids, and Bidder so agrees in submitting his bid, except in accordance with R.S. 38:2214 which states, in part, "Bids containing patently obvious, unintentional, and substantial mechanical, clerical, or mathematical errors, or errors of unintentional omission of a substantial quantity of work, labor, material, or services made directly in the compilation of the bid, may be withdrawn by the contractor if clear and convincing sworn, written evidence of such errors is furnished to the public entity within forty- eight hours of the bid opening excluding Saturdays, Sundays, and legal holidays".

5.4.2 Prior to the time and date designated for receipt of bids, bids submitted early may be modified or withdrawn only by notice to the party receiving bids at the place and prior to the time designated for receipt of bids.

5.4.3 Withdrawn bids may be resubmitted up to the time designated for the receipt of bids provided that they are then fully in conformance with these Instructions to Bidders.

5.4.4 Bid Security shall be in an amount sufficient for the bid as modified or resubmitted.

ARTICLE 6

CONSIDERATION OF BIDS

6.1 Opening of Bids

6.1.1 The properly identified Bids received on time will be opened publicly and will be read aloud, and a tabulation abstract of the amounts of the base bids and alternates, if any, will be made available to Bidders.

6.2 Rejection of Bids

6.2.1 The Owner shall have the right to reject any or all bids and in particular to reject a bid not accompanied by any required bid security or data required by the Bid Documents or a bid in any way incomplete or irregular.

6.3 Acceptance of Bid

6.3.1 It is the intent of the Owner, if he accepts any alternates, to accept them in the order in which they are listed in the Bid Form. Determination of the Low Bidder shall be on the basis of the sum of the base bid and the alternates accepted. However, the Owner shall reserve the right to accept alternates

in any order which does not affect determination of the Low Bidder.

ARTICLE 7

POST-BID INFORMATION

7.1 Submissions

7.1.1 At the Pre-Construction Conference, the Contractor shall submit the following information to the Architect.

7.1.1.1 A designation of the work to be performed by the Contractor with his own forces.

7.1.1.2 A breakdown of the Contract cost attributable to each item listed in the Schedule of Values Form (attached). No payments will be made to the Contractor until this is received.

7.1.1.3 The proprietary names and the suppliers of principal items or systems of material and equipment proposed for the work.

7.1.1.4 A list of names and business domiciles of all Subcontractors, manufacturers, suppliers or other persons or organizations (including those who are to furnish materials or equipment fabricated to a special design) proposed for the principal portions of the work. It is the preference of the Owner that, to the greatest extent possible or practical, the Contractor utilize Louisiana Subcontractors, manufacturers, suppliers and labor.

7.1.2 The General Contractor shall be responsible for actions or inactions of Subcontractors and/or material suppliers.

The General Contractor is totally responsible for any lost time or extra expense incurred due to a Subcontractor's or Material Supplier's failure to perform. Failure to perform includes, but is not limited to, a Subcontractor's financial failure, abandonment of the project, failure to make prompt delivery, or failure to do work up to standard. Under no circumstances shall the Owner mitigate the General Contractor's losses or reimburse the General Contractor for losses caused by these events.

7.1.3 The lowest responsive and responsible bidder shall submit to the Architect and the Owner within ten days after the bid opening a letter/letters from the manufacturer stating that the manufacturer will issue the roof system guarantee complying with the requirements of the specified roof system and include the name of the applicator acceptable to the manufacturer at the highest level of certification for installing the specified roof system. This manufacturer shall be one that has received prior approval or is named in the specifications.

In accordance with La. R.S. 38:2227 [references La R.S. 38:2212(A)(3)(c)(ii), which has since been renumbered as La R.S. 38:2212(B)(3)], La. R.S. 38:2212.10 and La. R.S. 23:1726(B) each bidder on this project must submit the completed Attestations Affidavit (Past Criminal Convictions of Bidders, Verification of Employees and Certification Regarding Unpaid Workers Compensation Insurance) form found within this bid package. The Attestations Affidavit form shall be submitted to the Owner within 10 days after the opening of bids.

ARTICLE 8

PERFORMANCE AND PAYMENT BOND

8.1 Bond Required

8.1.1 The Contractor shall furnish and pay for a Performance and Payment Bond written by a company licensed to do business in Louisiana, which shall be signed by the surety's agent or attorney-in-fact, in an amount equal to 100% of the Contract amount. Surety must be listed currently on the U. S. Department of Treasury Financial Management Service List (Treasury List) as approved for an amount equal to or greater than the contract amount, or must be an insurance company domiciled in Louisiana or owned by Louisiana residents. If surety is qualified other than by listing on the Treasury list, the contract amount may not exceed fifteen percent of policyholders' surplus as shown by surety's most recent financial statements filed with the Louisiana Department of Insurance and may not exceed the amount of $500,000. However, a Louisiana domiciled insurance company with at least an A- rating in the latest printing of the A. M. Best's Key Rating Guide shall not be subject to the $500,000 limitation, provided that the contract amount does not exceed ten percent of policyholders' surplus as shown in the latest A. M. Best's Key Rating Guide nor fifteen percent of

policyholders' surplus as shown by surety's most recent financial statements filed with the Louisiana Department of Insurance. The Bond shall be signed by the surety's agent or attorney-in-fact. The Bond shall be in favor of the Owner.

8.2 Time of Delivery and Form of Bond

8.2.1 The Bidder shall deliver the required bond to the Owner simultaneous with the execution of the Contract.

8.2.2 Bond shall be in the form furnished by the Architect, entitled CONTRACT BETWEEN OWNER AND CONTRACTOR AND PERFORMANCE AND PAYMENT BOND, a copy of which is included in the Bid Documents.

8.2.3 The Bidder shall require the Attorney-in-Fact who executes the required bond on behalf of the surety to affix thereto a certified and current copy of his power of Attorney.

ARTICLE 9

FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR

9.1 Form to be Used

9.1.1 Form of the Contract to be used shall be furnished by the Architect, an example of which is bound in the Bid Documents.

9.2 Award

9.2.1 After award of the Contract, the successful Bidder, if a corporation, shall furnish to the Owner the most current copy of a Disclosure of Ownership Affidavit on file with the Secretary of State.

9.2.2 In accordance with Louisiana Law, when the Contract is awarded, the successful Bidder shall, at the time of the signing of the Contract, execute the Non-Collusion Affidavit included in the Contract Documents

9.2.3 When this project is financed either partially or entirely with State Bonds, the award of this Contract is contingent upon the sale of bonds by the State Bond Commission. The State shall incur no obligation to the Contractor until the Contract Between Owner and Contractor is duly executed.

AIA® Document A201™ – 2017

General Conditions of the Contract for Construction

for the following PROJECT:
(Name and location or address)

.

THE OWNER:
(Name, legal status and address)

THE ARCHITECT:
(Name, legal status and address)

TABLE OF ARTICLES

1 GENERAL PROVISIONS

2 OWNER

3 CONTRACTOR

4 ARCHITECT

5 SUBCONTRACTORS

6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

7 CHANGES IN THE WORK

8 TIME

9 PAYMENTS AND COMPLETION

10 PROTECTION OF PERSONS AND PROPERTY

11 INSURANCE AND BONDS

12 UNCOVERING AND CORRECTION OF WORK

13 MISCELLANEOUS PROVISIONS

14 TERMINATION OR SUSPENSION OF THE CONTRACT

15 CLAIMS AND DISPUTES

ADDITIONS AND DELETIONS:
The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An *Additions and Deletions Report* that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

For guidance in modifying this document to include supplementary conditions, see AIA Document A503™, Guide for Supplementary Conditions.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

INDEX

(Topics and numbers in bold are Section headings.)

Acceptance of Nonconforming Work
9.6.6, 9.9.3, **12.3**
Acceptance of Work
9.6.6, 9.8.2, 9.9.3, 9.10.1, 9.10.3, 12.3
Access to Work
3.16, 6.2.1, 12.1
Accident Prevention
10
Acts and Omissions
3.2, 3.3.2, 3.12.8, 3.18, 4.2.3, 8.3.1, 9.5.1, 10.2.5, 10.2.8, 13.3.2, 14.1, 15.1.2, 15.2
Addenda
1.1.1
Additional Costs, Claims for
3.7.4, 3.7.5, 10.3.2, 15.1.5
Additional Inspections and Testing
9.4.2, 9.8.3, 12.2.1, **13.4**
Additional Time, Claims for
3.2.4, 3.7.4, 3.7.5, 3.10.2, 8.3.2, **15.1.6**
Administration of the Contract
3.1.3, **4.2**, 9.4, 9.5
Advertisement or Invitation to Bid
1.1.1
Aesthetic Effect
4.2.13
Allowances
3.8
Applications for Payment
4.2.5, 7.3.9, 9.2, **9.3**, 9.4, 9.5.1, 9.5.4, 9.6.3, 9.7, 9.10
Approvals
2.1.1, 2.3.1, 2.5, 3.1.3, 3.10.2, 3.12.8, 3.12.9, 3.12.10.1, 4.2.7, 9.3.2, 13.4.1
Arbitration
8.3.1, 15.3.2, **15.4**
ARCHITECT
4
Architect, Definition of
4.1.1
Architect, Extent of Authority
2.5, 3.12.7, 4.1.2, 4.2, 5.2, 6.3, 7.1.2, 7.3.4, 7.4, 9.2, 9.3.1, 9.4, 9.5, 9.6.3, 9.8, 9.10.1, 9.10.3, 12.1, 12.2.1, 13.4.1, 13.4.2, 14.2.2, 14.2.4, 15.1.4, 15.2.1
Architect, Limitations of Authority and Responsibility
2.1.1, 3.12.4, 3.12.8, 3.12.10, 4.1.2, 4.2.1, 4.2.2, 4.2.3, 4.2.6, 4.2.7, 4.2.10, 4.2.12, 4.2.13, 5.2.1, 7.4, 9.4.2, 9.5.4, 9.6.4, 15.1.4, 15.2
Architect's Additional Services and Expenses
2.5, 12.2.1, 13.4.2, 13.4.3, 14.2.4
Architect's Administration of the Contract
3.1.3, 3.7.4, 15.2, 9.4.1, 9.5
Architect's Approvals
2.5, 3.1.3, 3.5, 3.10.2, 4.2.7
Architect's Authority to Reject Work
3.5, 4.2.6, 12.1.2, 12.2.1
Architect's Copyright
1.1.7, 1.5
Architect's Decisions
3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 4.2.14, 6.3, 7.3.4, 7.3.9, 8.1.3, 8.3.1, 9.2, 9.4.1, 9.5, 9.8.4, 9.9.1, 13.4.2, 15.2
Architect's Inspections
3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 13.4
Architect's Instructions
3.2.4, 3.3.1, 4.2.6, 4.2.7, 13.4.2
Architect's Interpretations
4.2.11, 4.2.12
Architect's Project Representative
4.2.10
Architect's Relationship with Contractor
1.1.2, 1.5, 2.3.3, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2, 3.5, 3.7.4, 3.7.5, 3.9.2, 3.9.3, 3.10, 3.11, 3.12, 3.16, 3.18, 4.1.2, 4.2, 5.2, 6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5, 9.7, 9.8, 9.9, 10.2.6, 10.3, 11.3, 12, 13.3.2, 13.4, 15.2
Architect's Relationship with Subcontractors
1.1.2, 4.2.3, 4.2.4, 4.2.6, 9.6.3, 9.6.4, 11.3
Architect's Representations
9.4.2, 9.5.1, 9.10.1
Architect's Site Visits
3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.4
Asbestos
10.3.1
Attorneys' Fees
3.18.1, 9.6.8, 9.10.2, 10.3.3
Award of Separate Contracts
6.1.1, 6.1.2
Award of Subcontracts and Other Contracts for Portions of the Work
5.2
Basic Definitions
1.1
Bidding Requirements
1.1.1
Binding Dispute Resolution
8.3.1, 9.7, 11.5, 13.1, 15.1.2, 15.1.3, 15.2.1, 15.2.5, 15.2.6.1, 15.3.1, 15.3.2, 15.3.3, 15.4.1
Bonds, Lien
7.3.4.4, 9.6.8, 9.10.2, 9.10.3
Bonds, Performance, and Payment
7.3.4.4, 9.6.7, 9.10.3, **11.1.2**, 11.1.3, **11.5**
Building Information Models Use and Reliance
1.8
Building Permit
3.7.1
Capitalization
1.3
Certificate of Substantial Completion
9.8.3, 9.8.4, 9.8.5

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

Certificates for Payment
4.2.1, 4.2.5, 4.2.9, 9.3.3, **9.4**, 9.5, 9.6.1, 9.6.6, 9.7, 9.10.1, 9.10.3, 14.1.1.3, 14.2.4, 15.1.4
Certificates of Inspection, Testing or Approval
13.4.4
Certificates of Insurance
9.10.2
Change Orders
1.1.1, 3.4.2, 3.7.4, 3.8.2.3, 3.11, 3.12.8, 4.2.8, 5.2.3, 7.1.2, 7.1.3, **7.2**, 7.3.2, 7.3.7, 7.3.9, 7.3.10, 8.3.1, 9.3.1.1, 9.10.3, 10.3.2, 11.2, 11.5, 12.1.2
Change Orders, Definition of
7.2.1
CHANGES IN THE WORK
2.2.2, 3.11, 4.2.8, **7**, 7.2.1, 7.3.1, 7.4, 8.3.1, 9.3.1.1, 11.5
Claims, Definition of
15.1.1
Claims, Notice of
1.6.2, 15.1.3
CLAIMS AND DISPUTES
3.2.4, 6.1.1, 6.3, 7.3.9, 9.3.3, 9.10.4, 10.3.3, **15**, 15.4
Claims and Timely Assertion of Claims
15.4.1
Claims for Additional Cost
3.2.4, 3.3.1, 3.7.4, 7.3.9, 9.5.2, 10.2.5, 10.3.2, **15.1.5**
Claims for Additional Time
3.2.4, 3.3.1, 3.7.4, 6.1.1, 8.3.2, 9.5.2, 10.3.2, **15.1.6**
Concealed or Unknown Conditions, Claims for
3.7.4
Claims for Damages
3.2.4, 3.18, 8.3.3, 9.5.1, 9.6.7, 10.2.5, 10.3.3, 11.3, 11.3.2, 14.2.4, 15.1.7
Claims Subject to Arbitration
15.4.1
Cleaning Up
3.15, 6.3
Commencement of the Work, Conditions Relating to
2.2.1, 3.2.2, 3.4.1, 3.7.1, 3.10.1, 3.12.6, 5.2.1, 5.2.3, 6.2.2, 8.1.2, 8.2.2, 8.3.1, 11.1, 11.2, **15.1.5**
Commencement of the Work, Definition of
8.1.2
Communications
3.9.1, **4.2.4**
Completion, Conditions Relating to
3.4.1, 3.11, 3.15, 4.2.2, 4.2.9, 8.2, 9.4.2, 9.8, 9.9.1, 9.10, 12.2, 14.1.2, 15.1.2
COMPLETION, PAYMENTS AND
9
Completion, Substantial
3.10.1, 4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, 9.8, 9.9.1, 9.10.3, 12.2, 15.1.2
Compliance with Laws
2.3.2, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 10.2.2, 13.1, 13.3, 13.4.1, 13.4.2, 13.5, 14.1.1, 14.2.1.3, 15.2.8, 15.4.2, 15.4.3
Concealed or Unknown Conditions
3.7.4, 4.2.8, 8.3.1, 10.3
Conditions of the Contract
1.1.1, 6.1.1, 6.1.4
Consent, Written
3.4.2, 3.14.2, 4.1.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3, 13.2, 15.4.4.2
Consolidation or Joinder
15.4.4
CONSTRUCTION BY OWNER OR BY
SEPARATE CONTRACTORS
1.1.4, **6**
Construction Change Directive, Definition of
7.3.1
Construction Change Directives
1.1.1, 3.4.2, 3.11, 3.12.8, 4.2.8, 7.1.1, 7.1.2, 7.1.3, **7.3**, 9.3.1.1
Construction Schedules, Contractor's
3.10, 3.11, 3.12.1, 3.12.2, 6.1.3, 15.1.6.2
Contingent Assignment of Subcontracts
5.4, 14.2.2.2
Continuing Contract Performance
15.1.4
Contract, Definition of
1.1.2
CONTRACT, TERMINATION OR
SUSPENSION OF THE
5.4.1.1, 5.4.2, 11.5, **14**
Contract Administration
3.1.3, 4, 9.4, 9.5
Contract Award and Execution, Conditions Relating to
3.7.1, 3.10, 5.2, 6.1
Contract Documents, Copies Furnished and Use of
1.5.2, 2.3.6, 5.3
Contract Documents, Definition of
1.1.1
Contract Sum
2.2.2, 2.2.4, 3.7.4, 3.7.5, 3.8, 3.10.2, 5.2.3, 7.3, 7.4, **9.1**, 9.2, 9.4.2, 9.5.1.4, 9.6.7, 9.7, 10.3.2, 11.5, 12.1.2, 12.3, 14.2.4, 14.3.2, 15.1.4.2, **15.1.5, 15.2.5**
Contract Sum, Definition of
9.1
Contract Time
1.1.4, 2.2.1, 2.2.2, 3.7.4, 3.7.5, 3.10.2, 5.2.3, 6.1.5, 7.2.1.3, 7.3.1, 7.3.5, 7.3.6, 7, 7, 7.3.10, 7.4, 8.1.1, 8.2.1, 8.2.3, 8.3.1, 9.5.1, 9.7, 10.3.2, 12.1.1, 12.1.2, 14.3.2, 15.1.4.2, 15.1.6.1, 15.2.5
Contract Time, Definition of
8.1.1
CONTRACTOR
3
Contractor, Definition of
3.1, 6.1.2
Contractor's Construction and Submittal
Schedules
3.10, 3.12.1, 3.12.2, 4.2.3, 6.1.3, 15.1.6.2

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

Contractor's Employees
2.2.4, 3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6, 10.2, 10.3, 11.3, 14.1, 14.2.1.1
Contractor's Liability Insurance
11.1
Contractor's Relationship with Separate Contractors and Owner's Forces
3.12.5, 3.14.2, 4.2.4, 6, 11.3, 12.2.4
Contractor's Relationship with Subcontractors
1.2.2, 2.2.4, 3.3.2, 3.18.1, 3.18.2, 4.2.4, 5, 9.6.2, 9.6.7, 9.10.2, 11.2, 11.3, 11.4
Contractor's Relationship with the Architect
1.1.2, 1.5, 2.3.3, 3.1.3, 3.2.2, 3.2.3, 3.2.4, 3.3.1, 3.4.2, 3.5.1, 3.7.4, 3.10, 3.11, 3.12, 3.16, 3.18, 4.2, 5.2, 6.2.2, 7, 8.3.1, 9.2, 9.3, 9.4, 9.5, 9.7, 9.8, 9.9, 10.2.6, 10.3, 11.3, 12, 13.4, 15.1.3, 15.2.1
Contractor's Representations
3.2.1, 3.2.2, 3.5, 3.12.6, 6.2.2, 8.2.1, 9.3.3, 9.8.2
Contractor's Responsibility for Those Performing the Work
3.3.2, 3.18, 5.3, 6.1.3, 6.2, 9.5.1, 10.2.8
Contractor's Review of Contract Documents
3.2
Contractor's Right to Stop the Work
2.2.2, 9.7
Contractor's Right to Terminate the Contract
14.1
Contractor's Submittals
3.10, 3.11, 3.12, 4.2.7, 5.2.1, 5.2.3, 9.2, 9.3, 9.8.2, 9.8.3, 9.9.1, 9.10.2, 9.10.3
Contractor's Superintendent
3.9, 10.2.6
Contractor's Supervision and Construction Procedures
1.2.2, 3.3, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4, 7.1.3, 7.3.4, 7.3.6, 8.2, 10, 12, 14, 15.1.4
Coordination and Correlation
1.2, 3.2.1, 3.3.1, 3.10, 3.12.6, 6.1.3, 6.2.1
Copies Furnished of Drawings and Specifications
1.5, 2.3.6, 3.11
Copyrights
1.5, **3.17**
Correction of Work
2.5, 3.7.3, 9.4.2, 9.8.2, 9.8.3, 9.9.1, 12.1.2, **12.2**, 12.3, 15.1.3.1, 15.1.3.2, 15.2.1
Correlation and Intent of the Contract Documents
1.2
Cost, Definition of
7.3.4
Costs
2.5, 3.2.4, 3.7.3, 3.8.2, 3.15.2, 5.4.2, 6.1.1, 6.2.3, 7.3.3.3, 7.3.4, 7.3.8, 7.3.9, 9.10.2, 10.3.2, 10.3.6, 11.2, 12.1.2, 12.2.1, 12.2.4, 13.4, 14
Cutting and Patching
3.14, 6.2.5
Damage to Construction of Owner or Separate Contractors
3.14.2, 6.2.4, 10.2.1.2, 10.2.5, 10.4, 12.2.4
Damage to the Work
3.14.2, 9.9.1, 10.2.1.2, 10.2.5, 10.4, 12.2.4
Damages, Claims for
3.2.4, 3.18, 6.1.1, 8.3.3, 9.5.1, 9.6.7, 10.3.3, 11.3.2, 11.3, 14.2.4, 15.1.7
Damages for Delay
6.2.3, 8.3.3, 9.5.1.6, 9.7, 10.3.2, 14.3.2
Date of Commencement of the Work, Definition of
8.1.2
Date of Substantial Completion, Definition of
8.1.3
Day, Definition of
8.1.4
Decisions of the Architect
3.7.4, 4.2.6, 4.2.7, 4.2.11, 4.2.12, 4.2.13, 6.3, 7.3.4, 7.3.9, 8.1.3, 8.3.1, 9.2, 9.4, 9.5.1, 9.8.4, 9.9.1, 13.4.2, 14.2.2, 14.2.4, 15.1, 15.2
Decisions to Withhold Certification
9.4.1, **9.5**, 9.7, 14.1.1.3
Defective or Nonconforming Work, Acceptance, Rejection and Correction of
2.5, 3.5, 4.2.6, 6.2.3, 9.5.1, 9.5.3, 9.6.6, 9.8.2, 9.9.3, 9.10.4, 12.2.1
Definitions
1.1, 2.1.1, 3.1.1, 3.5, 3.12.1, 3.12.2, 3.12.3, 4.1.1, 5.1, 6.1.2, 7.2.1, 7.3.1, 8.1, 9.1, 9.8.1, 15.1.1
Delays and Extensions of Time
3.2, **3.7.4**, 5.2.3, 7.2.1, 7.3.1, **7.4**, **8.3**, 9.5.1, **9.7**, 10.3.2, **10.4**, 14.3.2, **15.1.6**, 15.2.5
Digital Data Use and Transmission
1.7
Disputes
6.3, 7.3.9, 15.1, 15.2
Documents and Samples at the Site
3.11
Drawings, Definition of
1.1.5
Drawings and Specifications, Use and Ownership of
3.11
Effective Date of Insurance
8.2.2
Emergencies
10.4, 14.1.1.2, **15.1.5**
Employees, Contractor's
3.3.2, 3.4.3, 3.8.1, 3.9, 3.18.2, 4.2.3, 4.2.6, 10.2, 10.3.3, 11.3, 14.1, 14.2.1.1
Equipment, Labor, or Materials
1.1.3, 1.1.6, 3.4, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 4.2.6, 4.2.7, 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1, 10.2.4, 14.2.1.1, 14.2.1.2
Execution and Progress of the Work
1.1.3, 1.2.1, 1.2.2, 2.3.4, 2.3.6, 3.1, 3.3.1, 3.4.1, 3.7.1, 3.10.1, 3.12, 3.14, 4.2, 6.2.2, 7.1.3, 7.3.6, 8.2, 9.5.1, 9.9.1, 10.2, 10.3, 12.1, 12.2, 14.2, 14.3.1, 15.1.4

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

Extensions of Time
3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3, 7.4, 9.5.1, 9.7, 10.3.2, 10.4, 14.3, 15.1.6, **15.2.5**
Failure of Payment
9.5.1.3, **9.7**, 9.10.2, 13.5, 14.1.1.3, 14.2.1.2
Faulty Work
(See Defective or Nonconforming Work)
Final Completion and Final Payment
4.2.1, 4.2.9, 9.8.2, **9.10**, 12.3, 14.2.4, 14.4.3
Financial Arrangements, Owner's
2.2.1, 13.2.2, 14.1.1.4
GENERAL PROVISIONS
1
Governing Law
13.1
Guarantees (See Warranty)
Hazardous Materials and Substances
10.2.4, **10.3**
Identification of Subcontractors and Suppliers
5.2.1
Indemnification
3.17, **3.18**, 9.6.8, 9.10.2, 10.3.3, 11.3
Information and Services Required of the Owner
2.1.2, **2.2**, 2.3, 3.2.2, 3.12.10.1, 6.1.3, 6.1.4, 6.2.5, 9.6.1, 9.9.2, 9.10.3, 10.3.3, 11.2, 13.4.1, 13.4.2, 14.1.1.4, 14.1.4, 15.1.4
Initial Decision
15.2
Initial Decision Maker, Definition of
1.1.8
Initial Decision Maker, Decisions
14.2.4, 15.1.4.2, 15.2.1, 15.2.2, 15.2.3, 15.2.4, 15.2.5
Initial Decision Maker, Extent of Authority
14.2.4, 15.1.4.2, 15.2.1, 15.2.2, 15.2.3, 15.2.4, 15.2.5
Injury or Damage to Person or Property
10.2.8, 10.4
Inspections
3.1.3, 3.3.3, 3.7.1, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 12.2.1, 13.4
Instructions to Bidders
1.1.1
Instructions to the Contractor
3.2.4, 3.3.1, 3.8.1, 5.2.1, 7, 8.2.2, 12, 13.4.2
Instruments of Service, Definition of
1.1.7
Insurance
6.1.1, 7.3.4, 8.2.2, 9.3.2, 9.8.4, 9.9.1, 9.10.2, 10.2.5, **11**
Insurance, Notice of Cancellation or Expiration
11.1.4, 11.2.3
Insurance, Contractor's Liability
11.1
Insurance, Effective Date of
8.2.2, 14.4.2
Insurance, Owner's Liability
11.2
Insurance, Property
10.2.5, 11.2, 11.4, 11.5
Insurance, Stored Materials
9.3.2
INSURANCE AND BONDS
11
Insurance Companies, Consent to Partial Occupancy
9.9.1
Insured loss, Adjustment and Settlement of
11.5
Intent of the Contract Documents
1.2.1, 4.2.7, 4.2.12, 4.2.13
Interest
13.5
Interpretation
1.1.8, 1.2.3, **1.4**, 4.1.1, 5.1, 6.1.2, 15.1.1
Interpretations, Written
4.2.11, 4.2.12
Judgment on Final Award
15.4.2
Labor and Materials, Equipment
1.1.3, 1.1.6, **3.4**, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1, 10.2.4, 14.2.1.1, 14.2.1.2
Labor Disputes
8.3.1
Laws and Regulations
1.5, 2.3.2, 3.2.3, 3.2.4, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 9.9.1, 10.2.2, 13.1, 13.3.1, 13.4.2, 13.5, 14, 15.2.8, 15.4
Liens
2.1.2, 9.3.1, 9.3.3, 9.6.8, 9.10.2, 9.10.4, 15.2.8
Limitations, Statutes of
12.2.5, 15.1.2, 15.4.1.1
Limitations of Liability
3.2.2, 3.5, 3.12.10, 3.12.10.1, 3.17, 3.18.1, 4.2.6, 4.2.7, 6.2.2, 9.4.2, 9.6.4, 9.6.7, 9.6.8, 10.2.5, 10.3.3, 11.3, 12.2.5, 13.3.1
Limitations of Time
2.1.2, 2.2, 2.5, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2.7, 5.2, 5.3, 5.4.1, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3, 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 12.2, 13.4, 14, 15, 15.1.2, 15.1.3, 15.1.5
Materials, Hazardous
10.2.4, **10.3**
Materials, Labor, Equipment and
1.1.3, 1.1.6, 3.4.1, 3.5, 3.8.2, 3.8.3, 3.12, 3.13, 3.15.1, 5.2.1, 6.2.1, 7.3.4, 9.3.2, 9.3.3, 9.5.1.3, 9.10.2, 10.2.1.2, 10.2.4, 14.2.1.1, 14.2.1.2
Means, Methods, Techniques, Sequences and Procedures of Construction
3.3.1, 3.12.10, 4.2.2, 4.2.7, 9.4.2
Mechanic's Lien
2.1.2, 9.3.1, 9.3.3, 9.6.8, 9.10.2, 9.10.4, 15.2.8
Mediation
8.3.1, 15.1.3.2, 15.2.1, 15.2.5, 15.2.6, **15.3**, 15.4.1, 15.4.1.1
Minor Changes in the Work
1.1.1, 3.4.2, 3.12.8, 4.2.8, 7.1, **7.4**

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

MISCELLANEOUS PROVISIONS
13
Modifications, Definition of
1.1.1
Modifications to the Contract
1.1.1, 1.1.2, 2.5, 3.11, 4.1.2, 4.2.1, 5.2.3, 7, 8.3.1, 9.7, 10.3.2
Mutual Responsibility
6.2
Nonconforming Work, Acceptance of
9.6.6, 9.9.3, **12.3**
Nonconforming Work, Rejection and Correction of
2.4, 2.5, 3.5, 4.2.6, 6.2.4, 9.5.1, 9.8.2, 9.9.3, 9.10.4, 12.2
Notice
1.6, 1.6.1, 1.6.2, 2.1.2, 2.2.2., 2.2.3, 2.2.4, 2.5, 3.2.4, 3.3.1, 3.7.4, 3.7.5, 3.9.2, 3.12.9, 3.12.10, 5.2.1, 7.4, 8.2.2 9.6.8, 9.7, 9.10.1, 10.2.8, 10.3.2, 11.5, 12.2.2.1, 13.4.1, 13.4.2, 14.1, 14.2.2, 14.4.2, 15.1.3, 15.1.5, 15.1.6, 15.4.1
Notice of Cancellation or Expiration of Insurance
11.1.4, 11.2.3
Notice of Claims
1.6.2, 2.1.2, 3.7.4, 9.6.8, 10.2.8, **15.1.3**, 15.1.5, 15.1.6, 15.2.8, 15.3.2, 15.4.1
Notice of Testing and Inspections
13.4.1, 13.4.2
Observations, Contractor's
3.2, 3.7.4
Occupancy
2.3.1, 9.6.6, 9.8
Orders, Written
1.1.1, 2.4, 3.9.2, 7, 8.2.2, 11.5, 12.1, 12.2.2.1, 13.4.2, 14.3.1
OWNER
2
Owner, Definition of
2.1.1
Owner, Evidence of Financial Arrangements
2.2, 13.2.2, 14.1.1.4
Owner, Information and Services Required of the
2.1.2, **2.2**, 2.3, 3.2.2, 3.12.10, 6.1.3, 6.1.4, 6.2.5, 9.3.2, 9.6.1, 9.6.4, 9.9.2, 9.10.3, 10.3.3, 11.2, 13.4.1, 13.4.2, 14.1.1.4, 14.1.4, 15.1.4
Owner's Authority
1.5, 2.1.1, 2.3.32.4, 2.5, 3.4.2, 3.8.1, 3.12.10, 3.14.2, 4.1.2, 4.2.4, 4.2.9, 5.2.1, 5.2.4, 5.4.1, 6.1, 6.3, 7.2.1, 7.3.1, 8.2.2, 8.3.1, 9.3.2, 9.5.1, 9.6.4, 9.9.1, 9.10.2, 10.3.2, 11.4, 11.5, 12.2.2, 12.3, 13.2.2, 14.3, 14.4, 15.2.7
Owner's Insurance
11.2
Owner's Relationship with Subcontractors
1.1.2, 5.2, 5.3, 5.4, 9.6.4, 9.10.2, 14.2.2
Owner's Right to Carry Out the Work
2.5, 14.2.2
Owner's Right to Clean Up
6.3
Owner's Right to Perform Construction and to Award Separate Contracts
6.1
Owner's Right to Stop the Work
2.4
Owner's Right to Suspend the Work
14.3
Owner's Right to Terminate the Contract
14.2, 14.4
Ownership and Use of Drawings, Specifications and Other Instruments of Service
1.1.1, 1.1.6, 1.1.7, **1.5**, 2.3.6, 3.2.2, 3.11, 3.17, 4.2.12, 5.3
Partial Occupancy or Use
9.6.6, **9.9**
Patching, Cutting and
3.14, 6.2.5
Patents
3.17
Payment, Applications for
4.2.5, 7.3.9, 9.2, **9.3**, 9.4, 9.5, 9.6.3, 9.7, 9.8.5, 9.10.1, 14.2.3, 14.2.4, 14.4.3
Payment, Certificates for
4.2.5, 4.2.9, 9.3.3, **9.4**, 9.5, 9.6.1, 9.6.6, 9.7, 9.10.1, 9.10.3, 14.1.1.3, 14.2.4
Payment, Failure of
9.5.1.3, **9.7**, 9.10.2, 13.5, 14.1.1.3, 14.2.1.2
Payment, Final
4.2.1, 4.2.9, **9.10**, 12.3, 14.2.4, 14.4.3
Payment Bond, Performance Bond and
7.3.4.4, 9.6.7, 9.10.3, **11.1.2**
Payments, Progress
9.3, **9.6**, 9.8.5, 9.10.3, 14.2.3, 15.1.4
PAYMENTS AND COMPLETION
9
Payments to Subcontractors
5.4.2, 9.5.1.3, 9.6.2, 9.6.3, 9.6.4, 9.6.7, 14.2.1.2
PCB
10.3.1
Performance Bond and Payment Bond
7.3.4.4, 9.6.7, 9.10.3, **11.1.2**
Permits, Fees, Notices and Compliance with Laws
2.3.1, **3.7**, 3.13, 7.3.4.4, 10.2.2
PERSONS AND PROPERTY, PROTECTION OF
10
Polychlorinated Biphenyl
10.3.1
Product Data, Definition of
3.12.2
Product Data and Samples, Shop Drawings
3.11, **3.12**, 4.2.7
Progress and Completion
4.2.2, **8.2**, 9.8, 9.9.1, 14.1.4, 15.1.4
Progress Payments
9.3, **9.6**, 9.8.5, 9.10.3, 14.2.3, 15.1.4

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

Project, Definition of
1.1.4
Project Representatives
4.2.10
Property Insurance
10.2.5, **11.2**
Proposal Requirements
1.1.1
PROTECTION OF PERSONS AND PROPERTY
10
Regulations and Laws
1.5, 2.3.2, 3.2.3, 3.6, 3.7, 3.12.10, 3.13, 9.6.4, 9.9.1, 10.2.2, 13.1, 13.3, 13.4.1, 13.4.2, 13.5, 14, 15.2.8, 15.4
Rejection of Work
4.2.6, 12.2.1
Releases and Waivers of Liens
9.3.1, 9.10.2
Representations
3.2.1, 3.5, 3.12.6, 8.2.1, 9.3.3, 9.4.2, 9.5.1, 9.10.1
Representatives
2.1.1, 3.1.1, 3.9, 4.1.1, 4.2.10, 13.2.1
Responsibility for Those Performing the Work
3.3.2, 3.18, 4.2.2, 4.2.3, 5.3, 6.1.3, 6.2, 6.3, 9.5.1, 10
Retainage
9.3.1, 9.6.2, 9.8.5, 9.9.1, 9.10.2, 9.10.3
Review of Contract Documents and Field Conditions by Contractor
3.2, 3.12.7, 6.1.3
Review of Contractor's Submittals by Owner and Architect
3.10.1, 3.10.2, 3.11, 3.12, 4.2, 5.2, 6.1.3, 9.2, 9.8.2
Review of Shop Drawings, Product Data and Samples by Contractor
3.12
Rights and Remedies
1.1.2, 2.4, 2.5, 3.5, 3.7.4, 3.15.2, 4.2.6, 5.3, 5.4, 6.1, 6.3, 7.3.1, 8.3, 9.5.1, 9.7, 10.2.5, 10.3, 12.2.1, 12.2.2, 12.2.4, **13.3**, 14, 15.4
Royalties, Patents and Copyrights
3.17
Rules and Notices for Arbitration
15.4.1
Safety of Persons and Property
10.2, 10.4
Safety Precautions and Programs
3.3.1, 4.2.2, 4.2.7, 5.3, **10.1**, 10.2, 10.4
Samples, Definition of
3.12.3
Samples, Shop Drawings, Product Data and
3.11, **3.12**, 4.2.7
Samples at the Site, Documents and
3.11
Schedule of Values
9.2, 9.3.1
Schedules, Construction
3.10, 3.12.1, 3.12.2, 6.1.3, 15.1.6.2
Separate Contracts and Contractors
1.1.4, 3.12.5, 3.14.2, 4.2.4, 4.2.7, 6, 8.3.1, 12.1.2
Separate Contractors, Definition of
6.1.1
Shop Drawings, Definition of
3.12.1
Shop Drawings, Product Data and Samples
3.11, **3.12**, 4.2.7
Site, Use of
3.13, 6.1.1, 6.2.1
Site Inspections
3.2.2, 3.3.3, 3.7.1, 3.7.4, 4.2, 9.9.2, 9.4.2, 9.10.1, 13.4
Site Visits, Architect's
3.7.4, 4.2.2, 4.2.9, 9.4.2, 9.5.1, 9.9.2, 9.10.1, 13.4
Special Inspections and Testing
4.2.6, 12.2.1, 13.4
Specifications, Definition of
1.1.6
Specifications
1.1.1, **1.1.6**, 1.2.2, 1.5, 3.12.10, 3.17, 4.2.14
Statute of Limitations
15.1.2, 15.4.1.1
Stopping the Work
2.2.2, 2.4, 9.7, 10.3, 14.1
Stored Materials
6.2.1, 9.3.2, 10.2.1.2, 10.2.4
Subcontractor, Definition of
5.1.1
SUBCONTRACTORS
5
Subcontractors, Work by
1.2.2, 3.3.2, 3.12.1, 3.18, 4.2.3, 5.2.3, 5.3, 5.4, 9.3.1.2, 9.6.7
Subcontractual Relations
5.3, 5.4, 9.3.1.2, 9.6, 9.10, 10.2.1, 14.1, 14.2.1
Submittals
3.10, 3.11, 3.12, 4.2.7, 5.2.1, 5.2.3, 7.3.4, 9.2, 9.3, 9.8, 9.9.1, 9.10.2, 9.10.3
Submittal Schedule
3.10.2, 3.12.5, 4.2.7
Subrogation, Waivers of
6.1.1, **11.3**
Substances, Hazardous
10.3
Substantial Completion
4.2.9, 8.1.1, 8.1.3, 8.2.3, 9.4.2, **9.8**, 9.9.1, 9.10.3, 12.2, 15.1.2
Substantial Completion, Definition of
9.8.1
Substitution of Subcontractors
5.2.3, 5.2.4
Substitution of Architect
2.3.3
Substitutions of Materials
3.4.2, 3.5, 7.3.8
Sub-subcontractor, Definition of
5.1.2

Init.
/

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

Subsurface Conditions
3.7.4
Successors and Assigns
13.2
Superintendent
3.9, 10.2.6
Supervision and Construction Procedures
1.2.2, **3.3**, 3.4, 3.12.10, 4.2.2, 4.2.7, 6.1.3, 6.2.4, 7.1.3, 7.3.4, 8.2, 8.3.1, 9.4.2, 10, 12, 14, 15.1.4
Suppliers
1.5, 3.12.1, 4.2.4, 4.2.6, 5.2.1, 9.3, 9.4.2, 9.5.4, 9.6, 9.10.5, 14.2.1
Surety
5.4.1.2, 9.6.8, 9.8.5, 9.10.2, 9.10.3, 11.1.2, 14.2.2, 15.2.7
Surety, Consent of
9.8.5, 9.10.2, 9.10.3
Surveys
1.1.7, 2.3.4
Suspension by the Owner for Convenience
14.3
Suspension of the Work
3.7.5, 5.4.2, 14.3
Suspension or Termination of the Contract
5.4.1.1, 14
Taxes
3.6, 3.8.2.1, 7.3.4.4
Termination by the Contractor
14.1, 15.1.7
Termination by the Owner for Cause
5.4.1.1, **14.2,** 15.1.7
Termination by the Owner for Convenience
14.4
Termination of the Architect
2.3.3
Termination of the Contractor Employment
14.2.2

TERMINATION OR SUSPENSION OF THE CONTRACT
14
Tests and Inspections
3.1.3, 3.3.3, 3.7.1, 4.2.2, 4.2.6, 4.2.9, 9.4.2, 9.8.3, 9.9.2, 9.10.1, 10.3.2, 12.2.1, **13.4**
TIME
8
Time, Delays and Extensions of
3.2.4, 3.7.4, 5.2.3, 7.2.1, 7.3.1, 7.4, **8.3**, 9.5.1, 9.7, 10.3.2, 10.4, 14.3.2, 15.1.6, 15.2.5
Time Limits
2.1.2, 2.2, 2.5, 3.2.2, 3.10, 3.11, 3.12.5, 3.15.1, 4.2, 5.2, 5.3, 5.4, 6.2.4, 7.3, 7.4, 8.2, 9.2, 9.3.1, 9.3.3, 9.4.1, 9.5, 9.6, 9.7, 9.8, 9.9, 9.10, 12.2, 13.4, 14, 15.1.2, 15.1.3, 15.4
Time Limits on Claims
3.7.4, 10.2.8, 15.1.2, 15.1.3
Title to Work
9.3.2, 9.3.3
UNCOVERING AND CORRECTION OF WORK
12
Uncovering of Work
12.1
Unforeseen Conditions, Concealed or Unknown
3.7.4, 8.3.1, 10.3
Unit Prices
7.3.3.2, 9.1.2
Use of Documents
1.1.1, 1.5, 2.3.6, 3.12.6, 5.3
Use of Site
3.13, 6.1.1, 6.2.1
Values, Schedule of
9.2, 9.3.1
Waiver of Claims by the Architect
13.3.2
Waiver of Claims by the Contractor
9.10.5, 13.3.2, **15.1.7**
Waiver of Claims by the Owner
9.9.3, 9.10.3, 9.10.4, 12.2.2.1, 13.3.2, 14.2.4, **15.1.7**
Waiver of Consequential Damages
14.2.4, 15.1.7
Waiver of Liens
9.3, 9.10.2, 9.10.4
Waivers of Subrogation
6.1.1, **11.3**
Warranty
3.5, 4.2.9, 9.3.3, 9.8.4, 9.9.1, 9.10.2, 9.10.4, 12.2.2, 15.1.2
Weather Delays
8.3, 15.1.6.2
Work, Definition of
1.1.3
Written Consent
1.5.2, 3.4.2, 3.7.4, 3.12.8, 3.14.2, 4.1.2, 9.3.2, 9.10.3, 13.2, 13.3.2, 15.4.4.2
Written Interpretations
4.2.11, 4.2.12
Written Orders
1.1.1, 2.4, 3.9, 7, 8.2.2, 12.1, 12.2, 13.4.2, 14.3.1

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

ARTICLE 1 GENERAL PROVISIONS

§ 1.1 Basic Definitions

§ 1.1.1 The Contract Documents

The Contract Documents are enumerated in the Agreement between the Owner and Contractor (hereinafter the Agreement) and consist of the Agreement, Conditions of the Contract (General, Supplementary and other Conditions), Drawings, Specifications, Addenda issued prior to execution of the Contract, other documents listed in the Agreement, and Modifications issued after execution of the Contract. A Modification is (1) a written amendment to the Contract signed by both parties, (2) a Change Order, (3) a Construction Change Directive, or (4) a written order for a minor change in the Work issued by the Architect. Unless specifically enumerated in the Agreement, the Contract Documents do not include the advertisement or invitation to bid, Instructions to Bidders, sample forms, other information furnished by the Owner in anticipation of receiving bids or proposals, the Contractor's bid or proposal, or portions of Addenda relating to bidding or proposal requirements.

§ 1.1.2 The Contract

The Contract Documents form the Contract for Construction. The Contract represents the entire and integrated agreement between the parties hereto and supersedes prior negotiations, representations, or agreements, either written or oral. The Contract may be amended or modified only by a Modification. The Contract Documents shall not be construed to create a contractual relationship of any kind (1) between the Contractor and the Architect or the Architect's consultants, (2) between the Owner and a Subcontractor or a Sub-subcontractor, (3) between the Owner and the Architect or the Architect's consultants, or (4) between any persons or entities other than the Owner and the Contractor. The Architect shall, however, be entitled to performance and enforcement of obligations under the Contract intended to facilitate performance of the Architect's duties.

§ 1.1.3 The Work

The term "Work" means the construction and services required by the Contract Documents, whether completed or partially completed, and includes all other labor, materials, equipment, and services provided or to be provided by the Contractor to fulfill the Contractor's obligations. The Work may constitute the whole or a part of the Project.

§ 1.1.4 The Project

The Project is the total construction of which the Work performed under the Contract Documents may be the whole or a part and which may include construction by the Owner and by Separate Contractors.

§ 1.1.5 The Drawings

The Drawings are the graphic and pictorial portions of the Contract Documents showing the design, location and dimensions of the Work, generally including plans, elevations, sections, details, schedules, and diagrams.

§ 1.1.6 The Specifications

The Specifications are that portion of the Contract Documents consisting of the written requirements for materials, equipment, systems, standards and workmanship for the Work, and performance of related services.

§ 1.1.7 Instruments of Service

Instruments of Service are representations, in any medium of expression now known or later developed, of the tangible and intangible creative work performed by the Architect and the Architect's consultants under their respective professional services agreements. Instruments of Service may include, without limitation, studies, surveys, models, sketches, drawings, specifications, and other similar materials.

§ 1.1.8 Initial Decision Maker

The Initial Decision Maker is the person identified in the Agreement to render initial decisions on Claims in accordance with Section 15.2. The Initial Decision Maker shall not show partiality to the Owner or Contractor and shall not be liable for results of interpretations or decisions rendered in good faith.

§ 1.2 Correlation and Intent of the Contract Documents

§ 1.2.1 The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary, and what is required by one shall be as binding as if required by all; performance by the Contractor shall be required only to the extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the indicated results.

Init.
/
AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 1.2.1.1 The invalidity of any provision of the Contract Documents shall not invalidate the Contract or its remaining provisions. If it is determined that any provision of the Contract Documents violates any law, or is otherwise invalid or unenforceable, then that provision shall be revised to the extent necessary to make that provision legal and enforceable. In such case the Contract Documents shall be construed, to the fullest extent permitted by law, to give effect to the parties' intentions and purposes in executing the Contract.

§ 1.2.2 Organization of the Specifications into divisions, sections and articles, and arrangement of Drawings shall not control the Contractor in dividing the Work among Subcontractors or in establishing the extent of Work to be performed by any trade.

§ 1.2.3 Unless otherwise stated in the Contract Documents, words that have well-known technical or construction industry meanings are used in the Contract Documents in accordance with such recognized meanings.

§ 1.3 Capitalization

Terms capitalized in these General Conditions include those that are (1) specifically defined, (2) the titles of numbered articles, or (3) the titles of other documents published by the American Institute of Architects.

§ 1.4 Interpretation

In the interest of brevity the Contract Documents frequently omit modifying words such as "all" and "any" and articles such as "the" and "an," but the fact that a modifier or an article is absent from one statement and appears in another is not intended to affect the interpretation of either statement.

§ 1.5 Ownership and Use of Drawings, Specifications, and Other Instruments of Service

§ 1.5.1 The Architect and the Architect's consultants shall be deemed the authors and owners of their respective Instruments of Service, including the Drawings and Specifications, and retain all common law, statutory, and other reserved rights in their Instruments of Service, including copyrights. The Contractor, Subcontractors, Sub-subcontractors, and suppliers shall not own or claim a copyright in the Instruments of Service. Submittal or distribution to meet official regulatory requirements or for other purposes in connection with the Project is not to be construed as publication in derogation of the Architect's or Architect's consultants' reserved rights.

§ 1.5.2 The Contractor, Subcontractors, Sub-subcontractors, and suppliers are authorized to use and reproduce the Instruments of Service provided to them, subject to any protocols established pursuant to Sections 1.7 and 1.8, solely and exclusively for execution of the Work. All copies made under this authorization shall bear the copyright notice, if any, shown on the Instruments of Service. The Contractor, Subcontractors, Sub-subcontractors, and suppliers may not use the Instruments of Service on other projects or for additions to the Project outside the scope of the Work without the specific written consent of the Owner, Architect, and the Architect's consultants.

§ 1.6 Notice

§ 1.6.1 Except as otherwise provided in Section 1.6.2, where the Contract Documents require one party to notify or give notice to the other party, such notice shall be provided in writing to the designated representative of the party to whom the notice is addressed and shall be deemed to have been duly served if delivered in person, by mail, by courier, or by electronic transmission if a method for electronic transmission is set forth in the Agreement.

§ 1.6.2 Notice of Claims as provided in Section 15.1.3 shall be provided in writing and shall be deemed to have been duly served only if delivered to the designated representative of the party to whom the notice is addressed by certified or registered mail, or by courier providing proof of delivery.

§ 1.7 Digital Data Use and Transmission

The parties shall agree upon protocols governing the transmission and use of Instruments of Service or any other information or documentation in digital form. The parties will use AIA Document E203™–2013, Building Information Modeling and Digital Data Exhibit, to establish the protocols for the development, use, transmission, and exchange of digital data.

§ 1.8 Building Information Models Use and Reliance

Any use of, or reliance on, all or a portion of a building information model without agreement to protocols governing the use of, and reliance on, the information contained in the model and without having those protocols set forth in AIA Document E203™–2013, Building Information Modeling and Digital Data Exhibit, and the requisite AIA Document

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

G202™–2013, Project Building Information Modeling Protocol Form, shall be at the using or relying party's sole risk and without liability to the other party and its contractors or consultants, the authors of, or contributors to, the building information model, and each of their agents and employees.

ARTICLE 2 OWNER

§ 2.1 General

§ 2.1.1 The Owner is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Owner shall designate in writing a representative who shall have express authority to bind the Owner with respect to all matters requiring the Owner's approval or authorization. Except as otherwise provided in Section 4.2.1, the Architect does not have such authority. The term "Owner" means the Owner or the Owner's authorized representative.

§ 2.1.2 The Owner shall furnish to the Contractor, within fifteen days after receipt of a written request, information necessary and relevant for the Contractor to evaluate, give notice of, or enforce mechanic's lien rights. Such information shall include a correct statement of the record legal title to the property on which the Project is located, usually referred to as the site, and the Owner's interest therein.

§ 2.2 Evidence of the Owner's Financial Arrangements

§ 2.2.1 Prior to commencement of the Work and upon written request by the Contractor, the Owner shall furnish to the Contractor reasonable evidence that the Owner has made financial arrangements to fulfill the Owner's obligations under the Contract. The Contractor shall have no obligation to commence the Work until the Owner provides such evidence. If commencement of the Work is delayed under this Section 2.2.1, the Contract Time shall be extended appropriately.

§ 2.2.2 Following commencement of the Work and upon written request by the Contractor, the Owner shall furnish to the Contractor reasonable evidence that the Owner has made financial arrangements to fulfill the Owner's obligations under the Contract only if (1) the Owner fails to make payments to the Contractor as the Contract Documents require; (2) the Contractor identifies in writing a reasonable concern regarding the Owner's ability to make payment when due; or (3) a change in the Work materially changes the Contract Sum. If the Owner fails to provide such evidence, as required, within fourteen days of the Contractor's request, the Contractor may immediately stop the Work and, in that event, shall notify the Owner that the Work has stopped. However, if the request is made because a change in the Work materially changes the Contract Sum under (3) above, the Contractor may immediately stop only that portion of the Work affected by the change until reasonable evidence is provided. If the Work is stopped under this Section 2.2.2, the Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shutdown, delay and start-up, plus interest as provided in the Contract Documents.

§ 2.2.3 After the Owner furnishes evidence of financial arrangements under this Section 2.2, the Owner shall not materially vary such financial arrangements without prior notice to the Contractor.

§ 2.2.4 Where the Owner has designated information furnished under this Section 2.2 as "confidential," the Contractor shall keep the information confidential and shall not disclose it to any other person. However, the Contractor may disclose "confidential" information, after seven (7) days' notice to the Owner, where disclosure is required by law, including a subpoena or other form of compulsory legal process issued by a court or governmental entity, or by court or arbitrator(s) order. The Contractor may also disclose "confidential" information to its employees, consultants, sureties, Subcontractors and their employees, Sub-subcontractors, and others who need to know the content of such information solely and exclusively for the Project and who agree to maintain the confidentiality of such information.

§ 2.3 Information and Services Required of the Owner

§ 2.3.1 Except for permits and fees that are the responsibility of the Contractor under the Contract Documents, including those required under Section 3.7.1, the Owner shall secure and pay for necessary approvals, easements, assessments and charges required for construction, use or occupancy of permanent structures or for permanent changes in existing facilities.

§ 2.3.2 The Owner shall retain an architect lawfully licensed to practice architecture, or an entity lawfully practicing architecture, in the jurisdiction where the Project is located. That person or entity is identified as the Architect in the Agreement and is referred to throughout the Contract Documents as if singular in number.

Init.
/
AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 2.3.3 If the employment of the Architect terminates, the Owner shall employ a successor to whom the Contractor has no reasonable objection and whose status under the Contract Documents shall be that of the Architect.

§ 2.3.4 The Owner shall furnish surveys describing physical characteristics, legal limitations and utility locations for the site of the Project, and a legal description of the site. The Contractor shall be entitled to rely on the accuracy of information furnished by the Owner but shall exercise proper precautions relating to the safe performance of the Work.

§ 2.3.5 The Owner shall furnish information or services required of the Owner by the Contract Documents with reasonable promptness. The Owner shall also furnish any other information or services under the Owner's control and relevant to the Contractor's performance of the Work with reasonable promptness after receiving the Contractor's written request for such information or services.

§ 2.3.6 Unless otherwise provided in the Contract Documents, the Owner shall furnish to the Contractor one copy of the Contract Documents for purposes of making reproductions pursuant to Section 1.5.2.

§ 2.4 Owner's Right to Stop the Work

If the Contractor fails to correct Work that is not in accordance with the requirements of the Contract Documents as required by Section 12.2 or repeatedly fails to carry out Work in accordance with the Contract Documents, the Owner may issue a written order to the Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, the right of the Owner to stop the Work shall not give rise to a duty on the part of the Owner to exercise this right for the benefit of the Contractor or any other person or entity, except to the extent required by Section 6.1.3.

§ 2.5 Owner's Right to Carry Out the Work

If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents and fails within a ten-day period after receipt of notice from the Owner to commence and continue correction of such default or neglect with diligence and promptness, the Owner may, without prejudice to other remedies the Owner may have, correct such default or neglect. Such action by the Owner and amounts charged to the Contractor are both subject to prior approval of the Architect and the Architect may, pursuant to Section 9.5.1, withhold or nullify a Certificate for Payment in whole or in part, to the extent reasonably necessary to reimburse the Owner for the reasonable cost of correcting such deficiencies, including Owner's expenses and compensation for the Architect's additional services made necessary by such default, neglect, or failure. If current and future payments are not sufficient to cover such amounts, the Contractor shall pay the difference to the Owner. If the Contractor disagrees with the actions of the Owner or the Architect, or the amounts claimed as costs to the Owner, the Contractor may file a Claim pursuant to Article 15.

ARTICLE 3 CONTRACTOR

§ 3.1 General

§ 3.1.1 The Contractor is the person or entity identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number. The Contractor shall be lawfully licensed, if required in the jurisdiction where the Project is located. The Contractor shall designate in writing a representative who shall have express authority to bind the Contractor with respect to all matters under this Contract. The term "Contractor" means the Contractor or the Contractor's authorized representative.

§ 3.1.2 The Contractor shall perform the Work in accordance with the Contract Documents.

§ 3.1.3 The Contractor shall not be relieved of its obligations to perform the Work in accordance with the Contract Documents either by activities or duties of the Architect in the Architect's administration of the Contract, or by tests, inspections or approvals required or performed by persons or entities other than the Contractor.

§ 3.2 Review of Contract Documents and Field Conditions by Contractor

§ 3.2.1 Execution of the Contract by the Contractor is a representation that the Contractor has visited the site, become generally familiar with local conditions under which the Work is to be performed, and correlated personal observations with requirements of the Contract Documents.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 3.2.2 Because the Contract Documents are complementary, the Contractor shall, before starting each portion of the Work, carefully study and compare the various Contract Documents relative to that portion of the Work, as well as the information furnished by the Owner pursuant to Section 2.3.4, shall take field measurements of any existing conditions related to that portion of the Work, and shall observe any conditions at the site affecting it. These obligations are for the purpose of facilitating coordination and construction by the Contractor and are not for the purpose of discovering errors, omissions, or inconsistencies in the Contract Documents; however, the Contractor shall promptly report to the Architect any errors, inconsistencies or omissions discovered by or made known to the Contractor as a request for information in such form as the Architect may require. It is recognized that the Contractor's review is made in the Contractor's capacity as a contractor and not as a licensed design professional, unless otherwise specifically provided in the Contract Documents.

§ 3.2.3 The Contractor is not required to ascertain that the Contract Documents are in accordance with applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, but the Contractor shall promptly report to the Architect any nonconformity discovered by or made known to the Contractor as a request for information in such form as the Architect may require.

§ 3.2.4 If the Contractor believes that additional cost or time is involved because of clarifications or instructions the Architect issues in response to the Contractor's notices or requests for information pursuant to Sections 3.2.2 or 3.2.3, the Contractor shall submit Claims as provided in Article 15. If the Contractor fails to perform the obligations of Sections 3.2.2 or 3.2.3, the Contractor shall pay such costs and damages to the Owner, subject to Section 15.1.7, as would have been avoided if the Contractor had performed such obligations. If the Contractor performs those obligations, the Contractor shall not be liable to the Owner or Architect for damages resulting from errors, inconsistencies or omissions in the Contract Documents, for differences between field measurements or conditions and the Contract Documents, or for nonconformities of the Contract Documents to applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities.

§ 3.3 Supervision and Construction Procedures

§ 3.3.1 The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for, and have control over, construction means, methods, techniques, sequences, and procedures, and for coordinating all portions of the Work under the Contract. If the Contract Documents give specific instructions concerning construction means, methods, techniques, sequences, or procedures, the Contractor shall evaluate the jobsite safety thereof and shall be solely responsible for the jobsite safety of such means, methods, techniques, sequences, or procedures. If the Contractor determines that such means, methods, techniques, sequences or procedures may not be safe, the Contractor shall give timely notice to the Owner and Architect, and shall propose alternative means, methods, techniques, sequences, or procedures. The Architect shall evaluate the proposed alternative solely for conformance with the design intent for the completed construction. Unless the Architect objects to the Contractor's proposed alternative, the Contractor shall perform the Work using its alternative means, methods, techniques, sequences, or procedures.

§ 3.3.2 The Contractor shall be responsible to the Owner for acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons or entities performing portions of the Work for, or on behalf of, the Contractor or any of its Subcontractors.

§ 3.3.3 The Contractor shall be responsible for inspection of portions of Work already performed to determine that such portions are in proper condition to receive subsequent Work.

§ 3.4 Labor and Materials

§ 3.4.1 Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for proper execution and completion of the Work, whether temporary or permanent and whether or not incorporated or to be incorporated in the Work.

§ 3.4.2 Except in the case of minor changes in the Work approved by the Architect in accordance with Section 3.12.8 or ordered by the Architect in accordance with Section 7.4, the Contractor may make substitutions only with the consent of the Owner, after evaluation by the Architect and in accordance with a Change Order or Construction Change Directive.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 3.4.3 The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Work. The Contractor shall not permit employment of unfit persons or persons not properly skilled in tasks assigned to them.

§ 3.5 Warranty

§ 3.5.1 The Contractor warrants to the Owner and Architect that materials and equipment furnished under the Contract will be of good quality and new unless the Contract Documents require or permit otherwise. The Contractor further warrants that the Work will conform to the requirements of the Contract Documents and will be free from defects, except for those inherent in the quality of the Work the Contract Documents require or permit. Work, materials, or equipment not conforming to these requirements may be considered defective. The Contractor's warranty excludes remedy for damage or defect caused by abuse, alterations to the Work not executed by the Contractor, improper or insufficient maintenance, improper operation, or normal wear and tear and normal usage. If required by the Architect, the Contractor shall furnish satisfactory evidence as to the kind and quality of materials and equipment.

§ 3.5.2 All material, equipment, or other special warranties required by the Contract Documents shall be issued in the name of the Owner, or shall be transferable to the Owner, and shall commence in accordance with Section 9.8.4.

§ 3.6 Taxes

The Contractor shall pay sales, consumer, use and similar taxes for the Work provided by the Contractor that are legally enacted when bids are received or negotiations concluded, whether or not yet effective or merely scheduled to go into effect.

§ 3.7 Permits, Fees, Notices and Compliance with Laws

§ 3.7.1 Unless otherwise provided in the Contract Documents, the Contractor shall secure and pay for the building permit as well as for other permits, fees, licenses, and inspections by government agencies necessary for proper execution and completion of the Work that are customarily secured after execution of the Contract and legally required at the time bids are received or negotiations concluded.

§ 3.7.2 The Contractor shall comply with and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities applicable to performance of the Work.

§ 3.7.3 If the Contractor performs Work knowing it to be contrary to applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of public authorities, the Contractor shall assume appropriate responsibility for such Work and shall bear the costs attributable to correction.

§ 3.7.4 Concealed or Unknown Conditions

If the Contractor encounters conditions at the site that are (1) subsurface or otherwise concealed physical conditions that differ materially from those indicated in the Contract Documents or (2) unknown physical conditions of an unusual nature that differ materially from those ordinarily found to exist and generally recognized as inherent in construction activities of the character provided for in the Contract Documents, the Contractor shall promptly provide notice to the Owner and the Architect before conditions are disturbed and in no event later than 14 days after first observance of the conditions. The Architect will promptly investigate such conditions and, if the Architect determines that they differ materially and cause an increase or decrease in the Contractor's cost of, or time required for, performance of any part of the Work, will recommend that an equitable adjustment be made in the Contract Sum or Contract Time, or both. If the Architect determines that the conditions at the site are not materially different from those indicated in the Contract Documents and that no change in the terms of the Contract is justified, the Architect shall promptly notify the Owner and Contractor, stating the reasons. If either party disputes the Architect's determination or recommendation, that party may submit a Claim as provided in Article 15.

§ 3.7.5 If, in the course of the Work, the Contractor encounters human remains or recognizes the existence of burial markers, archaeological sites or wetlands not indicated in the Contract Documents, the Contractor shall immediately suspend any operations that would affect them and shall notify the Owner and Architect. Upon receipt of such notice, the Owner shall promptly take any action necessary to obtain governmental authorization required to resume the operations. The Contractor shall continue to suspend such operations until otherwise instructed by the Owner but shall continue with all other operations that do not affect those remains or features. Requests for adjustments in the Contract Sum and Contract Time arising from the existence of such remains or features may be made as provided in Article 15.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 3.8 Allowances

§ 3.8.1 The Contractor shall include in the Contract Sum all allowances stated in the Contract Documents. Items covered by allowances shall be supplied for such amounts and by such persons or entities as the Owner may direct, but the Contractor shall not be required to employ persons or entities to whom the Contractor has reasonable objection.

§ 3.8.2 Unless otherwise provided in the Contract Documents,

- **.1** allowances shall cover the cost to the Contractor of materials and equipment delivered at the site and all required taxes, less applicable trade discounts;
- **.2** Contractor's costs for unloading and handling at the site, labor, installation costs, overhead, profit, and other expenses contemplated for stated allowance amounts shall be included in the Contract Sum but not in the allowances; and
- **.3** whenever costs are more than or less than allowances, the Contract Sum shall be adjusted accordingly by Change Order. The amount of the Change Order shall reflect (1) the difference between actual costs and the allowances under Section 3.8.2.1 and (2) changes in Contractor's costs under Section 3.8.2.2.

§ 3.8.3 Materials and equipment under an allowance shall be selected by the Owner with reasonable promptness.

§ 3.9 Superintendent

§ 3.9.1 The Contractor shall employ a competent superintendent and necessary assistants who shall be in attendance at the Project site during performance of the Work. The superintendent shall represent the Contractor, and communications given to the superintendent shall be as binding as if given to the Contractor.

§ 3.9.2 The Contractor, as soon as practicable after award of the Contract, shall notify the Owner and Architect of the name and qualifications of a proposed superintendent. Within 14 days of receipt of the information, the Architect may notify the Contractor, stating whether the Owner or the Architect (1) has reasonable objection to the proposed superintendent or (2) requires additional time for review. Failure of the Architect to provide notice within the 14-day period shall constitute notice of no reasonable objection.

§ 3.9.3 The Contractor shall not employ a proposed superintendent to whom the Owner or Architect has made reasonable and timely objection. The Contractor shall not change the superintendent without the Owner's consent, which shall not unreasonably be withheld or delayed.

§ 3.10 Contractor's Construction and Submittal Schedules

§ 3.10.1 The Contractor, promptly after being awarded the Contract, shall submit for the Owner's and Architect's information a Contractor's construction schedule for the Work. The schedule shall contain detail appropriate for the Project, including (1) the date of commencement of the Work, interim schedule milestone dates, and the date of Substantial Completion; (2) an apportionment of the Work by construction activity; and (3) the time required for completion of each portion of the Work. The schedule shall provide for the orderly progression of the Work to completion and shall not exceed time limits current under the Contract Documents. The schedule shall be revised at appropriate intervals as required by the conditions of the Work and Project.

§ 3.10.2 The Contractor, promptly after being awarded the Contract and thereafter as necessary to maintain a current submittal schedule, shall submit a submittal schedule for the Architect's approval. The Architect's approval shall not be unreasonably delayed or withheld. The submittal schedule shall (1) be coordinated with the Contractor's construction schedule, and (2) allow the Architect reasonable time to review submittals. If the Contractor fails to submit a submittal schedule, or fails to provide submittals in accordance with the approved submittal schedule, the Contractor shall not be entitled to any increase in Contract Sum or extension of Contract Time based on the time required for review of submittals.

§ 3.10.3 The Contractor shall perform the Work in general accordance with the most recent schedules submitted to the Owner and Architect.

§ 3.11 Documents and Samples at the Site

The Contractor shall make available, at the Project site, the Contract Documents, including Change Orders, Construction Change Directives, and other Modifications, in good order and marked currently to indicate field changes and selections made during construction, and the approved Shop Drawings, Product Data, Samples, and similar required submittals. These shall be in electronic form or paper copy, available to the Architect and Owner, and

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

delivered to the Architect for submittal to the Owner upon completion of the Work as a record of the Work as constructed.

§ 3.12 Shop Drawings, Product Data and Samples

§ 3.12.1 Shop Drawings are drawings, diagrams, schedules, and other data specially prepared for the Work by the Contractor or a Subcontractor, Sub-subcontractor, manufacturer, supplier, or distributor to illustrate some portion of the Work.

§ 3.12.2 Product Data are illustrations, standard schedules, performance charts, instructions, brochures, diagrams, and other information furnished by the Contractor to illustrate materials or equipment for some portion of the Work.

§ 3.12.3 Samples are physical examples that illustrate materials, equipment, or workmanship, and establish standards by which the Work will be judged.

§ 3.12.4 Shop Drawings, Product Data, Samples, and similar submittals are not Contract Documents. Their purpose is to demonstrate how the Contractor proposes to conform to the information given and the design concept expressed in the Contract Documents for those portions of the Work for which the Contract Documents require submittals. Review by the Architect is subject to the limitations of Section 4.2.7. Informational submittals upon which the Architect is not expected to take responsive action may be so identified in the Contract Documents. Submittals that are not required by the Contract Documents may be returned by the Architect without action.

§ 3.12.5 The Contractor shall review for compliance with the Contract Documents, approve, and submit to the Architect, Shop Drawings, Product Data, Samples, and similar submittals required by the Contract Documents, in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness and in such sequence as to cause no delay in the Work or in the activities of the Owner or of Separate Contractors.

§ 3.12.6 By submitting Shop Drawings, Product Data, Samples, and similar submittals, the Contractor represents to the Owner and Architect that the Contractor has (1) reviewed and approved them, (2) determined and verified materials, field measurements and field construction criteria related thereto, or will do so, and (3) checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents.

§ 3.12.7 The Contractor shall perform no portion of the Work for which the Contract Documents require submittal and review of Shop Drawings, Product Data, Samples, or similar submittals, until the respective submittal has been approved by the Architect.

§ 3.12.8 The Work shall be in accordance with approved submittals except that the Contractor shall not be relieved of responsibility for deviations from the requirements of the Contract Documents by the Architect's approval of Shop Drawings, Product Data, Samples, or similar submittals, unless the Contractor has specifically notified the Architect of such deviation at the time of submittal and (1) the Architect has given written approval to the specific deviation as a minor change in the Work, or (2) a Change Order or Construction Change Directive has been issued authorizing the deviation. The Contractor shall not be relieved of responsibility for errors or omissions in Shop Drawings, Product Data, Samples, or similar submittals, by the Architect's approval thereof.

§ 3.12.9 The Contractor shall direct specific attention, in writing or on resubmitted Shop Drawings, Product Data, Samples, or similar submittals, to revisions other than those requested by the Architect on previous submittals. In the absence of such notice, the Architect's approval of a resubmission shall not apply to such revisions.

§ 3.12.10 The Contractor shall not be required to provide professional services that constitute the practice of architecture or engineering unless such services are specifically required by the Contract Documents for a portion of the Work or unless the Contractor needs to provide such services in order to carry out the Contractor's responsibilities for construction means, methods, techniques, sequences, and procedures. The Contractor shall not be required to provide professional services in violation of applicable law.

§ 3.12.10.1 If professional design services or certifications by a design professional related to systems, materials, or equipment are specifically required of the Contractor by the Contract Documents, the Owner and the Architect will specify all performance and design criteria that such services must satisfy. The Contractor shall be entitled to rely

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

upon the adequacy and accuracy of the performance and design criteria provided in the Contract Documents. The Contractor shall cause such services or certifications to be provided by an appropriately licensed design professional, whose signature and seal shall appear on all drawings, calculations, specifications, certifications, Shop Drawings, and other submittals prepared by such professional. Shop Drawings, and other submittals related to the Work, designed or certified by such professional, if prepared by others, shall bear such professional's written approval when submitted to the Architect. The Owner and the Architect shall be entitled to rely upon the adequacy and accuracy of the services, certifications, and approvals performed or provided by such design professionals, provided the Owner and Architect have specified to the Contractor the performance and design criteria that such services must satisfy. Pursuant to this Section 3.12.10, the Architect will review and approve or take other appropriate action on submittals only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents.

§ 3.12.10.2 If the Contract Documents require the Contractor's design professional to certify that the Work has been performed in accordance with the design criteria, the Contractor shall furnish such certifications to the Architect at the time and in the form specified by the Architect.

§ 3.13 Use of Site

The Contractor shall confine operations at the site to areas permitted by applicable laws, statutes, ordinances, codes, rules and regulations, lawful orders of public authorities, and the Contract Documents and shall not unreasonably encumber the site with materials or equipment.

§ 3.14 Cutting and Patching

§ 3.14.1 The Contractor shall be responsible for cutting, fitting, or patching required to complete the Work or to make its parts fit together properly. All areas requiring cutting, fitting, or patching shall be restored to the condition existing prior to the cutting, fitting, or patching, unless otherwise required by the Contract Documents.

§ 3.14.2 The Contractor shall not damage or endanger a portion of the Work or fully or partially completed construction of the Owner or Separate Contractors by cutting, patching, or otherwise altering such construction, or by excavation. The Contractor shall not cut or otherwise alter construction by the Owner or a Separate Contractor except with written consent of the Owner and of the Separate Contractor. Consent shall not be unreasonably withheld. The Contractor shall not unreasonably withhold, from the Owner or a Separate Contractor, its consent to cutting or otherwise altering the Work.

§ 3.15 Cleaning Up

§ 3.15.1 The Contractor shall keep the premises and surrounding area free from accumulation of waste materials and rubbish caused by operations under the Contract. At completion of the Work, the Contractor shall remove waste materials, rubbish, the Contractor's tools, construction equipment, machinery, and surplus materials from and about the Project.

§ 3.15.2 If the Contractor fails to clean up as provided in the Contract Documents, the Owner may do so and the Owner shall be entitled to reimbursement from the Contractor.

§ 3.16 Access to Work

The Contractor shall provide the Owner and Architect with access to the Work in preparation and progress wherever located.

§ 3.17 Royalties, Patents and Copyrights

The Contractor shall pay all royalties and license fees. The Contractor shall defend suits or claims for infringement of copyrights and patent rights and shall hold the Owner and Architect harmless from loss on account thereof, but shall not be responsible for defense or loss when a particular design, process, or product of a particular manufacturer or manufacturers is required by the Contract Documents, or where the copyright violations are contained in Drawings, Specifications, or other documents prepared by the Owner or Architect. However, if an infringement of a copyright or patent is discovered by, or made known to, the Contractor, the Contractor shall be responsible for the loss unless the information is promptly furnished to the Architect.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 3.18 Indemnification

§ 3.18.1 To the fullest extent permitted by law, the Contractor shall indemnify and hold harmless the Owner, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses, and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work, provided that such claim, damage, loss, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), but only to the extent caused by the negligent acts or omissions of the Contractor, a Subcontractor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, regardless of whether or not such claim, damage, loss, or expense is caused in part by a party indemnified hereunder. Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity that would otherwise exist as to a party or person described in this Section 3.18.

§ 3.18.2 In claims against any person or entity indemnified under this Section 3.18 by an employee of the Contractor, a Subcontractor, anyone directly or indirectly employed by them, or anyone for whose acts they may be liable, the indemnification obligation under Section 3.18.1 shall not be limited by a limitation on amount or type of damages, compensation, or benefits payable by or for the Contractor or a Subcontractor under workers' compensation acts, disability benefit acts, or other employee benefit acts.

ARTICLE 4 ARCHITECT

§ 4.1 General

§ 4.1.1 The Architect is the person or entity retained by the Owner pursuant to Section 2.3.2 and identified as such in the Agreement.

§ 4.1.2 Duties, responsibilities, and limitations of authority of the Architect as set forth in the Contract Documents shall not be restricted, modified, or extended without written consent of the Owner, Contractor, and Architect. Consent shall not be unreasonably withheld.

§ 4.2 Administration of the Contract

§ 4.2.1 The Architect will provide administration of the Contract as described in the Contract Documents and will be an Owner's representative during construction until the date the Architect issues the final Certificate for Payment. The Architect will have authority to act on behalf of the Owner only to the extent provided in the Contract Documents.

§ 4.2.2 The Architect will visit the site at intervals appropriate to the stage of construction, or as otherwise agreed with the Owner, to become generally familiar with the progress and quality of the portion of the Work completed, and to determine in general if the Work observed is being performed in a manner indicating that the Work, when fully completed, will be in accordance with the Contract Documents. However, the Architect will not be required to make exhaustive or continuous on-site inspections to check the quality or quantity of the Work. The Architect will not have control over, charge of, or responsibility for the construction means, methods, techniques, sequences or procedures, or for the safety precautions and programs in connection with the Work, since these are solely the Contractor's rights and responsibilities under the Contract Documents.

§ 4.2.3 On the basis of the site visits, the Architect will keep the Owner reasonably informed about the progress and quality of the portion of the Work completed, and promptly report to the Owner (1) known deviations from the Contract Documents, (2) known deviations from the most recent construction schedule submitted by the Contractor, and (3) defects and deficiencies observed in the Work. The Architect will not be responsible for the Contractor's failure to perform the Work in accordance with the requirements of the Contract Documents. The Architect will not have control over or charge of, and will not be responsible for acts or omissions of, the Contractor, Subcontractors, or their agents or employees, or any other persons or entities performing portions of the Work.

§ 4.2.4 Communications

The Owner and Contractor shall include the Architect in all communications that relate to or affect the Architect's services or professional responsibilities. The Owner shall promptly notify the Architect of the substance of any direct communications between the Owner and the Contractor otherwise relating to the Project. Communications by and with the Architect's consultants shall be through the Architect. Communications by and with Subcontractors and suppliers shall be through the Contractor. Communications by and with Separate Contractors shall be through the Owner. The Contract Documents may specify other communication protocols.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 4.2.5 Based on the Architect's evaluations of the Contractor's Applications for Payment, the Architect will review and certify the amounts due the Contractor and will issue Certificates for Payment in such amounts.

§ 4.2.6 The Architect has authority to reject Work that does not conform to the Contract Documents. Whenever the Architect considers it necessary or advisable, the Architect will have authority to require inspection or testing of the Work in accordance with Sections 13.4.2 and 13.4.3, whether or not the Work is fabricated, installed or completed. However, neither this authority of the Architect nor a decision made in good faith either to exercise or not to exercise such authority shall give rise to a duty or responsibility of the Architect to the Contractor, Subcontractors, suppliers, their agents or employees, or other persons or entities performing portions of the Work.

§ 4.2.7 The Architect will review and approve, or take other appropriate action upon, the Contractor's submittals such as Shop Drawings, Product Data, and Samples, but only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents. The Architect's action will be taken in accordance with the submittal schedule approved by the Architect or, in the absence of an approved submittal schedule, with reasonable promptness while allowing sufficient time in the Architect's professional judgment to permit adequate review. Review of such submittals is not conducted for the purpose of determining the accuracy and completeness of other details such as dimensions and quantities, or for substantiating instructions for installation or performance of equipment or systems, all of which remain the responsibility of the Contractor as required by the Contract Documents. The Architect's review of the Contractor's submittals shall not relieve the Contractor of the obligations under Sections 3.3, 3.5, and 3.12. The Architect's review shall not constitute approval of safety precautions or of any construction means, methods, techniques, sequences, or procedures. The Architect's approval of a specific item shall not indicate approval of an assembly of which the item is a component.

§ 4.2.8 The Architect will prepare Change Orders and Construction Change Directives, and may order minor changes in the Work as provided in Section 7.4. The Architect will investigate and make determinations and recommendations regarding concealed and unknown conditions as provided in Section 3.7.4.

§ 4.2.9 The Architect will conduct inspections to determine the date or dates of Substantial Completion and the date of final completion; issue Certificates of Substantial Completion pursuant to Section 9.8; receive and forward to the Owner, for the Owner's review and records, written warranties and related documents required by the Contract and assembled by the Contractor pursuant to Section 9.10; and issue a final Certificate for Payment pursuant to Section 9.10.

§ 4.2.10 If the Owner and Architect agree, the Architect will provide one or more Project representatives to assist in carrying out the Architect's responsibilities at the site. The Owner shall notify the Contractor of any change in the duties, responsibilities and limitations of authority of the Project representatives.

§ 4.2.11 The Architect will interpret and decide matters concerning performance under, and requirements of, the Contract Documents on written request of either the Owner or Contractor. The Architect's response to such requests will be made in writing within any time limits agreed upon or otherwise with reasonable promptness.

§ 4.2.12 Interpretations and decisions of the Architect will be consistent with the intent of, and reasonably inferable from, the Contract Documents and will be in writing or in the form of drawings. When making such interpretations and decisions, the Architect will endeavor to secure faithful performance by both Owner and Contractor, will not show partiality to either, and will not be liable for results of interpretations or decisions rendered in good faith.

§ 4.2.13 The Architect's decisions on matters relating to aesthetic effect will be final if consistent with the intent expressed in the Contract Documents.

§ 4.2.14 The Architect will review and respond to requests for information about the Contract Documents. The Architect's response to such requests will be made in writing within any time limits agreed upon or otherwise with reasonable promptness. If appropriate, the Architect will prepare and issue supplemental Drawings and Specifications in response to the requests for information.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

ARTICLE 5 SUBCONTRACTORS

§ 5.1 Definitions

§ 5.1.1 A Subcontractor is a person or entity who has a direct contract with the Contractor to perform a portion of the Work at the site. The term "Subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Subcontractor or an authorized representative of the Subcontractor. The term "Subcontractor" does not include a Separate Contractor or the subcontractors of a Separate Contractor.

§ 5.1.2 A Sub-subcontractor is a person or entity who has a direct or indirect contract with a Subcontractor to perform a portion of the Work at the site. The term "Sub-subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Sub-subcontractor or an authorized representative of the Sub-subcontractor.

§ 5.2 Award of Subcontracts and Other Contracts for Portions of the Work

§ 5.2.1 Unless otherwise stated in the Contract Documents, the Contractor, as soon as practicable after award of the Contract, shall notify the Owner and Architect of the persons or entities proposed for each principal portion of the Work, including those who are to furnish materials or equipment fabricated to a special design. Within 14 days of receipt of the information, the Architect may notify the Contractor whether the Owner or the Architect (1) has reasonable objection to any such proposed person or entity or (2) requires additional time for review. Failure of the Architect to provide notice within the 14-day period shall constitute notice of no reasonable objection.

§ 5.2.2 The Contractor shall not contract with a proposed person or entity to whom the Owner or Architect has made reasonable and timely objection. The Contractor shall not be required to contract with anyone to whom the Contractor has made reasonable objection.

§ 5.2.3 If the Owner or Architect has reasonable objection to a person or entity proposed by the Contractor, the Contractor shall propose another to whom the Owner or Architect has no reasonable objection. If the proposed but rejected Subcontractor was reasonably capable of performing the Work, the Contract Sum and Contract Time shall be increased or decreased by the difference, if any, occasioned by such change, and an appropriate Change Order shall be issued before commencement of the substitute Subcontractor's Work. However, no increase in the Contract Sum or Contract Time shall be allowed for such change unless the Contractor has acted promptly and responsively in submitting names as required.

§ 5.2.4 The Contractor shall not substitute a Subcontractor, person, or entity for one previously selected if the Owner or Architect makes reasonable objection to such substitution.

§ 5.3 Subcontractual Relations

By appropriate written agreement, the Contractor shall require each Subcontractor, to the extent of the Work to be performed by the Subcontractor, to be bound to the Contractor by terms of the Contract Documents, and to assume toward the Contractor all the obligations and responsibilities, including the responsibility for safety of the Subcontractor's Work that the Contractor, by these Contract Documents, assumes toward the Owner and Architect. Each subcontract agreement shall preserve and protect the rights of the Owner and Architect under the Contract Documents with respect to the Work to be performed by the Subcontractor so that subcontracting thereof will not prejudice such rights, and shall allow to the Subcontractor, unless specifically provided otherwise in the subcontract agreement, the benefit of all rights, remedies, and redress against the Contractor that the Contractor, by the Contract Documents, has against the Owner. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with Sub-subcontractors. The Contractor shall make available to each proposed Subcontractor, prior to the execution of the subcontract agreement, copies of the Contract Documents to which the Subcontractor will be bound, and, upon written request of the Subcontractor, identify to the Subcontractor terms and conditions of the proposed subcontract agreement that may be at variance with the Contract Documents. Subcontractors will similarly make copies of applicable portions of such documents available to their respective proposed Sub-subcontractors.

§ 5.4 Contingent Assignment of Subcontracts

§ 5.4.1 Each subcontract agreement for a portion of the Work is assigned by the Contractor to the Owner, provided that

.1 assignment is effective only after termination of the Contract by the Owner for cause pursuant to Section 14.2 and only for those subcontract agreements that the Owner accepts by notifying the Subcontractor and Contractor; and

.2 assignment is subject to the prior rights of the surety, if any, obligated under bond relating to the Contract.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

When the Owner accepts the assignment of a subcontract agreement, the Owner assumes the Contractor's rights and obligations under the subcontract.

§ 5.4.2 Upon such assignment, if the Work has been suspended for more than 30 days, the Subcontractor's compensation shall be equitably adjusted for increases in cost resulting from the suspension.

§ 5.4.3 Upon assignment to the Owner under this Section 5.4, the Owner may further assign the subcontract to a successor contractor or other entity. If the Owner assigns the subcontract to a successor contractor or other entity, the Owner shall nevertheless remain legally responsible for all of the successor contractor's obligations under the subcontract.

ARTICLE 6 CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

§ 6.1 Owner's Right to Perform Construction and to Award Separate Contracts

§ 6.1.1 The term "Separate Contractor(s)" shall mean other contractors retained by the Owner under separate agreements. The Owner reserves the right to perform construction or operations related to the Project with the Owner's own forces, and with Separate Contractors retained under Conditions of the Contract substantially similar to those of this Contract, including those provisions of the Conditions of the Contract related to insurance and waiver of subrogation.

§ 6.1.2 When separate contracts are awarded for different portions of the Project or other construction or operations on the site, the term "Contractor" in the Contract Documents in each case shall mean the Contractor who executes each separate Owner-Contractor Agreement.

§ 6.1.3 The Owner shall provide for coordination of the activities of the Owner's own forces and of each Separate Contractor with the Work of the Contractor, who shall cooperate with them. The Contractor shall participate with any Separate Contractors and the Owner in reviewing their construction schedules. The Contractor shall make any revisions to its construction schedule deemed necessary after a joint review and mutual agreement. The construction schedules shall then constitute the schedules to be used by the Contractor, Separate Contractors, and the Owner until subsequently revised.

§ 6.1.4 Unless otherwise provided in the Contract Documents, when the Owner performs construction or operations related to the Project with the Owner's own forces or with Separate Contractors, the Owner or its Separate Contractors shall have the same obligations and rights that the Contractor has under the Conditions of the Contract, including, without excluding others, those stated in Article 3, this Article 6, and Articles 10, 11, and 12.

§ 6.2 Mutual Responsibility

§ 6.2.1 The Contractor shall afford the Owner and Separate Contractors reasonable opportunity for introduction and storage of their materials and equipment and performance of their activities, and shall connect and coordinate the Contractor's construction and operations with theirs as required by the Contract Documents.

§ 6.2.2 If part of the Contractor's Work depends for proper execution or results upon construction or operations by the Owner or a Separate Contractor, the Contractor shall, prior to proceeding with that portion of the Work, promptly notify the Architect of apparent discrepancies or defects in the construction or operations by the Owner or Separate Contractor that would render it unsuitable for proper execution and results of the Contractor's Work. Failure of the Contractor to notify the Architect of apparent discrepancies or defects prior to proceeding with the Work shall constitute an acknowledgment that the Owner's or Separate Contractor's completed or partially completed construction is fit and proper to receive the Contractor's Work. The Contractor shall not be responsible for discrepancies or defects in the construction or operations by the Owner or Separate Contractor that are not apparent.

§ 6.2.3 The Contractor shall reimburse the Owner for costs the Owner incurs that are payable to a Separate Contractor because of the Contractor's delays, improperly timed activities or defective construction. The Owner shall be responsible to the Contractor for costs the Contractor incurs because of a Separate Contractor's delays, improperly timed activities, damage to the Work or defective construction.

§ 6.2.4 The Contractor shall promptly remedy damage that the Contractor wrongfully causes to completed or partially completed construction or to property of the Owner or Separate Contractor as provided in Section 10.2.5.

Init.
/
AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 6.2.5 The Owner and each Separate Contractor shall have the same responsibilities for cutting and patching as are described for the Contractor in Section 3.14.

§ 6.3 Owner's Right to Clean Up

If a dispute arises among the Contractor, Separate Contractors, and the Owner as to the responsibility under their respective contracts for maintaining the premises and surrounding area free from waste materials and rubbish, the Owner may clean up and the Architect will allocate the cost among those responsible.

ARTICLE 7 CHANGES IN THE WORK

§ 7.1 General

§ 7.1.1 Changes in the Work may be accomplished after execution of the Contract, and without invalidating the Contract, by Change Order, Construction Change Directive or order for a minor change in the Work, subject to the limitations stated in this Article 7 and elsewhere in the Contract Documents.

§ 7.1.2 A Change Order shall be based upon agreement among the Owner, Contractor, and Architect. A Construction Change Directive requires agreement by the Owner and Architect and may or may not be agreed to by the Contractor. An order for a minor change in the Work may be issued by the Architect alone.

§ 7.1.3 Changes in the Work shall be performed under applicable provisions of the Contract Documents. The Contractor shall proceed promptly with changes in the Work, unless otherwise provided in the Change Order, Construction Change Directive, or order for a minor change in the Work.

§ 7.2 Change Orders

§ 7.2.1 A Change Order is a written instrument prepared by the Architect and signed by the Owner, Contractor, and Architect stating their agreement upon all of the following:

.1 The change in the Work;
.2 The amount of the adjustment, if any, in the Contract Sum; and
.3 The extent of the adjustment, if any, in the Contract Time.

§ 7.3 Construction Change Directives

§ 7.3.1 A Construction Change Directive is a written order prepared by the Architect and signed by the Owner and Architect, directing a change in the Work prior to agreement on adjustment, if any, in the Contract Sum or Contract Time, or both. The Owner may by Construction Change Directive, without invalidating the Contract, order changes in the Work within the general scope of the Contract consisting of additions, deletions, or other revisions, the Contract Sum and Contract Time being adjusted accordingly.

§ 7.3.2 A Construction Change Directive shall be used in the absence of total agreement on the terms of a Change Order.

§ 7.3.3 If the Construction Change Directive provides for an adjustment to the Contract Sum, the adjustment shall be based on one of the following methods:

.1 Mutual acceptance of a lump sum properly itemized and supported by sufficient substantiating data to permit evaluation;
.2 Unit prices stated in the Contract Documents or subsequently agreed upon;
.3 Cost to be determined in a manner agreed upon by the parties and a mutually acceptable fixed or percentage fee; or
.4 As provided in Section 7.3.4.

§ 7.3.4 If the Contractor does not respond promptly or disagrees with the method for adjustment in the Contract Sum, the Architect shall determine the adjustment on the basis of reasonable expenditures and savings of those performing the Work attributable to the change, including, in case of an increase in the Contract Sum, an amount for overhead and profit as set forth in the Agreement, or if no such amount is set forth in the Agreement, a reasonable amount. In such case, and also under Section 7.3.3.3, the Contractor shall keep and present, in such form as the Architect may prescribe, an itemized accounting together with appropriate supporting data. Unless otherwise provided in the Contract Documents, costs for the purposes of this Section 7.3.4 shall be limited to the following:

Init.
/
AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

.1 Costs of labor, including applicable payroll taxes, fringe benefits required by agreement or custom, workers' compensation insurance, and other employee costs approved by the Architect;
.2 Costs of materials, supplies, and equipment, including cost of transportation, whether incorporated or consumed;
.3 Rental costs of machinery and equipment, exclusive of hand tools, whether rented from the Contractor or others;
.4 Costs of premiums for all bonds and insurance, permit fees, and sales, use, or similar taxes, directly related to the change; and
.5 Costs of supervision and field office personnel directly attributable to the change.

§ 7.3.5 If the Contractor disagrees with the adjustment in the Contract Time, the Contractor may make a Claim in accordance with applicable provisions of Article 15.

§ 7.3.6 Upon receipt of a Construction Change Directive, the Contractor shall promptly proceed with the change in the Work involved and advise the Architect of the Contractor's agreement or disagreement with the method, if any, provided in the Construction Change Directive for determining the proposed adjustment in the Contract Sum or Contract Time.

§ 7.3.7 A Construction Change Directive signed by the Contractor indicates the Contractor's agreement therewith, including adjustment in Contract Sum and Contract Time or the method for determining them. Such agreement shall be effective immediately and shall be recorded as a Change Order.

§ 7.3.8 The amount of credit to be allowed by the Contractor to the Owner for a deletion or change that results in a net decrease in the Contract Sum shall be actual net cost as confirmed by the Architect. When both additions and credits covering related Work or substitutions are involved in a change, the allowance for overhead and profit shall be figured on the basis of net increase, if any, with respect to that change.

§ 7.3.9 Pending final determination of the total cost of a Construction Change Directive to the Owner, the Contractor may request payment for Work completed under the Construction Change Directive in Applications for Payment. The Architect will make an interim determination for purposes of monthly certification for payment for those costs and certify for payment the amount that the Architect determines, in the Architect's professional judgment, to be reasonably justified. The Architect's interim determination of cost shall adjust the Contract Sum on the same basis as a Change Order, subject to the right of either party to disagree and assert a Claim in accordance with Article 15.

§ 7.3.10 When the Owner and Contractor agree with a determination made by the Architect concerning the adjustments in the Contract Sum and Contract Time, or otherwise reach agreement upon the adjustments, such agreement shall be effective immediately and the Architect will prepare a Change Order. Change Orders may be issued for all or any part of a Construction Change Directive.

§ 7.4 Minor Changes in the Work

The Architect may order minor changes in the Work that are consistent with the intent of the Contract Documents and do not involve an adjustment in the Contract Sum or an extension of the Contract Time. The Architect's order for minor changes shall be in writing. If the Contractor believes that the proposed minor change in the Work will affect the Contract Sum or Contract Time, the Contractor shall notify the Architect and shall not proceed to implement the change in the Work. If the Contractor performs the Work set forth in the Architect's order for a minor change without prior notice to the Architect that such change will affect the Contract Sum or Contract Time, the Contractor waives any adjustment to the Contract Sum or extension of the Contract Time.

ARTICLE 8 TIME

§ 8.1 Definitions

§ 8.1.1 Unless otherwise provided, Contract Time is the period of time, including authorized adjustments, allotted in the Contract Documents for Substantial Completion of the Work.

§ 8.1.2 The date of commencement of the Work is the date established in the Agreement.

§ 8.1.3 The date of Substantial Completion is the date certified by the Architect in accordance with Section 9.8.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 8.1.4 The term "day" as used in the Contract Documents shall mean calendar day unless otherwise specifically defined.

§ 8.2 Progress and Completion

§ 8.2.1 Time limits stated in the Contract Documents are of the essence of the Contract. By executing the Agreement, the Contractor confirms that the Contract Time is a reasonable period for performing the Work.

§ 8.2.2 The Contractor shall not knowingly, except by agreement or instruction of the Owner in writing, commence the Work prior to the effective date of insurance required to be furnished by the Contractor and Owner.

§ 8.2.3 The Contractor shall proceed expeditiously with adequate forces and shall achieve Substantial Completion within the Contract Time.

§ 8.3 Delays and Extensions of Time

§ 8.3.1 If the Contractor is delayed at any time in the commencement or progress of the Work by (1) an act or neglect of the Owner or Architect, of an employee of either, or of a Separate Contractor; (2) by changes ordered in the Work; (3) by labor disputes, fire, unusual delay in deliveries, unavoidable casualties, adverse weather conditions documented in accordance with Section 15.1.6.2, or other causes beyond the Contractor's control; (4) by delay authorized by the Owner pending mediation and binding dispute resolution; or (5) by other causes that the Contractor asserts, and the Architect determines, justify delay, then the Contract Time shall be extended for such reasonable time as the Architect may determine.

§ 8.3.2 Claims relating to time shall be made in accordance with applicable provisions of Article 15.

§ 8.3.3 This Section 8.3 does not preclude recovery of damages for delay by either party under other provisions of the Contract Documents.

ARTICLE 9 PAYMENTS AND COMPLETION

§ 9.1 Contract Sum

§ 9.1.1 The Contract Sum is stated in the Agreement and, including authorized adjustments, is the total amount payable by the Owner to the Contractor for performance of the Work under the Contract Documents.

§ 9.1.2 If unit prices are stated in the Contract Documents or subsequently agreed upon, and if quantities originally contemplated are materially changed so that application of such unit prices to the actual quantities causes substantial inequity to the Owner or Contractor, the applicable unit prices shall be equitably adjusted.

§ 9.2 Schedule of Values

Where the Contract is based on a stipulated sum or Guaranteed Maximum Price, the Contractor shall submit a schedule of values to the Architect before the first Application for Payment, allocating the entire Contract Sum to the various portions of the Work. The schedule of values shall be prepared in the form, and supported by the data to substantiate its accuracy, required by the Architect. This schedule, unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's Applications for Payment. Any changes to the schedule of values shall be submitted to the Architect and supported by such data to substantiate its accuracy as the Architect may require, and unless objected to by the Architect, shall be used as a basis for reviewing the Contractor's subsequent Applications for Payment.

§ 9.3 Applications for Payment

§ 9.3.1 At least ten days before the date established for each progress payment, the Contractor shall submit to the Architect an itemized Application for Payment prepared in accordance with the schedule of values, if required under Section 9.2, for completed portions of the Work. The application shall be notarized, if required, and supported by all data substantiating the Contractor's right to payment that the Owner or Architect require, such as copies of requisitions, and releases and waivers of liens from Subcontractors and suppliers, and shall reflect retainage if provided for in the Contract Documents.

§ 9.3.1.1 As provided in Section 7.3.9, such applications may include requests for payment on account of changes in the Work that have been properly authorized by Construction Change Directives, or by interim determinations of the Architect, but not yet included in Change Orders.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 9.3.1.2 Applications for Payment shall not include requests for payment for portions of the Work for which the Contractor does not intend to pay a Subcontractor or supplier, unless such Work has been performed by others whom the Contractor intends to pay.

§ 9.3.2 Unless otherwise provided in the Contract Documents, payments shall be made on account of materials and equipment delivered and suitably stored at the site for subsequent incorporation in the Work. If approved in advance by the Owner, payment may similarly be made for materials and equipment suitably stored off the site at a location agreed upon in writing. Payment for materials and equipment stored on or off the site shall be conditioned upon compliance by the Contractor with procedures satisfactory to the Owner to establish the Owner's title to such materials and equipment or otherwise protect the Owner's interest, and shall include the costs of applicable insurance, storage, and transportation to the site, for such materials and equipment stored off the site.

§ 9.3.3 The Contractor warrants that title to all Work covered by an Application for Payment will pass to the Owner no later than the time of payment. The Contractor further warrants that upon submittal of an Application for Payment all Work for which Certificates for Payment have been previously issued and payments received from the Owner shall, to the best of the Contractor's knowledge, information, and belief, be free and clear of liens, claims, security interests, or encumbrances, in favor of the Contractor, Subcontractors, suppliers, or other persons or entities that provided labor, materials, and equipment relating to the Work.

§ 9.4 Certificates for Payment

§ 9.4.1 The Architect will, within seven days after receipt of the Contractor's Application for Payment, either (1) issue to the Owner a Certificate for Payment in the full amount of the Application for Payment, with a copy to the Contractor; or (2) issue to the Owner a Certificate for Payment for such amount as the Architect determines is properly due, and notify the Contractor and Owner of the Architect's reasons for withholding certification in part as provided in Section 9.5.1; or (3) withhold certification of the entire Application for Payment, and notify the Contractor and Owner of the Architect's reason for withholding certification in whole as provided in Section 9.5.1.

§ 9.4.2 The issuance of a Certificate for Payment will constitute a representation by the Architect to the Owner, based on the Architect's evaluation of the Work and the data in the Application for Payment, that, to the best of the Architect's knowledge, information, and belief, the Work has progressed to the point indicated, the quality of the Work is in accordance with the Contract Documents, and that the Contractor is entitled to payment in the amount certified. The foregoing representations are subject to an evaluation of the Work for conformance with the Contract Documents upon Substantial Completion, to results of subsequent tests and inspections, to correction of minor deviations from the Contract Documents prior to completion, and to specific qualifications expressed by the Architect. However, the issuance of a Certificate for Payment will not be a representation that the Architect has (1) made exhaustive or continuous on-site inspections to check the quality or quantity of the Work; (2) reviewed construction means, methods, techniques, sequences, or procedures; (3) reviewed copies of requisitions received from Subcontractors and suppliers and other data requested by the Owner to substantiate the Contractor's right to payment; or (4) made examination to ascertain how or for what purpose the Contractor has used money previously paid on account of the Contract Sum.

§ 9.5 Decisions to Withhold Certification

§ 9.5.1 The Architect may withhold a Certificate for Payment in whole or in part, to the extent reasonably necessary to protect the Owner, if in the Architect's opinion the representations to the Owner required by Section 9.4.2 cannot be made. If the Architect is unable to certify payment in the amount of the Application, the Architect will notify the Contractor and Owner as provided in Section 9.4.1. If the Contractor and Architect cannot agree on a revised amount, the Architect will promptly issue a Certificate for Payment for the amount for which the Architect is able to make such representations to the Owner. The Architect may also withhold a Certificate for Payment or, because of subsequently discovered evidence, may nullify the whole or a part of a Certificate for Payment previously issued, to such extent as may be necessary in the Architect's opinion to protect the Owner from loss for which the Contractor is responsible, including loss resulting from acts and omissions described in Section 3.3.2, because of

.1 defective Work not remedied;

.2 third party claims filed or reasonable evidence indicating probable filing of such claims, unless security acceptable to the Owner is provided by the Contractor;

.3 failure of the Contractor to make payments properly to Subcontractors or suppliers for labor, materials or equipment;

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

.4 reasonable evidence that the Work cannot be completed for the unpaid balance of the Contract Sum;
.5 damage to the Owner or a Separate Contractor;
.6 reasonable evidence that the Work will not be completed within the Contract Time, and that the unpaid balance would not be adequate to cover actual or liquidated damages for the anticipated delay; or
.7 repeated failure to carry out the Work in accordance with the Contract Documents.

§ 9.5.2 When either party disputes the Architect's decision regarding a Certificate for Payment under Section 9.5.1, in whole or in part, that party may submit a Claim in accordance with Article 15.

§ 9.5.3 When the reasons for withholding certification are removed, certification will be made for amounts previously withheld.

§ 9.5.4 If the Architect withholds certification for payment under Section 9.5.1.3, the Owner may, at its sole option, issue joint checks to the Contractor and to any Subcontractor or supplier to whom the Contractor failed to make payment for Work properly performed or material or equipment suitably delivered. If the Owner makes payments by joint check, the Owner shall notify the Architect and the Contractor shall reflect such payment on its next Application for Payment.

§ 9.6 Progress Payments

§ 9.6.1 After the Architect has issued a Certificate for Payment, the Owner shall make payment in the manner and within the time provided in the Contract Documents, and shall so notify the Architect.

§ 9.6.2 The Contractor shall pay each Subcontractor, no later than seven days after receipt of payment from the Owner, the amount to which the Subcontractor is entitled, reflecting percentages actually retained from payments to the Contractor on account of the Subcontractor's portion of the Work. The Contractor shall, by appropriate agreement with each Subcontractor, require each Subcontractor to make payments to Sub-subcontractors in a similar manner.

§ 9.6.3 The Architect will, on request, furnish to a Subcontractor, if practicable, information regarding percentages of completion or amounts applied for by the Contractor and action taken thereon by the Architect and Owner on account of portions of the Work done by such Subcontractor.

§ 9.6.4 The Owner has the right to request written evidence from the Contractor that the Contractor has properly paid Subcontractors and suppliers amounts paid by the Owner to the Contractor for subcontracted Work. If the Contractor fails to furnish such evidence within seven days, the Owner shall have the right to contact Subcontractors and suppliers to ascertain whether they have been properly paid. Neither the Owner nor Architect shall have an obligation to pay, or to see to the payment of money to, a Subcontractor or supplier, except as may otherwise be required by law.

§ 9.6.5 The Contractor's payments to suppliers shall be treated in a manner similar to that provided in Sections 9.6.2, 9.6.3 and 9.6.4.

§ 9.6.6 A Certificate for Payment, a progress payment, or partial or entire use or occupancy of the Project by the Owner shall not constitute acceptance of Work not in accordance with the Contract Documents.

§ 9.6.7 Unless the Contractor provides the Owner with a payment bond in the full penal sum of the Contract Sum, payments received by the Contractor for Work properly performed by Subcontractors or provided by suppliers shall be held by the Contractor for those Subcontractors or suppliers who performed Work or furnished materials, or both, under contract with the Contractor for which payment was made by the Owner. Nothing contained herein shall require money to be placed in a separate account and not commingled with money of the Contractor, create any fiduciary liability or tort liability on the part of the Contractor for breach of trust, or entitle any person or entity to an award of punitive damages against the Contractor for breach of the requirements of this provision.

§ 9.6.8 Provided the Owner has fulfilled its payment obligations under the Contract Documents, the Contractor shall defend and indemnify the Owner from all loss, liability, damage or expense, including reasonable attorney's fees and litigation expenses, arising out of any lien claim or other claim for payment by any Subcontractor or supplier of any tier. Upon receipt of notice of a lien claim or other claim for payment, the Owner shall notify the Contractor. If approved by the applicable court, when required, the Contractor may substitute a surety bond for the property against which the lien or other claim for payment has been asserted.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 9.7 Failure of Payment

If the Architect does not issue a Certificate for Payment, through no fault of the Contractor, within seven days after receipt of the Contractor's Application for Payment, or if the Owner does not pay the Contractor within seven days after the date established in the Contract Documents, the amount certified by the Architect or awarded by binding dispute resolution, then the Contractor may, upon seven additional days' notice to the Owner and Architect, stop the Work until payment of the amount owing has been received. The Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable costs of shutdown, delay and start-up, plus interest as provided for in the Contract Documents.

§ 9.8 Substantial Completion

§ 9.8.1 Substantial Completion is the stage in the progress of the Work when the Work or designated portion thereof is sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended use.

§ 9.8.2 When the Contractor considers that the Work, or a portion thereof which the Owner agrees to accept separately, is substantially complete, the Contractor shall prepare and submit to the Architect a comprehensive list of items to be completed or corrected prior to final payment. Failure to include an item on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents.

§ 9.8.3 Upon receipt of the Contractor's list, the Architect will make an inspection to determine whether the Work or designated portion thereof is substantially complete. If the Architect's inspection discloses any item, whether or not included on the Contractor's list, which is not sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work or designated portion thereof for its intended use, the Contractor shall, before issuance of the Certificate of Substantial Completion, complete or correct such item upon notification by the Architect. In such case, the Contractor shall then submit a request for another inspection by the Architect to determine Substantial Completion.

§ 9.8.4 When the Work or designated portion thereof is substantially complete, the Architect will prepare a Certificate of Substantial Completion that shall establish the date of Substantial Completion; establish responsibilities of the Owner and Contractor for security, maintenance, heat, utilities, damage to the Work and insurance; and fix the time within which the Contractor shall finish all items on the list accompanying the Certificate. Warranties required by the Contract Documents shall commence on the date of Substantial Completion of the Work or designated portion thereof unless otherwise provided in the Certificate of Substantial Completion.

§ 9.8.5 The Certificate of Substantial Completion shall be submitted to the Owner and Contractor for their written acceptance of responsibilities assigned to them in the Certificate. Upon such acceptance, and consent of surety if any, the Owner shall make payment of retainage applying to the Work or designated portion thereof. Such payment shall be adjusted for Work that is incomplete or not in accordance with the requirements of the Contract Documents.

§ 9.9 Partial Occupancy or Use

§ 9.9.1 The Owner may occupy or use any completed or partially completed portion of the Work at any stage when such portion is designated by separate agreement with the Contractor, provided such occupancy or use is consented to by the insurer and authorized by public authorities having jurisdiction over the Project. Such partial occupancy or use may commence whether or not the portion is substantially complete, provided the Owner and Contractor have accepted in writing the responsibilities assigned to each of them for payments, retainage, if any, security, maintenance, heat, utilities, damage to the Work and insurance, and have agreed in writing concerning the period for correction of the Work and commencement of warranties required by the Contract Documents. When the Contractor considers a portion substantially complete, the Contractor shall prepare and submit a list to the Architect as provided under Section 9.8.2. Consent of the Contractor to partial occupancy or use shall not be unreasonably withheld. The stage of the progress of the Work shall be determined by written agreement between the Owner and Contractor or, if no agreement is reached, by decision of the Architect.

§ 9.9.2 Immediately prior to such partial occupancy or use, the Owner, Contractor, and Architect shall jointly inspect the area to be occupied or portion of the Work to be used in order to determine and record the condition of the Work.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 9.9.3 Unless otherwise agreed upon, partial occupancy or use of a portion or portions of the Work shall not constitute acceptance of Work not complying with the requirements of the Contract Documents.

§ 9.10 Final Completion and Final Payment

§ 9.10.1 Upon receipt of the Contractor's notice that the Work is ready for final inspection and acceptance and upon receipt of a final Application for Payment, the Architect will promptly make such inspection. When the Architect finds the Work acceptable under the Contract Documents and the Contract fully performed, the Architect will promptly issue a final Certificate for Payment stating that to the best of the Architect's knowledge, information and belief, and on the basis of the Architect's on-site visits and inspections, the Work has been completed in accordance with the Contract Documents and that the entire balance found to be due the Contractor and noted in the final Certificate is due and payable. The Architect's final Certificate for Payment will constitute a further representation that conditions listed in Section 9.10.2 as precedent to the Contractor's being entitled to final payment have been fulfilled.

§ 9.10.2 Neither final payment nor any remaining retained percentage shall become due until the Contractor submits to the Architect (1) an affidavit that payrolls, bills for materials and equipment, and other indebtedness connected with the Work for which the Owner or the Owner's property might be responsible or encumbered (less amounts withheld by Owner) have been paid or otherwise satisfied, (2) a certificate evidencing that insurance required by the Contract Documents to remain in force after final payment is currently in effect, (3) a written statement that the Contractor knows of no reason that the insurance will not be renewable to cover the period required by the Contract Documents, (4) consent of surety, if any, to final payment, (5) documentation of any special warranties, such as manufacturers' warranties or specific Subcontractor warranties, and (6) if required by the Owner, other data establishing payment or satisfaction of obligations, such as receipts and releases and waivers of liens, claims, security interests, or encumbrances arising out of the Contract, to the extent and in such form as may be designated by the Owner. If a Subcontractor refuses to furnish a release or waiver required by the Owner, the Contractor may furnish a bond satisfactory to the Owner to indemnify the Owner against such lien, claim, security interest, or encumbrance. If a lien, claim, security interest, or encumbrance remains unsatisfied after payments are made, the Contractor shall refund to the Owner all money that the Owner may be compelled to pay in discharging the lien, claim, security interest, or encumbrance, including all costs and reasonable attorneys' fees.

§ 9.10.3 If, after Substantial Completion of the Work, final completion thereof is materially delayed through no fault of the Contractor or by issuance of Change Orders affecting final completion, and the Architect so confirms, the Owner shall, upon application by the Contractor and certification by the Architect, and without terminating the Contract, make payment of the balance due for that portion of the Work fully completed, corrected, and accepted. If the remaining balance for Work not fully completed or corrected is less than retainage stipulated in the Contract Documents, and if bonds have been furnished, the written consent of the surety to payment of the balance due for that portion of the Work fully completed and accepted shall be submitted by the Contractor to the Architect prior to certification of such payment. Such payment shall be made under terms and conditions governing final payment, except that it shall not constitute a waiver of Claims.

§ 9.10.4 The making of final payment shall constitute a waiver of Claims by the Owner except those arising from

- **.1** liens, Claims, security interests, or encumbrances arising out of the Contract and unsettled;
- **.2** failure of the Work to comply with the requirements of the Contract Documents;
- **.3** terms of special warranties required by the Contract Documents; or
- **.4** audits performed by the Owner, if permitted by the Contract Documents, after final payment.

§ 9.10.5 Acceptance of final payment by the Contractor, a Subcontractor, or a supplier, shall constitute a waiver of claims by that payee except those previously made in writing and identified by that payee as unsettled at the time of final Application for Payment.

ARTICLE 10 PROTECTION OF PERSONS AND PROPERTY

§ 10.1 Safety Precautions and Programs

The Contractor shall be responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Contract.

§ 10.2 Safety of Persons and Property

§ 10.2.1 The Contractor shall take reasonable precautions for safety of, and shall provide reasonable protection to prevent damage, injury, or loss to

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

.1 employees on the Work and other persons who may be affected thereby;
.2 the Work and materials and equipment to be incorporated therein, whether in storage on or off the site, under care, custody, or control of the Contractor, a Subcontractor, or a Sub-subcontractor; and
.3 other property at the site or adjacent thereto, such as trees, shrubs, lawns, walks, pavements, roadways, structures, and utilities not designated for removal, relocation, or replacement in the course of construction.

§ 10.2.2 The Contractor shall comply with, and give notices required by applicable laws, statutes, ordinances, codes, rules and regulations, and lawful orders of public authorities, bearing on safety of persons or property or their protection from damage, injury, or loss.

§ 10.2.3 The Contractor shall implement, erect, and maintain, as required by existing conditions and performance of the Contract, reasonable safeguards for safety and protection, including posting danger signs and other warnings against hazards; promulgating safety regulations; and notifying the owners and users of adjacent sites and utilities of the safeguards.

§ 10.2.4 When use or storage of explosives or other hazardous materials or equipment, or unusual methods are necessary for execution of the Work, the Contractor shall exercise utmost care and carry on such activities under supervision of properly qualified personnel.

§ 10.2.5 The Contractor shall promptly remedy damage and loss (other than damage or loss insured under property insurance required by the Contract Documents) to property referred to in Sections 10.2.1.2 and 10.2.1.3 caused in whole or in part by the Contractor, a Subcontractor, a Sub-subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable and for which the Contractor is responsible under Sections 10.2.1.2 and 10.2.1.3. The Contractor may make a Claim for the cost to remedy the damage or loss to the extent such damage or loss is attributable to acts or omissions of the Owner or Architect or anyone directly or indirectly employed by either of them, or by anyone for whose acts either of them may be liable, and not attributable to the fault or negligence of the Contractor. The foregoing obligations of the Contractor are in addition to the Contractor's obligations under Section 3.18.

§ 10.2.6 The Contractor shall designate a responsible member of the Contractor's organization at the site whose duty shall be the prevention of accidents. This person shall be the Contractor's superintendent unless otherwise designated by the Contractor in writing to the Owner and Architect.

§ 10.2.7 The Contractor shall not permit any part of the construction or site to be loaded so as to cause damage or create an unsafe condition.

§ 10.2.8 Injury or Damage to Person or Property
If either party suffers injury or damage to person or property because of an act or omission of the other party, or of others for whose acts such party is legally responsible, notice of the injury or damage, whether or not insured, shall be given to the other party within a reasonable time not exceeding 21 days after discovery. The notice shall provide sufficient detail to enable the other party to investigate the matter.

§ 10.3 Hazardous Materials and Substances
§ 10.3.1 The Contractor is responsible for compliance with any requirements included in the Contract Documents regarding hazardous materials or substances. If the Contractor encounters a hazardous material or substance not addressed in the Contract Documents and if reasonable precautions will be inadequate to prevent foreseeable bodily injury or death to persons resulting from a material or substance, including but not limited to asbestos or polychlorinated biphenyl (PCB), encountered on the site by the Contractor, the Contractor shall, upon recognizing the condition, immediately stop Work in the affected area and notify the Owner and Architect of the condition.

§ 10.3.2 Upon receipt of the Contractor's notice, the Owner shall obtain the services of a licensed laboratory to verify the presence or absence of the material or substance reported by the Contractor and, in the event such material or substance is found to be present, to cause it to be rendered harmless. Unless otherwise required by the Contract Documents, the Owner shall furnish in writing to the Contractor and Architect the names and qualifications of persons or entities who are to perform tests verifying the presence or absence of the material or substance or who are to perform the task of removal or safe containment of the material or substance. The Contractor and the Architect will

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

promptly reply to the Owner in writing stating whether or not either has reasonable objection to the persons or entities proposed by the Owner. If either the Contractor or Architect has an objection to a person or entity proposed by the Owner, the Owner shall propose another to whom the Contractor and the Architect have no reasonable objection. When the material or substance has been rendered harmless, Work in the affected area shall resume upon written agreement of the Owner and Contractor. By Change Order, the Contract Time shall be extended appropriately and the Contract Sum shall be increased by the amount of the Contractor's reasonable additional costs of shutdown, delay, and start-up.

§ 10.3.3 To the fullest extent permitted by law, the Owner shall indemnify and hold harmless the Contractor, Subcontractors, Architect, Architect's consultants, and agents and employees of any of them from and against claims, damages, losses, and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work in the affected area if in fact the material or substance presents the risk of bodily injury or death as described in Section 10.3.1 and has not been rendered harmless, provided that such claim, damage, loss, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself), except to the extent that such damage, loss, or expense is due to the fault or negligence of the party seeking indemnity.

§ 10.3.4 The Owner shall not be responsible under this Section 10.3 for hazardous materials or substances the Contractor brings to the site unless such materials or substances are required by the Contract Documents. The Owner shall be responsible for hazardous materials or substances required by the Contract Documents, except to the extent of the Contractor's fault or negligence in the use and handling of such materials or substances.

§ 10.3.5 The Contractor shall reimburse the Owner for the cost and expense the Owner incurs (1) for remediation of hazardous materials or substances the Contractor brings to the site and negligently handles, or (2) where the Contractor fails to perform its obligations under Section 10.3.1, except to the extent that the cost and expense are due to the Owner's fault or negligence.

§ 10.3.6 If, without negligence on the part of the Contractor, the Contractor is held liable by a government agency for the cost of remediation of a hazardous material or substance solely by reason of performing Work as required by the Contract Documents, the Owner shall reimburse the Contractor for all cost and expense thereby incurred.

§ 10.4 Emergencies

In an emergency affecting safety of persons or property, the Contractor shall act, at the Contractor's discretion, to prevent threatened damage, injury, or loss. Additional compensation or extension of time claimed by the Contractor on account of an emergency shall be determined as provided in Article 15 and Article 7.

ARTICLE 11 INSURANCE AND BONDS

§ 11.1 Contractor's Insurance and Bonds

§ 11.1.1 The Contractor shall purchase and maintain insurance of the types and limits of liability, containing the endorsements, and subject to the terms and conditions, as described in the Agreement or elsewhere in the Contract Documents. The Contractor shall purchase and maintain the required insurance from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located. The Owner, Architect, and Architect's consultants shall be named as additional insureds under the Contractor's commercial general liability policy or as otherwise described in the Contract Documents.

§ 11.1.2 The Contractor shall provide surety bonds of the types, for such penal sums, and subject to such terms and conditions as required by the Contract Documents. The Contractor shall purchase and maintain the required bonds from a company or companies lawfully authorized to issue surety bonds in the jurisdiction where the Project is located.

§ 11.1.3 Upon the request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor shall promptly furnish a copy of the bonds or shall authorize a copy to be furnished.

§ 11.1.4 Notice of Cancellation or Expiration of Contractor's Required Insurance. Within three (3) business days of the date the Contractor becomes aware of an impending or actual cancellation or expiration of any insurance required by the Contract Documents, the Contractor shall provide notice to the Owner of such impending or actual cancellation or

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

expiration. Upon receipt of notice from the Contractor, the Owner shall, unless the lapse in coverage arises from an act or omission of the Owner, have the right to stop the Work until the lapse in coverage has been cured by the procurement of replacement coverage by the Contractor. The furnishing of notice by the Contractor shall not relieve the Contractor of any contractual obligation to provide any required coverage.

§ 11.2 Owner's Insurance

§ 11.2.1 The Owner shall purchase and maintain insurance of the types and limits of liability, containing the endorsements, and subject to the terms and conditions, as described in the Agreement or elsewhere in the Contract Documents. The Owner shall purchase and maintain the required insurance from an insurance company or insurance companies lawfully authorized to issue insurance in the jurisdiction where the Project is located.

§ 11.2.2 Failure to Purchase Required Property Insurance. If the Owner fails to purchase and maintain the required property insurance, with all of the coverages and in the amounts described in the Agreement or elsewhere in the Contract Documents, the Owner shall inform the Contractor in writing prior to commencement of the Work. Upon receipt of notice from the Owner, the Contractor may delay commencement of the Work and may obtain insurance that will protect the interests of the Contractor, Subcontractors, and Sub-Subcontractors in the Work. When the failure to provide coverage has been cured or resolved, the Contract Sum and Contract Time shall be equitably adjusted. In the event the Owner fails to procure coverage, the Owner waives all rights against the Contractor, Subcontractors, and Sub-subcontractors to the extent the loss to the Owner would have been covered by the insurance to have been procured by the Owner. The cost of the insurance shall be charged to the Owner by a Change Order. If the Owner does not provide written notice, and the Contractor is damaged by the failure or neglect of the Owner to purchase or maintain the required insurance, the Owner shall reimburse the Contractor for all reasonable costs and damages attributable thereto.

§ 11.2.3 Notice of Cancellation or Expiration of Owner's Required Property Insurance. Within three (3) business days of the date the Owner becomes aware of an impending or actual cancellation or expiration of any property insurance required by the Contract Documents, the Owner shall provide notice to the Contractor of such impending or actual cancellation or expiration. Unless the lapse in coverage arises from an act or omission of the Contractor: (1) the Contractor, upon receipt of notice from the Owner, shall have the right to stop the Work until the lapse in coverage has been cured by the procurement of replacement coverage by either the Owner or the Contractor; (2) the Contract Time and Contract Sum shall be equitably adjusted; and (3) the Owner waives all rights against the Contractor, Subcontractors, and Sub-subcontractors to the extent any loss to the Owner would have been covered by the insurance had it not expired or been cancelled. If the Contractor purchases replacement coverage, the cost of the insurance shall be charged to the Owner by an appropriate Change Order. The furnishing of notice by the Owner shall not relieve the Owner of any contractual obligation to provide required insurance.

§ 11.3 Waivers of Subrogation

§ 11.3.1 The Owner and Contractor waive all rights against (1) each other and any of their subcontractors, sub-subcontractors, agents, and employees, each of the other; (2) the Architect and Architect's consultants; and (3) Separate Contractors, if any, and any of their subcontractors, sub-subcontractors, agents, and employees, for damages caused by fire, or other causes of loss, to the extent those losses are covered by property insurance required by the Agreement or other property insurance applicable to the Project, except such rights as they have to proceeds of such insurance. The Owner or Contractor, as appropriate, shall require similar written waivers in favor of the individuals and entities identified above from the Architect, Architect's consultants, Separate Contractors, subcontractors, and sub-subcontractors. The policies of insurance purchased and maintained by each person or entity agreeing to waive claims pursuant to this section 11.3.1 shall not prohibit this waiver of subrogation. This waiver of subrogation shall be effective as to a person or entity (1) even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, (2) even though that person or entity did not pay the insurance premium directly or indirectly, or (3) whether or not the person or entity had an insurable interest in the damaged property.

§ 11.3.2 If during the Project construction period the Owner insures properties, real or personal or both, at or adjacent to the site by property insurance under policies separate from those insuring the Project, or if after final payment property insurance is to be provided on the completed Project through a policy or policies other than those insuring the Project during the construction period, to the extent permissible by such policies, the Owner waives all rights in accordance with the terms of Section 11.3.1 for damages caused by fire or other causes of loss covered by this separate property insurance.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 11.4 Loss of Use, Business Interruption, and Delay in Completion Insurance

The Owner, at the Owner's option, may purchase and maintain insurance that will protect the Owner against loss of use of the Owner's property, or the inability to conduct normal operations, due to fire or other causes of loss. The Owner waives all rights of action against the Contractor and Architect for loss of use of the Owner's property, due to fire or other hazards however caused.

§11.5 Adjustment and Settlement of Insured Loss

§ 11.5.1 A loss insured under the property insurance required by the Agreement shall be adjusted by the Owner as fiduciary and made payable to the Owner as fiduciary for the insureds, as their interests may appear, subject to requirements of any applicable mortgagee clause and of Section 11.5.2. The Owner shall pay the Architect and Contractor their just shares of insurance proceeds received by the Owner, and by appropriate agreements the Architect and Contractor shall make payments to their consultants and Subcontractors in similar manner.

§ 11.5.2 Prior to settlement of an insured loss, the Owner shall notify the Contractor of the terms of the proposed settlement as well as the proposed allocation of the insurance proceeds. The Contractor shall have 14 days from receipt of notice to object to the proposed settlement or allocation of the proceeds. If the Contractor does not object, the Owner shall settle the loss and the Contractor shall be bound by the settlement and allocation. Upon receipt, the Owner shall deposit the insurance proceeds in a separate account and make the appropriate distributions. Thereafter, if no other agreement is made or the Owner does not terminate the Contract for convenience, the Owner and Contractor shall execute a Change Order for reconstruction of the damaged or destroyed Work in the amount allocated for that purpose. If the Contractor timely objects to either the terms of the proposed settlement or the allocation of the proceeds, the Owner may proceed to settle the insured loss, and any dispute between the Owner and Contractor arising out of the settlement or allocation of the proceeds shall be resolved pursuant to Article 15. Pending resolution of any dispute, the Owner may issue a Construction Change Directive for the reconstruction of the damaged or destroyed Work.

ARTICLE 12 UNCOVERING AND CORRECTION OF WORK

§ 12.1 Uncovering of Work

§ 12.1.1 If a portion of the Work is covered contrary to the Architect's request or to requirements specifically expressed in the Contract Documents, it must, if requested in writing by the Architect, be uncovered for the Architect's examination and be replaced at the Contractor's expense without change in the Contract Time.

§ 12.1.2 If a portion of the Work has been covered that the Architect has not specifically requested to examine prior to its being covered, the Architect may request to see such Work and it shall be uncovered by the Contractor. If such Work is in accordance with the Contract Documents, the Contractor shall be entitled to an equitable adjustment to the Contract Sum and Contract Time as may be appropriate. If such Work is not in accordance with the Contract Documents, the costs of uncovering the Work, and the cost of correction, shall be at the Contractor's expense.

§ 12.2 Correction of Work

§ 12.2.1 Before Substantial Completion

The Contractor shall promptly correct Work rejected by the Architect or failing to conform to the requirements of the Contract Documents, discovered before Substantial Completion and whether or not fabricated, installed or completed. Costs of correcting such rejected Work, including additional testing and inspections, the cost of uncovering and replacement, and compensation for the Architect's services and expenses made necessary thereby, shall be at the Contractor's expense.

§ 12.2.2 After Substantial Completion

§ 12.2.2.1 In addition to the Contractor's obligations under Section 3.5, if, within one year after the date of Substantial Completion of the Work or designated portion thereof or after the date for commencement of warranties established under Section 9.9.1, or by terms of any applicable special warranty required by the Contract Documents, any of the Work is found to be not in accordance with the requirements of the Contract Documents, the Contractor shall correct it promptly after receipt of notice from the Owner to do so, unless the Owner has previously given the Contractor a written acceptance of such condition. The Owner shall give such notice promptly after discovery of the condition. During the one-year period for correction of Work, if the Owner fails to notify the Contractor and give the Contractor an opportunity to make the correction, the Owner waives the rights to require correction by the Contractor and to make a claim for breach of warranty. If the Contractor fails to correct nonconforming Work within a reasonable time during

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

that period after receipt of notice from the Owner or Architect, the Owner may correct it in accordance with Section 2.5.

§ 12.2.2.2 The one-year period for correction of Work shall be extended with respect to portions of Work first performed after Substantial Completion by the period of time between Substantial Completion and the actual completion of that portion of the Work.

§ 12.2.2.3 The one-year period for correction of Work shall not be extended by corrective Work performed by the Contractor pursuant to this Section 12.2.

§ 12.2.3 The Contractor shall remove from the site portions of the Work that are not in accordance with the requirements of the Contract Documents and are neither corrected by the Contractor nor accepted by the Owner.

§ 12.2.4 The Contractor shall bear the cost of correcting destroyed or damaged construction of the Owner or Separate Contractors, whether completed or partially completed, caused by the Contractor's correction or removal of Work that is not in accordance with the requirements of the Contract Documents.

§ 12.2.5 Nothing contained in this Section 12.2 shall be construed to establish a period of limitation with respect to other obligations the Contractor has under the Contract Documents. Establishment of the one-year period for correction of Work as described in Section 12.2.2 relates only to the specific obligation of the Contractor to correct the Work, and has no relationship to the time within which the obligation to comply with the Contract Documents may be sought to be enforced, nor to the time within which proceedings may be commenced to establish the Contractor's liability with respect to the Contractor's obligations other than specifically to correct the Work.

§ 12.3 Acceptance of Nonconforming Work

If the Owner prefers to accept Work that is not in accordance with the requirements of the Contract Documents, the Owner may do so instead of requiring its removal and correction, in which case the Contract Sum will be reduced as appropriate and equitable. Such adjustment shall be effected whether or not final payment has been made.

ARTICLE 13 MISCELLANEOUS PROVISIONS

§ 13.1 Governing Law

The Contract shall be governed by the law of the place where the Project is located, excluding that jurisdiction's choice of law rules. If the parties have selected arbitration as the method of binding dispute resolution, the Federal Arbitration Act shall govern Section 15.4.

§ 13.2 Successors and Assigns

§ 13.2.1 The Owner and Contractor respectively bind themselves, their partners, successors, assigns, and legal representatives to covenants, agreements, and obligations contained in the Contract Documents. Except as provided in Section 13.2.2, neither party to the Contract shall assign the Contract as a whole without written consent of the other. If either party attempts to make an assignment without such consent, that party shall nevertheless remain legally responsible for all obligations under the Contract.

§ 13.2.2 The Owner may, without consent of the Contractor, assign the Contract to a lender providing construction financing for the Project, if the lender assumes the Owner's rights and obligations under the Contract Documents. The Contractor shall execute all consents reasonably required to facilitate the assignment.

§ 13.3 Rights and Remedies

§ 13.3.1 Duties and obligations imposed by the Contract Documents and rights and remedies available thereunder shall be in addition to and not a limitation of duties, obligations, rights, and remedies otherwise imposed or available by law.

§ 13.3.2 No action or failure to act by the Owner, Architect, or Contractor shall constitute a waiver of a right or duty afforded them under the Contract, nor shall such action or failure to act constitute approval of or acquiescence in a breach thereunder, except as may be specifically agreed upon in writing.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 13.4 Tests and Inspections

§ 13.4.1 Tests, inspections, and approvals of portions of the Work shall be made as required by the Contract Documents and by applicable laws, statutes, ordinances, codes, rules, and regulations or lawful orders of public authorities. Unless otherwise provided, the Contractor shall make arrangements for such tests, inspections, and approvals with an independent testing laboratory or entity acceptable to the Owner, or with the appropriate public authority, and shall bear all related costs of tests, inspections, and approvals. The Contractor shall give the Architect timely notice of when and where tests and inspections are to be made so that the Architect may be present for such procedures. The Owner shall bear costs of tests, inspections, or approvals that do not become requirements until after bids are received or negotiations concluded. The Owner shall directly arrange and pay for tests, inspections, or approvals where building codes or applicable laws or regulations so require.

§ 13.4.2 If the Architect, Owner, or public authorities having jurisdiction determine that portions of the Work require additional testing, inspection, or approval not included under Section 13.4.1, the Architect will, upon written authorization from the Owner, instruct the Contractor to make arrangements for such additional testing, inspection, or approval, by an entity acceptable to the Owner, and the Contractor shall give timely notice to the Architect of when and where tests and inspections are to be made so that the Architect may be present for such procedures. Such costs, except as provided in Section 13.4.3, shall be at the Owner's expense.

§ 13.4.3 If procedures for testing, inspection, or approval under Sections 13.4.1 and 13.4.2 reveal failure of the portions of the Work to comply with requirements established by the Contract Documents, all costs made necessary by such failure, including those of repeated procedures and compensation for the Architect's services and expenses, shall be at the Contractor's expense.

§ 13.4.4 Required certificates of testing, inspection, or approval shall, unless otherwise required by the Contract Documents, be secured by the Contractor and promptly delivered to the Architect.

§ 13.4.5 If the Architect is to observe tests, inspections, or approvals required by the Contract Documents, the Architect will do so promptly and, where practicable, at the normal place of testing.

§ 13.4.6 Tests or inspections conducted pursuant to the Contract Documents shall be made promptly to avoid unreasonable delay in the Work.

§ 13.5 Interest

Payments due and unpaid under the Contract Documents shall bear interest from the date payment is due at the rate the parties agree upon in writing or, in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located.

ARTICLE 14 TERMINATION OR SUSPENSION OF THE CONTRACT

§ 14.1 Termination by the Contractor

§ 14.1.1 The Contractor may terminate the Contract if the Work is stopped for a period of 30 consecutive days through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, their agents or employees, or any other persons or entities performing portions of the Work, for any of the following reasons:

.1 Issuance of an order of a court or other public authority having jurisdiction that requires all Work to be stopped;

.2 An act of government, such as a declaration of national emergency, that requires all Work to be stopped;

.3 Because the Architect has not issued a Certificate for Payment and has not notified the Contractor of the reason for withholding certification as provided in Section 9.4.1, or because the Owner has not made payment on a Certificate for Payment within the time stated in the Contract Documents; or

.4 The Owner has failed to furnish to the Contractor reasonable evidence as required by Section 2.2.

§ 14.1.2 The Contractor may terminate the Contract if, through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, their agents or employees, or any other persons or entities performing portions of the Work, repeated suspensions, delays, or interruptions of the entire Work by the Owner as described in Section 14.3, constitute in the aggregate more than 100 percent of the total number of days scheduled for completion, or 120 days in any 365-day period, whichever is less.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 14.1.3 If one of the reasons described in Section 14.1.1 or 14.1.2 exists, the Contractor may, upon seven days' notice to the Owner and Architect, terminate the Contract and recover from the Owner payment for Work executed, as well as reasonable overhead and profit on Work not executed, and costs incurred by reason of such termination.

§ 14.1.4 If the Work is stopped for a period of 60 consecutive days through no act or fault of the Contractor, a Subcontractor, a Sub-subcontractor, or their agents or employees or any other persons or entities performing portions of the Work because the Owner has repeatedly failed to fulfill the Owner's obligations under the Contract Documents with respect to matters important to the progress of the Work, the Contractor may, upon seven additional days' notice to the Owner and the Architect, terminate the Contract and recover from the Owner as provided in Section 14.1.3.

§ 14.2 Termination by the Owner for Cause

§ 14.2.1 The Owner may terminate the Contract if the Contractor

- .1 repeatedly refuses or fails to supply enough properly skilled workers or proper materials;
- .2 fails to make payment to Subcontractors or suppliers in accordance with the respective agreements between the Contractor and the Subcontractors or suppliers;
- .3 repeatedly disregards applicable laws, statutes, ordinances, codes, rules and regulations, or lawful orders of a public authority; or
- .4 otherwise is guilty of substantial breach of a provision of the Contract Documents.

§ 14.2.2 When any of the reasons described in Section 14.2.1 exist, and upon certification by the Architect that sufficient cause exists to justify such action, the Owner may, without prejudice to any other rights or remedies of the Owner and after giving the Contractor and the Contractor's surety, if any, seven days' notice, terminate employment of the Contractor and may, subject to any prior rights of the surety:

- .1 Exclude the Contractor from the site and take possession of all materials, equipment, tools, and construction equipment and machinery thereon owned by the Contractor;
- .2 Accept assignment of subcontracts pursuant to Section 5.4; and
- .3 Finish the Work by whatever reasonable method the Owner may deem expedient. Upon written request of the Contractor, the Owner shall furnish to the Contractor a detailed accounting of the costs incurred by the Owner in finishing the Work.

§ 14.2.3 When the Owner terminates the Contract for one of the reasons stated in Section 14.2.1, the Contractor shall not be entitled to receive further payment until the Work is finished.

§ 14.2.4 If the unpaid balance of the Contract Sum exceeds costs of finishing the Work, including compensation for the Architect's services and expenses made necessary thereby, and other damages incurred by the Owner and not expressly waived, such excess shall be paid to the Contractor. If such costs and damages exceed the unpaid balance, the Contractor shall pay the difference to the Owner. The amount to be paid to the Contractor or Owner, as the case may be, shall be certified by the Initial Decision Maker, upon application, and this obligation for payment shall survive termination of the Contract.

§ 14.3 Suspension by the Owner for Convenience

§ 14.3.1 The Owner may, without cause, order the Contractor in writing to suspend, delay or interrupt the Work, in whole or in part for such period of time as the Owner may determine.

§ 14.3.2 The Contract Sum and Contract Time shall be adjusted for increases in the cost and time caused by suspension, delay, or interruption under Section 14.3.1. Adjustment of the Contract Sum shall include profit. No adjustment shall be made to the extent

- .1 that performance is, was, or would have been, so suspended, delayed, or interrupted, by another cause for which the Contractor is responsible; or
- .2 that an equitable adjustment is made or denied under another provision of the Contract.

§ 14.4 Termination by the Owner for Convenience

§ 14.4.1 The Owner may, at any time, terminate the Contract for the Owner's convenience and without cause.

§ 14.4.2 Upon receipt of notice from the Owner of such termination for the Owner's convenience, the Contractor shall

- .1 cease operations as directed by the Owner in the notice;

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

.2 take actions necessary, or that the Owner may direct, for the protection and preservation of the Work; and

.3 except for Work directed to be performed prior to the effective date of termination stated in the notice, terminate all existing subcontracts and purchase orders and enter into no further subcontracts and purchase orders.

§ 14.4.3 In case of such termination for the Owner's convenience, the Owner shall pay the Contractor for Work properly executed; costs incurred by reason of the termination, including costs attributable to termination of Subcontracts; and the termination fee, if any, set forth in the Agreement.

ARTICLE 15 CLAIMS AND DISPUTES

§ 15.1 Claims

§ 15.1.1 Definition

A Claim is a demand or assertion by one of the parties seeking, as a matter of right, payment of money, a change in the Contract Time, or other relief with respect to the terms of the Contract. The term "Claim" also includes other disputes and matters in question between the Owner and Contractor arising out of or relating to the Contract. The responsibility to substantiate Claims shall rest with the party making the Claim. This Section 15.1.1 does not require the Owner to file a Claim in order to impose liquidated damages in accordance with the Contract Documents.

§ 15.1.2 Time Limits on Claims

The Owner and Contractor shall commence all Claims and causes of action against the other and arising out of or related to the Contract, whether in contract, tort, breach of warranty or otherwise, in accordance with the requirements of the binding dispute resolution method selected in the Agreement and within the period specified by applicable law, but in any case not more than 10 years after the date of Substantial Completion of the Work. The Owner and Contractor waive all Claims and causes of action not commenced in accordance with this Section 15.1.2.

§ 15.1.3 Notice of Claims

§ 15.1.3.1 Claims by either the Owner or Contractor, where the condition giving rise to the Claim is first discovered prior to expiration of the period for correction of the Work set forth in Section 12.2.2, shall be initiated by notice to the other party and to the Initial Decision Maker with a copy sent to the Architect, if the Architect is not serving as the Initial Decision Maker. Claims by either party under this Section 15.1.3.1 shall be initiated within 21 days after occurrence of the event giving rise to such Claim or within 21 days after the claimant first recognizes the condition giving rise to the Claim, whichever is later.

§ 15.1.3.2 Claims by either the Owner or Contractor, where the condition giving rise to the Claim is first discovered after expiration of the period for correction of the Work set forth in Section 12.2.2, shall be initiated by notice to the other party. In such event, no decision by the Initial Decision Maker is required.

§ 15.1.4 Continuing Contract Performance

§ 15.1.4.1 Pending final resolution of a Claim, except as otherwise agreed in writing or as provided in Section 9.7 and Article 14, the Contractor shall proceed diligently with performance of the Contract and the Owner shall continue to make payments in accordance with the Contract Documents.

§ 15.1.4.2 The Contract Sum and Contract Time shall be adjusted in accordance with the Initial Decision Maker's decision, subject to the right of either party to proceed in accordance with this Article 15. The Architect will issue Certificates for Payment in accordance with the decision of the Initial Decision Maker.

§ 15.1.5 Claims for Additional Cost

If the Contractor wishes to make a Claim for an increase in the Contract Sum, notice as provided in Section 15.1.3 shall be given before proceeding to execute the portion of the Work that is the subject of the Claim. Prior notice is not required for Claims relating to an emergency endangering life or property arising under Section 10.4.

§ 15.1.6 Claims for Additional Time

§ 15.1.6.1 If the Contractor wishes to make a Claim for an increase in the Contract Time, notice as provided in Section 15.1.3 shall be given. The Contractor's Claim shall include an estimate of cost and of probable effect of delay on progress of the Work. In the case of a continuing delay, only one Claim is necessary.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 15.1.6.2 If adverse weather conditions are the basis for a Claim for additional time, such Claim shall be documented by data substantiating that weather conditions were abnormal for the period of time, could not have been reasonably anticipated, and had an adverse effect on the scheduled construction.

§ 15.1.7 Waiver of Claims for Consequential Damages

The Contractor and Owner waive Claims against each other for consequential damages arising out of or relating to this Contract. This mutual waiver includes

.1 damages incurred by the Owner for rental expenses, for losses of use, income, profit, financing, business and reputation, and for loss of management or employee productivity or of the services of such persons; and

.2 damages incurred by the Contractor for principal office expenses including the compensation of personnel stationed there, for losses of financing, business and reputation, and for loss of profit, except anticipated profit arising directly from the Work.

This mutual waiver is applicable, without limitation, to all consequential damages due to either party's termination in accordance with Article 14. Nothing contained in this Section 15.1.7 shall be deemed to preclude assessment of liquidated damages, when applicable, in accordance with the requirements of the Contract Documents.

§ 15.2 Initial Decision

§ 15.2.1 Claims, excluding those where the condition giving rise to the Claim is first discovered after expiration of the period for correction of the Work set forth in Section 12.2.2 or arising under Sections 10.3, 10.4, and 11.5, shall be referred to the Initial Decision Maker for initial decision. The Architect will serve as the Initial Decision Maker, unless otherwise indicated in the Agreement. Except for those Claims excluded by this Section 15.2.1, an initial decision shall be required as a condition precedent to mediation of any Claim. If an initial decision has not been rendered within 30 days after the Claim has been referred to the Initial Decision Maker, the party asserting the Claim may demand mediation and binding dispute resolution without a decision having been rendered. Unless the Initial Decision Maker and all affected parties agree, the Initial Decision Maker will not decide disputes between the Contractor and persons or entities other than the Owner.

§ 15.2.2 The Initial Decision Maker will review Claims and within ten days of the receipt of a Claim take one or more of the following actions: (1) request additional supporting data from the claimant or a response with supporting data from the other party, (2) reject the Claim in whole or in part, (3) approve the Claim, (4) suggest a compromise, or (5) advise the parties that the Initial Decision Maker is unable to resolve the Claim if the Initial Decision Maker lacks sufficient information to evaluate the merits of the Claim or if the Initial Decision Maker concludes that, in the Initial Decision Maker's sole discretion, it would be inappropriate for the Initial Decision Maker to resolve the Claim.

§ 15.2.3 In evaluating Claims, the Initial Decision Maker may, but shall not be obligated to, consult with or seek information from either party or from persons with special knowledge or expertise who may assist the Initial Decision Maker in rendering a decision. The Initial Decision Maker may request the Owner to authorize retention of such persons at the Owner's expense.

§ 15.2.4 If the Initial Decision Maker requests a party to provide a response to a Claim or to furnish additional supporting data, such party shall respond, within ten days after receipt of the request, and shall either (1) provide a response on the requested supporting data, (2) advise the Initial Decision Maker when the response or supporting data will be furnished, or (3) advise the Initial Decision Maker that no supporting data will be furnished. Upon receipt of the response or supporting data, if any, the Initial Decision Maker will either reject or approve the Claim in whole or in part.

§ 15.2.5 The Initial Decision Maker will render an initial decision approving or rejecting the Claim, or indicating that the Initial Decision Maker is unable to resolve the Claim. This initial decision shall (1) be in writing; (2) state the reasons therefor; and (3) notify the parties and the Architect, if the Architect is not serving as the Initial Decision Maker, of any change in the Contract Sum or Contract Time or both. The initial decision shall be final and binding on the parties but subject to mediation and, if the parties fail to resolve their dispute through mediation, to binding dispute resolution.

§ 15.2.6 Either party may file for mediation of an initial decision at any time, subject to the terms of Section 15.2.6.1.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 15.2.6.1 Either party may, within 30 days from the date of receipt of an initial decision, demand in writing that the other party file for mediation. If such a demand is made and the party receiving the demand fails to file for mediation within 30 days after receipt thereof, then both parties waive their rights to mediate or pursue binding dispute resolution proceedings with respect to the initial decision.

§ 15.2.7 In the event of a Claim against the Contractor, the Owner may, but is not obligated to, notify the surety, if any, of the nature and amount of the Claim. If the Claim relates to a possibility of a Contractor's default, the Owner may, but is not obligated to, notify the surety and request the surety's assistance in resolving the controversy.

§ 15.2.8 If a Claim relates to or is the subject of a mechanic's lien, the party asserting such Claim may proceed in accordance with applicable law to comply with the lien notice or filing deadlines.

§ 15.3 Mediation

§ 15.3.1 Claims, disputes, or other matters in controversy arising out of or related to the Contract, except those waived as provided for in Sections 9.10.4, 9.10.5, and 15.1.7, shall be subject to mediation as a condition precedent to binding dispute resolution.

§ 15.3.2 The parties shall endeavor to resolve their Claims by mediation which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association in accordance with its Construction Industry Mediation Procedures in effect on the date of the Agreement. A request for mediation shall be made in writing, delivered to the other party to the Contract, and filed with the person or entity administering the mediation. The request may be made concurrently with the filing of binding dispute resolution proceedings but, in such event, mediation shall proceed in advance of binding dispute resolution proceedings, which shall be stayed pending mediation for a period of 60 days from the date of filing, unless stayed for a longer period by agreement of the parties or court order. If an arbitration is stayed pursuant to this Section 15.3.2, the parties may nonetheless proceed to the selection of the arbitrator(s) and agree upon a schedule for later proceedings.

§ 15.3.3 Either party may, within 30 days from the date that mediation has been concluded without resolution of the dispute or 60 days after mediation has been demanded without resolution of the dispute, demand in writing that the other party file for binding dispute resolution. If such a demand is made and the party receiving the demand fails to file for binding dispute resolution within 60 days after receipt thereof, then both parties waive their rights to binding dispute resolution proceedings with respect to the initial decision.

§ 15.3.4 The parties shall share the mediator's fee and any filing fees equally. The mediation shall be held in the place where the Project is located, unless another location is mutually agreed upon. Agreements reached in mediation shall be enforceable as settlement agreements in any court having jurisdiction thereof.

§ 15.4 Arbitration

§ 15.4.1 If the parties have selected arbitration as the method for binding dispute resolution in the Agreement, any Claim subject to, but not resolved by, mediation shall be subject to arbitration which, unless the parties mutually agree otherwise, shall be administered by the American Arbitration Association in accordance with its Construction Industry Arbitration Rules in effect on the date of the Agreement. The Arbitration shall be conducted in the place where the Project is located, unless another location is mutually agreed upon. A demand for arbitration shall be made in writing, delivered to the other party to the Contract, and filed with the person or entity administering the arbitration. The party filing a notice of demand for arbitration must assert in the demand all Claims then known to that party on which arbitration is permitted to be demanded.

§ 15.4.1.1 A demand for arbitration shall be made no earlier than concurrently with the filing of a request for mediation, but in no event shall it be made after the date when the institution of legal or equitable proceedings based on the Claim would be barred by the applicable statute of limitations. For statute of limitations purposes, receipt of a written demand for arbitration by the person or entity administering the arbitration shall constitute the institution of legal or equitable proceedings based on the Claim.

§ 15.4.2 The award rendered by the arbitrator or arbitrators shall be final, and judgment may be entered upon it in accordance with applicable law in any court having jurisdiction thereof.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

§ 15.4.3 The foregoing agreement to arbitrate and other agreements to arbitrate with an additional person or entity duly consented to by parties to the Agreement, shall be specifically enforceable under applicable law in any court having jurisdiction thereof.

§ 15.4.4 Consolidation or Joinder

§ 15.4.4.1 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, either party may consolidate an arbitration conducted under this Agreement with any other arbitration to which it is a party provided that (1) the arbitration agreement governing the other arbitration permits consolidation, (2) the arbitrations to be consolidated substantially involve common questions of law or fact, and (3) the arbitrations employ materially similar procedural rules and methods for selecting arbitrator(s).

§ 15.4.4.2 Subject to the rules of the American Arbitration Association or other applicable arbitration rules, either party may include by joinder persons or entities substantially involved in a common question of law or fact whose presence is required if complete relief is to be accorded in arbitration, provided that the party sought to be joined consents in writing to such joinder. Consent to arbitration involving an additional person or entity shall not constitute consent to arbitration of any claim, dispute or other matter in question not described in the written consent.

§ 15.4.4.3 The Owner and Contractor grant to any person or entity made a party to an arbitration conducted under this Section 15.4, whether by joinder or consolidation, the same rights of joinder and consolidation as those of the Owner and Contractor under this Agreement.

AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

Additions and Deletions Report for
AIA® Document A201™ – 2017

This Additions and Deletions Report, as defined on page 1 of the associated document, reproduces below all text the author has added to the standard form AIA document in order to complete it, as well as any text the author may have added to or deleted from the original AIA text. Added text is shown underlined. Deleted text is indicated with a horizontal line through the original AIA text.

Note: This Additions and Deletions Report is provided for information purposes only and is not incorporated into or constitute any part of the associated AIA document. This Additions and Deletions Report and its associated document were generated simultaneously by AIA software at 15:50:42 ET on 03/05/2019.

PAGE 1

.

Additions and Deletions Report for AIA Document A201™ – 2017. Copyright © 1911, 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1966, 1970, 1976, 1987, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

Certification of Document's Authenticity

AIA® Document D401™ – 2003

I, , hereby certify, to the best of my knowledge, information and belief, that I created the attached final document simultaneously with its associated Additions and Deletions Report and this certification at 15:50:42 ET on 03/05/2019 under Order No. 8779998754 from AIA Contract Documents software and that in preparing the attached final document I made no changes to the original text of AIA® Document A201™ – 2017, General Conditions of the Contract for Construction , as published by the AIA in its software, other than those additions and deletions shown in the associated Additions and Deletions Report.

_____

(Signed)

_____

(Title)

_____

(Dated)

AIA Document D401™ – 2003. Copyright © 1992 and 2003 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 15:50:42 ET on 03/05/2019 under Order No.8779998754 which expires on 06/19/2019, and is not for resale.
User Notes: (1950958384)

SUPPLEMENTARY CONDITIONS

These Supplementary Conditions modify, change, delete from or add to the General Conditions of the Contract for Construction, AIA Document A201, 2017 Edition. Where any Article of the General Conditions is modified or any Section, Paragraph, Subparagraph or Clause thereof is modified or deleted by these supplements, the unaltered provisions of that Section, Article, Paragraph, Subparagraph or Clause shall remain in effect.

Articles, Sections, Paragraphs, Subparagraphs or Clauses modified or deleted have the same numerical designation as those occurring in the General Conditions.

ARTICLE 1

GENERAL PROVISIONS

1.1 BASIC DEFINITIONS

1.1.1. The Contract Documents
In Section 1.1.1 delete the third sentence, and add the following sentence:
The Contract Documents shall include the Bid Documents as listed in the Instructions to Bidders and any modifications made thereto by addenda.

1.1.8 Initial Decision Maker
Delete all after the words, “shall not show partiality to the Owner or Contractor”.

1.5 OWNERSHIP AND USE OF DRAWINGS, SPECIFICATIONS AND OTHER INSTRUMENTS OF SERVICE [REFER TO *La R.S. 38:2317*]

1.5.1 Delete the first sentence of the paragraph.

1.5.1 In the third sentence: delete the remainder after the word “publication”.

1.7 DIGITAL DATA USE AND TRANSMISSION

In the first sentence after the words, “in digital form” delete “. The parties will use AIA Document E203 2013, Building Information Modeling and Digital Data Exhibit”.

1.8 BUILDING INFORMATION MODELS USE AND RELIANCE

Delete Section 1.8.

ARTICLE 2

OWNER

2.2 EVIDENCE OF THE OWNER’S FINANCIAL ARRANGEMENTS

Delete Section 2.2.

2.3 INFORMATION AND SERVICES REQUIRED OF THE OWNER

2.3.1 In the first sentence, delete: all before "the Owner shall secure…"

Delete Section 2.3.2 and substitute the following:

2.3.2 The term Architect, when used in the Contract Documents, shall mean the prime Designer (Architect, Engineer, or Landscape Architect), or his authorized representative, lawfully licensed to practice architecture, engineering, or landscape architecture in the State of Louisiana, identified as such in the Agreement and is referred to throughout the Contract Documents as if singular in number.

2.3.3 Delete the words: "to whom the Contractor has no reasonable objection and".

ARTICLE 3

CONTRACTOR

3.4 LABOR AND MATERIALS

3.4.2 Delete Section 3.4.2.

Delete Section 3.4.3 and substitute with the following:

3.4.3 Contractor and its employees, officers, agents, representatives, and Subcontractors shall conduct themselves in an appropriate and professional manner, in accordance with the Owner's requirements, at all times while working on the Project. Any such individual who behaves in an inappropriate manner or who engages in the use of inappropriate language or conduct while on Owner's property, as determined by the Owner, shall be removed from the Project at the Owner's request. Such individual shall not be permitted to return without the written permission of the Owner. The Owner shall not be responsible or liable to Contractor or any Subcontractor for any additional costs, expenses, losses, claims or damages incurred by Contractor or its Subcontractor as a result of the removal of an individual from the Owner's property pursuant to this Section. The Contractor shall not permit employment of unfit persons or persons not properly skilled in tasks assigned to them.

3.5 WARRANTY

3.5.2 Replace reference to "Section 9.8.4" with "Section 9.8.6".

3.7 PERMITS, FEES, NOTICES, AND COMPLIANCE WITH LAWS (La R.S. 40:1724[A])

3.7.1 Delete Section 3.7.1.

3.7.2 In Section 3.7.2, replace the word "public" with the word "State".

Delete Section 3.7.5 and substitute the following:

3.7.5 If, during the course of the Work, the Contractor discovers human remains, unmarked burial or archaeological sites, burial artifacts, or wetlands, which are not indicated in the Contract Documents, the Contractor shall follow all procedures mandated by State and Federal law, including but not limited to La R.S. 8:671 et seq., the Office of Coastal Protection and Restoration, and Sections 401 & 404 of the Federal Clean Water Act. Request for adjustment of the Contract Sum and Contract Time arising from the existence of such remains or features shall be submitted in writing to the Owner pursuant to the Contract Documents.

3.8 ALLOWANCES

Delete Sections 3.8.1, 3.8.2, and 3.8.3 in their entirety and add the following new Section 3.8.1:

3.8.1 Allowances shall not be made on any of the Work.

3.9 SUPERINTENDENT

3.9.1 Add the following to the end of the paragraph:
Important communications shall be confirmed in writing. Other communications shall be similarly confirmed on written request in each case.

3.10 CONTRACTOR'S CONSTRUCTION AND SUBMITTAL SCHEDULES

3.10.1 Add the following: For projects with a contract sum greater than $1,000,000.00, the Contractor shall include with the schedule, for the Owner's and Architect's information, a network analysis to identify those tasks which are on the critical path, i.e., where any delay in the completion of these tasks will lengthen the project timescale, unless action is taken. A revised schedule shall be submitted with each Application and Certificate for Payment. No payment shall be made until this schedule is received.

3.10.3 In the first sentence, delete the word "general".

After the first sentence, add the following:
If the Work is not on schedule, as determined by the Architect, and the Contractor fails to take action to bring the Work on schedule, then the Contractor shall be deemed in default under this Contract and the progress of the Work shall be deemed unsatisfactory. Such default may be considered grounds for termination by the Owner for cause in accordance with Section 14.2.

Add the following Sections:

3.10.4 Add the following: Submittal by the contractor of a schedule or other documentation showing a completion date for his Work prior to the completion date stated in the contract shall not impose any obligation or responsibility on the Owner or Architect for the earlier completion date.

3.10.5 In the event the Owner employs a commissioning consultant, the Contractor shall cooperate fully in the commissioning process and shall require all subcontractors and

others under his control to cooperate. The purpose of such services shall be to ensure that all systems perform correctly and interactively according to the provisions of the Contract Documents.

3.11 DOCUMENTS AND SAMPLES AT THE SITE

Add the following: This requirement is of the essence of the contract. The Architect shall determine the value of these documents and this amount shall not be approved for payment to the Contractor until all of the listed documents are delivered to the Architect in good order, completely marked with field changes and otherwise complete in all aspects.

ARTICLE 4

ARCHITECT

4.2 ADMINISTRATION OF THE CONTRACT

4.2.1 In the first sentence, delete the phrase: "the date the Architect issues the final Certificate for Payment" and replace with the phrase "final payment is due, and with the Owner's concurrence, from time to time during the one year period for correction of Work described in Section 12.2."

4.2.2 In the first sentence, after the phrase: "become generally familiar with"; insert the following: "and to keep the Owner informed about".

In the first sentence, after the phrase "portion of the Work completed", insert the following: "to endeavor to guard the Owner against defects and deficiencies in the Work,"

4.2.4 In the first sentence, delete all after "The Owner and Contractor", and add the following "may communicate directly with each other, when deemed necessary by the Owner, and the Owner will notify the Architect of any decision."

4.2.10 Add the following sentence to the end of Section 4.2.10: There shall be no restriction on the Owner having a Representative.

4.2.11 Add the following sentence to the end of Section 4.2.11:

If no agreement is made concerning the time within which interpretation required of the Architect shall be furnished in compliance with this Section 4.2, then delay shall not be recognized on account of failure by the Architect to furnish such interpretation until 15 days after written request is made for them.

4.2.14 Insert the following sentence between the second and third sentences of Section 4.2.14:

If no agreement is made concerning the time within which interpretation required of the Architect shall be furnished in compliance with this Section 4.2, then delay shall not be recognized on account of failure by the Architect to furnish such interpretation until 15 days after written request is made for them.

ARTICLE 5

SUBCONTRACTORS

5.2 AWARD OF SUBCONTRACTS AND OTHER CONTRACTS FOR PORTIONS OF THE WORK

Delete Section 5.2.1, and substitute the following:

5.2.1 Unless otherwise required by the Contract Documents, the Contractor shall furnish at the Pre-Construction Conference, to the Owner and the Architect, in writing, the names of the persons or entities (including those who are to furnish materials or equipment fabricated to a special design) proposed for each of the principal portions of the Work. No Contractor payments shall be made until this information is received.

Delete Section 5.2.2, and substitute the following:

5.2.2 The Contractor shall be solely responsible for selection and performance of all subcontractors. The Contractor shall not be entitled to claims for additional time and/or an increase in the contract sum due to a problem with performance or nonperformance of a subcontractor.

Delete Sections 5.2.3 and 5.2.4 and substitute the following:

5.2.3 The Contractor shall notify the Architect and the Owner when a subcontractor is to be changed and substituted with another subcontractor.

5.4 CONTINGENT ASSIGNMENT OF SUBCONTRACTS

Delete Sections 5.4, 5.4.1, 5.4.2 and 5.4.3

ARTICLE 7

CHANGES IN THE WORK

7.1 GENERAL

Add the following Sections:

7.1.4 As part of the pre-construction conference submittals, the Contractor shall submit the following prior to the Contractor’s initial request for payment:

7.1.4.1 Fixed job site overhead cost itemized with documentation to support daily rates.

7.1.4.2 Bond Premium Rate with supporting information from the General Contractor’s carrier.

7.1.4.3 Labor Burden by trade for both Subcontractors and General Contractor. The Labor Burden shall be supported by the Worker's Compensation and Employer's Liability Insurance Policy Information Page. Provide for all trades.

7.1.4.4 Internal Rate Charges for all significant company owned equipment.

7.1.5 If the General Contractor fails to submit the aforementioned documentation as part of the pre-construction submittals, then pay applications shall not be processed until such time as the Owner receives this information.

7.2 CHANGE ORDERS

Delete Section 7.2.1, and substitute the following Sections:

7.2.1 A Change Order is a written instrument prepared by the Architect and signed by the Owner, the Architect, and the Contractor issued after execution of the Contract, authorizing a change in the Work and/or an adjustment in the Contract Sum and/or the Contract Time. The Contract Sum and the Contract Time may be changed only by Change Order. A Change Order signed by the Contractor indicates his agreement therewith, including the adjustment in the Contract Sum or the Contract Time. Any reservation of rights, stipulation, or other modification made on the change order by the contractor shall have no effect.

7.2.2 "Cost of the Work" for the purpose of Change Orders shall be the eligible costs required to be incurred in performance of the Work and paid by the Contractor and Subcontractors which eligible costs shall be limited to:

7.2.2.1 Actual wages paid directly to labor personnel, with a labor burden markup exclusively limited to applicable payroll taxes, worker's compensation insurance, unemployment compensation, and social security taxes for those labor personnel performing the Work. Wages shall be the basic hourly labor rate paid an employee exclusive of fringe benefits or other employee costs. The labor burden percentage for the "Cost of the Work" is limited to categories listed herein. Employer-provided health insurance, fringe benefits, employee training (whether a requirement of employment or not), vacation pay, etc., are examples of ineligible labor burden costs which ***shall not*** be included, as these costs are already compensated by the Overhead and Profit markup.

Supervision shall not be included as a line item in the "Cost of the Work", except when the change results in a documented delay in the critical path, as described in Section 7.2.7.

7.2.2.2 Cost of all materials and supplies necessary and required to perform the Work, identifying each item and its individual cost, including taxes. Incidental consumables are not eligible costs and shall not be included.

7.2.2.3 Cost of each necessary piece of machinery and equipment required to perform the Work, identifying each item and its individual cost, including taxes. Incidental small tools of a specific trade (i.e., shovels, saws, hammers, air compressors, etc.,) and general use vehicles, such as pickup trucks even for

moving items around the site, fuel for these general use vehicles, travel, lodging, and/or meals are not eligible and shall not be included.

7.2.2.4 Eligible Insurance costs shall be limited to documented increases in "Builder's Risk" insurance premium / costs only. Commercial General Liability, Automobile Liability, and all other required insurances, where referenced in the Contract shall be considered part of normal overhead. These costs are already compensated by the Overhead and Profit markup.

7.2.2.5 Cost for the General Contractor Performance and Payment Bond premium, where the documented cost of the premiums have been increased due to the Change Order.

7.2.3 Overhead and Profit - The Contractor and Subcontractor shall be due home office fixed overhead and profits on the Cost of the Work, but shall not exceed a total of 16% of the direct cost of any portion of Work.

The credit to the Owner resulting from a change in the Work shall be the sum of those items above, including overhead and profit. Where a change results in both credits to the Owner and extras to the Contractor for related items, overhead and profit shall be computed for credits to the Owner and extras to the Contractor. The Owner shall receive full credit for the computed overhead and profit on credit change order items.

7.2.4 The cost to the Owner resulting from a change in the Work shall be the sum of: Cost of the Work (as defined at Section 7.2.2) and Overhead and Profit (as defined at Section 7.2.3), and shall be computed as follows:

7.2.4.1 When all of the Work is General Contractor Work; 8% markup on the Cost of the Work.

7.2.4.2 When the Work is all Subcontract Work; 8% markup on the Cost of the Work for Subcontractor's Overhead and Profit, plus 8% markup on the Cost of the Work, not including the Subcontractor's Overhead and Profit markup, for General Contractor's Overhead and Profit.

7.2.4.3 When the Work is a combination of General Contractor Work and Subcontract Work; that portion of the direct cost that is General Contract Work shall be computed per Section 7.2.4.1 and that portion of the direct cost that is Subcontract Work shall be computed per Section 7.2.4.2.

Premiums for the General Contractor's bond may be included, but after the markup is added to the Cost of the Work.
Premiums for the Subcontractor's Bond shall not be included.

7.2.4.4 Subcontract cost shall consist of the items in Section 7.2.2 above plus Overhead and Profit as defined in Section 7.2.3.

7.2.5 Before a Change Order is prepared, the Contractor shall prepare and deliver to the Architect the following information concerning the Cost of the Work, not subject to waiver, within a reasonable time after being notified to prepare said Change Order:

A detailed, itemized list of labor, material and equipment costs for the General Contractor's Work including quantities and unit costs for each item of labor, material and equipment.

An itemized list of labor, material and equipment costs for each Subcontractor's and/or Sub-Subcontractor's Work including quantities and unit costs for each item of labor, material and equipment.

7.2.6 After a Change Order has been approved, no future requests for extensions of time or additional cost shall be considered for that Change Order.

7.2.7 Extended fixed job-site costs are indirect costs that are necessary to support the work in the field. Examples of fixed job-site costs are field office rental, salaries of field office staff, field office utilities, and telephone.

Extended fixed job-site costs or equitable adjustment may be included in a Change Order due to a delay in the critical path, with the exception of weather related delays. In the event of a delay in the critical path, the Contractor shall submit all changes or adjustments to the Contract Time **within twenty-one (21) days** of the event giving rise to the delay. The Contractor shall submit documentation and justification for the adjustment by performing a critical path analysis of its most recent schedule in use prior to the change, which shows an extension in critical path activities.

The Contractor shall notify the Architect in writing that the Contractor is making a claim for extended fixed job-site overhead as required by Section 15.1.2. The Contractor shall provide proof that the Contractor is unable to mitigate financial damages through Alternate Work within this Contract or replacement work. "Replacement Work" is that work which the Contractor is obligated to perform under any construction contract separate from this Contract. Reasonable proof shall be required by the Architect that the delays affected the Completion Date.

7.2.8 "Cost of the Work" whether General Contractor cost or Subcontractor cost shall not apply to the following:

7.2.8.1 Salaries or other compensation of the Contractor's personnel at the Contractor's principal office and branch offices.

7.2.8.2 Any part of the Contractor's capital expenses, including interest on the Contractor's capital employed for the Work.

7.2.8.3 Overhead and general expenses of any kind or the cost of any item not specifically and expressly included above in Cost of the Work.

7.2.8.4 Cost of supervision refer to section 7.2.2.1, with exception as provided in Section 7.2.7.

7.2.9 When applicable as provided by the Contract, the cost to Owner for Change Orders shall be determined by quantities and unit prices. The quantity of any item shall be as

submitted by the Contractor and approved by the Architect. Unit prices shall cover cost of Material, Labor, Equipment, Overhead and Profit.

7.3 CONSTRUCTION CHANGE DIRECTIVES

7.3.3 In the first sentence after "following methods" insert: ", but not to exceed a specified amount".

7.3.4 From .1 of the list, delete all after "Costs of labor, including" and substitute the following "social security, old age and employment insurance, applicable payroll taxes, and workers' compensation insurance;"

Delete the following from .4 of the list: "permit fees,"

Delete Section 7.3.9 and substitute the following:

7.3.9 Pending final determination of the total costs of a Construction Change Directive to the Owner, amounts not in dispute for such changes in the Work shall be included in Applications for Payment accompanied by a Change Order indicating the parties' agreement with part or all of such costs.

ARTICLE 8

TIME

8.1 DEFINITIONS

Add the following:

8.1.5 The Contract Time shall not be changed by the submission of a schedule that shows an early completion date unless specifically authorized by change order.

8.2 PROGRESS AND COMPLETION

Add to Section 8.2.1 the following:

Completion of the Work must be within the Time for Completion stated in the Agreement, subject to such extensions as may be granted under Section 8.3. The Contractor agrees to commence Work not later than fourteen (14) days after the transmittal date of Written Notice to Proceed from the Owner and to substantially complete the project within the time stated in the Contract. The Owner will suffer financial loss if the project is not substantially complete in the time set forth in the Contract Documents. The Contractor and the Contractor's Surety shall be liable for and shall pay to the Owner the sum stated in the Contract Documents as fixed, agreed and liquidated damages for each consecutive calendar day (Saturdays, Sundays and holidays included) of delay until the Work is substantially complete. The Owner shall be entitled to the sum stated in the Contract Documents. Such Liquidated Damages shall be withheld by the Owner from the amounts due the Contractor for progress payments.

Delete Section 8.2.2.

8.3 DELAYS AND EXTENSIONS OF TIME

8.3.1 In the first sentence after the words "Owner pending" delete the words "mediation and binding dispute resolution" and add the word "litigation", and delete the last word "determine" and add the following: "recommend, subject to Owner's approval of Change Order. If the claim is not made within the limits of Article 15, all rights for future claims for that month are waived."

ARTICLE 9

PAYMENTS AND COMPLETION

9.1 CONTRACT SUM

Delete Section 9.1.2.

Delete Section 9.2 and substitute the following:

9.2 SCHEDULE OF VALUES

At the Pre-Construction Conference, the Contractor shall submit to the Owner and the Architect a Schedule of Values prepared as follows:

9.2.1 The attached Schedule of Values Format shall be used. If applicable, the cost of Work for each section listed under each division, shall be given. The cost for each section shall include Labor, Materials, Overhead and Profit.

9.2.2 The Total of all items shall equal the Total Contract Sum. This schedule, when approved by the Architect, shall be used as a basis for the Contractor's Applications for Payment and it may be used for determining the cost of the Work in deductive change orders, when a specific item of Work listed on the Schedule of Values is to be removed. Once the Schedule of Values is submitted at the Pre-Construction Conference, the schedule shall not be modified without approval from the Owner and Architect.

9.3 APPLICATIONS FOR PAYMENT

Delete Sections 9.3.1, 9.3.1.1, and 9.3.1.2 and substitute the following:

9.3.1 Monthly, the Contractor shall submit to the Architect a Facility Planning and Control – Application and Certification for Payment form, supported by any additional data substantiating the Contractor's right to payment as the Owner or the Architect may require. Application for Payment shall be submitted on or about the first of each month for the value of labor and materials incorporated into the Work and of materials, suitably stored, at the site as of the twenty-fifth day of the preceding month, less normal retainage as follows, per La R.S. 38:2248:

9.3.1.1 Projects with Contract price up to $500,000.00 – 10% of the Contract price.

9.3.1.2 Projects with Contract price of $500,000.00, or more – 5% of the Contract price.

9.3.1.3 No payment shall be made until the revised schedule required by Section 3.10.1 is received.

9.3.1.4 The normal retainage shall not be due the Contractor until after substantial completion and expiration of the forty-five day lien period and submission to the Architect of a clear lien certificate, consent of surety, and invoice for retainage.

Delete Section 9.3.2 and substitute the following:

9.3.2 Unless otherwise provided in the Contract Documents, payments shall be made on account of materials and equipment delivered and suitably stored at the site for subsequent incorporation in the Work. Payments for materials or equipment stored on the site shall be conditioned upon submission by the Contractor of bills of sale or such other procedures satisfactory to the Owner to establish the Owner's title to such materials and equipment or otherwise protect the Owner's interest, including applicable insurance.

9.5 DECISIONS TO WITHHOLD CERTIFICATION

Section 9.5.1.7: Delete the word "repeated".

Delete Section 9.5.4.

9.6 PROGRESS PAYMENTS

Delete Section 9.6.1 and substitute the following:

9.6.1 After the Architect has issued a Certificate for Payment, the Owner shall make payment within twenty days except for projects funded fully or in part by a Federal reimbursement program. For such projects the Owner will make payment in a timely manner consistent with reimbursement.

9.6.2 Delete the phrase: "no later than seven days" from the first sentence.

After the end of the second sentence, add the following:

La R.S. 9:2784 (A) and (C) require a Contractor or Subcontractor to make payment due to each Subcontractor and supplier within fourteen (14) consecutive days of the receipt of payment from the Owner. If not paid, a penalty in the amount of ½ of 1% per day is due, up to a maximum of 15% from the expiration date until paid. The contractor or subcontractor, whichever is applicable, is solely responsible for payment of a penalty.

9.6.4 Delete the first two sentences of Section 9.6.4 and add the following to the end of the Section:

Pursuant to La. R.S. 38:2242 and La. R.S. 38:2242.2, when the Owner receives any claim of nonpayment arising out of the Contract, the Owner shall deduct 125% of such claim from the Contract Sum. The Contractor, or any interested party, may deposit security, in accordance with La. R.S. 38:2242.2, guaranteeing payment of the claim with the recorder

of mortgages of the parish where the Work has been done. When the Owner receives original proof of such guarantee from the recorder of mortgages, the claim deduction will be added back to the Contract Sum.

Delete Section **9.7 FAILURE OF PAYMENT**.

Delete Section 9.8 and substitute the following:

9.8 SUBSTANTIAL COMPLETION

9.8.1 Substantial Completion is the stage in the progress of the Work when the Work is sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended use. The Architect shall determine if the project is substantially complete in accordance with this Section.

9.8.2 When the Contractor considers that the Work is Substantially Complete, the Contractor shall prepare and submit to the Architect a comprehensive list of items to be completed or corrected prior to final payment. Failure to include an item on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents.

9.8.3 Upon receipt of the Contractor's list, the Architect shall make an inspection to determine whether the Work is substantially complete. A prerequisite to the Work being considered as substantially complete is the Owner's receipt of the executed Roofing Contractor's and Roofing Manufacturer's guarantees, where roofing Work is part of the Contract. Prior to inspection by the Architect, the Contractor shall notify the Architect that the project is ready for inspection by the State Fire Marshal's office. If the Architect's inspection discloses any item, whether or not included on the Contractor's list, which is not sufficiently complete in accordance with the Contract Documents so that the Owner can occupy or utilize the Work for its intended use, the Contractor shall, before the Work can be considered as Substantially Complete, complete or correct such item upon notification by the Architect. In such case, the Contractor shall then submit a request for another inspection by the Architect to determine Substantial Completion.

9.8.4 When the Architect determines that the project is Substantially Complete, he shall prepare a punch list of exceptions and the dollar value related thereto. The monetary value assigned to this list will be the sum of the cost estimate for each particular item of Work the Architect develops based on the mobilization, labor, material and equipment costs of correcting the item and shall be retained from the monies owed the contractor, above and beyond the standard lien retainage. The cost of these items shall be prepared in the same format as the schedule of values. At the end of the forty-five day lien period payment shall be approved for all punch list items completed up to that time. After that payment, none of the remaining funds shall be due the contractor until all punch list items are completed and are accepted by the Architect. If the dollar value of the punch list exceeds the amount of funds, less the retainage amount, in the remaining balance of the Contract, then the Project shall not be considered as substantially complete. If funds remaining are less than that required to complete the Work, the Contractor shall pay the difference.

9.8.5 When the preparation of the punch list is complete the Architect shall prepare a Recommendation of Acceptance incorporating the punch list and submit it to the Owner. Upon approval of the Recommendation of Acceptance, the Owner may issue a Notice of Acceptance of Building Contract which shall establish the Date of Substantial Completion. The Contractor shall record the Notice of Acceptance with the Clerk of Court in the Parish in which the Work has been performed. If the Notice of Acceptance has not been recorded seven (7) days after issuance, the Owner may record the Acceptance at the Contractor's expense. All additive change orders must be processed before issuance of the Recommendation of Acceptance. The Owner shall not be responsible for payment for any Work associated with change orders that is not incorporated into the contract at the time of the Recommendation of Acceptance.

9.8.6 Warranties required by the Contract Documents shall commence on the date of Acceptance of the Work unless otherwise agreed to in writing by the Owner and Contractor. Unless otherwise agreed to in writing by the Owner and Contractor, security, maintenance, heat, utilities, damage to the Work not covered by the punch list and insurance shall become the Owner's responsibility on the Date of Substantial Completion.

9.8.7 If all punch list items have not been completed by the end of the forty-five (45) day lien period, through no fault of the Architect or Owner, the Owner may hold the Contractor in default. If the Owner finds the Contractor is in default, the Surety shall be notified. If within forty-five (45) days after notification, the Surety has not completed the punch list, through no fault of the Architect or Owner, the Owner may, at his option, contract to have the balance of the Work completed and pay for such Work with the unpaid funds remaining in the Contract sum. Finding the Contractor in default shall constitute a reason for disqualification of the Contractor from bidding on future state contracts. If the surety fails to complete the punch list within the stipulated time period, the Owner may not accept bonds submitted, in the future, by the surety.

9.9 PARTIAL OCCUPANCY OR USE

Delete Section 9.9.1 and substitute the following:

9.9.1 Partial Occupancy is that stage in the progress of the Work when a designated portion of the Work is sufficiently complete in accordance with the Contract Documents so the Owner can occupy or utilize the designated portion of the Work for its intended use. The Owner may occupy or use any substantially completed portion of the Work so designated by separate agreement with the Contractor and authorized by public authorities having jurisdiction over the Work. Such occupancy or use may commence provided the Owner and Contractor have accepted in writing the responsibilities assigned to each of them for payments, if any, security, maintenance, heat, utilities, damage to the Work and insurance, and have agreed in writing concerning the period for correction of the Work and commencement of warranties required by the Contract Documents. When the Contractor considers the designated portion substantially complete the Contractor shall prepare and submit a list to the Architect as provided under Section 9.8.2. Consent of the Contractor to partial occupancy or use shall not be unreasonably withheld.

9.10 FINAL COMPLETION AND FINAL PAYMENT

Delete Section 9.10.4 and replace with the following:

9.10.4 The making of final payment shall not constitute a waiver of Claims by the Owner for the following:

9.10.4.1 Claims, security interests, or encumbrances arising out of the Contract and unsettled;

9.10.4.2 failure of the Work to comply with the requirements of the Contract Documents irrespective of when such failure is discovered;

9.10.4.3 terms of special warranties required by the Contract Documents; or

9.10.4.4 audits performed by the Owner, after final payment.

ARTICLE 10

PROTECTION OF PERSONS AND PROPERTY

10.2 SAFETY OF PERSONS AND PROPERTY

10.2.2 In the first sentence, between the words: "bearing on" and "safety", add the words: "the health and,"

10.3 HAZARDOUS MATERIALS

10.3.1 In the second sentence after (PCB) add: "or lead".

10.3.2 After the first sentence, delete all remaining sentences.

Add at the end: "The Contract time shall be extended appropriately."

Delete Section 10.4 and substitute the following:

10.4 EMERGENCIES

In an emergency affecting the safety of persons or property, the Contractor shall notify the Owner and Architect immediately of the emergency, simultaneously acting at his discretion to prevent damage, injury or loss. Any additional compensation or extension of time claimed by the Contractor on account of emergency Work shall be determined as provided in Article 15 and Article 7.

ARTICLE 11

INSURANCE AND BONDS

AIA A101 – 2017 Exhibit A is not a part of these documents. Delete all of Sections 11.1, 11.2, 11.3, 11.4, and 11.5, and substitute the following:

INSURANCE REQUIREMENTS FOR
NEW CONSTRUCTION, ADDITIONS AND RENOVATIONS

11.1 CONTRACTOR'S LIABILITY INSURANCE

The Contractor shall purchase and maintain without interruption for the duration of the contract insurance against claims for injuries to persons or damages to property which may arise from or in connection with the performance of the Work hereunder by the Contractor, its agents, representatives, employees or subcontractors. The duration of the contract shall be from the inception of the contract until the date of final payment.

11.2 MINIMUM SCOPE AND LIMITS OF INSURANCE

11.2.1 Worker's Compensation

Worker's Compensation insurance shall be in compliance with the Worker's Compensation law of the Contractor's headquarters. Employers Liability is included with a minimum limit of $1,000,000 per accident/per disease/per employee. If Work is to be performed over water and involves maritime exposure, applicable LHWCA, Jones Act or other maritime law coverage shall be included. A.M. Best's insurance company rating requirement may be waived for Worker's compensation coverage only.

11.2.2 Commercial General Liability

Commercial General Liability insurance, including Personal and Advertising Injury Liability and Products and Completed Operations Liability, shall have a minimum limit per occurrence based on the project value. The Insurance Services Office (ISO) Commercial General Liability occurrence coverage form CG 00 01 (current form approved for use in Louisiana), or equivalent, is to be used in the policy. Claims-made form is unacceptable.

The aggregate loss limit must apply to each project. ISO form CG 25 03 (current form approved for use in Louisiana), or equivalent, shall also be submitted. The State project number, including part number, and project name shall be included on this endorsement.

COMBINED SINGLE LIMIT (CSL) PER OCCURRENCE

Type of Construction	**Projects up to $1,000,000**	**Projects over $1,000,000 up to $10,000,000**	**Projects over $10,000,000**
New Buildings:			
Each Occurrence Minimum Limit	$1,000,000	$2,000,000	$4,000,000
Per Project Aggregate	$2,000,000	$4,000,000	$8,000,000
Renovations:	**The building(s) value for the Project is $_____.**		
Each Occurrence Minimum Limit	$1,000,000**	$2,000,000**	$4,000,000**

Per Project Aggregate	2 times per occur limit**	2 times per occur limit**	2 times per occur limit**

**While the minimum Combined Single Limit of $1,000,000 is required for any renovation, the limit is calculated by taking 10% of the building value and rounding it to the nearest $1,000,000 to get the insurance limit. Example: Renovation on a $33,000,000 building would have a calculated $3,000,000 combined single limit of coverage (33,000,000 times .10 = 3,300,000 and then rounding down to $3,000,000). If the calculated limit is less than the minimum limit listed in the above chart, then the amount needed is the minimum listed in the chart. Maximum per occurrence limit required is $10,000,000 regardless of building value. The per project aggregate limit is then calculated as twice the per occurrence limit.

11.2.3 Automobile Liability

Automobile Liability Insurance shall have a minimum combined single limit per occurrence of $1,000,000. ISO form number CA 00 01 (current form approved for use in Louisiana), or equivalent, is to be used in the policy. This insurance shall include third-party bodily injury and property damage liability for owned, hired and non-owned automobiles.

11.2.4 Excess Umbrella

Excess Umbrella Insurance may be used to meet the minimum requirements for General Liability and Automobile Liability only.

11.2.5 Builder's Risk

11.2.5.1 Builder's Risk Insurance shall be in an amount equal to the amount of the construction contract including any amendments and shall be upon the entire Work included in the contract. The policy shall provide coverage equivalent to the ISO form number CP 10 20, Broad Form Causes of Loss (extended, if necessary, to include the perils of wind, earthquake, collapse, vandalism/malicious mischief, and theft, including theft of materials whether or not attached to any structure). The policy must include architects' and engineers' fees necessary to provide plans, specifications and supervision of Work for the repair and/or replacement of property damage caused by a covered peril, not to exceed 10% of the cost of the repair and/or replacement.

11.2.5.2 Flood coverage shall be provided by the Contractor on the first floor and below for all projects, except as otherwise noted. The builder's risk insurance policy, sub-limit for flood coverage shall not be less than ten percent (10%) of the total contract cost per occurrence. If flood is purchased as a separate policy, the limit shall be ten percent (10%) of the total contract cost per occurrence (with a max of $500,000 if NFIP). Coverage for roofing projects shall **not** require flood coverage.

11.2.5.3 A Specialty Contractor may provide an installation floater in lieu of a Builder's Risk policy, with the similar coverage as the Builder's Risk policy, upon the

system to be installed in an amount equal to the amount of the contract including any amendments. Flood coverage is not required.

11.2.5.4 The policy must include coverage for the Owner, Contractor and any subcontractors as their interests may appear.

11.2.6 Pollution Liability *(required when asbestos or other hazardous material abatement is included in the contract)*

Pollution Liability insurance, including gradual release as well as sudden and accidental, shall have a minimum limit of not less than $1,000,000 per claim. A claims-made form will be acceptable. A policy period inception date of no later than the first day of anticipated Work under this contract and an expiration date of no earlier than 30 days after anticipated completion of all Work under the contract shall be provided. There shall be an extended reporting period of at least 24 months, with full reinstatement of limits, from the expiration date of the policy if the policy is not renewed. The policy shall not be cancelled for any reason, except non-payment of premium.

11.2.7 Deductibles and Self-Insured Retentions

Any deductibles or self-insured retentions must be declared to and accepted by the Owner. The Contractor shall be responsible for all deductibles and self-insured retentions.

11.3 OTHER INSURANCE PROVISIONS

11.3.1 The policies are to contain, or be endorsed to contain, the following provisions:

11.3.1.1 Worker's Compensation and Employers Liability Coverage

11.3.1.1.1 To the fullest allowed by law, the insurer shall agree to waive all rights of subrogation against the Owner, its officers, agents, employees and volunteers for losses arising from Work performed by the Contractor for the Owner.

11.3.1.2 Commercial General Liability Coverage

11.3.1.2.1 The Owner, its officers, agents, employees and volunteers are to be added as additional insureds as respects liability arising out of activities performed by or on behalf of the Contractor; products and completed operations of the Contractor, premises owned, occupied or used by the Contractor. ISO Form CG 20 10 (for ongoing work) AND CG 20 37 (for completed work) (current forms approved for use in Louisiana), or equivalent, are to be used.

11.3.1.2.2 The Contractor's insurance shall be primary as respects the Owner, its officers, agents, employees and volunteers for any and all losses that occur under the contract. The coverage shall contain no special limitations on the scope of protection afforded to the Owner, its officers, officials, employees or volunteers. Any insurance or self-

insurance maintained by the Owner shall be excess and non-contributory of the Contractor's insurance.

11.3.1.3 Builder's Risk

The policy must include an endorsement providing the following:

In the event of a disagreement regarding a loss covered by this policy, which may also be covered by a State of Louisiana self-insurance or commercial property policy through the Office of Risk Management (ORM), Contractor and its insurer agree to follow the following procedure to establish coverage and/or the amount of loss:

Any party to a loss may make written demand for an appraisal of the matter in disagreement. Within 20 days of receipt of written demand, the Contractor's insurer and either ORM or its commercial insurance company shall each select a competent and impartial appraiser and notify the other of the appraiser selected. The two appraisers shall select a competent and impartial umpire. The appraisers shall then identify the policy or policies under which the loss is insured and, if necessary, state separately the value of the property and the amount of the loss that must be borne by each policy. If the two appraisers fail to agree, they shall submit their differences to the umpire. A written decision by any two shall determine the policy or policies and the amount of the loss. Each insurance company agrees that the decision of the appraisers and the umpire if involved shall be binding and final and that neither party will resort to litigation. Each of the two parties shall pay its chosen appraiser and bear the cost of the umpire equally.

11.3.1.4 All Coverages

11.3.1.4.1 All policies must be endorsed to require 30 days written notice of cancellation to the Agency. Ten-day written notice of cancellation is acceptable for non-payment of premium. Notifications shall comply with the standard cancellation provisions in the Contractor's policy. In addition, Contractor is required to notify Agency of policy cancellations or reductions in limits.

11.3.1.4.2 Neither the acceptance of the completed Work nor the payment thereof shall release the Contractor from the obligations of the insurance requirements or indemnification agreement.

11.3.1.4.3 The insurance companies issuing the policies shall have no recourse against the Owner for payment of premiums or for assessments under any form of the policies.

11.3.1.4.4 Any failure of the Contractor to comply with reporting provisions of the policy shall not affect coverage provided to the Owner, its officers, agents, employees and volunteers.

11.3.2 Acceptability of Insurers

All required insurance shall be provided by a company or companies lawfully authorized to do business in the jurisdiction in which the Project is located. Insurance shall be placed with insurers with an A.M. Best's rating of **A-: VI or higher**. This rating requirement may be waived for Worker's compensation coverage only.

If at any time an insurer issuing any such policy does not meet the minimum A.M. Best rating, the Contractor shall obtain a policy with an insurer that meets the A.M. Best rating and shall submit another certificate of insurance within 30 days.

11.3.3 Verification of Coverage

Contractor shall furnish the Owner with Certificates of Insurance reflecting proof of required coverage. The Certificates for each insurance policy are to be signed by a person authorized by that insurer to bind coverage on its behalf. The Certificates are to be received and approved by the Owner before Work commences and upon any contract renewal or insurance policy renewal thereafter. The Certificate Holder must be listed as follows:

State of Louisiana
Name of Owner
Owner Address
City, State, Zip
Attn: Project # _____

The Owner reserves the right to request complete certified copies of all required insurance policies at any time.

Upon failure of the Contractor to furnish, deliver and maintain required insurance, this contract, at the election of the Agency, may be suspended, discontinued, or terminated. Failure of the Contractor to purchase and/or maintain any required insurance shall not relieve the Contractor from any liability or indemnification under the contract.

If the Contractor does not meet the insurance requirements at policy renewal, at the option of the Owner, payment to the Contractor may be withheld until the requirements have been met, OR the Owner may pay the renewal premium and withhold such payment from any monies due the Contractor, OR the contract may be suspended or terminated for cause.

11.3.4 Subcontractors

Contractor shall include all subcontractors as insureds under its policies OR shall be responsible for verifying and maintaining the certificates provided by each subcontractor. Subcontractors shall be subject to all of the requirements stated herein. The Owner reserves the right to request copies of subcontractor's certificates at any time.

If Contractor does not verify subcontractors' insurance as described above, Owner has the right to withhold payments to the Contractor until the requirements have been met.

11.3.5 Worker's Compensation Indemnity

In the event Contractor is not required to provide or elects not to provide Worker's compensation coverage, the parties hereby agree the Contractor, its Owners, agents and employees shall have no cause of action against, and shall not assert a claim against, the State of Louisiana, its departments, agencies, agents and employees as an employer, whether pursuant to the Louisiana Worker's Compensation Act or otherwise, under any circumstance. The parties also hereby agree that the State of Louisiana, its departments, agencies, agents and employees shall in no circumstance be, or considered as, the employer or statutory employer of Contractor, its Owners, agents and employees. The parties further agree that Contractor is a wholly independent Contractor and is exclusively responsible for its employees, Owners, and agents. Contractor hereby agrees to protect, defend, indemnify and hold the State of Louisiana, its departments, agencies, agents and employees harmless from any such assertion or claim that may arise from the performance of this contract.

11.3.6 Indemnification/Hold Harmless Agreement

Contractor agrees to protect, defend, indemnify, save, and hold harmless, the State of Louisiana, all State Departments, Agencies, Boards and Commissions, its officers, agents, servants, employees and volunteers, from and against any and all claims, damages, expenses and liability arising out of injury or death to any person or the damage, loss or destruction of any property which may occur, or in any way grow out of, any act or omission of Contractor, its agents, servants and employees, or any and all costs, expenses and/or attorney fees incurred by Contractor as a result of any claims, demands, suits or causes of action, except those claims, demands, suits or causes of action arising out of the negligence of the State of Louisiana, all State Departments, Agencies, Boards, Commissions, its officers, agents, servants, employees and volunteers.

Contractor agrees to investigate, handle, respond to, provide defense for and defend any such claims, demands, suits or causes of action at its sole expense and agrees to bear all other costs and expenses related thereto, even if the claims, demands, suits, or causes of action are groundless, false or fraudulent. The State of Louisiana may, but is not required to, consult with the Contractor in the defense of claims, but this shall not affect the Contractor's responsibility for the handling and expenses of all claims.

11.4 PERFORMANCE AND PAYMENT BOND

11.4.1 The Owner shall have the right to require the Contractor to furnish bonds covering faithful performance of the Contract and payment of obligations arising thereunder as stipulated in bidding requirements or specifically required in the Contract Documents on the date of execution of the Contract.

11.4.2 Upon the request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor shall promptly furnish a copy of the bonds or shall authorize a copy to be furnished.

11.4.3 Recordation of Contract and Bond [La R.S. 38:2241 thru 38:2241.1]

The Owner shall record within thirty (30) days the Contract Between Owner and Contractor and Performance and Payment Bond with the Clerk of Court in the Parish in which the Work is to be performed.

ARTICLE 12

UNCOVERING AND CORRECTION OF WORK

12.2 CORRECTION OF WORK

12.2.1 Before Substantial Completion

At the end of the paragraph, add the following sentences:
"If the Contractor fails to correct Work identified as defective within a thirty (30) day period, through no fault of the Designer, the Owner may hold the Contractor in default. If the Owner finds the Contractor in default, the Surety shall be notified. If within thirty (30) days after notification, the Surety has not corrected the nonconforming Work, through no fault of the Architect or Owner, the Owner may contract to have nonconforming Work corrected and hold the Surety and Contractor responsible for the cost, including architectural fees and other indirect costs. If the Surety fails to correct the Work within the stipulated time period and fails to meet its obligation to pay the costs, the Owner may elect not to accept bonds submitted in the future by the Surety. Finding the Contractor in default shall constitute a reason for disqualification of the Contractor from bidding on future state contracts.

12.2.2 After Substantial Completion

12.2.2.1 At the end of the paragraph delete the last sentence and add the following sentences:
"If the Contractor fails to correct nonconforming Work, or Work covered by warranties, within a thirty (30) day period, through no fault of the Architect or Owner, the Owner may hold the Contractor in default. If the Owner finds the Contractor is in default, the Surety shall be notified. If within thirty (30) days after notification, the Surety has not corrected the non-conforming or warranty Work, through no fault of the Architect or Owner, the Owner may contract to have the nonconforming or warranty Work corrected and hold the Surety responsible for the cost including architects fees and other indirect costs. Corrections by the Owner shall be in accordance with Section 2.4. If the Surety fails to correct the nonconforming or warranty Work within the stipulated time period and fails to meet its obligation to pay the costs, the Owner may not accept bonds submitted, in the future, by the Surety."

ARTICLE 13

MISCELLANEOUS PROVISIONS

13.1 GOVERNING LAW

Delete all after the word "located".

13.2 SUCCESSORS AND ASSIGNS

13.2.1 In the second sentence, delete "Except as … 13.2.2"

Delete Section 13.2.2.

13.3 RIGHTS AND REMEDIES

Add the following Section 13.3.3:

13.3.3 The Fourth Judicial Court in and for the Parish of Ouachita, State of Louisiana shall have sole jurisdiction and venue in any action brought under this contract.

13.4 TESTS AND INSPECTIONS

In Section 13.4.1, delete the second sentence and substitute the following:

The Contractor shall make arrangements for such tests, inspections and approvals with the Testing Laboratory provided by the Owner, and the Owner shall bear all related costs of tests, inspections and approvals.

Delete the last two sentences of Section 13.4.1.

13.5 INTEREST

Delete Section 13.5.

ARTICLE 14

TERMINATION OR SUSPENSION OF THE CONTRACT

14.1 TERMINATION BY THE CONTRACTOR

Delete Section 14.1.1.4.

In Section 14.1.3, after the word "profit," delete the words "on Work not executed" and substitute the following: "for Work completed prior to stoppage".

14.2 TERMINATION BY THE OWNER FOR CAUSE

Add the following Section:

14.2.1.5 failure to complete the punch list within the lien period as provided in 9.8.7.

14.2.3 Add the following sentence:

"Termination by the Owner shall not suspend assessment of liquidated damages against the Surety."

Add the following Section:

14.2.5 If an agreed sum of liquidated damages has been established, termination by the Owner under this Article shall not relieve the Contractor and/or Surety of his obligations under the liquidated damages provisions and the Contractor and/or Surety shall be liable to the Owner for per diem liquidated damages.

14.4 TERMINATION BY THE OWNER FOR CONVENIENCE

In Section 14.4.3, delete all after "incurred by reason of the termination," and add "along with reasonable profit on the Work not executed."

ARTICLE 15

CLAIMS AND DISPUTES

15.1 CLAIMS

Delete Section 15.1.2, **Time Limit on Claims,** (See La R.S. 38:2189, and 38:2189.1).

15.1.3.1 Add the following to the end of the paragraph:
"A Reservation of Rights and similar stipulations shall not be recognized under this contract as having any effect. A party must make a claim as defined herein within the time limits provided."

15.1.4.2 In the first sentence of the Section, delete "Initial Decision Maker's" and replace with "Architect's". In the second sentence of the Section, delete "the decision of the Initial Decision Maker" and replace with: "his/her decision".

Delete Section 15.1.6.2 and substitute the following:

15.1.6.2 If adverse weather conditions are the basis for a claim for additional time, the Contractor shall document that weather conditions had an adverse effect on the scheduled construction. An increase in the contract time due to weather shall not be cause for an increase in the contract sum. At the end of each month, the Contractor shall make one Claim for any adverse weather days occurring within the month. The Claim must be accompanied by sufficient documentation evidencing the adverse days and the impact on construction. Failure to make such Claim within **twenty-one (21) days** from the last day of the month shall prohibit any future claims for adverse days for that month. No additional adverse weather days shall be granted after the original or extended contract completion date, except those adverse weather days associated with a National Weather Service named storm or federally declared weather related disaster directly affecting the project site.

Add the following Section:

15.1.6.3 The following are considered reasonably anticipated days of adverse weather on a monthly basis:

January	11 days	July	6 days
February	10 days	August	5 days
March	8 days	September	4 days
April	7 days	October	3 days
May	5 days	November	5 days
June	6 days	December	8 days

The Contractor shall ask for total adverse weather days. The Contractor's request shall be considered only for days over the allowable number of days stated above.

Note: Contract is on a calendar day basis.

15.2 INITIAL DECISION

15.2.1 In the second sentence, delete the word "will" and replace with: "shall always".

In the second sentence, delete the phrase: ", unless otherwise indicated in the Agreement."

In the third sentence, delete the word "mediation" and replace with: "litigation".

At the end of the third sentence, add: "arising prior to the date final payment is due".

Delete the fourth sentence.

15.2.5 In the middle of the first sentence, delete all after the phrase: "rejecting the Claim".

In the second sentence, delete the phrase: "and the Architect, if the Architect is not serving as the Initial Decision Maker,".

In the third sentence, delete all after: "binding on the parties" and add the following: "except that the Owner may reject the decision or suggest a compromise or both".

Delete Section 15.2.6.

Delete Section 15.2.6.1.

15.3 MEDIATION

Delete Section 15.3.

15.4 ARBITRATION

Delete Section 15.4.

AIA® Document A101™ – 2017

Standard Form of Agreement Between Owner and Contractor *where the basis of payment is a Stipulated Sum*

AGREEMENT made as of the day of in the year
(In words, indicate day, month and year.)

BETWEEN the Owner:
(Name, legal status, address and other information)

and the Contractor:
(Name, legal status, address and other information)

for the following Project:
(Name, location and detailed description)

.

The Architect:
(Name, legal status, address and other information)

The Owner and Contractor agree as follows.

ADDITIONS AND DELETIONS:
The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An *Additions and Deletions Report* that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

The parties should complete A101™–2017, Exhibit A, Insurance and Bonds, contemporaneously with this Agreement. AIA Document A201™–2017, General Conditions of the Contract for Construction, is adopted in this document by reference. Do not use with other general conditions unless this document is modified.

Init.
/

AIA Document A101™ – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 11:22:48 CT on 05/09/2019 under Order No.8779998754 which expires on 06/18/2019, and is not for resale.
User Notes:
(1130704723)

TABLE OF ARTICLES

1 THE CONTRACT DOCUMENTS

2 THE WORK OF THIS CONTRACT

3 DATE OF COMMENCEMENT AND SUBSTANTIAL COMPLETION

4 CONTRACT SUM

5 PAYMENTS

6 DISPUTE RESOLUTION

7 TERMINATION OR SUSPENSION

8 MISCELLANEOUS PROVISIONS

9 ENUMERATION OF CONTRACT DOCUMENTS

EXHIBIT A INSURANCE AND BONDS

ARTICLE 1 THE CONTRACT DOCUMENTS

The Contract Documents consist of this Agreement, Conditions of the Contract (General, Supplementary, and other Conditions), Drawings, Specifications, Addenda issued prior to execution of this Agreement, other documents listed in this Agreement, and Modifications issued after execution of this Agreement, all of which form the Contract, and are as fully a part of the Contract as if attached to this Agreement or repeated herein. The Contract represents the entire and integrated agreement between the parties hereto and supersedes prior negotiations, representations, or agreements, either written or oral. An enumeration of the Contract Documents, other than a Modification, appears in Article 9.

ARTICLE 2 THE WORK OF THIS CONTRACT

The Contractor shall fully execute the Work described in the Contract Documents, except as specifically indicated in the Contract Documents to be the responsibility of others.

ARTICLE 3 DATE OF COMMENCEMENT AND SUBSTANTIAL COMPLETION

§ 3.1 The date of commencement of the Work shall be:
(Check one of the following boxes.)

[ ] The date of this Agreement.

[ ] A date set forth in a notice to proceed issued by the Owner.

[ ] Established as follows:
(Insert a date or a means to determine the date of commencement of the Work.)

If a date of commencement of the Work is not selected, then the date of commencement shall be the date of this Agreement.

§ 3.2 The Contract Time shall be measured from the date of commencement of the Work.

§ 3.3 Substantial Completion

§ 3.3.1 Subject to adjustments of the Contract Time as provided in the Contract Documents, the Contractor shall achieve Substantial Completion of the entire Work:
(Check one of the following boxes and complete the necessary information.)

AIA Document A101™ – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 11:22:48 CT on 05/09/2019 under Order No.8779998754 which expires on 06/18/2019, and is not for resale.
User Notes:
(1130704723)

[ ] Not later than ( ) calendar days from the date of commencement of the Work.

[ ] By the following date:

§ 3.3.2 Subject to adjustments of the Contract Time as provided in the Contract Documents, if portions of the Work are to be completed prior to Substantial Completion of the entire Work, the Contractor shall achieve Substantial Completion of such portions by the following dates:

Portion of Work	Substantial Completion Date

§ 3.3.3 If the Contractor fails to achieve Substantial Completion as provided in this Section 3.3, liquidated damages, if any, shall be assessed as set forth in Section 4.5.

ARTICLE 4 CONTRACT SUM

§ 4.1 The Owner shall pay the Contractor the Contract Sum in current funds for the Contractor's performance of the Contract. The Contract Sum shall be ($), subject to additions and deductions as provided in the Contract Documents.

§ 4.2 Alternates

§ 4.2.1 Alternates, if any, included in the Contract Sum:

Item	Price

§ 4.2.2 Subject to the conditions noted below, the following alternates may be accepted by the Owner following execution of this Agreement. Upon acceptance, the Owner shall issue a Modification to this Agreement.
(Insert below each alternate and the conditions that must be met for the Owner to accept the alternate.)

Item	Price	Conditions for Acceptance

§ 4.3 Allowances, if any, included in the Contract Sum:
(Identify each allowance.)

Item	Price

§ 4.4 Unit prices, if any:
(Identify the item and state the unit price and quantity limitations, if any, to which the unit price will be applicable.)

Item	Units and Limitations	Price per Unit ($0.00)

§ 4.5 Liquidated damages, if any:
(Insert terms and conditions for liquidated damages, if any.)

§ 4.6 Other:
(Insert provisions for bonus or other incentives, if any, that might result in a change to the Contract Sum.)

AIA Document A101™ – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 11:22:48 CT on 05/09/2019 under Order No.8779998754 which expires on 06/18/2019, and is not for resale.
User Notes: (1130704723)

ARTICLE 5 PAYMENTS

§ 5.1 Progress Payments

§ 5.1.1 Based upon Applications for Payment submitted to the Architect by the Contractor and Certificates for Payment issued by the Architect, the Owner shall make progress payments on account of the Contract Sum to the Contractor as provided below and elsewhere in the Contract Documents.

§ 5.1.2 The period covered by each Application for Payment shall be one calendar month ending on the last day of the month, or as follows:

§ 5.1.3 Provided that an Application for Payment is received by the Architect not later than the day of a month, the Owner shall make payment of the amount certified to the Contractor not later than the day of the month. If an Application for Payment is received by the Architect after the application date fixed above, payment of the amount certified shall be made by the Owner not later than ( ) days after the Architect receives the Application for Payment.
(Federal, state or local laws may require payment within a certain period of time.)

§ 5.1.4 Each Application for Payment shall be based on the most recent schedule of values submitted by the Contractor in accordance with the Contract Documents. The schedule of values shall allocate the entire Contract Sum among the various portions of the Work. The schedule of values shall be prepared in such form, and supported by such data to substantiate its accuracy, as the Architect may require. This schedule of values shall be used as a basis for reviewing the Contractor's Applications for Payment.

§ 5.1.5 Applications for Payment shall show the percentage of completion of each portion of the Work as of the end of the period covered by the Application for Payment.

§ 5.1.6 In accordance with AIA Document A201™–2017, General Conditions of the Contract for Construction, and subject to other provisions of the Contract Documents, the amount of each progress payment shall be computed as follows:

§ 5.1.6.1 The amount of each progress payment shall first include:

.1 That portion of the Contract Sum properly allocable to completed Work;

.2 That portion of the Contract Sum properly allocable to materials and equipment delivered and suitably stored at the site for subsequent incorporation in the completed construction, or, if approved in advance by the Owner, suitably stored off the site at a location agreed upon in writing; and

.3 That portion of Construction Change Directives that the Architect determines, in the Architect's professional judgment, to be reasonably justified.

§ 5.1.6.2 The amount of each progress payment shall then be reduced by:

.1 The aggregate of any amounts previously paid by the Owner;

.2 The amount, if any, for Work that remains uncorrected and for which the Architect has previously withheld a Certificate for Payment as provided in Article 9 of AIA Document A201–2017;

.3 Any amount for which the Contractor does not intend to pay a Subcontractor or material supplier, unless the Work has been performed by others the Contractor intends to pay;

.4 For Work performed or defects discovered since the last payment application, any amount for which the Architect may withhold payment, or nullify a Certificate of Payment in whole or in part, as provided in Article 9 of AIA Document A201–2017; and

.5 Retainage withheld pursuant to Section 5.1.7.

§ 5.1.7 Retainage

§ 5.1.7.1 For each progress payment made prior to Substantial Completion of the Work, the Owner may withhold the following amount, as retainage, from the payment otherwise due:
(Insert a percentage or amount to be withheld as retainage from each Application for Payment. The amount of retainage may be limited by governing law.)

AIA Document A101™ – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 11:22:48 CT on 05/09/2019 under Order No.8779998754 which expires on 06/18/2019, and is not for resale.
User Notes:
(1130704723)

§ 5.1.7.1.1 The following items are not subject to retainage:
(Insert any items not subject to the withholding of retainage, such as general conditions, insurance, etc.)

§ 5.1.7.2 Reduction or limitation of retainage, if any, shall be as follows:
(If the retainage established in Section 5.1.7.1 is to be modified prior to Substantial Completion of the entire Work, including modifications for Substantial Completion of portions of the Work as provided in Section 3.3.2, insert provisions for such modifications.)

§ 5.1.7.3 Except as set forth in this Section 5.1.7.3, upon Substantial Completion of the Work, the Contractor may submit an Application for Payment that includes the retainage withheld from prior Applications for Payment pursuant to this Section 5.1.7. The Application for Payment submitted at Substantial Completion shall not include retainage as follows:
(Insert any other conditions for release of retainage upon Substantial Completion.)

§ 5.1.8 If final completion of the Work is materially delayed through no fault of the Contractor, the Owner shall pay the Contractor any additional amounts in accordance with Article 9 of AIA Document A201–2017.

§ 5.1.9 Except with the Owner's prior approval, the Contractor shall not make advance payments to suppliers for materials or equipment which have not been delivered and stored at the site.

§ 5.2 Final Payment

§ 5.2.1 Final payment, constituting the entire unpaid balance of the Contract Sum, shall be made by the Owner to the Contractor when

.1 the Contractor has fully performed the Contract except for the Contractor's responsibility to correct Work as provided in Article 12 of AIA Document A201–2017, and to satisfy other requirements, if any, which extend beyond final payment; and

.2 a final Certificate for Payment has been issued by the Architect.

§ 5.2.2 The Owner's final payment to the Contractor shall be made no later than 30 days after the issuance of the Architect's final Certificate for Payment, or as follows:

§ 5.3 Interest

Payments due and unpaid under the Contract shall bear interest from the date payment is due at the rate stated below, or in the absence thereof, at the legal rate prevailing from time to time at the place where the Project is located.
(Insert rate of interest agreed upon, if any.)

%

ARTICLE 6 DISPUTE RESOLUTION

§ 6.1 Initial Decision Maker

The Architect will serve as the Initial Decision Maker pursuant to Article 15 of AIA Document A201–2017, unless the parties appoint below another individual, not a party to this Agreement, to serve as the Initial Decision Maker.
(If the parties mutually agree, insert the name, address and other contact information of the Initial Decision Maker, if other than the Architect.)

AIA Document A101™ – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 11:22:48 CT on 05/09/2019 under Order No.8779998754 which expires on 06/18/2019, and is not for resale.
User Notes: (1130704723)

§ 6.2 Binding Dispute Resolution
For any Claim subject to, but not resolved by, mediation pursuant to Article 15 of AIA Document A201–2017, the method of binding dispute resolution shall be as follows:
(Check the appropriate box.)

[ ] Arbitration pursuant to Section 15.4 of AIA Document A201–2017

[ ] Litigation in a court of competent jurisdiction

[ ] Other *(Specify)*

If the Owner and Contractor do not select a method of binding dispute resolution, or do not subsequently agree in writing to a binding dispute resolution method other than litigation, Claims will be resolved by litigation in a court of competent jurisdiction.

ARTICLE 7 TERMINATION OR SUSPENSION

§ 7.1 The Contract may be terminated by the Owner or the Contractor as provided in Article 14 of AIA Document A201–2017.

§ 7.1.1 If the Contract is terminated for the Owner's convenience in accordance with Article 14 of AIA Document A201–2017, then the Owner shall pay the Contractor a termination fee as follows:
(Insert the amount of, or method for determining, the fee, if any, payable to the Contractor following a termination for the Owner's convenience.)

§ 7.2 The Work may be suspended by the Owner as provided in Article 14 of AIA Document A201–2017.

ARTICLE 8 MISCELLANEOUS PROVISIONS

§ 8.1 Where reference is made in this Agreement to a provision of AIA Document A201–2017 or another Contract Document, the reference refers to that provision as amended or supplemented by other provisions of the Contract Documents.

§ 8.2 The Owner's representative:
(Name, address, email address, and other information)

§ 8.3 The Contractor's representative:
(Name, address, email address, and other information)

AIA Document A101™ – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 11:22:48 CT on 05/09/2019 under Order No.8779998754 which expires on 06/18/2019, and is not for resale.
User Notes: (1130704723)

§ 8.4 Neither the Owner's nor the Contractor's representative shall be changed without ten days' prior notice to the other party.

§ 8.5 Insurance and Bonds

§ 8.5.1 The Owner and the Contractor shall purchase and maintain insurance as set forth in AIA Document A101™–2017, Standard Form of Agreement Between Owner and Contractor where the basis of payment is a Stipulated Sum, Exhibit A, Insurance and Bonds, and elsewhere in the Contract Documents.

§ 8.5.2 The Contractor shall provide bonds as set forth in AIA Document A101™–2017 Exhibit A, and elsewhere in the Contract Documents.

§ 8.6 Notice in electronic format, pursuant to Article 1 of AIA Document A201–2017, may be given in accordance with AIA Document E203™–2013, Building Information Modeling and Digital Data Exhibit, if completed, or as otherwise set forth below:
(If other than in accordance with AIA Document E203–2013, insert requirements for delivering notice in electronic format such as name, title, and email address of the recipient and whether and how the system will be required to generate a read receipt for the transmission.)

§ 8.7 Other provisions:

ARTICLE 9 ENUMERATION OF CONTRACT DOCUMENTS

§ 9.1 This Agreement is comprised of the following documents:

.1 AIA Document A101™–2017, Standard Form of Agreement Between Owner and Contractor

.2 AIA Document A101™–2017, Exhibit A, Insurance and Bonds

.3 AIA Document A201™–2017, General Conditions of the Contract for Construction

.4 AIA Document E203™–2013, Building Information Modeling and Digital Data Exhibit, dated as indicated below:
(Insert the date of the E203-2013 incorporated into this Agreement.)

.5 Drawings

Number	Title	Date

.6 Specifications

Section	Title	Date	Pages

.7 Addenda, if any:

Number	Date	Pages

Portions of Addenda relating to bidding or proposal requirements are not part of the Contract Documents unless the bidding or proposal requirements are also enumerated in this Article 9.

.8 Other Exhibits:
(Check all boxes that apply and include appropriate information identifying the exhibit where required.)

AIA Document A101™ – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 11:22:48 CT on 05/09/2019 under Order No.8779998754 which expires on 06/18/2019, and is not for resale.
User Notes: (1130704723)

[ ] AIA Document E204™–2017, Sustainable Projects Exhibit, dated as indicated below:
(Insert the date of the E204-2017 incorporated into this Agreement.)

[ ] The Sustainability Plan:

Title	Date	Pages

[ ] Supplementary and other Conditions of the Contract:

Document	Title	Date	Pages

.9 Other documents, if any, listed below:
(List here any additional documents that are intended to form part of the Contract Documents. AIA Document A201™–2017 provides that the advertisement or invitation to bid, Instructions to Bidders, sample forms, the Contractor's bid or proposal, portions of Addenda relating to bidding or proposal requirements, and other information furnished by the Owner in anticipation of receiving bids or proposals, are not part of the Contract Documents unless enumerated in this Agreement. Any such documents should be listed here only if intended to be part of the Contract Documents.)

This Agreement entered into as of the day and year first written above.

OWNER *(Signature)*	**CONTRACTOR** *(Signature)*
(Printed name and title)	*(Printed name and title)*

AIA Document A101™ – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 11:22:48 CT on 05/09/2019 under Order No.8779998754 which expires on 06/18/2019, and is not for resale.
User Notes: (1130704723)

Additions and Deletions Report for

AIA® Document A101™ – 2017

This Additions and Deletions Report, as defined on page 1 of the associated document, reproduces below all text the author has added to the standard form AIA document in order to complete it, as well as any text the author may have added to or deleted from the original AIA text. Added text is shown underlined. Deleted text is indicated with a horizontal line through the original AIA text.

Note: This Additions and Deletions Report is provided for information purposes only and is not incorporated into or constitute any part of the associated AIA document. This Additions and Deletions Report and its associated document were generated simultaneously by AIA software at 11:22:48 CT on 05/09/2019.

PAGE 1

Additions and Deletions Report for AIA Document A101™ – 2017. Copyright © 1915, 1918, 1925, 1937, 1951, 1958, 1961, 1963, 1967, 1974, 1977, 1987, 1991, 1997, 2007 and 2017 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 11:22:48 CT on 05/09/2019 under Order No.8779998754 which expires on 06/18/2019, and is not for resale.
User Notes: (1130704723)

Certification of Document's Authenticity

AIA® Document D401™ – 2003

I, , hereby certify, to the best of my knowledge, information and belief, that I created the attached final document simultaneously with its associated Additions and Deletions Report and this certification at 11:22:48 CT on 05/09/2019 under Order No. 8779998754 from AIA Contract Documents software and that in preparing the attached final document I made no changes to the original text of AIA® Document A101™ – 2017, Standard Form of Agreement Between Owner and Contractor where the basis of payment is a Stipulated Sum, as published by the AIA in its software, other than those additions and deletions shown in the associated Additions and Deletions Report.

_____

(Signed)

_____

(Title)

_____

(Dated)

AIA Document D401™ – 2003. Copyright © 1992 and 2003 by The American Institute of Architects. **All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law.** This document was produced by AIA software at 11:22:48 CT on 05/09/2019 under Order No.8779998754 which expires on 06/18/2019, and is not for resale.
User Notes: (1130704723)

DOCUMENT 002513 – PRE-BID MEETINGS

1.1 PREBID MEETING

A. Owner, Architect, & Construction Manager will conduct a Prebid meeting as indicated below:

1. Meeting Date: October 17, 2025
2. Meeting Time: 10:00 AM
3. Location: 112 Arrant Road – West Monroe, LA. 71292 – Main Entrance to Lenwil Elementary School.

B. Attendance:

1. Prime Bidders: Attendance at Prebid meeting is **Mandatory**.
2. Subcontractors: Attendance at Prebid meeting is recommended but **not mandatory**
3. Notice: Bids will only be accepted from prime bidders represented on Pre-bid Meeting sign-in sheet.

C. Bidder Questions: Submit written questions to be addressed at Pre-bid meeting minimum of two (2) business days prior to meeting.

D. Agenda: Prebid meeting agenda will include review of topics that may affect proper preparation and submittal of bids, which may include the following:

1. Procurement and Contracting Requirements:

a. Advertisement for Bids.
b. Instructions to Bidders.
c. Bidder Qualifications.
d. Bonding.
e. Insurance.
f. Bid Security.
g. Bid Form and Attachments.
h. Bid Submittal Requirements.
i. Bid Submittal
j. Notice of Award.

2. Communication during Bidding Period:

a. Obtaining documents.
b. Access to Project Web site.
c. Bidder's Requests for Information.
d. Bidder's Substitution Request/Prior Approval Request.
e. Addenda.

3. Contracting Requirements:

a. Agreement.
b. The General Conditions.

c. The Supplementary Conditions.
d. Other Owner requirements.

4. Construction Documents:

a. Scopes of Work.
b. Temporary Facilities.
c. Use of Site.
d. Work Restrictions.
e. Alternates, Allowances, and Unit Prices.
f. Substitutions following award.

5. Separate Contracts:

a. Work by Owner.
b. Work of Other Contracts.

6. Schedule:

a. Project Schedule.
b. Contract Time.
c. Liquidated Damages.
d. Other Bidder Questions.

7. Site/facility visit or walkthrough.
8. Post-Meeting Addendum.

E. Addenda: Nothing discussed or contemplated, during the pre-bid meeting shall be construed as changing the requirements of the bid documents. Changes in the requirements of the bid documents will be by officially issued addenda only.

END OF DOCUMENT 002513

DOCUMENT 002600 - PROCUREMENT SUBSTITUTION PROCEDURES

1.1 DEFINITIONS

A. Procurement Substitution Requests: Requests for changes in products, materials, equipment, and methods of construction from those indicated in the Procurement and Contracting Documents, submitted **prior to receipt of bids**.

B. Substitution Requests: Requests for changes in products, materials, equipment, and methods of construction from those indicated in the Contract Documents, submitted following Contract award. See Section 012500 "Substitution Procedures" for conditions under which Substitution requests will be considered following Contract award.

1.2 QUALITY ASSURANCE

A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

1.3 PROCUREMENT SUBSTITUTIONS

A. Procurement Substitutions, General: By submitting a bid, the Bidder represents that its bid is based on materials and equipment described in the Procurement and Contracting Documents, including Addenda. Bidders are encouraged to request approval of qualifying substitute materials and equipment when the Specifications Sections list materials and equipment by product or manufacturer name.

B. Procurement Substitution Requests will be received and considered by Owner when the following conditions are satisfied, as determined by Architect; otherwise requests will be returned without action:

1. Extensive revisions to the Contract Documents are not required.
2. Proposed changes are in keeping with the general intent of the Contract Documents, including the level of quality of the Work represented by the requirements therein.
3. The request is fully documented and properly submitted.

1.4 SUBMITTALS

A. Procurement Substitution Request: Submit to [**Architect**] [**Construction Manager**]. Procurement Substitution Request must be made in writing[**by prime contract Bidder only**] in compliance with the following requirements:

1. Requests for substitution of materials and equipment will be considered if received no later than [**10**] days prior to date of bid opening.
2. Submittal Format: Submit [**three**] 3 copies of each written Procurement Substitution Request, using [**CSI Substitution Request Form 1.5C**].

3. Submittal Format: Submit Procurement Substitution Request, using format provided on Project Web site.

    a. Identify the product or the fabrication or installation method to be replaced in each request. Include related Specifications Sections and drawing numbers.
    b. Provide complete documentation on both the product specified and the proposed substitute, including the following information as appropriate:

        1) Point-by-point comparison of specified and proposed substitute product data, fabrication drawings, and installation procedures.
        2) Copies of current, independent third-party test data of salient product or system characteristics.
        3) Samples where applicable or when requested by Architect.
        4) Detailed comparison of significant qualities of the proposed substitute with those of the Work specified. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
        5) Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
        6) Research reports, where applicable, evidencing compliance with building code in effect for Project, from [**ICC-ES**] <**Insert applicable code organization**>.
        7) Coordination information, including a list of changes or modifications needed to other parts of the Work and to construction performed by Owner and separate contractors, which will become necessary to accommodate the proposed substitute.

    c. Provide certification by manufacturer that the substitute proposed is equal to or superior to that required by the Procurement and Contracting Documents, and that its in-place performance will be equal to or superior to the product or equipment specified in the application indicated.
    d. Bidder, in submitting the Procurement Substitution Request, waives the right to additional payment or an extension of Contract Time because of the failure of the substitute to perform as represented in the Procurement Substitution Request.

B. Architect's Action:

1. Architect may request additional information or documentation necessary for evaluation of the Procurement Substitution Request. Architect will notify all bidders of acceptance of the proposed substitute by means of an Addendum to the Procurement and Contracting Documents.

C. Architect's approval of a substitute during bidding does not relieve Contractor of the responsibility to submit required shop drawings and to comply with all other requirements of the Contract Documents.

END OF DOCUMENT 002600

LOUISIANA UNIFORM PUBLIC WORK BID FORM

TO: Ouachita Parish School Board
1600 Nth 7th Street
West Monroe, Louisiana 71291
Bid Number 5-26

BID FOR: Lenwil Elementary School
Cafeteria Renovation
112 Arrant Road – West Monroe, LA. 71292

The undersigned bidder hereby declares and represents that she/he: a) has carefully examined and understands the Bidding Documents, b) has not received, relied on, or based his bid on any verbal instructions contrary to the Bidding Documents or any addenda, c) has personally inspected and is familiar with the project site, and hereby proposes to provide all labor, materials, tools, appliances and facilities as required to perform, in a workmanlike manner, all work and services for the construction and completion of the referenced project, all in strict accordance with the Bidding Documents prepared by: TBA Studio Architect and dated: October 2025

Bidders must acknowledge all addenda. The Bidder acknowledges receipt of the following **ADDENDA:** (Enter the number the Designer has assigned to each of the addenda that the Bidder is acknowledging) _____ .

TOTAL BASE BID: For all work required by the Bidding Documents (including any and all unit prices designated "Base Bid" * but not alternates) the sum of:

_____ Dollars ($ _____)

ALTERNATES: For any and all work required by the Bidding Documents for Alternates including any and all unit prices designated as alternates in the unit price description.

Alternate No. 1 *(Overlay of existing parking lot))* for the lump sum of:

_____ Dollars ($ _____)

Alternate No. 2 *()* for the lump sum of:

_____ Dollars ($ _____)

Alternate No. (*)* for the lump sum of:

_____ Dollars ($_____)

NAME OF BIDDER: _____

ADDRESS OF BIDDER: _____

_____

LOUISIANA CONTRACTOR'S LICENSE NUMBER: _____

NAME OF AUTHORIZED SIGNATORY OF BIDDER: _____

TITLE OF AUTHORIZED SIGNATORY OF BIDDER: _____

SIGNATURE OF AUTHORIZED SIGNATORY OF BIDDER **: _____

DATE: _____

THE FOLLOWING ITEMS ARE TO BE INCLUDED WITH THE SUBMISSION OF THIS LOUISIANA UNIFORM PUBLIC WORK BID FORM:

* The Unit Price Form shall be used if the contract includes unit prices. Otherwise it is not required and need not be included with the form. The number of unit prices that may be included is not limited and additional sheets may be included if needed.

**** A CORPORATE RESOLUTION OR WRITTEN EVIDENCE** of the authority of the person signing the bid for the public work as prescribed by LA R.S. 38:2212(B)(5).

BID SECURITY in the form of a bid bond, certified check or cashier's check as prescribed by LA R.S. 38:2218(A) attached to and made a part of this bid.

004313 - BID BOND

Date: _____

KNOW ALL MEN BY THESE PRESENTS:

That_____of_____, as Principal, and_____, as Surety, are held and firmly bound unto the Ouachita Parish School Board (Obligee), in the full and just sum of five (5%) percent of the total amount of this proposal, including all alternates, lawful money of the United States, for payment of which sum, well and truly be made, we bind ourselves, our heirs, executors, administrators, successors and assigns, jointly and severally firmly by these presents.

Surety represents that it is listed on the current U. S. Department of the Treasury Financial Management Service list of approved bonding companies as approved for an amount equal to or greater that the amount for which it obligates itself in this instrument or that it is a Louisiana domiciled insurance company with at least an A - rating in the latest printing of the A. M. Best's Key Rating Guide. If surety qualifies by virtue of its Best's listing, the Bond amount may not exceed ten percent of policyholders' surplus as shown in the latest A. M. Best's Key Rating Guide.

Surety further represents that it is licensed to do business in the State of Louisiana and that this Bond is signed by surety's agent or attorney-in-fact. This Bid Bond is accompanied by appropriate power of attorney.

THE CONDITION OF THIS OBLIGATION IS SUCH that, whereas said Principal is herewith submitting its proposal to the Obligee on a Contract for:

_____

NOW, THEREFORE, if the said Contract be awarded to the Principal and the Principal shall, within such time as may be specified, enter into the Contract in writing and give a good and sufficient bond to secure the performance of the terms and conditions of the Contract with surety acceptable to the Obligee, then this obligation shall be void; otherwise this obligation shall become due and payable.

_____	_____
PRINCIPAL (BIDDER)	SURETY
BY: _____	BY: _____
AUTHORIZED OFFICER-OWNER-PARTNER	AGENT OR ATTORNEY-IN-FACT(SEAL)

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Project information.
2. Work covered by Contract Documents.
3. Work under separate contracts.
4. Access to site.
5. Work restrictions.
6. Specification and drawing conventions.
7. Miscellaneous provisions.

B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.

1.2 PROJECT INFORMATION

A. Project Identification:

1. Project Location: 112 Arrant Road – West Monroe, LA. 71292

B. Owner: Ouachita Parish School System

C. Architect: TBA Studio Architects

D. Project Web Site: A project Web site administered by Architect will be used for purposes of managing communication and documents during the construction stage.

1. See Section 013100 "Project Management and Coordination." for requirements for using Project Web site.

1.3 WORK COVERED BY CONTRACT DOCUMENTS

A. The Work of this Project is defined by the Contract Documents and consists of the following:

a. **Area A:** The renovation of the cafeteria dining and kitchen.
b. **Add Alternate 1:** The parking lot overlay.

NOTE: The GC is expected to start immediately upon Notice to Proceed and understand that there is an expected delayed mobilization. Regardless of Notice to Proceed date, contractor shall be aware that mobilization cannot occur until after December 20, 2025. Parking lot work shall be done during summer months or during a holiday break if Add. Alternate No. 1 is taken.

B. Type of Contract.

1. Project will be constructed under a single prime contract.

1.4 WORK UNDER SEPARATE CONTRACTS

A. General: Cooperate fully with separate contractors so work on those contracts may be carried out smoothly, without interfering with or delaying work under this Contract or other contracts. Coordinate the Work of this Contract with work performed under separate contracts.

1.5 ACCESS TO SITE

A. Pre-Bid Access: The buildings will be available for field verification on the day of the pre-bid unless other arrangements are made with the owner/Principal. Parties seeking access to the buildings shall notify Architect, through Prime Bidders, to coordinate scheduling of access. Failure to provide said notification shall not be cause for claim of inability to perform pre-bid field verification, nor shall failure of party(s) to make themselves available, during the time period the buildings are available.

B. General: Contractor shall have full use of Project site for construction operations during construction period. Contractor's use of Project site is limited only by Owner's right to perform work or to retain other contractors on portions of Project. See Notes above for additional information.

C. Use of Site: Limit use of Project site to work in areas indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.

1. Limits: Limit site disturbance, including earthwork and clearing of vegetation, to 40 feet beyond building perimeter; 10 feet beyond surface walkways, patios, surface parking, and utilities less than 12 inches in diameter; 15 feet beyond primary roadway curbs and main utility branch trenches; and 25 feet beyond constructed areas with permeable surfaces (such as pervious paving areas, storm-water detention facilities, and playing fields) that require additional staging areas in order to limit compaction in the constructed area.

2. Driveways, Walkways and Entrances: Keep driveways, loading areas and entrances serving premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.

    a. Schedule deliveries to minimize use of driveways and entrances by construction operations.
    b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.

D. Condition of Existing Building: Maintain portions of existing building affected by construction operations in a weathertight condition throughout construction period. Repair damage caused by construction operations.

1.6 WORK RESTRICTIONS

A. Work Restrictions, General: Comply with restrictions on construction operations.

1. Comply with limitations on use of public streets and with other requirements of authorities having jurisdiction.

B. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after providing temporary utility services according to requirements indicated:

1. Notify Architect not less than 3 business days in advance of proposed utility interruptions.
2. Obtain Architect's written permission before proceeding with utility interruptions.

C. Noise, Vibration, and Odors: Coordinate operations that may result in high levels of noise and vibration, odors, or other disruption to Owner occupancy with Owner.

1. Notify Architect not less than two business days in advance of proposed disruptive operations.
2. Obtain Architect's written permission before proceeding with disruptive operations.

D. Nonsmoking Building: Smoking is not permitted within the building or within 25 feet of entrances, operable windows, or outdoor-air intakes.

E. Controlled Substances: Use of tobacco products and other controlled substances on Project site is not permitted.

1.7 SPECIFICATION AND DRAWING CONVENTIONS

A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:

1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.

2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.

B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.

C. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:

1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
2. Abbreviations: Materials and products are identified by abbreviations published as part of the U.S. National CAD Standard and scheduled on Drawings.
3. Keynoting: Materials and products are identified by reference keynotes referencing Specification Section numbers found in this Project Manual.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

SECTION 012500 - SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for substitutions.

B. Related Requirements:

1. Section 016000 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

1.2 DEFINITIONS

A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.

1.3 ACTION SUBMITTALS

A. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.

1. Substitution Request Form: Use CSI Form 13.1A.
2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:

a. Statement indicating why specified product or fabrication or installation cannot be provided, if applicable.
b. Coordination information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors that will be necessary to accommodate proposed substitution.
c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
e. Samples, where applicable or requested.
f. Certificates and qualification data, where applicable or requested.
g. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners.
h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.

i. Research reports evidencing compliance with building code in effect for Project, from ICC-ES, NFPA & ADA.
j. Detailed comparison of Contractor's construction schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
k. Cost information, including a proposal of change, if any, in the Contract Sum.
l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.

3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven (7) days of receipt of a request for substitution. Architect will notify Contractor through Construction Manager of acceptance or rejection of proposed substitution within (15) fifteen days of receipt of request, or (7) seven days of receipt of additional information or documentation, whichever is later.

a. Forms of Acceptance: Change Order, or Architect's Supplemental Instructions for minor changes in the Work.
b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

1.4 QUALITY ASSURANCE

A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

PART 2 - PRODUCTS

2.1 SUBSTITUTIONS

A. Substitutions for Cause: Submit requests for substitution immediately on discovery of need for change, but not later than (15) fifteen days prior to time required for preparation and review of related submittals.

1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied:

a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
b. Requested substitution will not adversely affect Contractor's construction schedule.

c. Requested substitution has received necessary approvals of authorities having jurisdiction.
d. Requested substitution is compatible with other portions of the Work.
e. Requested substitution has been coordinated with other portions of the Work.
f. Requested substitution provides specified warranty.
g. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

B. Substitutions for Convenience: Not allowed unless otherwise indicated.

PART 3 - EXECUTION (Not Used)

END OF SECTION 012500

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

1.2 MINOR CHANGES IN THE WORK

A. Architect will issue, through Construction Manager, supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on the "Architect's Supplemental Instructions" form included in Project Manual.

1.3 PROPOSAL REQUESTS

A. Owner-Initiated Proposal Requests: Architect or Construction Manager will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.

1. Work Change Proposal Requests issued by Architect or Construction Manager are not instructions either to stop work in progress or to execute the proposed change.
2. Within 10 days after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.

    a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
    b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
    c. Include costs of labor and supervision directly attributable to the change.
    d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
    e. Quotation Form: Use forms acceptable to Architect.

B. Contractor-Initiated Work Change Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect or Construction Manager.

1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.

2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
4. Include costs of labor and supervision directly attributable to the change.
5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
7. Work Change Proposal Request Form: Use form acceptable to Architect.

1.4 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Work Changes Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on AIA Document G701 (form included in Project Manual).

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600

SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.

B. Related Requirements:
1. Section 012600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
2. Section 013200 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

1.2 SCHEDULE OF VALUES

A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule. Cost-loaded Critical Path Method Schedule may serve to satisfy requirements for the schedule of values.

1. Coordinate line items in the schedule of values with other required administrative forms and schedules, including the following:

a. Application for Payment forms with continuation sheets.
b. Submittal schedule.
c. Items required to be indicated as separate activities in Contractor's construction schedule.

2. Submit the schedule of values to Architect through Construction Manager at earliest possible date but no later than seven (7) days before the date scheduled for submittal of initial Applications for Payment.
3. Sub-schedules for Phased Work: Where the Work is separated into phases, requiring separately phased payments, provide sub-schedules showing values, coordinated with each phase of payment.

B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.

1. Identification: Include the following Project identification on the schedule of values:

a. Owner – Ouachita Parish School Board, Monroe, Louisiana 71201
b. Architect - TBA Studio, West Monroe, Louisiana 71291
c. Architect's project number 25-WM0015
d. Contractor's name and address.
e. Date of submittal.

2. Arrange schedule of values consistent with format of AIA Document G703. Retain option in first subparagraph below where Contractor's ongoing activities related to Project closeout will be a line item subject to Application for Payment approval.
3. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with Project Manual table of contents. Provide multiple line items for principal subcontract amounts in excess of five (5) percent of the Contract Sum.

4. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
5. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
6. Provide separate line items in the schedule of values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
7. Allowances: Provide a separate line item in the schedule of values for each allowance. Show line-item value of unit-cost allowances, as a product of the unit cost, multiplied by measured quantity. Use information indicated in the Contract Documents to determine quantities.
8. Each item in the schedule of values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.

    a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the schedule of values or distributed as general overhead expense, at Contractor's option.

9. Schedule Updating: Update and resubmit the schedule of values before the next Applications for Payment when Change Orders result in a change in the Contract Sum.

1.3 APPLICATIONS FOR PAYMENT

A. Each Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.

    1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.

B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.

C. Payment Application Times: Submit Application for Payment to Architect by the 30th of the month. The period covered by each Application for Payment is one month, ending on the last day of the month

D. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.

E. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.

1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
2. Include amounts of Change Orders issued, before last day of construction period covered by application.

F. Transmittal: Submit five (5) signed and notarized original copies of each Application for Payment to Architect. One copy shall include waivers of lien and similar attachments if required.

1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.

G. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from entities lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.

1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
2. When an application shows completion of an item, submit conditional final or full waivers.
3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
4. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.

H. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:

1. List of subcontractors.
2. Schedule of values.
3. Contractor's construction schedule (preliminary if not final).
4. Schedule of unit prices.
5. Submittal schedule (preliminary if not final).
6. List of Contractor's staff assignments.
7. List of Contractor's principal consultants.
8. Copies of building permits.
9. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
10. Initial progress report.
11. Report of preconstruction conference.
12. Certificates of insurance and insurance policies.

I. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.

1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
2. This application shall reflect Certificates of Partial Substantial Completion issued previously for Owner occupancy of designated portions of the Work.

J. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:

1. Evidence of completion of Project closeout requirements.
2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
3. Updated final statement, accounting for final changes to the Contract Sum.
4. AIA Document G706-1994, "Contractor's Affidavit of Payment of Debts and Claims."
5. AIA Document G706A-1994, "Contractor's Affidavit of Release of Liens."
6. AIA Document G707-1994, "Consent of Surety to Final Payment."
7. Evidence that claims have been settled.
8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
9. Final liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:

1. Coordination drawings.
2. Requests for Information (RFIs).
3. Project Web site.
4. Project meetings.

B. Related Requirements:

1. Section 017300 "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.

1.2 DEFINITIONS

A. RFI: Request from Owner, Construction Manager, Architect, or Contractor seeking information required by or clarifications of the Contract Documents.

1.3 INFORMATIONAL SUBMITTALS

A. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:

1. Name, address, and telephone number of entity performing subcontract or supplying products.
2. Number and title of related Specification Section(s) covered by subcontract.
3. Drawing number and detail references, as appropriate, covered by subcontract.

1.4 GENERAL COORDINATION PROCEDURES

A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections that depend on each other for proper installation, connection, and operation.

1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.

2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
3. Make adequate provisions to accommodate items scheduled for later installation.

B. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.

1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.

C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and activities of other contractors to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:

1. Preparation of Contractor's construction schedule.
2. Preparation of the schedule of values.
3. Installation and removal of temporary facilities and controls.
4. Delivery and processing of submittals.
5. Progress meetings.
6. Preinstallation conferences.
7. Project closeout activities.
8. Startup and adjustment of systems.

1.5 COORDINATION DRAWINGS

A. Coordination Drawings, General: Prepare coordination drawings according to requirements in individual Sections, where installation is not completely shown on Shop Drawings, where limited space availability necessitates coordination, or if coordination is required to facilitate integration of products and materials fabricated or installed by more than one entity.

1. Content: Project-specific information, drawn accurately to a scale large enough to indicate and resolve conflicts. Do not base coordination drawings on standard printed data. Include the following information, as applicable:

a. Indicate functional and spatial relationships of components of architectural, structural, civil, mechanical, and electrical systems.
b. Indicate dimensions shown on the Drawings. Specifically note dimensions that appear to be in conflict with submitted equipment and minimum clearance requirements. Provide alternate sketches to Architect indicating proposed resolution of such conflicts. Minor dimension changes and difficult installations will not be considered changes to the Contract.

B. Coordination Drawing Organization: Organize coordination drawings as follows:

1. Floor Plans and Reflected Ceiling Plans: Show architectural and structural elements, and mechanical, plumbing, fire-protection, fire-alarm, and electrical Work. Show locations of visible ceiling-mounted devices relative to acoustical ceiling grid.

2. Plenum Space: Indicate sub-framing for support of ceiling and wall systems, mechanical and electrical equipment, and related Work. Locate components within ceiling plenum to accommodate layout of light fixtures indicated on Drawings.
3. Mechanical Rooms: Provide coordination drawings for mechanical rooms showing plans and elevations of mechanical, plumbing, fire-protection, fire-alarm, and electrical equipment.
4. Structural Penetrations: Indicate penetrations and openings required for all disciplines.
5. Slab Edge and Embedded Items: Indicate slab edge locations and sizes and locations of embedded items for metal fabrications, sleeves, anchor bolts, bearing plates, angles, door floor closers, slab depressions for floor finishes, curbs and housekeeping pads, and similar items.
6. Review: Architect will review coordination drawings to confirm that the Work is being coordinated, but not for the details of the coordination, which are Contractor's responsibility.

1.6 REQUESTS FOR INFORMATION (RFIs)

A. General: Immediately on discovery of the need for additional information or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.

1. Architect will return RFIs submitted to Architect by other entities controlled by Contractor with no response.
2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.

B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:

1. Project name.
2. Project number.
3. Date.
4. Name of Contractor.
5. Name of Architect and Construction Manager
6. RFI number, numbered sequentially.
7. RFI subject.
8. Specification Section number and title and related paragraphs, as appropriate.
9. Drawing number and detail references, as appropriate.
10. Field dimensions and conditions, as appropriate.
11. Contractor's suggested resolution. If Contractor's solution(s) impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
12. Contractor's signature.
13. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.

C. RFI Forms: AIA Document G716 acceptable to Architect.

D. Architect's and Construction Manager's Action: Architect and Construction Manager will review each RFI, determine action required, and respond. Allow seven (7) working days for

Architect's response for each RFI. RFIs received by the Construction Manager, after 1:00 p.m., will be considered as received the following working day.

1. The following RFIs will be returned without action:

    a. Requests for approval of submittals.
    b. Requests for approval of substitutions.
    c. Requests for coordination information already indicated in the Contract Documents.
    d. Requests for adjustments in the Contract Time or the Contract Sum.
    e. Requests for interpretation of Architect's actions on submittals.
    f. Incomplete RFIs or inaccurately prepared RFIs.

2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt of additional information.
3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 012600 "Contract Modification Procedures."

    a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify the Construction Manager in writing within (10) ten days of receipt of the RFI response.

E. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly. Include the following:

1. Project name.
2. Name and address of Contractor.
3. Name and address of Architect and Construction Manager.
4. RFI number including RFIs that were dropped and not submitted.
5. RFI description.
6. Date the RFI was submitted.
7. Date Architect's and Construction Manager's response was received.

F. On receipt of Architect's and Construction Manager's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect and Construction Manager within seven (7) days if Contractor disagrees with response.

1. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
2. Identification of related Field Order, Work Change Directive, and Proposal Request, as appropriate.

1.7 PROJECT MEETINGS

A. General: Schedule and conduct, Construction Manager will schedule and conduct meetings and conferences at Project site unless otherwise indicated.

1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
3. Minutes: Entity responsible for conducting meeting will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner, Construction Manager, and Architect, within three (3) days of the meeting.

B. Preconstruction Conference: Architect or Construction Manager will schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement.

1. Attendees: Authorized representatives of Owner, Construction Manager, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
2. Agenda: Discuss items of significance that could affect progress, including the following:

    a. Tentative construction schedule.
    b. Phasing.
    c. Critical work sequencing and long-lead items.
    d. Designation of key personnel and their duties.
    e. Procedures for processing field decisions and Change Orders.
    f. Procedures for RFIs.
    g. Procedures for testing and inspecting.
    h. Procedures for processing Applications for Payment.
    i. Distribution of the Contract Documents.
    j. Submittal procedures.
    k. Preparation of record documents.
    l. Use of the premises[and existing building].
    m. Work restrictions.
    n. Working hours.
    o. Owner's occupancy requirements.
    p. Responsibility for temporary facilities and controls.
    q. Procedures for moisture and mold control.
    r. Procedures for disruptions and shutdowns.
    s. Parking availability.
    t. Office, work, and storage areas.
    u. Equipment deliveries and priorities.
    v. First aid.
    w. Security.
    x. Progress cleaning.

3. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes.

C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.

1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect, Construction Manager, and Owner of scheduled meeting dates.
2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:

    a. Contract Documents.
    b. Options.
    c. Related RFIs.
    d. Related Change Orders.
    e. Purchases.
    f. Deliveries.
    g. Submittals.
    h. Review of mockups.
    i. Possible conflicts.
    j. Compatibility problems.
    k. Time schedules.
    l. Weather limitations.
    m. Manufacturer's written instructions.
    n. Warranty requirements.
    o. Compatibility of materials.
    p. Acceptability of substrates.
    q. Temporary facilities and controls.
    r. Space and access limitations.
    s. Regulations of authorities having jurisdiction.
    t. Testing and inspecting requirements.
    u. Installation procedures.
    v. Coordination with other work.
    w. Required performance results.
    x. Protection of adjacent work.
    y. Protection of construction and personnel.

3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
4. Reporting: Distribute minutes of the meeting to each party present and to other parties requiring information.
5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.

D. Progress Meetings: Conduct progress meetings at monthly intervals.

1. Attendees: In addition to representatives of Owner, Construction Manager, and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
2. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.

a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.

1) Review schedule for next period.

b. Review present and future needs of each entity present, including the following:

1) Interface requirements.
2) Sequence of operations.
3) Status of submittals.
4) Deliveries.
5) Off-site fabrication.
6) Access.
7) Site utilization.
8) Temporary facilities and controls.
9) Progress cleaning.
10) Quality and work standards.
11) Status of correction of deficient items.
12) Field observations.
13) Status of RFIs.
14) Status of proposal requests.
15) Pending changes.
16) Status of Change Orders.
17) Pending claims and disputes.
18) Documentation of information for payment requests.

3. Minutes: Entity responsible for conducting the meeting will record and distribute the meeting minutes to each party present and to parties requiring information.

a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013100

SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:

1. Contractor's construction schedule.
2. Construction schedule updating reports.
3. Daily construction reports.
4. Site condition reports.

B. Related Requirements:

1.2 DEFINITIONS

A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.

1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
2. Predecessor Activity: An activity that precedes another activity in the network.
3. Successor Activity: An activity that follows another activity in the network.

B. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.

C. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.

D. Float: The measure of leeway in starting and completing an activity.

1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date].

1.3 INFORMATIONAL SUBMITTALS

A. Format for Submittals: Submit required submittals in the following format:

1. Working electronic copy of schedule file, where indicated.
2. PDF electronic file.
3. Two paper copies.

B. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.

C. CPM Reports: Concurrent with CPM schedule, submit each of the following reports. Format for each activity in reports shall contain activity number, activity description, original duration, remaining duration, early start date, early finish date, late start date, late finish date, and total float in calendar days.

1. Activity Report: List of all activities sorted by activity number and then early start date, or actual start date if known.
2. Logic Report: List of preceding and succeeding activities for all activities, sorted in ascending order by activity number and then early start date, or actual start date if known.
3. Total Float Report: List of all activities sorted in ascending order of total float.
4. Earnings Report: Compilation of Contractor's total earnings from the Notice to Proceed until most recent Application for Payment.

D. Construction Schedule Updating Reports: Submit with Applications for Payment.

E. Daily Construction Reports: Submit at monthly intervals.

F. Site Condition Reports: Submit at time of discovery of differing conditions.

1.4 COORDINATION

A. Coordinate Contractor's construction schedule with the schedule of values,[list of subcontracts,] submittal schedule, progress reports, payment requests, and other required schedules and reports.

1. Secure time commitments for performing critical elements of the Work from entities involved.
2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

PART 2 - PRODUCTS

2.1 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

A. Time Frame: Extend schedule from date established from the “Notice to Proceed” to date of Substantial Completion.

1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.

B. Activities: Treat each story or separate area as a separate numbered activity for each main element of the Work. Comply with the following:

1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.

2. Procurement Activities: Include procurement process activities for the following long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.

    a. <Insert list of major items or pieces of equipment>.

3. Submittal Review Time: Include review and re-submittal times indicated in Section 013300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's construction schedule with submittal schedule.
4. Startup and Testing Time: Include no fewer than 15 days for startup and testing.
5. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's and Construction Manager's administrative procedures necessary for certification of Substantial Completion.
6. Punch List and Final Completion: Include not more than 30 days for completion of punch list items and final completion.

C. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.

1. Phasing: Arrange list of activities on schedule by phase.
2. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.
3. Work Restrictions: Show the effect of the following items on the schedule:

    a. Coordination with existing construction.
    b. Limitations of continued occupancies.
    c. Uninterruptible services.
    d. Partial occupancy before Substantial Completion.
    e. Use of premises restrictions.
    f. Provisions for future construction.
    g. Seasonal variations.
    h. Environmental control.

4. Work Stages: Indicate important stages of construction for each major portion of the Work.
5. Other Constraints:

D. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and final completion, and the following milestone:

1. <Insert milestones not indicated elsewhere>.

E. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:

1. Unresolved issues.
2. Unanswered Requests for Information.
3. Rejected or unreturned submittals.
4. Notations on returned submittals.

5. Pending modifications affecting the Work and Contract Time.

F. Recovery Schedule: When periodic update indicates the Work is 14 or more calendar days behind the current approved schedule, submit a separate recovery schedule indicating means by which Contractor intends to regain compliance with the schedule.

G. Computer Scheduling Software: Prepare schedules using current version of a program that has been developed specifically to manage construction schedules.

2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE (GANTT CHART)

A. Gantt-Chart Schedule: Submit a comprehensive, fully developed, horizontal, Gantt-chart-type, Contractor's construction schedule within 30 days of date established for the Notice to Proceed.

B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line.

1. For construction activities that require three months or longer for completion indicate an estimated completion percentage in ten (10) percent increments within time bar.

2.3 CONTRACTOR'S CONSTRUCTION SCHEDULE (CPM SCHEDULE)

A. General: Prepare network diagrams using AON (activity-on-node) format.

B. Startup Network Diagram: Submit diagram within 14 days of date established for the Notice to Proceed. Outline significant construction activities for the first 90 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.

C. CPM Schedule: Prepare Contractor's construction schedule using a[cost- and resource-loaded,] time-scaled CPM network analysis diagram for the Work.

1. Develop network diagram in sufficient time to submit CPM schedule so it can be accepted for use no later than 60 days after date established for [the Notice to Proceed.

a. Failure to include any work item required for performance of this Contract shall not excuse Contractor from completing all work within applicable completion dates, regardless of Architect's approval of the schedule.

2. Establish procedures for monitoring and updating CPM schedule and for reporting progress. Coordinate procedures with progress meeting and payment request dates.
3. Use "one workday" as the unit of time for individual activities. Indicate nonworking days and holidays incorporated into the schedule in order to coordinate with the Contract Time.

D. CPM Schedule Preparation: Prepare a list of all activities required to complete the Work. Using the startup network diagram, prepare a skeleton network to identify probable critical paths.

1. Activities: Indicate the estimated time duration, sequence requirements, and relationship of each activity in relation to other activities. Include estimated time frames for the following activities:

    a. Preparation and processing of submittals.
    b. Mobilization and demobilization.
    c. Purchase of materials.
    d. Delivery.
    e. Fabrication.
    f. Utility interruptions.
    g. Installation.
    h. Work by Owner that may affect or be affected by Contractor's activities.
    i. Testing and commissioning.
    j. Punch list and final completion.
    k. Activities occurring following final completion.

2. Critical Path Activities: Identify critical path activities, including those for interim completion dates. Scheduled start and completion dates shall be consistent with Contract milestone dates.
3. Processing: Process data to produce output data on a computer-drawn, time-scaled network. Revise data, reorganize activity sequences, and reproduce as often as necessary to produce the CPM schedule within the limitations of the Contract Time.
4. Format: Mark the critical path. Locate the critical path near center of network; locate paths with most float near the edges.

    a. Sub-networks on separate sheets are permissible for activities clearly off the critical path.

E. Contract Modifications: For each proposed contract modification and concurrent with its submission, prepare a time-impact analysis using a network fragment to demonstrate the effect of the proposed change on the overall project schedule.

F. Initial Issue of Schedule: Prepare initial network diagram from a sorted activity list indicating straight "early start-total float." Identify critical activities. Prepare tabulated reports showing the following:

1. Contractor or subcontractor and the Work or activity.
2. Description of activity.
3. Main events of activity.
4. Immediate preceding and succeeding activities.
5. Early and late start dates.
6. Early and late finish dates.
7. Activity duration in workdays.
8. Total float or slack time.
9. Average size of workforce.
10. Dollar value of activity (coordinated with the schedule of values).

G. Schedule Updating: Concurrent with making revisions to schedule, prepare tabulated reports showing the following:

1. Identification of activities that have changed.

2. Changes in early and late start dates.
3. Changes in early and late finish dates.
4. Changes in activity durations in workdays.
5. Changes in the critical path.
6. Changes in total float or slack time.
7. Changes in the Contract Time.

2.4 REPORTS

A. Daily Construction Reports: Prepare a daily construction report recording the following information concerning events at Project site:

1. List of subcontractors at Project site.
2. List of separate contractors at Project site.
3. Approximate count of personnel at Project site.
4. Equipment at Project site.
5. Material deliveries.
6. High and low temperatures and general weather conditions, including presence of rain or snow.
7. Accidents.
8. Meetings and significant decisions.
9. Unusual events.
10. Stoppages, delays, shortages, and losses.
11. Meter readings and similar recordings.
12. Emergency procedures.
13. Orders and requests of authorities having jurisdiction.
14. Change Orders received and implemented.

B. Site Condition Reports: Immediately on discovery of a difference between site conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

PART 3 - EXECUTION

3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

A. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week, before each regularly scheduled progress meeting.

1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
3. As the Work progresses, indicate final completion percentage for each activity.

B. Distribution: Distribute copies of approved schedule to Architect or Construction Manager, Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.

1. Post copies in Project meeting rooms and temporary field offices.
2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

END OF SECTION 013200

SECTION 013233 - PHOTOGRAPHIC DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for the following:

1. Preconstruction photographs.
2. Periodic construction photographs.

B. Related Requirements:

1. Section 017700 "Closeout Procedures" for submitting photographic documentation as Project Record Documents at Project closeout.

1.2 INFORMATIONAL SUBMITTALS

A. Key Plan: Submit key plan of Project site and building with notation of vantage points marked for location and direction of each photograph or video recording. Indicate elevation or story of construction. Include same information as corresponding photographic documentation.

B. Digital Construction Photographs: Submit unaltered, original, full-size image files within three days of taking photographs.

1. Digital Camera: Minimum sensor resolution of 8 megapixels.
2. Identification: Provide the following information with each image description in file metadata tag:

a. Name of Project.
b. Name of Architect and Construction Manager.
c. Name of Contractor.
d. Date photograph was taken if not date stamped by camera.
e. Description of vantage point, indicating location, direction (by compass point), and elevation or story of construction.
f. Unique sequential identifier keyed to accompanying key plan.

1.3 USAGE RIGHTS

A. Obtain and transfer copyright usage rights from contractor to Owner for unlimited reproduction of photographic documentation.

PART 2 - PRODUCTS

2.1 PHOTOGRAPHIC MEDIA

A. Digital Images: Provide images in JPG format, with minimum size of 8 megapixels.

PART 3 - EXECUTION

3.1 CONSTRUCTION PHOTOGRAPHS

A. General: Take photographs using the maximum range of depth of field, and that are in focus, to clearly show the Work. Photographs with blurry or out-of-focus areas will not be accepted.

1. Maintain key plan with each set of construction photographs that identifies each photographic location.

B. Digital Images: Submit digital images exactly as originally recorded in the digital camera, without alteration, manipulation, editing, or modifications using image-editing software.

1. Date and Time: Include date and time in file name for each image.
2. Field Office Images: Maintain one set of images accessible in the field office at Project site, available at all times for reference. Identify images in the same manner as those submitted to Construction Manager.

C. Preconstruction Photographs: Before starting construction, take photographs of Project site and surrounding properties, including existing items to remain during construction, from different vantage points, as directed by Construction Manager.

1. Flag excavation areas, construction limits before taking construction photographs.
2. Take 20 photographs to show existing conditions adjacent to property before starting the Work.

D. Periodic Construction Photographs: Take 20 photographs monthly, coinciding with the cutoff date associated with each Application for Payment. Select vantage points to show status of construction and progress since last photographs were taken.

E. Final Completion Construction Photographs: Take 20 color photographs after date of Substantial Completion for submission as Project Record Documents. Architect or Construction Manager will inform contractor of desired vantage points.

F. Additional Photographs: Architect or Construction Manager may request photographs in addition to periodic photographs specified. Additional photographs shall be included in the Contract Sum.

1. Three days' notice will be given, where feasible.
2. In emergency situations, take additional photographs within 24 hours of request.
3. Circumstances that could require additional photographs include, but are not limited to, the following:

a. Special events planned at Project site.
b. Immediate follow-up when on-site events result in construction damage or losses.
c. Photographs to be taken at fabrication locations away from Project site. These photographs are not subject to unit prices or unit-cost allowances.
d. Substantial Completion of a major phase or component of the Work.
e. Extra record photographs at time of final acceptance.
f. Owner's request for special publicity photographs.

END OF SECTION 013233

SECTION 013300 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes requirements for the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.

1. Submittals for Special Systems, required by the Authority(s) Having Jurisdiction, are not exempt, from the requirements of this Section.

B. All documents transmitted for the purpose of administration among team members shall be through the project management software **PROCORE (www.procore.com)** The Contractors use of this software shall be discussed at the pre-construction meeting.

C. Besides submittals for review, information, and closeout, this procedure applies to requests for information (RFIs), progress documentation, contract modification documents, supplementary instructions, change proposals, change orders, applications for payment, field reports and meeting minutes, and any other document any participant wishes to make part of the project record.

D. Contractor and Architect is required to use this service.

E. It is the contractors responsibility to submit documents in PDF format. All documents submitted to the architect shall first be review by the contractor and shall carry the contractors approval stamp indicating compliance with the Contract Documents.

F. Users of the service need an email address, internet access, and PDF review software that includes ability to mark up and apply electronic stamps (such as Adobe Acrobat).

G. PAPER document transmittals **will not** be reviewed; emailed PDF documents **will not** be reviewed. Provide paper submittals when required to submit fire alarm or sprinkler shop drawings that will be submitted to the Fire Marshal.

H. All other submittal and document transmission procedures apply, except that electronic document requirement will not apply to samples or color selection charts.

I. The service will be at no cost.

J. Submittal Service: The selected service is PROCORE - (866) 477-6267, www.procore.com.

K. Training one, one hour web-based training session will be arranged for all participants, with representatives of TBA Studio and contractor participating, further training is the responsibility of the user of the service.

L. Project Closeout: TBA Studio will determine when to terminate the service for the project and is responsible for obtaining archive copies of the files..

M. Related Requirements:

1. Section 013200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
2. Section 017823 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
3. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
4. Section 017900 "Demonstration and Training" for submitting video recordings of demonstration of equipment and training of Owner's personnel.

1.2 DEFINITIONS

A. Action Submittals: Written and graphic information and physical samples that require Architect's and Construction Manager's responsive action.

B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's and Construction Manager's responsive action. Submittals may be rejected for not complying with requirements.

1.3 ACTION SUBMITTALS

A. Submittal Schedule: Submit a schedule of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals noted by Architect[and Construction Manager] and additional time for handling and reviewing submittals required by those corrections.

1.4 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

A. Architect's Digital Data Files: Electronic copies of digital data files of the Contract Drawings will be provided by Architect for Contractor's use in preparing submittals as noted below.

1. Architect will furnish Contractor one set of digital data drawing files of the Contract Drawings for use in preparing Shop Drawings and Project record drawings.

B. Electronic Submittals: Identify and incorporate information in each electronic submittal file as follows:

1. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
2. Name file with submittal number or other unique identifier, including revision identifier.

a. File name shall use project identifier and Specification Section number followed by a decimal point and then a sequential number (e.g., LNHS-061000.01). Resubmittals shall include an alphabetic suffix after another decimal point (e.g., LNHS-061000.01.A).

3. Provide means for insertion to permanently record Contractor's review and approval markings and action taken by Architect and Construction Manager.
4. Transmittal Form for Electronic Submittals: Use software-generated form from PROCORE (www.procore.com), containing the following information:

    a. Project name.
    b. Date.
    c. Name and address of Architect.
    d. Name of Construction Manager.
    e. Name of Contractor.
    f. Name of firm or entity that prepared submittal.
    g. Names of subcontractor, manufacturer, and supplier.
    h. Category and type of submittal.
    i. Submittal purpose and description.
    j. Specification Section number and title.
    k. Specification paragraph number or drawing designation and generic name for each of multiple items.
    l. Drawing number and detail references, as appropriate.
    m. Location(s) where product is to be installed, as appropriate.
    n. Related physical samples submitted directly.
    o. Indication of full or partial submittal.
    p. Transmittal number, numbered consecutively.
    q. Submittal and transmittal distribution record.
    r. Other necessary identification.
    s. Remarks.

5. Metadata: Include the following information as keywords in the electronic submittal file metadata:

    a. Project name.
    b. Number and title of appropriate Specification Section.
    c. Manufacturer name.
    d. Product name.

C. Options: Identify options requiring selection by Architect.

D. Deviations: Identify deviations from the Contract Documents on submittals.

E. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.

1. Note date and content of previous submittal.
2. Note date and content of revision in label or title block and clearly indicate extent of revision.
3. Resubmit submittals until they are marked with approval notation from Architect's[and Construction Manager's] action stamp.

F. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.

G. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's and Construction Manager' action stamp.

H.

PART 2 - PRODUCTS

2.1 SUBMITTAL PROCEDURES

A. General Submittal Procedure Requirements:

1. Send electronic submittals as PDF electronic files directly to Architect and /or Construction Manager specifically established for Project.

    a. Architect, through Construction Manager, will return annotated file. Annotate and retain one copy of file as an electronic Project record document file.

2. Submit electronic submittals via email as PDF electronic files.

    a. Architect, through Construction Manager, will return annotated file. Annotate and retain one copy of file as an electronic Project record document file.

3. Action Submittals: Submit three paper copies of each submittal unless otherwise indicated. Architect, through Construction Manager, will return two copies.
4. Informational Submittals: Submit two paper copies of each submittal unless otherwise indicated. Architect and Construction Manager will not return copies.
5. Certificates and Certifications Submittals: Provide a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.

    a. Provide a digital signature with digital certificate on electronically-submitted certificates and certifications where indicated.
    b. Provide a notarized statement on original paper copy certificates and certifications where indicated.

B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.

1. If information must be specially prepared for submittal because standard published data are not suitable for use, submit as Shop Drawings, not as Product Data.
2. Mark each copy of each submittal to show which products and options are applicable.
3. Include the following information, as applicable:

    a. Manufacturer's catalog cuts.
    b. Manufacturer's product specifications.
    c. Standard color charts.
    d. Statement of compliance with specified referenced standards.

e. Testing by recognized testing agency.
f. Application of testing agency labels and seals.
g. Notation of coordination requirements.
h. Availability and delivery time information.

4. For equipment, include the following in addition to the above, as applicable:

a. Wiring diagrams showing factory-installed wiring.
b. Printed performance curves.
c. Operational range diagrams.
d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.

5. Submit Product Data before or concurrent with Samples.
6. Submit Product Data in the following format:

a. PDF electronic file.

C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data, unless submittal based on Architect's digital data drawing files is otherwise permitted.

1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:

a. Identification of products.
b. Schedules.
c. Compliance with specified standards.
d. Notation of coordination requirements.
e. Notation of dimensions established by field measurement.
f. Relationship and attachment to adjoining construction clearly indicated.
g. Seal and signature of professional engineer if specified.

2. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches (215 by 280 mm), but no larger than 24 by 36 inches (914 by 607).
3. Submit Shop Drawings in the following format:

a. PDF electronic file.
b. Three opaque copies of each submittal. Architect and Construction Manager will retain one copy; remainder will be returned.

D. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.

1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
2. Identification: Attach label on unexposed side of Samples that includes the following:

a. Generic description of Sample.

b. Product name and name of manufacturer.
c. Sample source.
d. Number and title of applicable Specification Section.

3. For projects where electronic submittals are required, provide corresponding electronic submittal of Sample transmittal, digital image file illustrating Sample characteristics, and identification information for record.
4. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.

   a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
   b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.

5. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.

   a. Number of Samples: Submit one full set of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect, through Construction Manager, will return submittal with options selected.

6. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.

   a. Number of Samples: Submit three sets of Samples. Architect and Construction Manager will retain two Sample sets; remainder will be returned. Mark up and retain one returned Sample set as a project record sample.

      1) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least three number sets of paired units that show approximate limits of variations.

E. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:

1. Submit product schedule in the following format:

   a. PDF electronic file.
   b. Three paper copies of product schedule or list unless otherwise indicated. Architect, through Construction Manager, will return two copies.

F. Coordination Drawings Submittals: Comply with requirements specified in Section 013100 "Project Management and Coordination."

G. Contractor's Construction Schedule: Comply with requirements specified in Section 013200 "Construction Progress Documentation."

H. Application for Payment and Schedule of Values: Comply with requirements specified in Section 012900 "Payment Procedures.

I. Test and Inspection Reports and Schedule of Tests and Inspections Submittals: Comply with requirements specified in Section 014000 "Quality Requirements."

J. Closeout Submittals and Maintenance Material Submittals: Comply with requirements specified in Section 017700 "Closeout Procedures."

K. Maintenance Data: Comply with requirements specified in Section 017823 "Operation and Maintenance Data."

L. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.

M. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of Welding Procedure Specification and Procedure Qualification Record on AWS forms. Include names of firms and personnel certified.

N. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.

O. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.

P. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.

Q. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.

R. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.

S. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.

T. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project.

U. Schedule of Tests and Inspections: Comply with requirements specified in Section 014000 "Quality Requirements."

V. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.

W. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.

X. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.

Y. Design Data: Prepare and submit written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.

2.2 DELEGATED-DESIGN SERVICES

A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.

1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.

B. Delegated-Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF electronic file and three paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.

1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

A. Action and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections

and field dimensions. Mark with approval stamp before submitting to Architect and Construction Manager.

B. Project Closeout and Maintenance Material Submittals: See requirements in Section 017700 "Closeout Procedures."

C. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

3.2 ARCHITECT'S AND CONSTRUCTION MANAGER'S ACTION

A. General: Architect and Construction Manager will not review submittals that do not bear Contractor's approval stamp and will return them without action.

B. Action Submittals: Architect and Construction Manager will review each submittal, make marks to indicate corrections or revisions required, and return it. Architect or Construction Manager will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action.

C. Informational Submittals: Architect and Construction Manager will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect and Construction Manager will forward each submittal to appropriate party.

D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.

E. Submittals not required by the Contract Documents may not be reviewed and may be discarded.

END OF SECTION 013300

SECTION 014000 - QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for quality assurance and quality control.

B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.

1. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
2. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, Construction Manager, or authorities having jurisdiction are not limited by provisions of this Section.
3. Specific test and inspection requirements are not specified in this Section.

1.2 DEFINITIONS

A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.

B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect or Construction Manager.

C. Mockups: Full-size physical assemblies that are constructed on-site. Mockups are constructed to verify selections made under Sample submittals; to demonstrate aesthetic effects and, where indicated, qualities of materials and execution; to review coordination, testing, or operation; to show interface between dissimilar materials; and to demonstrate compliance with specified installation tolerances. Mockups are not Samples. Unless otherwise indicated, approved mockups establish the standard by which the Work will be judged.

1. Laboratory Mockups: Full-size physical assemblies constructed at testing facility to verify performance characteristics.

D. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.

E. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.

F. Source Quality-Control Testing: Tests and inspections that are performed at the source, e.g., plant, mill, factory, or shop.

G. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.

H. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.

I. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.

1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).

J. Experienced: When used with an entity or individual, "experienced" means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

1.3 CONFLICTING REQUIREMENTS

A. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for a decision before proceeding.

B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.4 INFORMATIONAL SUBMITTALS

A. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility sent to authorities having jurisdiction before starting work on the following systems:

1. Seismic-force-resisting system, designated seismic system, or component listed in the designated seismic system quality-assurance plan prepared by Architect.

2. Main wind-force-resisting system or a wind-resisting component listed in the wind-force-resisting system quality-assurance plan prepared by Architect.

B. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.

1.5 REPORTS AND DOCUMENTS

A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:

1. Date of issue.
2. Project title and number.
3. Name, address, and telephone number of testing agency.
4. Dates and locations of samples and tests or inspections.
5. Names of individuals making tests and inspections.
6. Description of the Work and test and inspection method.
7. Identification of product and Specification Section.
8. Complete test or inspection data.
9. Test and inspection results and an interpretation of test results.
10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
12. Name and signature of laboratory inspector.
13. Recommendations on retesting and re-inspecting.

B. Manufacturer's Field Reports: Prepare written information documenting tests and inspections specified in other Sections. Include the following:

1. Name, address, and telephone number of representative making report.
2. Statement on condition of substrates and their acceptability for installation of product.
3. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
4. Results of operational and other tests and a statement of whether observed performance complies with requirements.
5. Other required items indicated in individual Specification Sections.

C. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

1.6 QUALITY ASSURANCE

A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.

B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

D. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.

E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or products that are similar in material, design, and extent to those indicated for this Project.

F. Specialists: Certain Specification Sections require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.

1. Requirements of authorities having jurisdiction shall supersede requirements for specialists.

G. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented according to ASTM E 329; and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.

1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.
2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.

H. Manufacturer's Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.

I. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:

1. Contractor responsibilities include the following:

a. Provide test specimens representative of proposed products and construction.
b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
c. Build laboratory mockups at testing facility using personnel, products, and methods of construction indicated for the completed Work.

d. When testing is complete, remove test specimens, assemblies, mockups and laboratory mockups; do not reuse products on Project.

2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect, through Construction Manager, with copy to Contractor. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from the Contract Documents.

J. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:

1. Build mockups in location and of size indicated or, if not indicated, as directed by Architect or Construction Manager.
2. Notify Architect and Construction Manager seven days in advance of dates and times when mockups will be constructed.
3. Demonstrate the proposed range of aesthetic effects and workmanship.
4. Obtain Architect's and Construction Manager's approval of mockups before starting work, fabrication, or construction.

a. Allow seven days for initial review and each re-review of each mockup.

5. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
6. Demolish and remove mockups when directed unless otherwise indicated.

K. Laboratory Mockups: Comply with requirements of preconstruction testing and those specified in individual Specification Sections.

1.7 QUALITY CONTROL

A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.

1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.
2. Costs for retesting and re-inspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor.

B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities required to verify that the Work complies with requirements, whether specified or not.

1. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.

a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.

2. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
3. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
4. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
5. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.

C. Manufacturer's Field Services: Where indicated, engage a manufacturer's representative to observe and inspect the Work. Manufacturer's representative's services include examination of substrates and conditions, verification of materials, inspection of completed portions of the Work, and submittal of written reports.

D. Retesting/Re-inspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and re-inspecting, for construction that replaced Work that failed to comply with the Contract Documents.

E. Testing Agency Responsibilities: Cooperate with Architect, Construction Manager, and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.

1. Notify Architect, Construction Manager, and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
6. Do not perform any duties of Contractor.

F. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:

1. Access to the Work.
2. Incidental labor and facilities necessary to facilitate tests and inspections.
3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
4. Facilities for storage and field curing of test samples.
5. Delivery of samples to testing agencies.
6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
7. Security and protection for samples and for testing and inspecting equipment at Project site.

G. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.

1. Schedule times for tests, inspections, obtaining samples, and similar activities.

1.8 SPECIAL TESTS AND INSPECTIONS

A. Special Tests and Inspections: Owner will engage a qualified testing agency or special inspector to conduct special tests and inspections required by authorities having jurisdiction as the responsibility of Owner and as follows:

B. Special Tests and Inspections: Conducted by a qualified testing agency or special inspector as required by authorities having jurisdiction, as indicated in individual Specification Sections and as follows:

1. Verifying that manufacturer maintains detailed fabrication and quality-control procedures and reviews the completeness and adequacy of those procedures to perform the Work.
2. Notifying Construction Manager and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
3. Submitting a certified written report of each test, inspection, and similar quality-control service to Architect, through Construction Manager, with copy to Contractor and to authorities having jurisdiction.
4. Submitting of a final report of special tests and inspections at Substantial Completion, which includes a list of unresolved deficiencies.
5. Interpreting tests and inspections and stating in each report whether tested and inspected work complies with or deviates from the Contract Documents.
6. Retesting and re-inspecting corrected work.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:

1. Date test or inspection was conducted.
2. Description of the Work tested or inspected.
3. Date test or inspection results were transmitted to Architect.
4. Identification of testing agency or special inspector conducting test or inspection.

B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's and Construction Manager's reference during normal working hours.

3.2 REPAIR AND PROTECTION

A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.

1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 017300 "Execution."

B. Protect construction exposed by or for quality-control service activities.

C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 014000

SECTION 014100- TESTING LABORATORY SERVICES

PART 1- GENERAL

1.01 SECTION INCLUDES

A. Coordination with Owner-elected laboratory as required for material and construction testing.

1.02 LABORATORY SELCTION AND PAYMENT

A. The Owner shall engage and pay for the services of an independent testing laboratory to perform inspection and tests of materials and construction as defined in the General Conditions, except that in the event of a test failure the Contractor shall pay for re-testing.

1.03 QUALITY ASSURANCE

A. With the approval of the Owner and Engineer, the Testing Laboratory will recommend the type and number of tests to be performed on the project. The Contractor shall be advised of the number and type of tests to be performed by the Testing Laboratory. The Contractor is responsible for supplying concrete that meets the concrete design mixes specified under Division 3 of the Contract Documents.

PART 2- PRODUCTS

Not used

PART 3- EXECUTION

3.01 FIELD QUALITY CONTROL

A. The Contractor shall cooperate with the laboratory and:
    a. Make available, without costs, samples of all materials to be tested in accordance with applicable standard specifications
    b. Furnish such nominal labor and sheltered working space as necessary to obtain samples at the project.
    c. Advise the laboratory of the identity of materials sources and instruct the supplier to allow test of inspections by the laboratory.
    d. Notify the laboratory sufficiently in advance of operations to allow for completion of initial tests and assignment of inspection personnel.
    e. Notify the laboratory sufficiently in advance of cancellation of required testing operation. The Contractor shall be responsible to the laboratory for charges due to failure to notify if requirements for testing are cancelled.

B. Test Methods: Test and inspections shall be conducted in accordance with the latest standards or ASTM or other recognized authorities.

END OF SECTION

SECTION 014200 - REFERENCES

PART 1 - GENERAL

1.1 DEFINITIONS

A. General: Basic Contract definitions are included in the Conditions of the Contract.

B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.

C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."

D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."

E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.

F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.

G. "Install": Unload, temporarily store, unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, protect, clean, and similar operations at Project site.

H. "Provide": Furnish and install, complete and ready for the intended use.

I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.2 INDUSTRY STANDARDS

A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.

B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.

C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.

1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

1.3 ABBREVIATIONS AND ACRONYMS

A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.

1. AABC - Associated Air Balance Council; www.aabc.com.
2. AAMA - American Architectural Manufacturers Association; www.aamanet.org.
3. AAPFCO - Association of American Plant Food Control Officials; www.aapfco.org.
4. AASHTO - American Association of State Highway and Transportation Officials; www.transportation.org.
5. AATCC - American Association of Textile Chemists and Colorists; www.aatcc.org.
6. ABMA - American Bearing Manufacturers Association; www.americanbearings.org.
7. ACI - American Concrete Institute; (Formerly: ACI International); www.concrete.org.
8. ACPA - American Concrete Pipe Association; www.concrete-pipe.org.
9. AEIC - Association of Edison Illuminating Companies, Inc. (The); www.aeic.org.
10. AF&PA - American Forest & Paper Association; www.afandpa.org.
11. AGA - American Gas Association; www.aga.org.
12. AHAM - Association of Home Appliance Manufacturers; www.aham.org.
13. AHRI - Air-Conditioning, Heating, and Refrigeration Institute (The); www.ahrinet.org.
14. AI - Asphalt Institute; www.asphaltinstitute.org.
15. AIA - American Institute of Architects (The); www.aia.org.
16. AISC - American Institute of Steel Construction; www.aisc.org.
17. AISI - American Iron and Steel Institute; www.steel.org.
18. AITC - American Institute of Timber Construction; www.aitc-glulam.org.
19. AMCA - Air Movement and Control Association International, Inc.; www.amca.org.
20. ANSI - American National Standards Institute; www.ansi.org.
21. AOSA - Association of Official Seed Analysts, Inc.; www.aosaseed.com.
22. APA - APA - The Engineered Wood Association; www.apawood.org.
23. APA - Architectural Precast Association; www.archprecast.org.
24. API - American Petroleum Institute; www.api.org.
25. ARI - Air-Conditioning & Refrigeration Institute; (See AHRI).
26. ARI - American Refrigeration Institute; (See AHRI).
27. ARMA - Asphalt Roofing Manufacturers Association; www.asphaltroofing.org.
28. ASCE - American Society of Civil Engineers; www.asce.org.
29. ASCE/SEI - American Society of Civil Engineers/Structural Engineering Institute; (See ASCE).
30. ASHRAE - American Society of Heating, Refrigerating and Air-Conditioning Engineers; www.ashrae.org.
31. ASME - ASME International; (American Society of Mechanical Engineers); www.asme.org.
32. ASSE - American Society of Safety Engineers (The); www.asse.org.
33. ASSE - American Society of Sanitary Engineering; www.asse-plumbing.org.
34. ASTM - ASTM International; (American Society for Testing and Materials International); www.astm.org.
35. ATIS - Alliance for Telecommunications Industry Solutions; www.atis.org.
36. AWEA - American Wind Energy Association; www.awea.org.
37. AWI - Architectural Woodwork Institute; www.awinet.org.

38. AWMAC - Architectural Woodwork Manufacturers Association of Canada; www.awmac.com.
39. AWPA - American Wood Protection Association; (Formerly: American Wood-Preservers' Association); www.awpa.com.
40. AWS - American Welding Society; www.aws.org.
41. AWWA - American Water Works Association; www.awwa.org.
42. BHMA - Builders Hardware Manufacturers Association; www.buildershardware.com.
43. BIA - Brick Industry Association (The); www.gobrick.com.
44. BICSI - BICSI, Inc.; www.bicsi.org.
45. BIFMA - BIFMA International; (Business and Institutional Furniture Manufacturer's Association); www.bifma.com.
46. BISSC - Baking Industry Sanitation Standards Committee; www.bissc.org.
47. BOCA - BOCA; (Building Officials and Code Administrators International Inc.); (See ICC).
48. BWF - Badminton World Federation; (Formerly: International Badminton Federation); www.bwfbadminton.org.
49. CDA - Copper Development Association; www.copper.org.
50. CEA - Canadian Electricity Association; www.electricity.ca.
51. CEA - Consumer Electronics Association; www.ce.org.
52. CFFA - Chemical Fabrics & Film Association, Inc.; www.chemicalfabricsandfilm.com.
53. CFSEI - Cold-Formed Steel Engineers Institute; www.cfsei.org.
54. CGA - Compressed Gas Association; www.cganet.com.
55. CIMA - Cellulose Insulation Manufacturers Association; www.cellulose.org.
56. CISCA - Ceilings & Interior Systems Construction Association; www.cisca.org.
57. CISPI - Cast Iron Soil Pipe Institute; www.cispi.org.
58. CLFMI - Chain Link Fence Manufacturers Institute; www.chainlinkinfo.org.
59. CPA - Composite Panel Association; www.pbmdf.com.
60. CRI - Carpet and Rug Institute (The); www.carpet-rug.org.
61. CRRC - Cool Roof Rating Council; www.coolroofs.org.
62. CRSI - Concrete Reinforcing Steel Institute; www.crsi.org.
63. CSA - Canadian Standards Association; www.csa.ca.
64. CSA - CSA International; (Formerly: IAS - International Approval Services); www.csa-international.org.
65. CSI - Construction Specifications Institute (The); www.csinet.org.
66. CSSB - Cedar Shake & Shingle Bureau; www.cedarbureau.org.
67. CTI - Cooling Technology Institute; (Formerly: Cooling Tower Institute); www.cti.org.
68. CWC - Composite Wood Council; (See CPA).
69. DASMA - Door and Access Systems Manufacturers Association; www.dasma.com.
70. DHI - Door and Hardware Institute; www.dhi.org.
71. ECA - Electronic Components Association; www.ec-central.org.
72. ECAMA - Electronic Components Assemblies & Materials Association; (See ECA).
73. EIA - Electronic Industries Alliance; (See TIA).
74. EIMA - EIFS Industry Members Association; www.eima.com.
75. EJMA - Expansion Joint Manufacturers Association, Inc.; www.ejma.org.
76. ESD - ESD Association; (Electrostatic Discharge Association); www.esda.org.
77. ESTA - Entertainment Services and Technology Association; (See PLASA).
78. EVO - Efficiency Valuation Organization; www.evo-world.org.
79. FIBA - Federation Internationale de Basketball; (The International Basketball Federation); www.fiba.com.
80. FIVB - Federation Internationale de Volleyball; (The International Volleyball Federation); www.fivb.org.

81. FM Approvals - FM Approvals LLC; www.fmglobal.com.
82. FM Global - FM Global; (Formerly: FMG - FM Global); www.fmglobal.com.
83. FRSA - Florida Roofing, Sheet Metal & Air Conditioning Contractors Association, Inc.; www.floridaroof.com.
84. FSA - Fluid Sealing Association; www.fluidsealing.com.
85. FSC - Forest Stewardship Council U.S.; www.fscus.org.
86. GA - Gypsum Association; www.gypsum.org.
87. GANA - Glass Association of North America; www.glasswebsite.com.
88. GS - Green Seal; www.greenseal.org.
89. HI - Hydraulic Institute; www.pumps.org.
90. HI/GAMA - Hydronics Institute/Gas Appliance Manufacturers Association; (See AHRI).
91. HMMA - Hollow Metal Manufacturers Association; (See NAAMM).
92. HPVA - Hardwood Plywood & Veneer Association; www.hpva.org.
93. HPW - H. P. White Laboratory, Inc.; www.hpwhite.com.
94. IAPSC - International Association of Professional Security Consultants; www.iapsc.org.
95. IAS - International Approval Services; (See CSA).
96. ICBO - International Conference of Building Officials; (See ICC).
97. ICC - International Code Council; www.iccsafe.org.
98. ICEA - Insulated Cable Engineers Association, Inc.; www.icea.net.
99. ICPA - International Cast Polymer Alliance; www.icpa-hq.org.
100. ICRI - International Concrete Repair Institute, Inc.; www.icri.org.
101. IEC - International Electrotechnical Commission; www.iec.ch.
102. IEEE - Institute of Electrical and Electronics Engineers, Inc. (The); www.ieee.org.
103. IES - Illuminating Engineering Society; (Formerly: Illuminating Engineering Society of North America); www.ies.org.
104. IESNA - Illuminating Engineering Society of North America; (See IES).
105. IEST - Institute of Environmental Sciences and Technology; www.iest.org.
106. IGMA - Insulating Glass Manufacturers Alliance; www.igmaonline.org.
107. IGSHPA - International Ground Source Heat Pump Association; www.igshpa.okstate.edu.
108. ILI - Indiana Limestone Institute of America, Inc.; www.iliai.com.
109. Intertek - Intertek Group; (Formerly: ETL SEMCO; Intertek Testing Service NA); www.intertek.com.
110. ISA - International Society of Automation (The); (Formerly: Instrumentation, Systems, and Automation Society); www.isa.org.
111. ISAS - Instrumentation, Systems, and Automation Society (The); (See ISA).
112. ISFA - International Surface Fabricators Association; (Formerly: International Solid Surface Fabricators Association); www.isfanow.org.
113. ISO - International Organization for Standardization; www.iso.org.
114. ISSFA - International Solid Surface Fabricators Association; (See ISFA).
115. ITU - International Telecommunication Union; www.itu.int/home.
116. KCMA - Kitchen Cabinet Manufacturers Association; www.kcma.org.
117. LMA - Laminating Materials Association; (See CPA).
118. LPI - Lightning Protection Institute; www.lightning.org.
119. MBMA - Metal Building Manufacturers Association; www.mbma.com.
120. MCA - Metal Construction Association; www.metalconstruction.org.
121. MFMA - Maple Flooring Manufacturers Association, Inc.; www.maplefloor.org.
122. MFMA - Metal Framing Manufacturers Association, Inc.; www.metalframingmfg.org.
123. MHIA - Material Handling Industry of America; www.mhia.org.
124. MIA - Marble Institute of America; www.marble-institute.com.

125. MMPA - Moulding & Millwork Producers Association; (Formerly: Wood Moulding & Millwork Producers Association); www.wmmpa.com.
126. MPI - Master Painters Institute; www.paintinfo.com.
127. MSS - Manufacturers Standardization Society of The Valve and Fittings Industry Inc.; www.mss-hq.org.
128. NAAMM - National Association of Architectural Metal Manufacturers; www.naamm.org.
129. NACE - NACE International; (National Association of Corrosion Engineers International); www.nace.org.
130. NADCA - National Air Duct Cleaners Association; www.nadca.com.
131. NAIMA - North American Insulation Manufacturers Association; www.naima.org.
132. NBGQA - National Building Granite Quarries Association, Inc.; www.nbgqa.com.
133. NCAA - National Collegiate Athletic Association (The); www.ncaa.org.
134. NCMA - National Concrete Masonry Association; www.ncma.org.
135. NEBB - National Environmental Balancing Bureau; www.nebb.org.
136. NECA - National Electrical Contractors Association; www.necanet.org.
137. NeLMA - Northeastern Lumber Manufacturers Association; www.nelma.org.
138. NEMA - National Electrical Manufacturers Association; www.nema.org.
139. NETA - InterNational Electrical Testing Association; www.netaworld.org.
140. NFHS - National Federation of State High School Associations; www.nfhs.org.
141. NFPA - NFPA; (National Fire Protection Association); www.nfpa.org.
142. NFPA - NFPA International; (See NFPA).
143. NFRC - National Fenestration Rating Council; www.nfrc.org.
144. NHLA - National Hardwood Lumber Association; www.nhla.com.
145. NLGA - National Lumber Grades Authority; www.nlga.org.
146. NOFMA - National Oak Flooring Manufacturers Association; (See NWFA).
147. NOMMA - National Ornamental & Miscellaneous Metals Association; www.nomma.org.
148. NRCA - National Roofing Contractors Association; www.nrca.net.
149. NRMCA - National Ready Mixed Concrete Association; www.nrmca.org.
150. NSF - NSF International; (National Sanitation Foundation International); www.nsf.org.
151. NSPE - National Society of Professional Engineers; www.nspe.org.
152. NSSGA - National Stone, Sand & Gravel Association; www.nssga.org.
153. NTMA - National Terrazzo & Mosaic Association, Inc. (The); www.ntma.com.
154. NWFA - National Wood Flooring Association; www.nwfa.org.
155. PCI - Precast/Prestressed Concrete Institute; www.pci.org.
156. PDI - Plumbing & Drainage Institute; www.pdionline.org.
157. PLASA - PLASA; (Formerly: ESTA - Entertainment Services and Technology Association); www.plasa.org.
158. RCSC - Research Council on Structural Connections; www.boltcouncil.org.
159. RFCI - Resilient Floor Covering Institute; www.rfci.com.
160. RIS - Redwood Inspection Service; www.redwoodinspection.com.
161. SAE - SAE International; (Society of Automotive Engineers); www.sae.org.
162. SCTE - Society of Cable Telecommunications Engineers; www.scte.org.
163. SDI - Steel Deck Institute; www.sdi.org.
164. SDI - Steel Door Institute; www.steeldoor.org.
165. SEFA - Scientific Equipment and Furniture Association; www.sefalabs.com.
166. SEI/ASCE - Structural Engineering Institute/American Society of Civil Engineers; (See ASCE).
167. SIA - Security Industry Association; www.siaonline.org.
168. SJI - Steel Joist Institute; www.steeljoist.org.
169. SMA - Screen Manufacturers Association; www.smainfo.org.

170. SMACNA - Sheet Metal and Air Conditioning Contractors' National Association; www.smacna.org.
171. SMPTE - Society of Motion Picture and Television Engineers; www.smpte.org.
172. SPFA - Spray Polyurethane Foam Alliance; www.sprayfoam.org.
173. SPIB - Southern Pine Inspection Bureau; www.spib.org.
174. SPRI - Single Ply Roofing Industry; www.spri.org.
175. SRCC - Solar Rating and Certification Corporation; www.solar-rating.org.
176. SSINA - Specialty Steel Industry of North America; www.ssina.com.
177. SSPC - SSPC: The Society for Protective Coatings; www.sspc.org.
178. STI - Steel Tank Institute; www.steeltank.com.
179. SWI - Steel Window Institute; www.steelwindows.com.
180. SWPA - Submersible Wastewater Pump Association; www.swpa.org.
181. TCA - Tilt-Up Concrete Association; www.tilt-up.org.
182. TCNA - Tile Council of North America, Inc.; (Formerly: Tile Council of America); www.tileusa.com.
183. TEMA - Tubular Exchanger Manufacturers Association, Inc.; www.tema.org.
184. TIA - Telecommunications Industry Association; (Formerly: TIA/EIA - Telecommunications Industry Association/Electronic Industries Alliance); www.tiaonline.org.
185. TIA/EIA - Telecommunications Industry Association/Electronic Industries Alliance; (See TIA).
186. TMS - The Masonry Society; www.masonrysociety.org.
187. TPI - Truss Plate Institute; www.tpinst.org.
188. TPI - Turfgrass Producers International; www.turfgrasssod.org.
189. TRI - Tile Roofing Institute; www.tileroofing.org.
190. UBC - Uniform Building Code; (See ICC).
191. UL - Underwriters Laboratories Inc.; www.ul.com.
192. UNI - Uni-Bell PVC Pipe Association; www.uni-bell.org.
193. USAV - USA Volleyball; www.usavolleyball.org.
194. USGBC - U.S. Green Building Council; www.usgbc.org.
195. USITT - United States Institute for Theatre Technology, Inc.; www.usitt.org.
196. WASTEC - Waste Equipment Technology Association; www.wastec.org.
197. WCLIB - West Coast Lumber Inspection Bureau; www.wclib.org.
198. WCMA - Window Covering Manufacturers Association; www.wcmanet.org.
199. WDMA - Window & Door Manufacturers Association; www.wdma.com.
200. WI - Woodwork Institute; (Formerly: WIC - Woodwork Institute of California); www.wicnet.org.
201. WMMPA - Wood Moulding & Millwork Producers Association; (See MMPA).
202. WSRCA - Western States Roofing Contractors Association; www.wsrca.com.
203. WPA - Western Wood Products Association; www.wwpa.org.

B. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.

1. DIN - Deutsches Institut fur Normung e.V.; www.din.de.
2. IAPMO - International Association of Plumbing and Mechanical Officials; www.iapmo.org.
3. ICC - International Code Council; www.iccsafe.org.
4. ICC-ES - ICC Evaluation Service, LLC; www.icc-es.org.

C. Federal Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.

1. COE - Army Corps of Engineers; www.usace.army.mil.
2. CPSC - Consumer Product Safety Commission; www.cpsc.gov.
3. DOC - Department of Commerce; National Institute of Standards and Technology; www.nist.gov.
4. DOD - Department of Defense; http://dodssp.daps.dla.mil.
5. DOE - Department of Energy; www.energy.gov.
6. EPA - Environmental Protection Agency; www.epa.gov.
7. FAA - Federal Aviation Administration; www.faa.gov.
8. FG - Federal Government Publications; www.gpo.gov.
9. GSA - General Services Administration; www.gsa.gov.
10. HUD - Department of Housing and Urban Development; www.hud.gov.
11. LBL - Lawrence Berkeley National Laboratory; Environmental Energy Technologies Division; http://eetd.lbl.gov.
12. OSHA - Occupational Safety & Health Administration; www.osha.gov.
13. SD - Department of State; www.state.gov.
14. TRB - Transportation Research Board; National Cooperative Highway Research Program; www.trb.org.
15. USDA - Department of Agriculture; Agriculture Research Service; U.S. Salinity Laboratory; www.ars.usda.gov.
16. USDA - Department of Agriculture; Rural Utilities Service; www.usda.gov.
17. USDJ - Department of Justice; Office of Justice Programs; National Institute of Justice; www.ojp.usdoj.gov.
18. USP - U.S. Pharmacopeia; www.usp.org.
19. USPS - United States Postal Service; www.usps.com.

D. Standards and Regulations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the standards and regulations in the following list.

1. CFR - Code of Federal Regulations; Available from Government Printing Office; www.gpo.gov/fdsys.
2. DOD - Department of Defense; Military Specifications and Standards; Available from Department of Defense Single Stock Point; http://dodssp.daps.dla.mil.
3. DSCC - Defense Supply Center Columbus; (See FS).
4. FED-STD - Federal Standard; (See FS).
5. FS - Federal Specification; Available from Department of Defense Single Stock Point; http://dodssp.daps.dla.mil.

    a. Available from Defense Standardization Program; www.dsp.dla.mil.
    b. Available from General Services Administration; www.gsa.gov.
    c. Available from National Institute of Building Sciences/Whole Building Design Guide; www.wbdg.org/ccb.

6. MILSPEC - Military Specification and Standards; (See DOD).
7. USAB - United States Access Board; www.access-board.gov.
8. USATBCB - U.S. Architectural & Transportation Barriers Compliance Board; (See USAB).

E. State Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.

1. CBHF - State of California; Department of Consumer Affairs; Bureau of Electronic Appliance and Repair, Home Furnishings and Thermal Insulation; www.bearhfti.ca.gov.
2. CCR - California Code of Regulations; Office of Administrative Law; California Title 24 Energy Code; www.calregs.com.
3. CDHS - California Department of Health Services; (See CDPH).
4. CDPH - California Department of Public Health; Indoor Air Quality Program; www.cal-iaq.org.
5. CPUC - California Public Utilities Commission; www.cpuc.ca.gov.
6. SCAQMD - South Coast Air Quality Management District; www.aqmd.gov.
7. TFS - Texas Forest Service; Forest Resource Development and Sustainable Forestry; http://txforestservice.tamu.edu.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 014200

SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.

B. Related Requirements:

1. Section 011000 "Summary" for work restrictions and limitations on utility interruptions.

1.2 USE CHARGES

A. General: Installation and removal of and use charges for temporary facilities shall be included in the Contract Sum unless otherwise indicated. Allow other entities to use temporary services and facilities without cost, including, but not limited to, Owner's construction forces, Architect, testing agencies, and authorities having jurisdiction.

B. Water and Sewer Service from Existing System: Water from Owner's existing water system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

C. Electric Power Service from Existing System: Electric power from Owner's existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

1.3 INFORMATIONAL SUBMITTALS

A. Site Plan: Show temporary facilities, utility hookups, staging areas, and parking areas for construction personnel.

B. Erosion- and Sedimentation-Control Plan: Show compliance with requirements of EPA Construction General Permit or authorities having jurisdiction, whichever is more stringent.

C. Fire-Safety Program: Show compliance with requirements of NFPA 241 and authorities having jurisdiction. Indicate Contractor personnel responsible for management of fire prevention program.

1.4 QUALITY ASSURANCE

A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.

B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.

C. Accessible Temporary Egress: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines and ICC/ANSI A117.1.

1.5 PROJECT CONDITIONS

A. Temporary Use of Permanent Facilities: Engage Installer of each permanent service to assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

PART 2 - PRODUCTS

2.1 MATERIALS FOR TEMPORARY FACILITIES

A. Chain-Link Fencing: Minimum 2-inch, 0.148-inch thick, galvanized-steel, chain-link fabric fencing; minimum 6 feet high with galvanized-steel pipe posts; minimum 2-3/8-inch OD line posts and 2-7/8-inch OD corner and pull posts, with 1-5/8-inch OD top rails.

B. Portable Chain-Link Fencing: Minimum 2-inch, 0.148-inch thick, galvanized-steel, chain-link fabric fencing; minimum 6 feet high with galvanized-steel pipe posts; minimum 2-3/8-inch OD line posts and 2-7/8-inch OD corner and pull posts, with 1-5/8-inch OD top and bottom rails. Provide concrete or galvanized-steel bases for supporting posts.

2.2 TEMPORARY FACILITIES

A. Field Offices, General: Securable/Lockable prefabricated or mobile units with adequate space & amenities for review of construction drawings, by the Construction Manager & up to 3 other persons, and foundations adequate for normal loading.

B. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment for construction operations.

2.3 EQUIPMENT FOR TEMPORARY FACILITIES

A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.

B. HVAC Equipment: Unless Owner authorizes use of permanent HVAC system, provide vented, self-contained, liquid-propane-gas or fuel-oil heaters with individual space thermostatic control.

1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.

2. Heating Units: Listed and labeled for type of fuel being consumed, by a qualified testing agency acceptable to authorities having jurisdiction, and marked for intended location and application.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.

3.2 TEMPORARY UTILITY INSTALLATION

A. General: Install temporary service or connect to existing service.

1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.

B. Sewers and Drainage: Provide temporary utilities to remove effluent lawfully.

1. Connect temporary sewers to municipal system as directed by authorities having jurisdiction.

C. Water Service: Install water service and distribution piping in sizes and pressures adequate for construction.

D. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.

1. Toilets: Use of Owner's existing toilet facilities will be permitted, as long as facilities are cleaned and maintained in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.

E. Heating and Cooling: Provide temporary heating and cooling required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.

F. Ventilation and Humidity Control: Provide temporary ventilation required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed. Coordinate ventilation requirements to produce ambient condition required and minimize energy consumption.

G. Electric Power Service: Provide electric power service and distribution system of sufficient size, capacity, and power characteristics required for construction operations.

1. Install electric power service underground unless otherwise indicated.

H. Telephone Service:

1. Provide superintendent with cellular telephone for use at and when away from field office.

3.3 SUPPORT FACILITIES INSTALLATION

A. General: Comply with the following:

1. Provide construction for temporary offices, shops, and sheds located within construction area or within 30 feet of building lines that is noncombustible according to ASTM E 136. Comply with NFPA 241.
2. Maintain support facilities until Architect schedules Substantial Completion inspection. Remove before Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.

B. Temporary Roads and Paved Areas: Construct and maintain temporary roads and paved areas adequate for construction operations. Locate temporary roads and paved areas as indicated on Drawings.

1. Provide dust-control treatment that is nonpolluting and non-tracking. Reapply treatment as required to minimize dust.

C. Temporary Use of Permanent Roads and Paved Areas: Locate temporary roads and paved areas in same location as permanent roads and paved areas. Construct and maintain temporary roads and paved areas adequate for construction operations. Extend temporary roads and paved areas, within construction limits indicated, as necessary for construction operations.

1. Coordinate elevations of temporary roads and paved areas with permanent roads and paved areas.
2. Prepare sub-grade and install sub-base and base for temporary roads and paved areas according to Section 312000 "Earth Moving."
3. Recondition base after temporary use, including removing contaminated material, re-grading, proof-rolling, compacting, and testing.
4. Delay installation of final course of permanent hot-mix asphalt pavement until immediately before Substantial Completion. Repair hot-mix asphalt base-course pavement before installation of final course according to Section 321216 "Asphalt Paving."

D. Traffic Controls: Comply with requirements of authorities having jurisdiction.

1. Protect existing site improvements to remain including curbs, pavement, and utilities.
2. Maintain access for fire-fighting equipment and access to fire hydrants.

E. Parking: Provide temporary or Use designated areas of Owner's existing parking areas for construction personnel as approved by owner prior to starting construction.

F. Dewatering Facilities and Drains: Comply with requirements of authorities having jurisdiction. Maintain Project site, excavations, and construction free of water.

1. Dispose of rainwater in a lawful manner that will not result in flooding Project or adjoining properties or endanger permanent Work or temporary facilities.
2. Remove snow and ice as required to minimize accumulations.

G. Project Signs: Provide Project signs as indicated. Unauthorized signs are not permitted.

1. Identification Signs: Provide Project identification signs as indicated on Drawings.
2. Temporary Signs: Provide other signs as indicated and as required to inform public and individuals seeking entrance to Project.

a. Provide temporary, directional signs for construction personnel and visitors.

3. Maintain and touchup signs so they are legible at all times.

H. Waste Disposal Facilities: Comply with requirements specified in Section 017419 "Construction Waste Management and Disposal."

I. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of authorities having jurisdiction. Comply with progress cleaning requirements in Section 017300 "Execution."

J. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.

1. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.

K. Temporary Stairs: Until permanent stairs are available, provide temporary stairs where ladders are not adequate.

L. Temporary Use of Permanent Stairs: Use of new stairs for construction traffic will be permitted, provided stairs are protected and finishes restored to new condition at time of Substantial Completion.

3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.

B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.

C. Temporary Erosion and Sedimentation Control: Comply with[requirements of 2003 EPA Construction General Permit or authorities having jurisdiction, whichever is more stringent and] requirements specified in Section 311000 "Site Clearing."

D. Storm-water Control: Comply with requirements of authorities having jurisdiction. Provide barriers in and around excavations and subgrade construction to prevent flooding by runoff of storm-water from heavy rains.

E. Tree and Plant Protection: Comply with requirements specified in Section 015639 "Temporary Tree and Plant Protection."

F. Pest Control: Engage pest-control service to recommend practices to minimize attraction and harboring of rodents, roaches, and other pests and to perform extermination and control procedures at regular intervals so Project will be free of pests and their residues at Substantial Completion. Perform control operations lawfully, using environmentally safe materials.

G. Site Enclosure Fence: Before construction operations begin and Prior to commencing earthwork, furnish and install site enclosure fence in a manner that will prevent people and animals from easily entering site except by entrance gates.

1. Extent of Fence: As required to enclose entire Project site or portion determined sufficient to accommodate construction operations.

H. Security Enclosure and Lockup: Install temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each work day.

I. Barricades, Warning Signs, and Lights: Comply with requirements of authorities having jurisdiction for erecting structurally adequate barricades, including warning signs and lighting.

J. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weather-tight enclosure for building exterior.

1. Where heating or cooling is needed and permanent enclosure is not complete, insulate temporary enclosures.
2. Construct dustproof partitions with two layers of 6-mil polyethylene sheet on each side. Cover floor with two layers of 6-mil polyethylene sheet, extending sheets 18 inches up the sidewalls. Overlap and tape full length of joints. Cover floor with fire-retardant-treated plywood.

    a. Construct vestibule and airlock at each entrance through temporary partition with not less than 48 inches between doors. Maintain water-dampened foot mats in vestibule.

3. Where fire-resistance-rated temporary partitions are indicated or are required by authorities having jurisdiction, construct partitions according to the rated assemblies.
4. Insulate partitions to control noise transmission to occupied areas.
5. Seal joints and perimeter. Equip partitions with gasketed, dustproof doors and security locks where openings are required.
6. Protect air-handling equipment.
7. Provide walk-off mats at each entrance through temporary partition.

K. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241; manage fire prevention program.

1. Prohibit smoking in construction areas.
2. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition according to requirements of authorities having jurisdiction.
3. Develop and supervise an overall fire-prevention and -protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.
4. Provide temporary standpipes and hoses for fire protection. Hang hoses with a warning sign stating that hoses are for fire-protection purposes only and are not to be removed. Match hose size with outlet size and equip with suitable nozzles.

3.5 MOISTURE AND MOLD CONTROL

A. Contractor's Moisture Protection Plan: Avoid trapping water in finished work. Document visible signs of mold that may appear during construction.

B. Exposed Construction Phase: Before installation of weather barriers, when materials are subject to wetting and exposure and to airborne mold spores, protect materials from water damage and keep porous and organic materials from coming into prolonged contact with concrete.

C. Partially Enclosed Construction Phase: After installation of weather barriers but before full enclosure and conditioning of building, when installed materials are still subject to infiltration of moisture and ambient mold spores, protect as follows:

1. Do not load or install drywall or other porous materials or components, or items with high organic content, into partially enclosed building.
2. Keep interior spaces reasonably clean and protected from water damage.
3. Discard or replace water-damaged and wet material.
4. Discard, replace, or clean stored or installed material that begins to grow mold.
5. Perform work in a sequence that allows any wet materials adequate time to dry before enclosing the material in drywall or other interior finishes.

D. Controlled Construction Phase of Construction: After completing and sealing of the building enclosure but prior to the full operation of permanent HVAC systems, maintain as follows:

1. Control moisture and humidity inside building by maintaining effective dry-in conditions.
2. Remove materials that cannot be completely restored to their manufactured moisture level within 48 hours.

3.6 OPERATION, TERMINATION, AND REMOVAL

A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.

B. Maintenance: Maintain facilities in good operating condition until removal.

1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.

C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.

D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.

1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
2. At Substantial Completion, repair, renovate, and clean permanent facilities used during construction period. Comply with final cleaning requirements specified in Section 017700 "Closeout Procedures."

END OF SECTION 015000

SECTION 015639 - TEMPORARY TREE AND PLANT PROTECTION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes general protection and pruning of existing trees and plants that are affected by execution of the Work, whether temporary or permanent construction.

1.2 DEFINITIONS

A. Protection Zone: Area surrounding individual trees, groups of trees, shrubs, or other vegetation to be protected during construction, and defined by a circle concentric with each tree with a radius 1.5 times the diameter of the drip line unless otherwise indicated.

1.3 INFORMATIONAL SUBMITTALS

A. Existing Conditions: Documentation of existing trees and plantings indicated to remain, which establishes preconstruction conditions that might be misconstrued as damage caused by construction activities.

1.4 PROJECT CONDITIONS

A. The following practices are prohibited within protection zones:

1. Storage of construction materials, debris, or excavated material.
2. Parking vehicles or equipment.
3. Foot traffic.
4. Erection of sheds or structures.
5. Impoundment of water.
6. Excavation or other digging unless otherwise indicated.
7. Attachment of signs to or wrapping materials around trees or plants unless otherwise indicated.

B. Do not direct vehicle or equipment exhaust toward protection zones.

C. Prohibit heat sources, flames, ignition sources, and smoking within or near protection zones and organic mulch.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Protection-Zone Fencing: Fencing fixed in position and meeting the following requirements.

1. Plastic Protection-Zone Fencing: Plastic construction fencing constructed of high-density extruded and stretched polyethylene fabric with 2-inch maximum opening in pattern and supported by tubular or T-shape galvanized-steel posts spaced not more than 8 feet apart. High-visibility orange color, non-fading.
2. Height of Fencing: 4 feet.

PART 3 - EXECUTION

3.1 EXAMINATION AND PREPARATION

A. Protect tree root systems from damage caused by runoff or spillage of noxious materials while mixing, placing, or storing construction materials. Protect root systems from ponding, eroding, or excessive wetting caused by dewatering operations.

3.2 PROTECTION ZONES

A. Protection-Zone Fencing: Install protection-zone fencing along edges of protection zones in a manner that will prevent people from easily entering protected area except by entrance gates.

1. Posts: Set or drive posts into ground one-third the total height of the fence without concrete footings. Where a post is located on existing paving or concrete to remain, provide appropriate means of post support acceptable to Architect.

B. Repair or replace trees, shrubs, and other vegetation indicated to remain or be relocated that are damaged by construction operations, in a manner approved by Architect.

C. Maintain protection-zone fencing and signage in good condition as acceptable to Architect and remove when construction operations are complete and equipment has been removed from the site.

3.3 EXCAVATION

A. Trenching near Trees: Where utility trenches are required within protection zones, hand excavate under or around tree roots or tunnel under the roots by drilling, auger boring, or pipe jacking. Do not cut main lateral tree roots or taproots; cut only smaller roots that interfere with installation of utilities. Cut roots as required for root pruning.

B. Do not allow exposed roots to dry out before placing permanent backfill.

3.4 ROOT PRUNING

A. Prune roots that are affected by temporary and permanent construction. Prune roots as follows:

1. Cut roots manually by digging a trench and cutting exposed roots with sharp pruning instruments; do not break, tear, chop, or slant the cuts. Do not use a backhoe or other equipment that rips, tears, or pulls roots.

2. Temporarily support and protect roots from damage until they are permanently covered with soil.
3. Cover exposed roots with burlap and water regularly.
4. Backfill as soon as possible according to requirements in Section 312000 "Earth Moving."

B. Root Pruning at Edge of Protection Zone: Prune roots by cleanly cutting all roots to the depth of the required excavation.

C. Root Pruning within Protection Zone: Clear and excavate by hand to the depth of the required excavation to minimize damage to root systems. Use narrow-tine spading forks, comb soil to expose roots, and cleanly cut roots as close to excavation as possible.

3.5 REGRADING

A. Lowering Grade: Where new finish grade is indicated below existing grade around trees, slope grade beyond the protection zone. Maintain existing grades within the protection zone.

B. Raising Grade: Where new finish grade is indicated above existing grade around trees, slope grade beyond the protection zone. Maintain existing grades within the protection zone.

C. Minor Fill within Protection Zone: Where existing grade is 2 inches or less below elevation of finish grade, fill with topsoil. Place topsoil in a single un-compacted layer and hand grade to required finish elevations.

3.6 FIELD QUALITY CONTROL

A. Inspections: Engage a qualified arborist to direct plant-protection measures in the vicinity of trees, shrubs, and other vegetation indicated to remain and to prepare inspection reports.

3.7 REPAIR AND REPLACEMENT

A. General: Repair or replace trees, shrubs, and other vegetation indicated to remain or be relocated that are damaged by construction operations, in a manner approved by Architect.

1. Perform repairs within 24 hours.
2. Replace vegetation that cannot be repaired and restored to full-growth status, as determined by Architect.

3.8 DISPOSAL OF SURPLUS AND WASTE MATERIALS

A. Disposal: Remove excess excavated material, displaced trees, trash and debris, and legally dispose of them off Owner's property.

END OF SECTION 015639

SECTION 016000 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.

B. Related Requirements:

1. Section 012500 "Substitution Procedures" for requests for substitutions.

1.2 DEFINITIONS

A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.

1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature, that is current as of date of the Contract Documents.
2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
3. Comparable Product: Product that is demonstrated and approved through submittal process to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.

B. Basis-of-Design Product Specification: A specification in which a specific manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of additional manufacturers named in the specification.

1.3 ACTION SUBMITTALS

A. Comparable Product Requests: Submit request for consideration of each comparable product. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.

1. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Architect will notify Contractor **through Construction Manager** of approval or

rejection of proposed comparable product request within **15** days of receipt of request, or **seven** days of receipt of additional information or documentation, whichever is later.

a. Form of Approval: As specified in Section 013300 "Submittal Procedures."
b. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.

B. Basis-of-Design Product Specification Submittal: Comply with requirements in Section 013300 "Submittal Procedures." Show compliance with requirements.

1.4 QUALITY ASSURANCE

A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.

B. ** Under no circumstances shall any materials containing asbestos be used in this project. The contractor shall provide documentation verifying that all materials supplied are asbestos-free, in accordance with local, state, and federal regulations.

1.5 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

B. Delivery and Handling:

1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
4. Inspect products on delivery to determine compliance with the Contract Documents and to determine that products are undamaged and properly protected.

C. Storage:

1. Store products to allow for inspection and measurement of quantity or counting of units.
2. Store materials in a manner that will not endanger Project structure.
3. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
4. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
5. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.

6. Protect stored products from damage and liquids from freezing.

1.6 PRODUCT WARRANTIES

A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturers' disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.

1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner.

B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.

1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
2. Specified Form: When specified forms are included with the Specifications, prepare a written document using indicated form properly executed.
3. Refer to other Sections for specific content requirements and particular requirements for submitting special warranties.

C. Submittal Time: Comply with requirements in Section 017700 "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.

1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
4. Where products are accompanied by the term "as selected," Architect will make selection.
5. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.

B. Product Selection Procedures:

1. Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
2. Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
3. Products:

    a. Restricted List: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience **will** be considered **unless otherwise indicated**.
    b. Non-restricted List: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed, or an unnamed product, that complies with requirements. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product.

4. Manufacturers:

    a. Restricted List: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience **will** be considered **unless otherwise indicated**.
    b. Non-restricted List: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed, or a product by an unnamed manufacturer, that complies with requirements. Comply with requirements in "Comparable Products" Article for consideration of an unnamed manufacturer's product.

5. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.

C. Visual Matching Specification: Where Specifications require "match Architect's sample", provide a product that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches.

1. If no product available within specified category matches and complies with other specified requirements, comply with requirements in Section 012500 "Substitution Procedures" for proposal of product.

D. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

2.2 COMPARABLE PRODUCTS

A. Conditions for Consideration: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with these requirements:

1. Evidence that the proposed product does not require revisions to the Contract Documents, that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
3. Evidence that proposed product provides specified warranty.
4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
5. Samples, if requested.

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000

SECTION 017300 - EXECUTION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes general administrative and procedural requirements governing execution of the Work including, but not limited to, the following:

1. Construction layout.
2. Field engineering and surveying.
3. Installation of the Work.
4. Cutting and patching.
5. Coordination of Owner-installed products.
6. Progress cleaning.
7. Starting and adjusting.
8. Protection of installed construction.

B. Related Requirements:

1. Section 011000 "Summary" for limits on use of Project site.
2. Section 017700 "Closeout Procedures" for submitting final property survey with Project Record Documents, recording of Owner-accepted deviations from indicated lines and levels, and final cleaning.
3. Section 078413 "Penetration Firestopping" for patching penetrations in fire-rated construction.

1.2 INFORMATIONAL SUBMITTALS

A. Certificates: Submit certificate signed by land surveyor or professional engineer certifying that location and elevation of improvements comply with requirements.

B. Landfill Receipts: Submit copy of receipts issued by a landfill facility, licensed to accept hazardous materials, for hazardous waste disposal.

C. Certified Surveys: Submit two copies signed by land surveyor or professional engineer.

D. Final Property Survey: Submit 10 copies showing the Work performed and record survey data.

1.3 QUALITY ASSURANCE

A. Land Surveyor Qualifications: A professional land surveyor who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing land-surveying services of the kind indicated.

B. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.

1. Structural Elements: When cutting and patching structural elements, notify Architect of locations and details of cutting and await directions from Architect before proceeding. Shore, brace, and support structural element during cutting and patching. Do not cut and patch structural elements in a manner that could change their load-carrying capacity or increase deflection

2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety.

3. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety.

4. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.

PART 2 - PRODUCTS

2.1 MATERIALS

A. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.

1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of in-place materials.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Existing Conditions: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of underground utilities, mechanical and electrical systems, and other construction affecting the Work.

1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; underground electrical services, and other utilities.
2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.

B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.

1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.

C. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Existing Utility Information: Furnish information to local utility or Owner that is necessary to adjust, move, or relocate existing utility structures, utility poles, lines, services, or other utility appurtenances located in or affected by construction. Coordinate with authorities having jurisdiction.

B. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

C. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.

D. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents caused by differing field conditions outside the control of Contractor, submit a request for information to Architect according to requirements in Section 013100 "Project Management and Coordination."

3.3 CONSTRUCTION LAYOUT

A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks. If discrepancies are discovered, notify Architect and Construction Manager promptly.

B. General: Engage a land surveyor or professional engineer] to lay out the Work using accepted surveying practices.

1. Establish benchmarks and control points to set lines and levels at each story of construction and elsewhere as needed to locate each element of Project.
2. Establish limits on use of Project site.

3. Establish dimensions within tolerances indicated. Do not scale Drawings to obtain required dimensions.
4. Inform installers of lines and levels to which they must comply.
5. Check the location, level and plumb, of every major element as the Work progresses.
6. Notify Construction Manager when deviations from required lines and levels exceed allowable tolerances.
7. Close site surveys with an error of closure equal to or less than the standard established by authorities having jurisdiction.

C. Site Improvements: Locate and lay out site improvements, including pavements, grading, fill and topsoil placement, utility slopes, and rim and invert elevations.

D. Building Lines and Levels: Locate and lay out control lines and levels for structures, building foundations, column grids, and floor levels, including those required for mechanical and electrical work. Transfer survey markings and elevations for use with control lines and levels. Level foundations and piers from two or more locations.

E. Record Log: Maintain a log of layout control work. Record deviations from required lines and levels. Include beginning and ending dates and times of surveys, weather conditions, name and duty of each survey party member, and types of instruments and tapes used. Make the log available for reference by Architect and Construction Manager.

3.4 FIELD ENGINEERING

A. Reference Points: Locate existing permanent benchmarks, control points, and similar reference points before beginning the Work. Preserve and protect permanent benchmarks and control points during construction operations.

B. Benchmarks: Establish and maintain a minimum of two permanent benchmarks on Project site, referenced to data established by survey control points. Comply with authorities having jurisdiction for type and size of benchmark.

1. Record benchmark locations, with horizontal and vertical data, on Project Record Documents.

C. Certified Survey: On completion of foundation walls, major site improvements, and other work requiring field-engineering services, prepare a certified survey showing dimensions, locations, angles, and elevations of construction and site-work.

D. Final Property Survey: Engage a land surveyor or professional engineer to prepare a final property survey showing significant features (real property) for Project. Include on the survey a certification, signed by land surveyor or professional engineer, that principal metes, bounds, lines, and levels of Project are accurately positioned as shown on the survey.

1. Recording: At Substantial Completion, have the final property survey recorded by or with authorities having jurisdiction as the official "property survey."

3.5 INSTALLATION

A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.

1. Make vertical work plumb and make horizontal work level.
2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
3. Conceal pipes, ducts, and wiring in finished areas unless otherwise indicated.

B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.

C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.

D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.

E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on site and placement in permanent locations.

F. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.

G. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.

H. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions.

1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
2. Allow for building movement, including thermal expansion and contraction.
3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

I. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.

J. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

3.6 CUTTING AND PATCHING

A. Cutting and Patching, General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.

1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.

B. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during installation or cutting and patching operations, by methods and with materials so as not to void existing warranties.

C. Temporary Support: Provide temporary support of work to be cut.

D. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.

E. Adjacent Occupied Areas: Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.

F. Existing Utility Services and Mechanical/Electrical Systems: Where existing services/systems are required to be removed, relocated, or abandoned, bypass such services/systems before cutting to minimize or prevent interruption to occupied areas.

G. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.

1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
3. Concrete and Masonry : Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
4. Excavating and Backfilling: Comply with requirements in applicable Sections where required by cutting and patching operations.
5. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
6. Proceed with patching after construction operations requiring cutting are complete.

H. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other work. Patch with durable seams that are as invisible as practicable. Provide materials and comply with installation requirements specified in other Sections, where applicable.

1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.

2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will minimize evidence of patching and refinishing.
3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.
4. Ceilings: Patch, repair, or rehang in-place ceilings as necessary to provide an even-plane surface of uniform appearance.
5. Exterior Building Enclosure: Patch components in a manner that restores enclosure to a weathertight condition and ensures thermal and moisture integrity of building enclosure.

I. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

3.7 PROGRESS CLEANING

A. General: Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.

1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F.
3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.

B. Site: Maintain Project site free of waste materials and debris.

C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.

1. Remove liquid spills promptly.
2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.

D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.

E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.

F. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.

G. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways.

H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.

I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.

J. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

3.8 STARTING AND ADJUSTING

A. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.

B. Adjust equipment for proper operation. Adjust operating components for proper operation without binding.

C. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

D. Manufacturer's Field Service: Comply with qualification requirements in Section 014000 "Quality Requirements"

3.9 PROTECTION OF INSTALLED CONSTRUCTION

A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.

B. Comply with manufacturer's written instructions for temperature and relative humidity.

END OF SECTION 017300

SECTION 017419 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for the following:
   1. Disposing of nonhazardous demolition and construction waste.

B. Related Requirements:

   1. Section 042000 "Unit Masonry" for disposal requirements for masonry waste.
   2. Section 311000 "Site Clearing" for disposition of waste resulting from site clearing and removal of above- and below-grade improvements.

1.2 DEFINITIONS

A. Construction Waste: Building and site improvement materials and other solid waste resulting from construction, remodeling, renovation, or repair operations. Construction waste includes packaging.

B. Demolition Waste: Building and site improvement materials resulting from demolition or selective demolition operations.

C. Disposal: Removal off-site of demolition and construction waste and subsequent sale, recycling, reuse, or deposit in landfill or incinerator acceptable to authorities having jurisdiction.

1.3 INFORMATIONAL SUBMITTALS

A. Landfill and Incinerator Disposal Records: Indicate receipt and acceptance of waste by landfills and incinerator facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.

1.4 WASTE MANAGEMENT PLAN

A. General: Develop a waste management plan according to ASTM E 1609 and requirements in this Section. Plan shall consist of waste identification, and cost/revenue analysis. Distinguish between demolition and construction waste. Indicate quantities by weight or volume, but use same units of measure throughout waste management plan.

   1. Disposed Materials: Indicate how and where materials will be disposed of. Include name, address, and telephone number of each landfill and incinerator facility.

PRODUCTS (Not Used)

PART 2 - EXECUTION

2.1 PLAN IMPLEMENTATION

A. General: Implement approved waste management plan. Provide handling, containers, storage, signage, transportation, and other items as required to implement waste management plan during the entire duration of the Contract.

B. Site Access and Temporary Controls: Conduct waste management operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
   1. Comply with Section 015000 "Temporary Facilities and Controls" for controlling dust and dirt, environmental protection, and noise control.

2.2 DISPOSAL OF WASTE

A. General: Remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.

   1. Except as otherwise specified, do not allow waste materials that are to be disposed of accumulate on-site.
   2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

B. Burning: Do not burn waste materials.

C. Disposal: Remove waste materials and dispose of at designated spoil areas on Owner's property.

D. Disposal: Remove waste materials from Owner's property and legally dispose of them.

END OF SECTION 017419

SECTION 017700 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:

1. Substantial Completion procedures.
2. Final completion procedures.
3. Warranties.
4. Final cleaning.
5. Repair of the Work.

B. Related Requirements:

1. Section 013233 "Photographic Documentation" for submitting final completion construction photographic documentation.
2. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.
3. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
4. Section 017900 "Demonstration and Training" for requirements for instructing Owner's personnel.

1.2 ACTION SUBMITTALS

A. Product Data: For cleaning agents.

B. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.

C. Certified List of Incomplete Items: Final submittal at Final Completion.

1.3 CLOSEOUT SUBMITTALS

A. Certificates of Release: From authorities having jurisdiction.

B. Certificate of Insurance: For continuing coverage.

C. Field Report: For pest control inspection.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Schedule of Maintenance Material Items: For maintenance material submittal items specified in other Sections.

1.5 SUBSTANTIAL COMPLETION PROCEDURES

A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.

B. Submittals Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.

1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
2. Submit closeout submittals specified in other Division 01 Sections, including project record documents, operation and maintenance manuals, final completion construction photographic documentation, damage or settlement surveys, property surveys, and similar final record information.
3. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
4. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Architect or Construction Manager. Label with manufacturer's name and model number where applicable.

    a. Schedule of Maintenance Material Items: Prepare and submit schedule of maintenance material submittal items, including name and quantity of each item and name and number of related Specification Section. Obtain Architect's or Construction Manager's signature for receipt of submittals.

5. Submit test/adjust/balance records.
6. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.

C. Procedures Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.

1. Advise Owner of pending insurance changeover requirements.
2. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
3. Complete startup and testing of systems and equipment.
4. Perform preventive maintenance on equipment used prior to Substantial Completion.
5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems. Submit demonstration and training video recordings specified in Section 017900 "Demonstration and Training."
6. Advise Owner of changeover in heat and other utilities.
7. Participate with Owner in conducting inspection and walkthrough with local emergency responders.
8. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.

9. Complete final cleaning requirements, including touchup painting.
10. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.

D. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 10 days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Architect and Construction Manager will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.

1. Re-inspection: Request re-inspection when the Work identified in previous inspections as incomplete is completed or corrected.
2. Results of completed inspection will form the basis of requirements for final completion.

1.6 FINAL COMPLETION PROCEDURES

A. Preliminary Procedures: Before requesting final inspection for determining final completion, complete the following:

1. Submit a final Application for Payment according to Section 012900 "Payment Procedures."
2. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
4. Submit pest-control final inspection report and warranty.
5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems.

B. Inspection: Submit a written request for final inspection to determine acceptance. On receipt of request, Architect and Construction Manager will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

1. Re-inspection: Request re-inspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.7 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction. Use CSI Form 14.1A.

1. Organize list of spaces in sequential order, starting with exterior areas first and proceeding from lowest floor to highest floor.
2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
3. Submit list of incomplete items in the following format:

    a. PDF electronic file. Architect[, through Construction Manager,] will return annotated copy.

1.8 SUBMITTAL OF PROJECT WARRANTIES

A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated, or when delay in submittal of warranties might limit Owner's rights under warranty.

B. Organize warranty documents into an orderly sequence based on the table of contents of the Project Manual.

1. Bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
4. Warranty Electronic File: Scan warranties and bonds and assemble complete warranty and bond submittal package into a single indexed electronic PDF file with links enabling navigation to each item. Provide bookmarked table of contents at beginning of document.

C. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

1. Use cleaning products that comply with Green Seal's GS-37, or if GS-37 is not applicable, use products that comply with the California Code of Regulations maximum allowable VOC levels.

PART 3 - EXECUTION

3.1 FINAL CLEANING

A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.

B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.

1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:

a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
c. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
d. Remove tools, construction equipment, machinery, and surplus material from Project site.
e. Remove snow and ice to provide safe access to building.
f. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
g. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
h. Sweep concrete floors broom clean in unoccupied spaces.
i. Vacuum carpet and similar soft surfaces, removing debris and excess nap; clean according to manufacturer's recommendations if visible soil or stains remain.
j. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Replace chipped or broken glass and other damaged transparent materials. Polish mirrors and glass, taking care not to scratch surfaces.
k. Remove labels that are not permanent.
l. Wipe surfaces of mechanical and electrical equipment, elevator equipment, and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
m. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
n. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
o. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency.
p. Leave Project clean and ready for occupancy.

C. Pest Control: Comply with pest control requirements in Section 015000 "Temporary Facilities and Controls." Prepare written report.

3.2 REPAIR OF THE WORK

A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.

B. Repair or remove and replace defective construction. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Remove and replace operating components that cannot be repaired. Restore damaged construction and permanent facilities used during construction to specified condition.

1. Remove and replace chipped, scratched, and broken glass, reflective surfaces, and other damaged transparent materials.
2. Touch up and otherwise repair and restore marred or exposed finishes and surfaces. Replace finishes and surfaces that that already show evidence of repair or restoration.

    a. Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates. Remove paint applied to required labels and identification.

3. Replace parts subject to operating conditions during construction that may impede operation or reduce longevity.
4. Replace burned-out bulbs, bulbs noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.

END OF SECTION 017700

SECTION 017823 - OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:

1. Operation and maintenance documentation directory.
2. Emergency manuals.
3. Operation manuals for systems, subsystems, and equipment.
4. Product maintenance manuals.
5. Systems and equipment maintenance manuals.

1.2 CLOSEOUT SUBMITTALS

A. Manual Content: Operations and maintenance manual content is specified in individual Specification Sections to be reviewed at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.

1. Architect will comment on whether content of operations and maintenance submittals are acceptable.
2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.

B. Format: Submit operations and maintenance manuals in the following format:

1. Three paper copies. Include a complete operation and maintenance directory. Enclose title pages and directories in clear plastic sleeves. Architect, through Construction Manager, will return two copies.

C. Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion and at least 15 days before commencing demonstration and training. Architect will return copy with comments.

1. Correct or revise each manual to comply with Architect's comments. Submit copies of each corrected manual within 15 days of receipt of Architect's comments and prior to commencing demonstration and training.

PART 2 - PRODUCTS

2.1 REQUIREMENTS FOR EMERGENCY, OPERATION, AND MAINTENANCE MANUALS

A. Directory: Prepare a single, comprehensive directory of emergency, operation, and maintenance data and materials, listing items and their location to facilitate ready access to desired information.

B. Organization: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain the following materials, in the order listed:

1. Title page.
2. Table of contents.
3. Manual contents.

C. Title Page: Include the following information:

1. Subject matter included in manual.
2. Name and address of Project.
3. Name and address of Owner.
4. Date of submittal.
5. Name and contact information for Contractor.
6. Name and contact information for Construction Manager.
7. Name and contact information for Architect.
8. Name and contact information for Commissioning Authority.
9. Names and contact information for major consultants to the Architect that designed the systems contained in the manuals.
10. Cross-reference to related systems in other operation and maintenance manuals.

D. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.

E. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.

F. Manuals, Paper Copy: Submit manuals in the form of hard copy, bound and labeled volumes.

1. Binders: Heavy-duty, three-ring, vinyl-covered, loose-leaf, post-type binders, in thickness necessary to accommodate contents, sized to hold 8-1/2-by-11-inch paper; with clear plastic sleeve on spine to hold label describing contents and with pockets inside covers to hold folded oversize sheets.

a. Identify each binder on front and spine, with printed title "OPERATION AND MAINTENANCE MANUAL," Project title or name and subject matter of contents, and indicate Specification Section number on bottom of spine. Indicate volume number for multiple-volume sets.

2. Dividers: Heavy-paper dividers with plastic-covered tabs for each section of the manual. Mark each tab to indicate contents. Include typed list of products and major components of equipment included in the section on each divider, cross-referenced to Specification Section number and title of Project Manual.
3. Protective Plastic Sleeves: Transparent plastic sleeves designed to enclose diagnostic software storage media for computerized electronic equipment.
4. Drawings: Attach reinforced, punched binder tabs on drawings and bind with text.

    a. If oversize drawings are necessary, fold drawings to same size as text pages and use as foldouts.
    b. If drawings are too large to be used as foldouts, fold and place drawings in labeled envelopes and bind envelopes in rear of manual. At appropriate locations in manual, insert typewritten pages indicating drawing titles, descriptions of contents, and drawing locations.

2.2 EMERGENCY MANUALS

A. Content: Organize manual into a separate section for each of the following:

1. Type of emergency.
2. Emergency instructions.
3. Emergency procedures.

B. Type of Emergency: Where applicable for each type of emergency indicated below, include instructions and procedures for each system, subsystem, piece of equipment, and component:

1. Fire.
2. Flood.
3. Gas leak.
4. Water leak.
5. Power failure.
6. Water outage.
7. System, subsystem, or equipment failure.
8. Chemical release or spill.

C. Emergency Instructions: Describe and explain warnings, trouble indications, error messages, and similar codes and signals. Include responsibilities of Owner's operating personnel for notification of Installer, supplier, and manufacturer to maintain warranties.

D. Emergency Procedures: Include the following, as applicable:

1. Instructions on stopping.
2. Shutdown instructions for each type of emergency.
3. Operating instructions for conditions outside normal operating limits.
4. Required sequences for electric or electronic systems.
5. Special operating instructions and procedures.

2.3 OPERATION MANUALS

A. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:

1. System, subsystem, and equipment descriptions. Use designations for systems and equipment indicated on Contract Documents.
2. Performance and design criteria if Contractor is delegated design responsibility.
3. Operating standards.
4. Operating procedures.
5. Operating logs.
6. Wiring diagrams.
7. Control diagrams.
8. Piped system diagrams.
9. Precautions against improper use.
10. License requirements including inspection and renewal dates.

B. Descriptions: Include the following:

1. Product name and model number. Use designations for products indicated on Contract Documents.
2. Manufacturer's name.
3. Equipment identification with serial number of each component.
4. Equipment function.
5. Operating characteristics.
6. Limiting conditions.
7. Performance curves.
8. Engineering data and tests.
9. Complete nomenclature and number of replacement parts.

C. Operating Procedures: Include the following, as applicable:

1. Startup procedures.
2. Equipment or system break-in procedures.
3. Routine and normal operating instructions.
4. Regulation and control procedures.
5. Instructions on stopping.
6. Normal shutdown instructions.
7. Seasonal and weekend operating instructions.
8. Required sequences for electric or electronic systems.
9. Special operating instructions and procedures.

D. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.

E. Piped Systems: Diagram piping as installed, and identify color-coding where required for identification.

2.4 PRODUCT MAINTENANCE MANUALS

A. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.

B. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual.

C. Product Information: Include the following, as applicable:

1. Product name and model number.
2. Manufacturer's name.
3. Color, pattern, and texture.
4. Material and chemical composition.
5. Reordering information for specially manufactured products.

D. Maintenance Procedures: Include manufacturer's written recommendations and the following:

1. Inspection procedures.
2. Types of cleaning agents to be used and methods of cleaning.
3. List of cleaning agents and methods of cleaning detrimental to product.
4. Schedule for routine cleaning and maintenance.
5. Repair instructions.

E. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.

F. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

2.5 SYSTEMS AND EQUIPMENT MAINTENANCE MANUALS

A. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranty and bond information, as described below.

B. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual.

C. Manufacturers' Maintenance Documentation: Manufacturers' maintenance documentation including the following information for each component part or piece of equipment:

1. Standard maintenance instructions and bulletins.

2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
3. Identification and nomenclature of parts and components.
4. List of items recommended to be stocked as spare parts.

D. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:

1. Test and inspection instructions.
2. Troubleshooting guide.
3. Precautions against improper maintenance.
4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
5. Aligning, adjusting, and checking instructions.
6. Demonstration and training video recording, if available.

E. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.

F. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.

G. Maintenance Service Contracts: Include copies of maintenance agreements with name and telephone number of service agent.

H. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

PART 3 - EXECUTION

3.1 MANUAL PREPARATION

A. Emergency Manual: Assemble a complete set of emergency information indicating procedures for use by emergency personnel and by Owner's operating personnel for types of emergencies indicated.

B. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.

C. Operation and Maintenance Manuals: Assemble a complete set of operation and maintenance data indicating operation and maintenance of each system, subsystem, and piece of equipment not part of a system.

D. Manufacturers' Data: Where manuals contain manufacturers' standard printed data, include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.

E. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in record Drawings to ensure correct illustration of completed installation.

1. Do not use original project record documents as part of operation and maintenance manuals.

F. Comply with Section 017700 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

END OF SECTION 017823

SECTION 017839 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for project record documents, including the following:

1. Record Drawings.
2. Record Specifications.
3. Record Product Data.

B. Related Requirements:

1. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.

1.2 CLOSEOUT SUBMITTALS

A. Record Drawings: Comply with the following:

1. Number of Copies: Submit one set of marked-up record prints.
2. Number of Copies: Submit copies of record Drawings as follows:

a. Initial Submittal:

1) Submit one paper-copy set of marked-up record prints.
2) Submit PDF electronic files of scanned record prints and one set of file prints.
3) Submit record digital data files and one set of plots.
4) Architect will indicate whether general scope of changes, additional information recorded, and quality of drafting are acceptable.

b. Final Submittal:

1) Submit three paper-copy sets of marked-up record prints.
2) Submit PDF electronic files of scanned record prints and three sets of prints.
3) Print each drawing, whether or not changes and additional information were recorded.

B. Record Specifications: Submit one paper copy and annotated PDF electronic files of Project's Specifications, including addenda and contract modifications.

C. Record Product Data: Submit one paper copy and annotated PDF electronic files and directories of each submittal.

PART 2 - PRODUCTS

2.1 RECORD DRAWINGS

A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised Drawings as modifications are issued.

1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.

a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
b. Record data as soon as possible after obtaining it.
c. Record and check the markup before enclosing concealed installations.

2. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
3. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
4. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

B. Record Digital Data Files: Immediately before inspection for Certificate of Substantial Completion, review marked-up record prints with Construction Manager. When authorized, prepare a full set of corrected digital data files of the Contract Drawings, as follows:

1. Format: Same digital data software program, version, and operating system as the original Contract Drawings.
2. Incorporate changes and additional information previously marked on record prints. Delete, redraw, and add details and notations where applicable.
3. Refer instances of uncertainty to Architect through Construction Manager for resolution.
4. Architect will furnish Contractor one set of digital data files of the Contract Drawings for use in recording information.

C. Format: Identify and date each record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.

1. Record Prints: Organize record prints and newly prepared record Drawings into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
2. Format: Annotated PDF electronic file with comment function enabled.
3. Record Digital Data Files: Organize digital data information into separate electronic files that correspond to each sheet of the Contract Drawings. Name each file with the sheet identification. Include identification in each digital data file.
4. Identification: As follows:

a. Project name.

b. Date.
c. Designation "PROJECT RECORD DRAWINGS."
d. Name of Architect and Construction Manager.
e. Name of Contractor.

2.2 RECORD SPECIFICATIONS

A. Preparation: Mark Specifications to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.

1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
3. Record the name of manufacturer, supplier, Installer, and other information necessary to provide a record of selections made.
4. Note related Change Orders[, record Product Data,] and record Drawings where applicable.

B. Format: Submit record Specifications as annotated PDF electronic file or paper copy.

2.3 RECORD PRODUCT DATA

A. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.

1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
3. Note related Change Orders[, record Specifications,] and record Drawings where applicable.

B. Format: Submit record Product Data as annotated PDF electronic file or paper copy.

2.4 MISCELLANEOUS RECORD SUBMITTALS

A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.

B. Format: Submit miscellaneous record submittals as [PDF electronic file or paper copy.

PART 3 - EXECUTION

3.1 RECORDING AND MAINTENANCE

A. Recording: Maintain one copy of each submittal during the construction period for project record document purposes. Post changes and revisions to project record documents as they occur; do not wait until end of Project.

B. Maintenance of Record Documents and Samples: Store record documents and Samples in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Architect's[and Construction Manager's] reference during normal working hours.

END OF SECTION 017839

SECTION 017900 - DEMONSTRATION AND TRAINING

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:

1. Demonstration of operation of systems, subsystems, and equipment.
2. Training in operation and maintenance of systems, subsystems, and equipment.
3. Demonstration and training video recordings.

1.2 INFORMATIONAL SUBMITTALS

A. Instruction Program: Submit outline of instructional program for demonstration and training, including a list of training modules and a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.

1. Indicate proposed training modules using manufacturer-produced demonstration and training video recordings for systems, equipment, and products in lieu of video recording of live instructional module.

1.3 CLOSEOUT SUBMITTALS

A. Demonstration and Training Video Recordings: Submit two copies within seven days of end of each training module.

1. At completion of training, submit complete training manual(s) for Owner's use in PDF electronic file format on compact disc].

1.4 QUALITY ASSURANCE

A. Facilitator Qualifications: A firm or individual experienced in training or educating maintenance personnel in a training program similar in content and extent to that indicated for this Project, and whose work has resulted in training or education with a record of successful learning performance.

B. Instructor Qualifications: A factory-authorized service representative, complying with requirements in Section 014000 "Quality Requirements," experienced in operation and maintenance procedures and training.

C. Pre-instruction Conference: Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." Review methods and procedures related to demonstration and training.

1.5 COORDINATION

A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations and to ensure availability of Owner's personnel.

B. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data has been reviewed and approved by Architect.

PART 2 - PRODUCTS

2.1 INSTRUCTION PROGRAM

A. Program Structure: Develop an instruction program that includes individual training modules for each system and for equipment not part of a system, as required by individual Specification Sections.

B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following as applicable to the system, equipment, or component:

1. Basis of System Design, Operational Requirements, and Criteria: Include the following:

   a. System, subsystem, and equipment descriptions.
   b. Performance and design criteria if Contractor is delegated design responsibility.
   c. Operating standards.
   d. Regulatory requirements.
   e. Equipment function.
   f. Operating characteristics.
   g. Limiting conditions.
   h. Performance curves.

2. Documentation: Review the following items in detail:

   a. Emergency manuals.
   b. Operations manuals.
   c. Maintenance manuals.
   d. Project record documents.
   e. Identification systems.
   f. Warranties and bonds.
   g. Maintenance service agreements and similar continuing commitments.

3. Emergencies: Include the following, as applicable:

   a. Instructions on meaning of warnings, trouble indications, and error messages.
   b. Instructions on stopping.
   c. Shutdown instructions for each type of emergency.
   d. Operating instructions for conditions outside of normal operating limits.

e. Sequences for electric or electronic systems.
f. Special operating instructions and procedures.

4. Operations: Include the following, as applicable:

a. Startup procedures.
b. Equipment or system break-in procedures.
c. Routine and normal operating instructions.
d. Regulation and control procedures.
e. Control sequences.
f. Safety procedures.
g. Instructions on stopping.
h. Normal shutdown instructions.
i. Operating procedures for emergencies.
j. Operating procedures for system, subsystem, or equipment failure.
k. Seasonal and weekend operating instructions.
l. Required sequences for electric or electronic systems.
m. Special operating instructions and procedures.

5. Adjustments: Include the following:

a. Alignments.
b. Checking adjustments.
c. Noise and vibration adjustments.
d. Economy and efficiency adjustments.

6. Troubleshooting: Include the following:

a. Diagnostic instructions.
b. Test and inspection procedures.

7. Maintenance: Include the following:

a. Inspection procedures.
b. Types of cleaning agents to be used and methods of cleaning.
c. List of cleaning agents and methods of cleaning detrimental to product.
d. Procedures for routine cleaning
e. Procedures for preventive maintenance.
f. Procedures for routine maintenance.
g. Instruction on use of special tools.

8. Repairs: Include the following:

a. Diagnosis instructions.
b. Repair instructions.
c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
d. Instructions for identifying parts and components.
e. Review of spare parts needed for operation and maintenance.

PART 3 - EXECUTION

3.1 PREPARATION

A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a training manual organized in coordination with requirements in Section 017823 "Operation and Maintenance Data."

3.2 INSTRUCTION

A. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Owner for number of participants, instruction times, and location.

B. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.

1. Architect will furnish an instructor to describe basis of system design, operational requirements, criteria, and regulatory requirements.
2. Owner will furnish an instructor to describe Owner's operational philosophy.
3. Owner will furnish Contractor with names and positions of participants.

C. Scheduling: Provide instruction at mutually agreed on times. For equipment that requires seasonal operation, provide similar instruction at start of each season.

1. Schedule training with Owner, through Construction Manager, with at least seven days' advance notice.

D. Training Location and Reference Material: Conduct training on-site in the completed and fully operational facility using the actual equipment in-place. Conduct training using final operation and maintenance data submittals.

E. Evaluation: At conclusion of each training module, assess and document each participant's mastery of module by use of a demonstration performance-based test.

3.3 DEMONSTRATION AND TRAINING VIDEO RECORDINGS

A. General: Engage a qualified commercial videographer to record demonstration and training video recordings. Record each training module separately. Include classroom instructions and demonstrations, board diagrams, and other visual aids, but not student practice.

1. At beginning of each training module, record each chart containing learning objective and lesson outline.

B. Video Recording Format: Provide high-quality color video recordings with menu navigation in format acceptable to Architect.

C. Narration: Describe scenes on video recording by audio narration by microphone while dubbing audio narration off-site after video recording is recorded. Include description of items being viewed.

D. Pre-produced Video Recordings: Provide video recordings used as a component of training modules in same format as recordings of live training.

END OF SECTION 017900

SECTION 024000 - GRADING

PART 1 - GENERAL

This section includes all grading work required for the construction of the driveway and parking improvements shown on the Drawings within the project area. Grading operations shall include rough and finish grading as indicated on the Drawings to provide adequate drainage for the project area. Grading operations shall also include rough and finish grading of ditches to provide positive drainage from pipe invert to pipe invert.

1.1. Related Work Specified Elsewhere

A. Excavating, Backfilling and Compacting for Pavement – Section 02300 “Earthwork”.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 Site shall be graded to meet existing contours on adjacent properties to the construction site so as to provide positive drainage into existing catch basins or other drainage structures.

3.2 Finish grading shall include excavating, stockpiling, and placing approved native material as required to cover entire site to an elevation appropriate for the placing of sod or seed as required elsewhere in these specifications and as shown on the drawings.

3.3.0 Ditch Bottom Grading

1. Grading shall include excavating, and placing approved native material as required to obtain positive drainage from pipe invert to pipe invert. The ditch bottom shall be free of voids and pockets.

2. Excess excavated material from ditches shall become the property of the Contractor and shall be disposed of off site, at the Contractor’s expense, all in accordance with local codes and ordinances governing locations and safety laws.

3. Contractor shall not reshape ditches side slopes, except in cases of roadway realignment encroaching on the existing ditch alignment, as approved by the Engineer. Ditches requiring reshaping shall have maximum side slopes of 1 vertical on 3 horizontal. In no case shall the ditches encroach upon private property.

END OF SECTION

SECTION 024100 - DEMOLITION

PART 1 GENERAL

1.1 SUMMARY

A. Scope of Work:
1. Section includes removal and disposal and/or salvage of pavement, minor structures, utilities and other miscellaneous existing features affecting the project as identified in the Drawings.
2. The Contractor shall furnish all materials, tools, equipment, devices, appurtenances, facilities and services as required for performing the demolition work.

1.2 QUALITY ASSURANCE

A. Conform to applicable code for demolition of structures, safety of adjacent structures, dust control, and disposal.

B. Conform to applicable State of Louisiana code requirements for procedures when hazardous or contaminated materials are discovered.

C. Obtain required permits from authorities having jurisdiction.

1.3 SITE CONDITIONS

A. Protection of Persons and Property:
1. Erect and maintain temporary bracing, shoring, lights, barricades, signs and other measures as necessary to protect the public, workers and adjoining property from damage from demolition work.
2. Open depressions and excavations occurring as part of this work shall be barricaded and posted with warning lights when accessible through adjacent property or through public access. Operate warning lights during hours from dusk to dawn each day and as otherwise required.
3. Protect utilities, pavements and facilities from damage caused by settlement, lateral movement, undermining, washout and other hazards created by demolition operations.

B. Protection of Utilities:
1. Protect active sewer, water, gas, electric and other utilities as well as drainage and irrigation lines indicated, or when not indicated, found or otherwise made known to the Contractor before or during demolition work. If utility is damaged, immediately notify the utility owner to schedule corrective action.
2. Arrange with and perform work required by Owner, utility companies and municipal departments for discontinuance or interruption of utility services due to demolition work.

C. Unknown Conditions:

1. The Drawings and related documents may not represent all surface conditions at the site and adjoining areas. The known surface conditions are as indicated, and shall be compared with actual conditions before commencement of work.
2. Existing utilities and drainage systems below grade are located from existing documents and from surface utilities such as manholes, valve boxes, area drains and other surface fixtures.
3. If existing active services encountered are not indicated or otherwise made known to the Contractor and interfere with the permanent facilities under construction, notify the Engineer in writing, requesting instructions on their disposition. Take immediate steps to ensure that the service provide is not interrupted.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

3.1 PREPARATION

A. Call Louisiana One Call at 1-800-272-3020 not less than three working days before performing Work.
   1. Request underground utilities to be located and marked within and surrounding construction areas.

B. Notify affected utility companies before starting work and comply with utility's requirements.

C. Erect, and maintain temporary barriers and security devices , including warning signs and lights, and similar measures, for protection of the public and existing improvements indicated to remain.

3.2 DEMOLITION REQUIREMENTS

A. Use of explosives is not permitted.

B. Conduct demolition to minimize interference with adjacent facilities.

C. Cease operations immediately when adjacent facilities appear to be in danger. Notify Engineer and do not resume operations until directed.

D. Conduct operations with minimum interference to public or private accesses to occupied adjacent facilities.

3.3 DEMOLITION

A. Perform demolition of miscellaneous items as indicated in the Drawings.

B. Empty underground wetwells or tanks located within demolition area.

C. Maintain flow of existing sewers through the project site at all times.

D. Remove underground wetwell, manholes, tanks, components, and piping from site as indicated in the drawings.

E. Remove materials to be re-installed or retained in manner to prevent damage.

F. Fill voids, compact and rough grade areas affected by demolition to maintain site grades and contours. Fill material used to fill voids shall be select fill and shall be compacted to 95% Standard Proctor Density.

G. Continuously clean-up and remove demolished materials from site. Do not allow materials to accumulate on site.

H. Do not burn or bury materials on site. Leave site in clean condition.

END OF SECTION

SECTION 024119 - SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Demolition and removal of selected portions of building or structure.
2. Demolition and removal of selected site elements.
3. Salvage of existing items to be reused or recycled.

1.2 MATERIALS OWNERSHIP

A. Unless otherwise indicated, demolition waste becomes property of Contractor.

B. Historic items, relics, antiques, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, and other items of interest or value to Owner that may be uncovered during demolition remain the property of Owner.

1. Carefully salvage in a manner to prevent damage and promptly return to Owner.

1.3 PREINSTALLATION MEETINGS

A. Predemolition Conference: Conduct conference at Project site.

1.4 INFORMATIONAL SUBMITTALS

A. Schedule of selective demolition activities with starting and ending dates for each activity.

B. Predemolition photographs or video.

C. Statement of Refrigerant Recovery: Signed by refrigerant recovery technician.

1.5 CLOSEOUT SUBMITTALS

A. Inventory of items that have been removed and salvaged.

1.6 QUALITY ASSURANCE

A. Refrigerant Recovery Technician Qualifications: Certified by an EPA-approved certification program.

1.7 FIELD CONDITIONS

A. Owner will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.

B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.

C. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.

D. Hazardous Materials: Refer to Section 011000 “Summary” for information, regarding hazardous materials, which will be present during construction.

1. If suspected hazardous materials, beyond those indicated, by said Section 011000, are encountered, do not disturb; immediately notify Architect and Owner. Hazardous materials will be removed by Owner under a separate contract.

E. Storage or sale of removed items or materials on-site is not permitted.

F. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.

1. Maintain fire-protection facilities in service during selective demolition operations.

G. Arrange selective demolition schedule so as not to interfere with Owner's operations.

1.8 WARRANTY

A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials and using approved contractors so as not to void existing warranties.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.

B. Standards: Comply with ASSE A10.6 and NFPA 241.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify that utilities have been disconnected and capped before starting selective demolition operations.

B. Inventory and record the condition of items to be removed and salvaged.

3.2 PREPARATION

A. Refrigerant: Before starting demolition, remove refrigerant from mechanical equipment according to 40 CFR 82 and regulations of authorities having jurisdiction.

3.3 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage.

B. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off utility services and mechanical/electrical systems serving areas to be selectively demolished.

1. Owner will arrange to shut off indicated services/systems when requested by Contractor.
2. Arrange to shut off utilities with utility companies.
3. If services/systems are required to be removed, relocated, or abandoned, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
4. Disconnect, demolish, and remove fire-suppression systems, plumbing, and HVAC systems, equipment, and components indicated on Drawings to be removed.

    a. Piping to Be Removed: Remove portion of piping indicated to be removed and cap or plug remaining piping with same or compatible piping material.
    b. Piping to Be Abandoned in Place: Drain piping and cap or plug piping with same or compatible piping material and leave in place.
    c. Equipment to Be Removed: Disconnect and cap services and remove equipment.
    d. Equipment to Be Removed and Reinstalled: Disconnect and cap services and remove, clean, and store equipment; when appropriate, reinstall, reconnect, and make equipment operational.
    e. Equipment to Be Removed and Salvaged: Disconnect and cap services and remove equipment and deliver to Owner.
    f. Ducts to Be Removed: Remove portion of ducts indicated to be removed and plug remaining ducts with same or compatible ductwork material.
    g. Ducts to Be Abandoned in Place: Cap or plug ducts with same or compatible ductwork material and leave in place.

3.4 PROTECTION

A. Temporary Protection: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.

B. Temporary Shoring: Design, provide, and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.

C. Remove temporary barricades and protections where hazards no longer exist.

3.5 SELECTIVE DEMOLITION

A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:

1. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping. Temporarily cover openings to remain.
2. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
3. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
4. Maintain fire watch during and for at least <Insert number> hours after flame-cutting operations.
5. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
6. Dispose of demolished items and materials promptly. Comply with requirements in Section 017419 "Construction Waste Management and Disposal."

B. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.

C. Removed and Reinstalled Items:

1. Clean and repair items to functional condition adequate for intended reuse.
2. Pack or crate items after cleaning and repairing. Identify contents of containers.
3. Protect items from damage during transport and storage.
4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.

D. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable,

protected storage location during selective demolition and cleaned and reinstalled in their original locations after selective demolition operations are complete.

3.6 CLEANING

A. Remove demolition waste materials from Project site and dispose of them in an EPA-approved construction and demolition waste landfill acceptable to authorities having jurisdiction and recycle or dispose of them according to Section 017419 "Construction Waste Management and Disposal."

1. Do not allow demolished materials to accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
4. Comply with requirements specified in Section 017419 "Construction Waste Management and Disposal."

B. Burning: Do not burn demolished materials.

C. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION 024119

SECTION 027000 - CONCRETE WORK

PART 1 GENERAL

1.01 SUMMARY

A. This section includes the following:

1. This section complements Standard Specifications, where applicable, for concrete work associated with building construction. Whenever reference is made to “Standard Specifications”, such reference is to the 2006 Edition or latest revision thereof of “Standard Specifications for Roads and Bridges”, by the Office of Highways, Department of Transportation and Development, State of Louisiana.

1.02 SUBMITTALS

A. Product Data: Submit data for proprietary materials and items, including reinforcement and forming accessories, admixtures, patching compounds, waterstops, joint systems, curing compounds, dry-shake finish materials, and others as requested by Architect.

B. Shop Drawings; Reinforcement: Submit shop drawings for fabrication, bending, and placement of concrete reinforcement. Comply with ACI 315 "Manual of Standard Practice for Detailing Reinforced Concrete Structures" showing bar schedules, stirrup spacing, diagrams of bent bars, and arrangement of concrete reinforcement. Include special reinforcement required for openings through concrete structures.

C. Samples: Submit samples of materials as specified and as otherwise requested by Architect, including names, sources, and descriptions.

D. Laboratory Test Reports: Submit laboratory test reports for concrete materials and mix design test as specified.

1.03 QUALITY ASSURANCE

A. Codes and Standards: Comply with provisions of following codes, specifications, and standards, except where more stringent requirements are shown or specified:

1. ACI 301 "Specifications for Structural Concrete for Buildings".

2. ACI 318 "Building Code Requirements for Reinforced Concrete".

3. Concrete Reinforcing Steel Institute (CRSI), "Manual of Standard Practice".

B. Concrete Testing Service: Contractor to engage and pay a testing laboratory acceptable to Architect to perform material evaluation tests and to design concrete mixes.

C. Materials and installed work may require testing and retesting, as directed by Architect, at anytime during progress of work. Allow free access to material stockpiles and facilities. Retesting of rejected materials for installed work shall be done at Contractor's expense.

PART 2 PRODUCTS

2.01 FORM MATERIALS

A. Forms for Exposed Finish Concrete: Unless otherwise indicated, construct formwork for exposed concrete surfaces with plywood, metal, metal-framed plywood faced, or other acceptable panel-type materials, to provide continuous, straight, smooth, exposed surfaces. Furnish in largest practicable sizes to minimize number of joints and to conform to joint system shown on drawings. Provide form material with sufficient thickness to withstand pressure of newly-placed concrete without bow or deflection.

1. Use overlaid plywood complying with U.S. Product Standard PS-1 "A-C or B-B High Density Overlaid Concrete Form", Class I.

B. Forms for Unexposed Finish Concrete: Form concrete surfaces which will be unexposed in finished structure with plywood, lumber, metal, or other acceptable material. Provide lumber dressed on at least 2 edges and one side for tight fit.

C. Forms for Textured Finish Concrete: Form textured finish concrete surfaces with units of face design, size, arrangement, and configuration as shown on drawings or as required to match Architect's control sample. Provide solid backing and form supports to ensure stability of textured form liners.

D. Forms for Cylindrical Columns and Supports: Form round-section members with metal, fiberglass reinforced plastic, or paper or fiber tubes. Construct paper or fiber tubes of laminated plies using water-resistant adhesive with wax-impregnated exterior for weather and moisture protection. Provide units with sufficient wall thickness to resist loads imposed by wet concrete without deformation.

E. Form Coatings: Provide commercial formulation form-coating compounds that will not bond with, stain, nor adversely affect concrete surfaces, and will not impair subsequent treatments of concrete surfaces.

2.02 REINFORCING MATERIALS

A. Reinforcing Bars: ASTM A 615, Grade 60, deformed.

B. Steel Wire: ASTM A 82, plain, cold-drawn steel.

C. Welded Wire Fabric: ASTM A 185, welded steel wire fabric.

D. Welded Deformed Steel Wire Fabric: ASTM A 497.

E. Supports for Reinforcement: Provide supports for reinforcement including bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars and welded wire fabric in place. Use wire bar type supports complying with CRSI specifications, unless otherwise acceptable.

1. For slabs-on-grade, use supports with sand plates or horizontal runners where base material will not support chair legs.

2. For exposed-to-view concrete surfaces, where legs of supports are in contact with forms, provide supports with legs which are plastic protected (CRSI, Class 1) or stainless steel protected (CRSI, Class 2).

2.03 CONCRETE MATERIALS

A. Portland Cement: ASTM C 150, Type I, unless otherwise acceptable to Architect.

B. Use one brand of cement throughout project, unless otherwise acceptable to Architect.

C. Fly Ash or Slag: Not permitted.

D. Normal Weight Aggregates: ASTM C 33, and as herein specified. Provide aggregates from a single source for exposed concrete.

1. For exterior exposed surfaces, do not use fine or coarse aggregates containing spalling-causing deleterious substances.

2. Local aggregates not complying with ASTM C 33 but which have shown by special test or actual service to produce concrete of adequate strength and durability may be used when acceptable to Architect.

E. Water: Drinkable.

F. Air-Entraining Admixture: ASTM C 260 - Coordinate use with Ashford Formula.

1. Available Products: Subject to compliance with requirements, products which may be incorporated in the work include, but are not limited to, the following:

a. "Sika Aer"; Sika Corp.

b. "MB-VR or MB-AE"; Master Builders.

c. "Darex AEA"; W. R. Grace.

d. "Edoco 2001 or 2002"; Edoco Technical Products.

G. Water-Reducing Admixture: ASTM C 494, Type A, and containing not more than 0.1 percent chloride ions.

1. Available Products: Subject to compliance with requirements, products which may be incorporated in the work include, but are not limited to, the following:

a. "Eucon WR-75"; Euclid Chemical Co.

b. "Pozzolith 344"; Master Builders.

c. "Plastocrete 160"; Sika Chemical Corp.

d. "Chemtard"; Chem-Masters Corp.

H. High-Range Water-Reducing Admixture (Super Plasticizer): ASTM C 494, Type F or Type G and containing not more than 0.1 percent chloride ions.

1. Available Products: Subject to compliance with requirements, products which may be incorporated in the work include, but are not limited to, the following:
    a. "WRDA 19"; W. R. Grace.
    b. "PSP"; Protex Industries Inc.
    c. "Super P"; Anti-Hydro.
    d. "Sikament"; Sika Chemical Corp.
    e. "Mighty 150"; ICI Americas Corp.
    f. "Eucon 37"; Euclid Chemical Co.
    g. "PSI Super"; Gifford-Hill.
    h. "Pozzolith 400"; Master Builders.

I. Water-Reducing, Non-Chloride Accelerator Admixture: ASTM C 494, Type E, and containing not more than 0.1 percent chloride ions.

1. Available Products: Subject to compliance with requirements, products which may be incorporated in the work include, but are not limited to, the following:
    a. "Accelquard 80"; Euclid Chemical Co.
    b. "Pozzolith 500"; Master Builders.

J. Water-Reducing, Retarding Admixture: ASTM C 494, Type D, and containing not more than 0.1 percent chloride ions.

1. Available Products: Subject to compliance with requirements, products which may be incorporated in the work include, but are not limited to, the following:
    a. "Edoco 20006"; Edoco Technical Products.
    b. "Pozzolith 300-R"; Master Builders.
    c. "Eucon Retarder 75"; Euclid Chemical Co.
    d. "Daratard"; W.R. Grace.
    e. "Plastiment"; Sika Chemical Co.

K. Calcium Chloride or admixtures containing more than 0.1% chloride ions are not permitted.

2.04 RELATED MATERIALS

A. Waterstops: Provide flat, dumbbell type or centerbulb type waterstops at construction joints and other joints as indicated, unless noted otherwise. Size to suit joints.

B. Rubber Waterstops: Corps of Engineers CRD-C 513.

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products which may be incorporated in the work include, but are not limited to, the following:
    a. The Burke Co.

b. Progress Unlimited.

c. Williams Products.

d. Edoco Technical Products.

e. Cetco

C. Polyvinyl Chloride Waterstops: Corps of Engineers CRD-C 572.

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products which may be incorporated in the work include, but are not limited to, the following:

a. AFCO Products.

b. The Burke Co.

c. Edoco Technical Products.

d. Greenstreet Plastic Products.

e. Harbour Town Products.

f. W. R. Meadows.

g. Progress Unlimited.

h. Schleigel Corp.

i. Vinylex Corp.

D. Vapor Retarder (Under Slab): Shall conform to ASTM E 1745, Class C or better and shall have a maximum water vapor permeance of 0.04 perms when tested in accordance with ASTM E96. Vapor retarder component no less than 10 mils thick in accordance with ACI 302, 1R-96. Products: STEGO WRAP VAPOR BARRIER (10 mil) by Stego Industries, Griffolyn T-85 by Reef Industries, or Rufco D16WB by Raven Industries or approved equal.

E. Non-Shrink Grout: CRD-C 621, factory pre-mixed grout.

1. Available Products: Subject to compliance with requirements, products which may be incorporated in the work include, but are not limited to, the following:

a. Metallic:

1) "Vibrofoil"; A.C. Horn, Inc.

2) "Metallic Spec. Grout"; The Burke Co.

3) "Embeco 636"; Master Builders.

4) "Ferrolith"; Sonneborn-Contech.

5) "Firmix"; Euclid Chemical Co.

6) "Kemox G"; Sika Chemical Co.

7) "Ferrogrout"; L & M Const. Chemical Co.

b. Non-metallic:

1) "Masterflow 713"; Master Builders.

2) "Sonogrout"; Sonneborn-Contech.

3) "Euco-NS"; Euclid Chemical Co.
4) "Crystex"; L & M Const. Chemical Co.
5) "Sure-Grip Grout"; Dayton Superior Corp.
6) "Horngrout"; A.C. Horn, Inc.

F. Moisture-Retaining Cover: One of the following, complying with ASTM C 171.

1. Waterproof paper.
2. Polyethylene film.
3. Polyethylene-coated burlap.

G. Liquid Membrane-Forming Curing Compound: Liquid type membrane- forming curing compound complying with ASTM C 309, Type I, Class A unless other type acceptable to Architect. Moisture loss not more than 0.055 gr./sq. cm. when applied at 200 sq. ft./gal.

1. Available Products: Subject to compliance with requirements, products which may be incorporated in the work include, but are not limited to, the following.
   a. "Kurez DR"; Euclid Chemical Co. - or other approved equal.

H. Bonding Compound: Polyvinyl acetate or acrylic base, rewettable type.

1. Available Products: Subject to compliance with requirements, products which may be incorporated in the work include, but are not limited to, the following:
   a. "J-40 Bonding Agent"; Dayton Superior Corp.
   b. "Weldcrete"; Larsen Products.
   c. "Everbond"; L & M Construction Chemicals.
   d. "EucoWeld"; Euclid Chemical Co.
   e. "Hornweld"; A.C. Horn.
   f. "Sonocrete"; Sonneborn-Contech.
   g. "Acrylic Bondcrete"; The Burke Co.

I. Epoxy Adhesive: ASTM C 881, two component material suitable for use on dry or damp surfaces. Provide material "Type", "Grade", and "Class" to suit project requirements.

1. Available Products: Subject to compliance with requirements, products which may be incorporated in the work include, but are not limited to, the following:
   a. "Epoxtite"; A.C. Horn, Inc.
   b. "Edoco 2118 Epoxy Adhesive"; Edoco Technical Prod.
   c. "Sikadur Hi-Mod"; Sika Chemical Corp.
   d. "Euco Epoxy 463 or 615"; Euclid Chemical Co.
   e. "Patch and Bond Epoxy"; The Burke Co.
   f. "Sure-Poxy"; Kaufman Products Inc.

2.05 PROPORTIONING AND DESIGN OF MIXES

A. Prepare design mixes for each type and strength of concrete by either laboratory trial batch or field experience methods as specified in ACI 301. If trial batch method used, use an independent testing facility acceptable to Architect for preparing and reporting proposed mix designs. The testing facility shall not be the same as used for field quality control testing unless otherwise acceptable to Architect.

B. Submit written reports to Architect of each proposed mix for each class of concrete at least 15 days prior to start of work. Do not begin concrete production until mixes have been reviewed by Architect.

C. Design mixes to provide normal weight concrete with the properties as indicated on the structural drawings.

D. Adjustment to Concrete Mixes: Mix design adjustments may be requested by Contractor when characteristics of materials, job conditions, weather, test results, or other circumstances warrant; at no additional cost to Owner and as accepted by Architect. Laboratory test data for revised mix design and strength results must be submitted to and accepted by Architect before using in work.

2.06 CONCRETE MIXES

A. Ready-Mix Concrete: Comply with requirements of ASTM C 94, and as herein specified.

B. During hot weather, or under conditions contributing to rapid setting of concrete, a shorter mixing time than specified in ASTM C 94 may be required.

1. When air temperature is between 85 deg. F (30 deg. C) and 90 deg. F (32 deg. C), reduce mixing and delivery time from 1-1/2 hours to 75 minutes, and when air temperature is above 90 deg. F (32 deg. C), reduce mixing and delivery time to 60 minutes.

2.07 ADMIXTURES

A. Use water-reducing admixture or high range water-reducing admixture (super plasticizer) in concrete as required for placement and workability.

B. Use non-chloride accelerating admixture in concrete slabs placed at ambient temperatures below 50 deg. F (10 deg. C).

C. Use admixtures for water-reducing and set-control in strict compliance with manufacturer's directions.

D. Slump Limits: Proportion and design mixes to result in concrete slump at point of placement as follows:

1. Ramps, slabs, and sloping surfaces: Not more than 3".

2. Reinforced foundation systems: Not less than 1" and not more than 4".

3. Concrete containing HRWR admixture (super-plasticizer): Not more than 8" after addition of HRWR to site-verified 2"-3" slump concrete.

4. Other concrete: Not more than 4".

PART 3 EXECUTION

3.01 FORMS

A. Design, erect, support, brace, and maintain formwork to support vertical and lateral loads that might be applied until such loads can be supported by concrete structure. Construct formwork so concrete members and structures are of correct size, shape, alignment, elevation, and position.

B. Design formwork to be readily removable without impact, shock, or damage to cast-in-place concrete surfaces and adjacent materials.

C. Construct forms to sizes, shapes, lines, and dimensions shown, and to obtain accurate alignment, location, grades, level and plumb work in finished structures. Provide for openings, offsets, sinkages, keyways, recesses, moldings, rustications, reglets, chamfers, blocking, screeds, bulkheads, anchorages and inserts, and other features required in work. Use selected materials to obtain required finishes. Solidly butt joints and provide back-up at joints to prevent leakage of cement paste.

D. Fabricate forms for easy removal without hammering or prying against concrete surfaces. Provide crush plates or wrecking plates where stripping may damage cast concrete surfaces. Provide top forms for inclined surfaces where slope is too steep to place concrete with bottom forms only. Kerf wood inserts for forming keyways, reglets, recesses, and the like, to prevent swelling and for easy removal.

E. Provide temporary openings where interior area of formwork is inaccessible for cleanout, for inspection before concrete placement, and for placement of concrete. Securely brace temporary openings and set tightly to forms to prevent loss of concrete mortar. Locate temporary openings on forms at inconspicuous locations.

F. Chamfer exposed corners and edges as indicated, using wood, metal, PVC, or rubber chamfer strips fabricated to produce uniform smooth lines and tight edge joints.

G. Form Ties: Factory-fabricated, adjustable-length, removable or snapoff metal form ties, designed to prevent form deflection, and to prevent spalling concrete surfaces upon removal.

1. Unless otherwise indicated, provide ties so portion remaining within concrete after removal is 1" inside concrete and will not leave holes larger than 1" diameter in concrete surface.

H. Provisions for Other Trades: Provide openings in concrete formwork to accommodate work of other trades. Determine size and location of openings, recesses, and chases from trades providing such items. Accurately place and securely support items built into forms.

I. Cleaning and Tightening: Thoroughly clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt, or other debris just before concrete is placed. Retightening forms and bracing after concrete placement is required to eliminate mortar leaks and maintain proper alignment.

3.02 PLACING REINFORCEMENT

A. Comply with Concrete Reinforcing Steel Institute's recommended practice for "Placing Reinforcing Bars", for details and methods of reinforcement placement and supports, and as herein specified.

B. Clean reinforcement of loose rust and mill scale, earth, ice, and other materials which reduce or destroy bond with concrete.

C. Accurately position, support, and secure reinforcement against displacement by formwork, construction, or concrete placement operations. Locate and support reinforcing by metal chairs, runners, bolsters, spacers, and hangers, as required.

D. Place reinforcement to obtain at least minimum coverages for concrete protection. Arrange, space, and securely tie bars and bar supports to hold reinforcement in position during concrete placement operations. Set wire ties so ends are directed into concrete, not toward exposed concrete surfaces.

E. Install welded wire fabric in as long lengths as practicable. Lap adjoining pieces at least one full mesh and lace splices with wire. Offset end laps in adjacent widths to prevent continuous laps in either direction.

3.03 JOINTS

A. Construction Joints: Locate and install construction joints as indicated or, if not indicated, locate so as not to impair strength and appearance of the structure, as acceptable to Architect.

B. Provide keyways at least 1-1/2" deep in construction joints in walls, slabs, and between walls and footings; accepted bulkheads designed for this purpose may be used for slabs.

C. Place construction joints perpendicular to main reinforcement. Continue reinforcement across construction joints, except as otherwise indicated.

D. Waterstops: Provide waterstops in construction joints as indicated. Install waterstops to form continuous diaphragm in each joint. Make provisions to support and protect exposed waterstops during progress of work. Fabricate field joints in waterstops in accordance with manufacturer's printed instructions.

1. Joint filler and sealant materials are specified in Division-7 sections of these specifications.

E. Contraction (Control) Joints in Slabs-on-Ground: Construct contraction joints in slabs-on-ground as shown on structural drawings.

3.04 INSTALLATION OF EMBEDDED ITEMS

A. General: Set and build into work anchorage devices and other embedded items required for other work that is attached to, or supported by, cast-in-place concrete. Use setting drawings, diagrams, instructions, and directions provided by suppliers of items to be attached thereto.

B. Edge Forms and Screed Strips for Slabs: Set edge forms or bulkheads and intermediate screed strips for slabs to obtain required elevations and contours in finished slab surface. Provide and secure units sufficiently strong to support types of screed strips by use of strike-off templates or accepted compacting type screeds.

3.05 PREPARATION OF FORM SURFACES

A. Clean re-used forms of concrete matrix residue, repair and patch as required to return forms to acceptable surface condition.

B. Coat contact surfaces of forms with a form-coating compound before reinforcement is placed.

C. Thin form-coating compounds only with thinning agent of type, and in amount, and under conditions of form-coating compound manufacturer's directions. Do not allow excess form-coating material to accumulate in forms or to come into contact with in-place concrete surfaces against which fresh concrete will be placed. Apply in compliance with manufacturer's instructions.

D. Coat steel forms with a non-staining, rust-preventative form oil or otherwise protect against rusting. Rust-stained steel formwork is not acceptable.

3.06 CONCRETE PLACEMENT

A. Preplacement Inspection: Before placing concrete, inspect and complete formwork installation, reinforcing steel, and items to be embedded or cast-in. Notify other crafts to permit installation of their work; cooperate with other trades in setting such work. Moisten wood forms immediately before placing concrete where form coatings are not used.

B. Coordinate the installation of joint materials and moisture barriers with placement of forms and reinforcing steel.

C. General: Comply with ACI 304 "Recommended Practice for Measuring, Mixing, Transporting, and Placing Concrete", and as herein specified.

D. Deposit concrete continuously or in layers of such thickness that no concrete will be placed on concrete which has hardened sufficiently to cause the formation of seams or planes of weakness. If a section cannot be placed continuously, provide construction joints as herein specified. Deposit concrete as nearly as practicable to its final location to avoid segregation.

E. Placing Concrete in Forms: Deposit concrete in forms in horizontal layers not deeper than 24" and in a manner to avoid inclined construction joints. Where placement consists of several layers, place each layer while preceding layer is still plastic to avoid cold joints.

F. Consolidate placed concrete by mechanical vibrating equipment supplemented by hand-spading, rodding, or tamping. Use equipment and procedures for consolidation of concrete in accordance with ACI 309.

G. Do not use vibrators to transport concrete inside forms. Insert and withdraw vibrators vertically at uniformly spaced locations not farther than visible effectiveness of machine. Place vibrators to rapidly penetrate placed layer and at least 6" into preceding layer. Do not insert vibrators into lower layers of concrete that have begun to set. At each insertion limit duration of vibration to time necessary to consolidate concrete and complete embedment of reinforcement and other embedded items without causing segregation of mix.

H. Placing Concrete Slabs: Deposit and consolidate concrete slabs in a continuous operation, within limits of construction joints, until the placing of a panel or section is completed.

I. Consolidate concrete during placing operations so that concrete is thoroughly worked around reinforcement and other embedded items and into corners.

J. Bring slab surfaces to correct level with straightedge and strikeoff. Use bull floats or darbies to smooth surface, free of humps or hollows. Do not disturb slab surfaces prior to beginning finishing operations.

K. Maintain reinforcing in proper position during concrete placement operations.

L. Cold Weather Placing: Protect concrete work from physical damage or reduced strength which could be caused by frost, freezing actions, or low temperatures, in compliance with ACI 306 and as herein specified.

M. When air temperature has fallen to or is expected to fall below 40 deg. F (4 deg. C), uniformly heat water and aggregates before mixing to obtain a concrete mixture temperature of not less than 50 deg. F (10 deg. C), and not more than 80 deg. F (27 deg. C) at point of placement.

N. Do not use frozen materials or materials containing ice or snow. Do not place concrete on frozen subgrade or on subgrade containing frozen materials.

O. Do not use calcium chloride, salt, and other materials containing antifreeze agents or chemical accelerators, unless otherwise accepted in mix designs.

P. Hot Weather Placing: When hot weather conditions exist that would seriously impair quality and strength of concrete, place concrete in compliance with ACI 305 and as herein specified.

Q. Cool ingredients before mixing to maintain concrete temperature at time of placement below 90 deg. F (32 deg. C). Mixing water may be chilled, or chopped ice may be used to control temperature provided water equivalent of ice is calculated to total amount of mixing water. Use of liquid nitrogen to cool concrete is Contractor's option.

R. Cover reinforcing steel with water-soaked burlap if it becomes too hot, so that steel temperature will not exceed the ambient air temperature immediately before embedment in concrete.

S. Fog spray forms, reinforcing steel, and subgrade just before concrete is placed.

T. Use water-reducing retarding admixture (Type D) when required by high temperatures, low humidity, or other adverse placing conditions.

3.07 FINISH OF FORMED SURFACES

A. Rough Form Finish: For formed concrete surfaces not exposed-to-view in the finish work or by other construction, unless otherwise indicated. This is the concrete surface having texture imparted by form facing material used, with tie holes and defective areas repaired and patched and fins and other projections exceeding 1/4" in height rubbed down or chipped off.

B. Smooth Form Finish: For formed concrete surfaces exposed-to-view, or that are to be covered with a coating material applied directly to concrete, or a covering material applied directly to concrete, such as waterproofing, dampproofing, veneer plaster, painting, or other similar system. This is as-cast concrete surface obtained with selected form facing material, arranged orderly and symmetrically with a minimum of seams. Repair and patch defective areas with fins or other projections completely removed and smoothed.

C. Smooth Rubbed Finish: Provide smooth rubbed finish to scheduled concrete surfaces, which have received smooth form finish treatment, not later than one day after form removal.

D. Moisten concrete surfaces and rub with carborundum brick or other abrasive until a uniform color and texture is produced. Do not apply cement grout other than that created by the rubbing process.

E. Grout Cleaned Finish: Provide grout cleaned finish to scheduled concrete surfaces which have received smooth form finish treatment.

F. Combine one part portland cement to 1-1/2 parts fine sand by volume, and mix with water to consistency of thick paint. Proprietary additives may be used at Contractor's option. Blend standard portland cement and white portland cement, amounts determined by trial patches, so that final color of dry grout will match adjacent surfaces.

G. Thoroughly wet concrete surfaces and apply grout to coat surfaces and fill small holes. Remove excess grout by scraping and rubbing with clean burlap. Keep damp by fog spray for at least 36 hours after rubbing.

H. Related Unformed Surfaces: At tops of walls, horizontal offsets, and similar unformed surfaces occurring adjacent to formed surfaces, strike-off smooth and finish with a texture matching adjacent formed surfaces. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces, unless otherwise indicated.

3.08 MONOLITHIC SLAB FINISHES

A. Scratch Finish: Apply scratch finish to monolithic slab surfaces that are to receive concrete floor topping or mortar setting beds for tile, portland cement terrazzo, and other bonded applied cementitious finish flooring material, and as otherwise indicated.

B. After placing slabs, plane surface so that depressions between high spots do not exceed 1/2" under a 10' straightedge. Slope surfaces uniformly to drains where required. After leveling, roughen surface before final set, with stiff brushes, brooms, or rakes.

C. Float Finish: Apply float finish to monolithic slab surface to receive trowel finish and other finishes as hereinafter specified, and slab surfaces which are to be covered with membrane or elastic waterproofing, membrane or elastic roofing, or sand-bed terrazzo, and as otherwise indicated.

D. After screeding, consolidating, and leveling concrete slabs, do not work surface until ready for floating. Begin floating when surface water has disappeared or when concrete has stiffened sufficiently to permit operation of power-driven floats, or both. Consolidate surface with power-driven floats, or by hand-floating if area is small or inaccessible to power units. Check and level surface plane so that depressions between high spots do not exceed 5/16" under a 10' straightedge. Cut down high spots and fill low spots. Uniformly slope surfaces to drains. Immediately after leveling, refloat surface to a uniform, smooth, granular texture.

E. Trowel Finish: Apply trowel finish to monolithic slab surfaces to be exposed-to-view, and slab surfaces to be covered with resilient flooring, carpet, ceramic or quarry tile, paint, or other thin film finish coating, system.

F. After floating, begin first trowel finish operation using a power-driven trowel. Begin final troweling when surface produces a ringing sound as trowel is moved over surface. Consolidate concrete surface by final hand-troweling operation, free of trowel marks, uniform in texture and appearance. The finish slab shall meet Fl 25 and Ff 25 requirements as defined by ACI 302. Grind smooth surface defects which would telegraph through applied floor covering system.

G. Trowel and Fine Broom Finish: Where ceramic or quarry tile is to be installed with thin-set mortar, apply trowel finish as specified, then immediately follow with slightly scarifying surface by fine brooming.

H. Non-Slip Broom Finish: Apply non-slip broom finish to exterior concrete platforms, steps and ramps, and elsewhere as indicated.

I. Immediately after float finishing, slightly roughen concrete surface by brooming with fiber bristle broom perpendicular to main traffic route. Coordinate required final finish with Architect before application.

J. Non-slip Aggregate Finish: Apply non-slip aggregate finish to concrete stair treads, platforms, ramps, sloped walks, and elsewhere as indicated.

K. After completion of float finishing, and before starting trowel finish, uniformly spread 25 lbs. of dampened non-slip aggregate per 100 sq. ft. of surface. Tamp aggregate flush with surface using a steel trowel, but do not force below surface. After broadcasting and tamping, apply trowel finishing as herein specified.

L. After curing, lightly work surface with a steel wire brush, or an abrasive stone, and water to expose non-slip aggregate.

3.09 CONCRETE CURING AND PROTECTION

A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures.

B. Start initial curing as soon as free water has disappeared from concrete surface after placing and finishing. Weather permitting, keep continuously moist for not less than 7 days.

C. Begin final curing procedures immediately following initial curing and before concrete has dried. Continue final curing for at least 7 days in accordance with ACI 301 procedures. Avoid rapid drying at end of final curing period.

D. Curing Methods: Perform curing of concrete by curing and sealing compound, by moist curing, by moisture-retaining cover curing, and by combinations thereof, as herein specified.

E. Provide moisture curing by following methods:

1. Keep concrete surface continuously wet by covering with water.

2. Continuous water-fog spray.

3. Covering concrete surface with specified absorptive cover, thoroughly saturating cover with water and keeping continuously wet. Place absorptive cover to provide coverage of concrete surfaces and edges, with 4" lap over adjacent absorptive covers.

F. Provide moisture-cover curing as follows:

1. Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width with sides and ends lapped at least 3" and sealed by waterproof tape of adhesive. Immediately repair any holes or tears during curing period using cover material and waterproof tape.

G. Provide curing and sealing compound to interior slabs with resilient flooring, carpet over cushion, or left exposed; and to exterior slabs, walks and curbs, as follows:

1. Apply specified curing and sealing compound to concrete slabs as soon as final finishing operations are complete (within 2 hours). Apply uniformly in continuous operation by power-spray or roller in accordance with manufacturer's directions. Recoat areas subjected to heavy rainfall within 3 hours after initial application. Maintain continuity of coating and repair damage during curing period.

H. Do not use membrane curing compounds on surfaces which are to be covered with coating material applied directly to concrete, liquid floor hardener, waterproofing, dampproofing, membrane roofing, flooring (such as ceramic or quarry tile, glue-down carpet), painting, and other coatings and finish materials, unless otherwise acceptable to Architect.

I. Curing Formed Surfaces: Cure formed concrete surfaces, including undersides of beams, supported slabs, and other similar surfaces by moist curing with forms in place for full curing period or until forms are removed. If forms are removed, continue curing by methods specified above, as applicable.

J. Curing Unformed Surfaces: Cure unformed surfaces, such as slabs, floor topping, and other flat surfaces by application of appropriate curing method.

K. Final cure concrete surfaces to receive liquid floor hardener or finish flooring by use of moisture-retaining cover, unless otherwise directed.

L. Sealer and Dustproofer: Apply a second coat of specified curing and sealing compound only to surfaces given a first coat.

3.10 REMOVAL OF FORMS

A. Formwork not supporting weight of concrete, such as sides of beams, walls, columns, and similar parts of the work, may be removed after cumulatively curing at not less than 50 deg F (10 deg C) for 24 hours after placing concrete, provided concrete is sufficiently hard to not be damaged by form removal operations, and provided curing and protection operations are maintained.

B. Formwork supporting weight of concrete, such as beam soffits, joists, slabs, and other structural elements, may not be removed in less than 14 days and until concrete has attained design minimum compressive strength at 28 days. Determine potential compressive strength of in-place concrete by testing field-cured specimens representative of concrete location or members.

C. Form facing material may be removed 4 days after placement, only if shores and other vertical supports have been arranged to permit removal of form facing material without loosening or disturbing shores and supports.

3.11 RE-USE OF FORMS

A. Clean and repair surfaces of forms to be re-used in work. Split, frayed, delaminated, or otherwise damaged form facing material will not be acceptable for exposed surfaces. Apply new form coating compound as specified for new formwork.

B. When forms are extended for successive concrete placement, thoroughly clean surfaces, remove fins and laitance, and tighten forms to close joints. Align and secure joint to avoid offsets. Do not use "patched" forms for exposed concrete surfaces, except as acceptable to Architect.

3.12 MISCELLANEOUS CONCRETE ITEMS

A. Filling-In: Fill-in holes and openings left in concrete structures for passage of work by other trades, unless otherwise shown or directed, after work of other trades is in place. Mix, place, and cure concrete as herein specified, to blend with in-place construction. Provide other miscellaneous concrete filling shown or required to complete work.

B. Curbs: Provide monolithic finish to interior curbs by stripping forms while concrete is still green and steel-troweling surfaces to a hard, dense finish with corners, intersections, and terminations slightly rounded.

C. Equipment Bases and Foundations: Provide machine and equipment bases and foundations, as shown on drawings. Set anchor bolts for machines and equipment to template at correct elevations, complying with certified diagrams or templates of manufacturer furnishing machines and equipment.

D. Grout base plates and foundations as indicated, using specified non-shrink grout. Use non-metallic grout for exposed conditions, unless otherwise indicated.

3.13 CONCRETE SURFACE REPAIRS

A. Patching Defective Areas: Repair and patch defective areas with cement mortar immediately after removal of forms, when acceptable to Architect.

B. Cut out honeycomb, rock pockets, voids over 1/4" in any dimension, and holes left by tie rods and bolts, down to solid concrete but, in no case to a depth of less than 1". Make edges of cuts perpendicular to the concrete surface. Thoroughly clean, dampen with water, and brush-coat the area to be patched with specified bonding agent. Place patching mortar after bonding compound has dried.

C. For exposed-to-view surfaces, blend white portland cement and standard portland cement so that, when dry, patching mortar will match color surrounding. Provide test areas at inconspicuous location to verify mixture and color match before proceeding with patching. Compact mortar in place and strike-off slightly higher than surrounding surface.

D. Repair of Formed Surfaces: Remove and replace concrete having defective surfaces if defects cannot be repaired to satisfaction of Architect. Surface defects, as such, include color and texture irregularities, cracks, spalls, air bubbles, honeycomb, rock pockets; fins and other projections on surface; and stains and other discolorations that cannot be removed by cleaning. Flush out form tie holes, fill with dry pack mortar, or precast cement cone plugs secured in place with bonding agent.

E. Repair concealed formed surfaces, where possible, that contain defects that affect the durability of concrete. If defects cannot be repaired, remove and replace concrete.

F. Repair of Unformed Surfaces: Test unformed surfaces, such as monolithic slabs, for smoothness and verify surface plane to tolerances specified for each surface and finish. Correct low and high areas as herein specified. Test unformed surfaces sloped to drain for trueness of slope, in addition to smoothness using a template having required slope.

G. Repair finished unformed surfaces that contain defects which affect durability of concrete. Surface defects, as such, include crazing, cracks in excess of 0.01" wide or which penetrate to reinforcement or completely through non-reinforced sections regardless of width, spalling, pop-outs, honeycomb, rock pockets, and other objectionable conditions.

H. Correct high areas in unformed surfaces by grinding, after concrete has cured at least 14 days.

I. Correct low areas in unformed surfaces during or immediately after completion of surface finishing operations by cutting out low areas and replacing with fresh concrete. Finish repaired areas to blend into adjacent concrete. Proprietary patching compounds may be used when acceptable to Architect.

J. Repair defective areas, except random cracks and single holes not exceeding 1" diameter, by cutting out and replacing with fresh concrete. Remove defective areas to sound concrete with clean, square cuts and expose reinforcing steel with at least 3/4" clearance all around. Dampen concrete surfaces in contact with patching concrete and apply bonding compound. Mix patching concrete of same materials to provide concrete of same type or class as original concrete. Place, compact, and finish to blend with adjacent finished concrete. Cure in same manner as adjacent concrete.

K. Repair isolated random cracks and single holes not over 1" in diameter by dry-pack method. Groove top of cracks and cut-out holes to sound concrete and clean of dust, dirt, and loose particles. Dampen cleaned concrete surfaces and apply bonding compound. Mix dry-pack, consisting of one part portland cement to 2-1/2 parts fine aggregate passing a No. 16 mesh sieve, using only enough water as required for handling and placing. Place dry pack after bonding compound has dried. Compact dry-pack mixture in place and finish to match adjacent concrete. Keep patched area continuously moist for not less than 72 hours.

L. Perform structural repairs with prior approval of Architect or Structural Engineer for method and procedure, using specified epoxy adhesive and mortar.

M. Repair methods not specified above may be used, subject to acceptance of Architect.

3.14 FIELD QUALITY CONTROL

A. The Owner shall employ and pay a testing laboratory to perform tests and to submit test reports. Contractor shall pay for retesting of all failed tests.

B. Sampling and testing for quality control during placement of concrete may include the following, as directed by Architect.

C. Sampling Fresh Concrete: ASTM C 172, except modified for slump to comply with ASTM C 94.

1. Slump: ASTM C 143; one test at point of discharge for each day's pour of each type of concrete; additional tests when concrete consistency seems to have changed.

2. Air Content: ASTM C 173, volumetric method for lightweight or normal weight concrete; ASTM C 231 pressure method for normal weight concrete; one for each day's pour of each type of air- entrained concrete.

3. Concrete Temperature: Test hourly when air temperature is 40 deg. F (4 deg. C) and below, and when 80 deg. F (27 deg. C) and above; and each time a set of compression test specimens made.

4. Compression Test Specimen: ASTM C 31; one set of 4 standard cylinders for each compressive strength test, unless otherwise directed. Mold and store cylinders for laboratory cured test specimens except when field-cure test specimens are required.

5. Compressive Strength Tests: ASTM C 39; one set for each day's pour exceeding 5 cu. yds. plus additional sets for each 50 cu. yds. over and above the first 25 cu. yds. of each concrete class placed in any one day; one specimen tested at 7 days, two specimens tested at 28 days, and one specimen retained in reserve for later testing if required.

6. When frequency of testing will provide less than 5 strength tests for a given class of concrete, conduct testing from at least 5 randomly selected batches or from each batch if fewer than 5 are used.

7. When total quantity of a given class of concrete is less than 50 cu. yds., strength test may be waived by Architect if, in his judgement, adequate evidence of satisfactory strength is provided.

8. When strength of field-cured cylinders is less than 85 percent of companion laboratory-cured cylinders, evaluate current operations and provide corrective procedures for protecting and curing the in-place concrete.

9. Strength level of concrete will be considered satisfactory if averages of sets of three consecutive strength test results equal or exceed specified compressive strength, and no individual strength test result falls below specified compressive strength by more than 500 psi.

D. Test results will be reported in writing to Architect, Structural Engineer and Contractor within 24 hours that tests are made. Reports of compressive strength tests shall contain the project identification name and number, date of concrete placement, name of concrete testing service, concrete type and class, location of concrete batch in structure, design compressive strength at 28 days, concrete mix proportions and materials; compressive breaking strength and type of break for both 7-day tests and 28-day tests.

E. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted but shall not be used as the sole basis for acceptance or rejection.

F. Additional Tests: The testing service will make additional tests of in-place concrete when test results indicate specified concrete strengths and other characteristics have not been attained in the structure, as directed by Architect. Testing service may conduct tests to determine adequacy of concrete by cored cylinders complying with ASTM C 42, or by other methods as directed. Contractor shall pay for such tests conducted, and any other additional testing as may be required, when unacceptable concrete is verified.

END OF SECTION

SECTION 03 10 00 - CONCRETE FORMWORK

1. PART 1 GENERAL

1.1. SECTION INCLUDES

A. Formwork for cast-in place concrete, with shoring, bracing and anchorage.
B. Openings for other work.
C. Form accessories.
D. Form stripping.

1.2. PRODUCTS INSTALLED BUT NOT FURNISHED UNDER THIS SECTION

A. Section 03 30 00 - Cast-In-Place Concrete: Supply of concrete accessories for placement by this section.

1.3. RELATED SECTIONS

A. Section 03 20 00 - Concrete Reinforcement.
B. Section 03 30 00 - Cast-in-Place Concrete.
C. Section 02 36 20 – Drilled Concrete Piers.

1.4. UNIT PRICE - MEASUREMENT AND PAYMENT

A. Concrete formwork will not be paid for directly but will be included in the cost bid for other items.

1.5. REFERENCES

Codes and Standards: Comply with provisions of following codes, specifications, and standards, except where more stringent requirements are shown or specified:

A. 2015 edition of the International Building Code (IBC), including applicable local ordinances and amendments.
B. ACI 117 "Standard Specifications for Tolerances for Concrete Construction and Materials."
C. ACI 301 "Specifications for Structural Concrete for Buildings".
D. ACI 302 "Guide for Concrete Floor and Slab Construction."
E. ACI 304 "Recommended Practice for Measuring, Mixing, Transporting, and Placing Concrete."
F. ACI 305 "Hot Weather Concreting."
G. ACI 306 "Cold Weather Concreting."
H. ACI 309 Specification for Liquid Membrane Forming Compounds for Curing Concrete."
I. ACI 315 "Manual of Standard Practice for Detailing Concrete Structures.
J. ACI 318 "Building Code Requirements for Reinforced Concrete."
K. ASTM A 123 "Specifications for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel."
L. ASTM "Specification for Steel Welded Wire Fabric, Plain, for Concrete Reinforcement."
M. ASTM A 615 "Specification for Deformed and Plain Billet-Steel Bars for Concrete
N. Reinforcement."ASTM A 706 "Specification for Low-Alloy Steel Deformed Bars for Concrete Reinforcement."
O. ASTM C 31 "Method of Making and Curing Concrete Test Specimens in the Field."."
P. ASTM C 33 "Specification for Concrete Aggregates."
Q. ASTM C 39 "Test Method for Compressive Strength of Cylindrical Concrete Specimens."
R. ASTM C94 "Specification for Ready Mix Concrete."

S. ASTM C 143 "Test Method for Slump of Portland Cement Concrete."
T. ASTM C 150 "Specification for Portland Cement."
U. Concrete Reinforcing Steel Institute, (CRSI) "Manual of Standard Practice," latest edition.
V. Concrete Reinforcing Steel Institute, (CRSI) "Manual of Standard Practice and Specifications for Placing Reinforcement," latest edition.

1.6. DESIGN REQUIREMENTS

A. Design, engineer and construct formwork, shoring and bracing to conform to code requirements; resultant concrete to conform to required shape, line and dimension.

1.7. SUBMITTALS

A. Submit under provisions of Section 01300.
B. Shop Drawings: Indicate pertinent dimensions, materials, bracing, and arrangement of joints and ties.
C. Product Data: Provide data on void form materials [and installation requirements].

1.8. QUALITY ASSURANCE

A. Perform Work in accordance with ACI 318.

1.9. QUALIFICATIONS

A. Design formwork under direct supervision of a Professional Structural Engineer experienced in design of this work and licensed in the state where the Project is located.

1.10. REGULATORY REQUIREMENTS

A. Conform to applicable code for design, fabrication, erection and removal of formwork.

1.11. FIELD SAMPLES

A. Provide under provisions of Section 01400. Coordinate with requirements stated in Section 03100 and 03300.

1.12. DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, protect and handle products to site under provisions of Section 01600.
B. Deliver void forms and installation instructions in manufacturer's packaging.
C. Store off ground in ventilated and protected manner to prevent deterioration from moisture.

1.13. COORDINATION

A. Coordinate work under provisions of Section 01039.
B. Coordinate this Section with other Sections of work which require attachment of components to formwork.
C. If formwork is placed after reinforcement resulting in insufficient concrete cover over reinforcement before proceeding, request instructions from Architect/Engineer.

2. PART 2 PRODUCTS

2.1. WOOD FORM MATERIALS

A. Forms for Exposed Finish Concrete: Plywood, metal, metal-framed plywood faced, or other acceptable panel-type materials, to provide continuous, straight, smooth, exposed surfaces. Furnish in largest practicable sizes to minimize number of joints and to

conform to joint system shown on drawings.

B. Use overlaid plywood complying with U.S. Product Standard PS-1 "A-C or B-B High Density Overlaid Concrete Form", Class I.
C. Forms for Unexposed Finish Concrete: Plywood, lumber, metal, or other acceptable material. Provide lumber dressed on at least 2 edges and one side for tight fit.
D. Form Coatings: Provide commercial formulation form-coating compounds that will not bond with, stain nor adversely affect concrete surfaces, and will not impair subsequent treatments of concrete surfaces.

2.2. FORMWORK ACCESSORIES

A. Form Ties: Snap-off type, metal, adjustable length, 1 inch back break dimension, free of defects that could leave holes larger than 1 inch in concrete surface.
B. Form Release Agent: Colorless mineral oil which will not stain concrete, or absorb moisture or impair natural bonding or color characteristics of coating intended for use on concrete.
C. Corners: Chamfer, wood strip1x 1 inch size; maximum possible lengths
D. Flashing Reglets: Galvanized steel, 22 gage thick, longest possible lengths, with alignment splines for joints, release tape sealed slots, anchors for securing to concrete formwork.
E. Nails, Spikes, Lag Bolts, Through Bolts, Anchorages: Sized as required, of sufficient strength and character to maintain formwork in place while placing concrete.
F. Waterstops: Polyvinyl chloride, minimum 1,750 psi tensile strength, minimum 50 degrees F to plus 175 degrees F working temperature range, maximum possible lengths, ribbed profile, preformed corner sections, heat welded jointing; manufactured by Greenstreak.

3. PART 3 EXECUTION

3.1. EXAMINATION

A. Verify lines, levels and centers before proceeding with formwork. Ensure that dimensions agree with drawings.

3.2. EARTH FORMS

A. All grade beams shall be formed. Earth Forms are not acceptable.

3.3. ERECTION - FORMWORK

A. Erect formwork, shoring and bracing to achieve design requirements, in accordance with requirements of ACI 301.
B. Provide bracing to ensure stability of formwork. Shore or strengthen formwork subject to over stressing by construction loads.
C. Arrange and assemble formwork to permit dismantling and stripping. Do not damage concrete during stripping. Permit removal of remaining principal shores.
D. Align joints and make watertight. Keep form joints to a minimum.
E. Obtain approval before framing openings in structural members which are not indicated on Drawings.
F. Install void forms in accordance with manufacturer's recommendations. Protect forms from moisture or crushing.

3.4. APPLICATION - FORM RELEASE AGENT

A. Apply form release agent on formwork in accordance with manufacturer's recommendations.
B. Apply prior to placement of reinforcing steel, anchoring devices, and embedded items.
C. Do not apply form release agent where concrete surfaces will receive special finishes or applied coverings which are effected by agent. Soak inside surfaces of untreated forms with clean water. Keep surfaces coated prior to placement of concrete.

3.5. INSERTS, EMBEDDED PARTS, AND OPENINGS

A. Provide formed openings where required for items to be embedded in passing through concrete work.
B. Locate and set in place items which will be cast directly into concrete.
C. Coordinate with work of other sections in forming and placing openings, slots, reglets, recesses, sleeves, bolts, anchors, other inserts, and components of other Work.
D. Position recessed reglets for brick veneer masonry anchors to spacing and intervals specified in Section 04300.
E. Install accessories in accordance with manufacturer's instructions, straight, level, and plumb. Ensure items are not disturbed during concrete placement.
F. Install waterstops continuous without displacing reinforcement.
G. Provide temporary ports or openings in formwork where required to facilitate cleaning and inspection. Locate openings at bottom of forms to allow flushing water to drain.
H. Close temporary openings with tight fitting panels, flush with inside face of forms, and neatly fitted so joints will not be apparent in exposed concrete surfaces.

3.6. FORM CLEANING

A. Clean forms as erection proceeds, to remove foreign matter within forms.
B. Clean formed cavities of debris prior to placing concrete.
C. Flush with water or use compressed air to remove remaining foreign matter. Ensure that water and debris drain to exterior through clean-out ports.
D. During cold weather, remove ice and snow from within forms. Do not use de-icing salts. Do not use water to clean out forms, unless formwork and concrete construction proceed within heated enclosure. Use compressed air or other means to remove foreign matter.

3.7. FORMWORK TOLERANCES

A. Construct formwork to maintain tolerances required by ACI 301.

3.8. FIELD QUALITY CONTROL

A. Inspect erected formwork, shoring, and bracing to ensure that work is in accordance with formwork design, and that supports, fastenings, wedges, ties, and items are secure.
B. Do not reuse wood formwork more than 1 times for concrete surfaces to be exposed to view. Do not patch formwork.

3.9. FORM REMOVAL

A. Do not remove forms or bracing until concrete has gained sufficient strength to carry its own weight and imposed loads.
B. Loosen forms carefully. Do not wedge pry bars, hammers, or tools against finish concrete surfaces scheduled for exposure to view.
C. Store removed forms in manner that surfaces to be in contact with fresh concrete will not be damaged. Discard damaged forms.

END OF SECTION 03 10 00

SECTION 031521 - TERMITE BARRIER

PART ONE - GENERAL

DESCRIPTION

Provide soil treatment for termite control under and around buildings or construction as described below.

Provide termite treatment on existing wood sleeper system at auditorium once existing flooring is removed and prior to installation of new wood floor.

RELATED WORK SPECIFIED ELSEWHERE

General & Supplementary Conditions, Special Requirements:
Earthwork: Section 02200
Cast-in-Place Concrete: Section 03300

QUALITY ASSURANCE

Applicator shall be registered or licensed as required by state or other governing jurisdictions.

Applicator shall comply with termite control requirements of the state or other governing jurisdictions and with the requirements of this Specification where it exceeds other requirements. Should Government Regulations outlaw or restrict use of any pesticide as specified, Contractor shall submit revised and equal treatment to Architect prior to application.

GUARANTEE

Deliver to the Owner a bonded guarantee that the below listed requirements have been met and that re-treatment will be made, without cost to Owner, on evidence of termite infestation within a period of five *(5)* years after date of Substantial Completion. Re-treatment material shall be same quality and rate of concentration as originally used materials.

SUBMITTALS

Before proceeding with the work, provide Architect with manufacturer’s mixing and application instructions.

PART TWO - PRODUCTS

MATERIALS

Apply one of the listed chemicals, at not less than the designated concentration, to areas to be treated:

Permathrin (Dragnet FT & Torpedo): 0.5 – 1.0 percent applied in water emulsion.

Biflex TC: 0.06 – 0.12 percent applied in water emulsion.

Demon: 0.25 – 0.50 percent applied in water emulsion.

Bifenthrin: .0.06 – 0.12 percent applied in water emulsion

Cypermethrin: 0.25 – 0.50 percent applied in water emulsion

Imidacloprid: 0.05 – 0.10 percent applied in water emulsion

Proprietary materials, which pass a 5-year test by U. S. Forest Service or U. S. Department of Agriculture, and contain one or more of the above chemicals in the proper concentrations, and can provide proof that no toxic effect will result in human, beneficial plant or animal life, are acceptable. Contractor shall not use any material that is banned or prohibited by any U. S. Government Agency. If any such material is called for herein, Contractor shall notify Architect, who will select an acceptable substitute.

MIXES

Follow manufacturer's mixing instructions.

PART THREE - EXECUTION

INSPECTION

Notify Architect 48 hours prior to planned application of chemicals. Do not proceed without approval of Architect.

Do not begin work until all fill under slabs has been compacted, and after piping and other sub-slab work is in place. Treat before installation of vapor barrier.

Verify that soil is in friable condition with moisture content low enough to permit absorption of toxicant solution.

APPLICATION

Apply to areas beneath concrete floor slabs on grade or fill, and along both sides of interior and exterior grade beams.

Apply also at expansion joints, construction joints, conduit, piping and other construction

penetrations through slabs.

SLABS ON GRADE: One (10) gallon to each ten (10) square feet of area within building lines.

GRADE BEAMS: One (1) gallon (each side) for each for (4) lineal feet of grade beam.

EXPANSION AND CONSTRUCTION JOINTS: Two (2) gallons for each five *(5)* linear feet of joint.

PIPE CONDUITS & OTHER SLAB PENETRATIONS: Two (2) gallons for each seven (7) square feet for a minimum radius of three (3) feet from penetration.

PROTECTION

Allow not less than 12 hours for drying after application, before beginning concrete placement or other construction activities.

Cover areas immediately following application of material.

Provide protection necessary to prevent human and animal contact with treatment materials and with treated surfaces.

Protect persons from injury and property damage. Satisfactorily repair or remove and replace work that has been damaged.

CLEANING

Clean adjacent surfaces not intended for treatment from soil, stain and adhered materials. Remove and replace damaged work that cannot be restored to original conditions.

Remove excess material and debris from site.

END OF SECTION

SECTION 03 20 00 - CONCRETE REINFORCEMENT

1. PART 1 GENERAL

1.1. SECTION INCLUDES
A. Reinforcing steel bars, wire fabric and accessories for cast-in-place concrete.

1.2. RELATED SECTIONS
A. Section 03 10 00 - Concrete Formwork.
B. Section 03 30 00 - Cast-in-Place Concrete.
C. Section 02 36 20 – Drilled Concrete Piers.

1.3. UNIT PRICE - MEASUREMENT AND PAYMENT
A. Concrete reinforcement shall not be paid for directly but shall be included in the prices bid for other items.

1.4. REFERENCES
A. ACI 301 - Structural Concrete for Buildings.
B. ACI 318 - Building Code Requirements For Reinforced Concrete.]
C. ACI SP-66 - American Concrete Institute - Detailing Manual.
D. ANSI/ASTM A82 - Cold Drawn Steel Wire for Concrete Reinforcement.
E. ANSI/ASTM A184 - Fabricated Deformed Steel Bar Mats for Concrete Reinforcement.
F. ANSI/ASTM A185 - Welded Steel Wire Fabric for Concrete Reinforcement.
G. ANSI/ASTM A496 - Deformed Steel Wire Fabric for Concrete Reinforcement.
H. ANSI/ASTM A497 - Welded Deformed Steel Wire Fabric for Concrete Reinforcement.
I. ANSI/AWS D1.4 - Structural Welding Code for Reinforcing Steel.
J. ASTM A615 - Deformed and Plain Billet Steel Bars for Concrete Reinforcement.
K. ASTM A616 - Rail Steel Deformed and Plain Bars for Concrete Reinforcement.
L. ASTM A617 - Axle Steel Deformed and Plain Bars for Concrete Reinforcement.
M. ASTM A704 - Welded Steel Plain Bar or Rod Mats for Concrete Reinforcement.
N. ASTM A706 - Low-Alloy Steel Deformed Bars for Concrete Reinforcement.
O. ASTM A767 - Zinc-Coated (Galvanized) Bars for Concrete Reinforcement.
P. ASTM A775 - Epoxy-Coated Reinforcing Steel Bars.
Q. ASTM D3963 - Epoxy-Coated Reinforcing Steel.
R. AWS D12.1 - Welding Reinforcement Steel, Metal Inserts and Connections in Reinforced Concrete Construction.
S. CRSI - Concrete Reinforcing Steel Institute - Manual of Practice.
T. CRSI 63 - Placing Reinforcing Bars.
U. ASTM A884 - Epoxy-Coated Steel Wire and Welded Wire Fabric for Reinforcement.

1.5. SUBMITTALS
A. Submit under provisions of Section 01300.
B. Shop Drawings: Indicate bar sizes, spacings, locations, and quantities of reinforcing steel and wire fabric, bending and cutting schedules, and supporting and spacing devices and.
C. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.

1.6. QUALITY ASSURANCE

A. Perform Work in accordance with CRSI - Manual of Standard Practice, ACI 301, and ACI 318.
B. Submit certified copies of mill test report of reinforcement materials analysis.
C. Provide Architect/Engineer with access to fabrication plant to facilitate inspection of reinforcement. Provide notification of commencement and duration of shop fabrication in sufficient time to allow inspection.

1.7. QUALIFICATIONS
A. Design reinforcement under direct supervision of a Professional Structural Engineer experienced in design of this work and licensed in the State where the Project is located.
B. Welders' Certificates: Submit under provisions of Section 01400 Manufacturer's Certificates, certifying welders employed on the Work, verifying AWS qualification within the previous 12 months.

1.8. COORDINATION
A. Coordinate work under provisions of Section 01039.
B. Coordinate with placement of formwork, formed openings and other Work.

2. PART 2 PRODUCTS

2.1. REINFORCEMENT
A. Reinforcing Steel: ASTM A615, 60 ksi yield grade; deformed billet steel bars, unfinished
B. Welded Reinforcing Steel: ASTM A706, 60 ksi yield grade; deformed low-alloy steel bars, unfinished.
C. Welded Steel Wire Fabric: ASTM A185 in flat sheets unfinished

2.2. ACCESSORY MATERIALS
A. Tie Wire: Minimum 16 gage annealed type
B. Chairs, Bolsters, Bar Supports, Spacers: Sized and shaped for strength and support of reinforcement during concrete placement conditions including load bearing pad on bottom to prevent vapor barrier puncture.
C. Special Chairs, Bolsters, Bar Supports, Spacers Adjacent to Weather Exposed Concrete Surfaces: Plastic coated steel type; size and shape as required.

2.3. FABRICATION
A. Fabricate concrete reinforcing in accordance with CRSI Manual of Practice.
B. Weld reinforcement in accordance with AWS D1.4.
C. Locate reinforcing splices not indicated on drawings, at point of minimum stress. Review location of splices with Architect/Engineer.

3. PART 3 EXECUTION

3.1. PLACEMENT
A. Place, support and secure reinforcement against displacement. Do not deviate from required position.
B. Do not displace or damage vapor barrier.
C. Accommodate placement of formed openings.

D. Maintain concrete cover around reinforcing as follows:
E. Conform to ACI 318-02 code for concrete cover over reinforcement.
F. Bond and ground all reinforcement to requirements of Section 16170.

3.2. FIELD QUALITY CONTROL

A. Field inspection will be performed under provisions of Section 01 45 00.

END OF SECTION 03 20 00

SECTION 040519 - MASONRY ANCHORAGE AND REINFORCING

PART 1 GENERAL

1. 01 SUMMARY

A. Section Includes
   1. Installation of masonry repair systems.

B. Related Requirements
   1. Section 01 25 00- Substitution Procedures.
   2. Section 01 33 00- Submittal Procedures.
   3. Section 01 35 91- Historic Preservation Inspection Services
   4. Section 01 45 80- Testing Laboratory Services.
   5. Section 01 60 00- Product Requirements.
   6. Section 04 01 00- Maintenance of Masonry.
   7. Section 04 01 20.91- Unit Masonry Restoration.
   8. Section 04 01 40.91 Stone Restoration.
   9. Section 04 20 00- Unit Masonry.
   10. Section 04 26 13 – Masonry Veneer.

1.02 REFERENCES

A. The date of the standard is that in effect as the date of receipt of bids for the project.

B. The Masonry Society (TMS):
   1. TMS 402/602 Building Code Requirements and Specifications for Masonry Structures.

C. ASTM International (ASTM):
   1. ASTM A 276/ 276M- Standard Specification for Stainless Steel Bars and Shapes.
   2. ASTM A580/580M – Standard Specification for Stainless Steel Wire.
   3. ASTM A582 – Standard Specification for Free-Machining Stainless Steel Bars.
   4. ASTM B16/16M – Standard Specification for Free-Cutting Brass Rod, Bar, and Shapes for Use in Screw Machines.
   5. ASTM C 1093- Standard Practice for Accreditation of Testing Agencies for Masonry.

D. The Brick Industry Association (BIA):
   1. Tek Note #44b- Wall Ties for Brick Masonry.

1.03 ADMINISTRATIVE REQUIREMENTS

A. Pre-Installation Meeting: Convene before the start of work on new concrete slabs, patching of existing concrete slabs and start of application of concrete finish system.
   1. Require attendance of parties directly affecting work of this Section, including the Owner’s Representative, Contractor, Architect, Engineer, and Installer. Meeting should only convene when required parties are present.
   2. Review the following:
      a. Installation procedure.
      b. Quality control.

c. Coordination with other Work.

1.04 SUBMITTALS

A. Product Data:
1. Submit manufacturer's product data sheets and tested physical and performance properties for each product to be used, indicating the size and length of anchor to be used for the work.

1.05 QUALITY ASSURANCE

A. Installer Qualifications:
1. Installer to be familiar with the specified requirements and the methods needed for proper installation of anchoring systems, including coordination with wall assembly components. Installer must have the proper equipment available to perform work within the scope of this project on a timely basis.

B. Manufacturer: Provide product design, product engineering, and technical assistance for the selection, application, and installation of an appropriate anchoring system for the project.

C. Testing Agency:
1. Field Testing: The inspector must be experienced with the proper use of calibrated test equipment.
2. Laboratory Testing: The testing agency must be qualified in accordance with ASTM C1093 for the testing indicated.

D. Mock-up: On-site, prior to the start of work within this section.
1. Require attendance of parties directly affecting work of this Section, including the Contractor, Installer, Architect, Engineer, and Owner's Representative.
2. Notify the above parties at least one week in advance of the date and time when the mock-up will be completed.
3. Install anchor for evaluation of application of workmanship
4. Perform in-situ testing of the installed anchors in the wall to be repaired to confirm the retrofit anchor performs as expected in both the veneer and backup independently.
5. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in the mockups unless the Architect/Engineer specifically approves such deviations in writing.
6. Subject to compliance with requirements, an approved mockup may become part of the completed work.

1.06 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials to the worksite in manufacturer's original and unopened package, labeled with manufacturer's name and type of product.

B. Store materials in an environment recommended on published manufacturer's product datasheets.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Basis of Design: PROSOCO, Inc., (800) 255-4255, customercare@prosoco.com.

B. Substitutions: In accordance with Section 012500 – Substitution Procedures.

2.02 ANCHORS AND TIES

A. Mechanical expansion anchors: For veneers three inches or greater, provide a torque-activated anchor with components that expand in an umbrella shape, compressing against the base material to provide a positive connection.
   1. Material:
      a. Provide ties and anchors specified in this article that are made from materials that comply with the following, unless otherwise indicated.
         1) Stainless steel threaded rod: ASTM A276, Type [304][316].
         2) Brass: ASTM B16/16M, Type 360.
   2. Application:
      a. Solid concrete backup conditions:
         1) 5000 Series Grip-Tie Anchors.
         2) 5000R Series Grip-Tie Anchors.
      b. Hollow CMU backup conditions:
         1) 5100 Series Grip-Tie Anchors.
      c. Structural steel backup conditions:
         1) Stitch-Tie 5200 Series Grip-Tie Anchors.
      d. Stud (wood or steel) backup conditions:
         1) 5300 Series Grip-Tie Anchors.

B. Thin panel veneer mechanical anchors: For veneers less than three inches thick, provide torque or hammer activated anchor with components that expand in an umbrella shape at the backup material, and a larger diameter anchor head for panel restraint. The panel anchors can be used for a load transfer of both gravity and lateral loading.
   1. Material:
      a. Provide ties and anchors specified in this article that are made from materials that comply with the following, unless otherwise indicated.
         1) Stainless steel threaded rod: ASTM A276, Type [304][316].
         2) Stainless steel rod: ASTM A582, Type 303.
         3) Brass: ASTM B16/16M, Type 360.
   2. Application:
      a. Lateral only load transfer with solid concrete backup:
         1) 6000-1 Series Stone-GripTie Anchors by PROSOCO, Inc.
         2) 6000-2 Series Stone-GripTie Anchors by PROSOCO, Inc.
         3) 6000-2LD Series Stone-GripTie Anchors by PROSOCO, Inc.
      b. Lateral only load transfer with hollow backup:
         1) 6100-1 Series Stone-GripTie Anchors by PROSOCO, Inc.
         2) 6100-2 Series Stone-GripTie Anchors by PROSOCO, Inc.
         3) 6100-2LD Series Stone-GripTie Anchors by PROSOCO, Inc.
      c. Lateral only load transfer with structural steel or clay tile backup:
         1) 6200-1 Series Stone-GripTie Anchors by PROSOCO, Inc.
         2) 6200-2 Series Stone-GripTie Anchors by PROSOCO, Inc.
         3) 6200-2LD Series Stone-GripTie Anchors by PROSOCO, Inc.
      d. Lateral only load transfer with structural metal or wood stud backup:
         1) 6300-1 Series Stone-GripTie Anchors by PROSOCO, Inc.
         2) 6300-2LD Series Stone-GripTie Anchors by PROSOCO, Inc.
      e. Gravity and lateral load transfer with solid backup
         1) 6500-3 Series Stone-GripTie Anchors by PROSOCO, Inc.

2) 6600-3 Series Stone-GripTie Anchors by PROSOCO, Inc.
3) 6800-3 Series Stone-GripTie Anchors by PROSOCO, Inc.

f. Gravity and lateral load transfer with hollow backup
1) 6500-3 Series Stone-GripTie Anchors by PROSOCO, Inc.
2) 6600-3 Series Stone-GripTie Anchors by PROSOCO, Inc.

C. Helical ties: Provide an in-plane flexible connection between wythes of material, while maintaining a threaded connection to resist out-of-plane loading for both tension and compression resistance.
1. Material:
a. Provide ties and anchors specified in this article that are made from materials that comply with the following, unless otherwise indicated.
1) Stainless steel wire: ASTM A580/A580M, Type [304][316].
2. Application:
a. Masonry veneer to solid concrete backup:
1) Asymmetric Stitch-Tie by PROSOCO, Inc., [8mm][10mm] diameter.
2) Stitch-Tie by PROSOCO, Inc., [8mm][10mm] diameter.
b. Masonry veneer to hollow CMU backup:
1) Stitch-Tie by PROSOCO, Inc., [8mm][10mm] diameter.
c. Masonry Veneer to timber backup:
1) Stitch-Tie by PROSOCO, Inc., [8mm][10mm] diameter.
d. Mass brick masonry:
1) Stitch-Tie by PROSOCO, Inc., [8mm][10mm] diameter.

D. Reinforced Grouted Helical Anchors: Provide stability to a masonry wall by filling voids in loose material by injecting thixotropic grout reinforced with a helical anchor.
1. Material:
a. Provide ties and anchors specified in this article that are made from materials that comply with the following, unless otherwise indicated.
1) Stainless steel wire: ASTM A580/A580M, Type [304][316].
2) Grout: BS EN 998-2.
2. Anchor System
a. Grout-Tie by PROSOCO, Inc.
1) 8mm Stitch-Ties by PROSOCO, Inc.
2) SureGrout S (3900 psi / 27.5 Mpa) by Sure CPS.

E. Injection grout sock anchors: Provide engineered sock anchors composed of an encapsulated reinforced stainless-steel core with injection grout to strengthen masonry and repair cracked or delaminated stone with minimal disruption.
1. Material:
a. Provide ties and anchors specified in this article that are made from materials that comply with the following, unless otherwise indicated.
1) Stainless steel rod: ASTM A276, Type 304.
2) Grout: BS EN 445, 446, 447, 196-1, and 196-3
2. Anchor System
a. Heavy Duty Sock (HDS) Anchor by PROSOCO, Inc.
1) HDS Anchor by PROSOCO, Inc.
2) HDS Single component grout (9430 psi / 65 N/mm^2) by PROSOCO, Inc.

F. Horizontal Reinforcement: Provide supplemental joint reinforcement to reinforce cracked masonry and to create structural beams from existing brick veneers.
1. Material:

a. Provide ties and anchors specified in this article that are made from materials that comply with the following, unless otherwise indicated.
   1) Stainless steel wire: ASTM A580/A580M, Type [304][316].
   2) Grout: BS EN 998-2.

2. Application:
   a. Crack Stitching:
      1) Stitch-Tie Bar by PROSOCO, Inc., [4mm][6mm] diameter.
      2) Grout: SureGrout S (3900 psi / 27.5 Mpa) by Sure CPS.
   b. Structural helical beam reinforcement:
      1) Stitch-Tie Bar by PROSOCO, Inc., 6mm diameter.
      2) Grout: SureGrout S (3900 psi / 27.5 Mpa) by Sure CPS.

2.03 EQUIPMENT

A. Tools and Equipment:
   1. Mechanical expansion anchors:
      a. Hammer drill or SDS+ rotary hammer drill for solid material pilot holes.
      b. Hammer drill for hollow or thin-shelled material pilot holes.
      c. Drill bits, as required.
      d. Appropriate setting tools per anchor variation as noted in the installation instructions.
   2. Thin panel veneer mechanical anchors:
      a. Hammer drill or SDS+ rotary hammer drill for solid material pilot holes.
      b. Hammer drill for hollow or thin-shelled material pilot holes.
      c. Drill bits, as required.
      d. Appropriate setting tools per anchor variation as noted in the installation instructions.
   3. Helical ties:
      a. Hammer drill or SDS+ rotary hammer drill for solid material pilot holes.
      b. Hammer drill for hollow or thin-shelled material pilot holes.
      c. Drill bits, as required.
      d. Setting tool with SDS+ chuck adapter for hammer only installation per the installation instructions.
   4. Reinforced grouted helical anchors:
      a. Hammer drill or SDS+ rotary hammer drill for solid material pilot holes.
      b. Hammer drill for hollow or thin-shelled material pilot holes.
      c. Drill bits, as required.
      d. Grout mixing paddle.
      e. Grout gun.
      f. Grout installation pinning nozzle with the grout gun adapter.
   5. Injection grout sock anchors:
      a. Appropriate rotary hammer drill or rotary only core drill for the substrate.
      b. Drill bits or core bits, as required.
      c. Cement paddle mixing drill.
      d. Mixing buckets, 5-gallon minimum.
      e. HDS Anchor component kit (1 per anchor assembly).
      f. HDS Grout Fill kit (minimum 1 per project).
      g. Grout injection equipment for smaller projects:
         1) Battery-powered Albion grout gun, model DL-59-T13E.
         2) Albion nozzle adapter, model 966-1.
         3) Albion threaded front ring cap, model 421-G01.
         4) PROSOCO Grout gun component kit, includes adapters and an in-line pressure gauge connecting the Albion DL-59-T13E to the PROSOCO HDS hose fitting.
      h. Grout injection equipment for larger projects:

1) Pressure pot, 5-gallon, with a minimum outlet diameter of 1/2", 1/4 turn ball valve for feed control, and a pressure gauge for monitoring feet pressure
   a. Recommended source that meets specifications: Void span 5 gallon pressure pot (https://www.voidspan.com/product/5-gallon-pressure-pot/)
2) Air compressor, minimum 2 H.P.
3) Additional plumbing fittings to adapt the pressure pot feed outlet to the 1/2" diameter PROSOCO HDS hose fitting.

6. Horizontal Reinforcement:
   a. Angle Grinder.
   b. Cement paddle mixing drill.
   c. Manual lever grout gun.
   d. Appropriate Trowel.

PART 3 EXECUTION

3.01 EXAMINATION

A. Examine conditions, with installer present, for compliance with requirements for installation tolerances and other conditions affecting the performance of Work.

B. Do not begin installation until unsatisfactory conditions are resolved. Beginning work constitutes acceptance of site conditions and responsibility for defective installation caused by prior observable conditions.

3.02 PREPARATION

A. Clean dirt, dust, oil, grease, and other contaminants that interfere with penetration or performance of the specified product from surfaces.

B. Locate anchors in the area to be anchored as indicated on the Drawings.

C. Do not proceed until unsatisfactory conditions have been corrected.

D. Install accessory products in accordance with the manufacturer's published recommendations and as noted on Drawings.

3.03 INSTALLATION

A. Install anchor in accordance with manufacturer's published recommendations and mock-up.

B. Mechanical expansion anchor installation:
   1. Select proper anchor length by field verification.
   2. Drill proper pilot hole size per the anchor type. See manufacturer's product data for recommendations.
   3. Blow out drill dust and debris from the pilot hole.
   4. Using the appropriate setting tool or adapter, install the anchor into the pre-drilled hole
   5. Using the appropriate setting tool or adapter, tighten the backup portion of the anchor to the recommended torque range.
   6. Using the appropriate setting tool or adapter, tighten the facade portion of the anchor to the recommended torque range.
   7. Conceal the anchor with the specified patching compound.

C. Thin panel veneer mechanical anchors:
   1. Select proper anchor length by field verification.
   2. Drill proper pilot hole size per the anchor type. See manufacturer's product data for recommendations.
   3. Countersink hole in veneer if required. See manufacturer's product data for recommendations.
   4. Blow out drill dust and debris from the pilot hole.
   5. Using the appropriate setting tool or adapter, install the anchor into the pre-drilled hole
   6. Using the appropriate setting tool or adapter, tighten the backup portion of the anchor to the recommended torque range.
   7. Using the appropriate setting tool or adapter, install toggle if applicable.
   8. Install the anchor head, washer, and gasket on the threaded shaft.
   9. Conceal the anchor with the specified patching compound if countersunk.

D. Helical tie installation:
   1. Select proper anchor length by field verification.
   2. Drill proper pilot hole size per the anchor type. See manufacturer's product data for recommendations.
   3. Install helical tie into the dry setting too mounted in an SDS drill.
   4. Drive the helical tie anchor in the pilot hole and into the backup material.
   5. The setting tool will recess the helical tie approximately 3/8 inch from the surface.
   6. Conceal anchor with specified patching compound.
   7. Space anchors in a staggered diamond pattern 16 inches on center vertically and 18 inches on center horizontally (1 Tie per 2 square feet). Install additional anchors within 8 inches of openings and discontinuities per BIA Technical note 44b.

E. Reinforced grouted helical anchor installation:
   1. Select proper anchor length by field verification.
   2. Drill proper pilot hole size per the anchor type. See manufacturer's product data for recommendations.
   3. Clean the hole with water.
   4. Prepare the helical anchor within the grout pinning nozzle.
   5. Insert into the back of the drilled hole.
   6. As the grout is injected, the helical anchor is carried with it.
   7. Backpressure pushes the nozzle out of the hole to leave the full grouted tie in place.

F. Injection grout sock anchor installation:
   1. Select proper anchor length by field verification.
   2. Drill proper pilot hole size per the anchor type. See manufacturer's product data for recommendations.
   3. Clean to ensure all debris is removed from the hole. Blow out drill dust and debris from the pilot hole.
   4. Screw the blanking plug to the end of the sock anchor and install the anchor into the drilled hole, connecting the anchors to the desired length.
   5. Attach the grout fill kit to the threaded end of the sock anchor.
   6. Add the appropriate amount of water to the mixing bucket, limit water content to 6 to 7 liters maximum per 44 lb bag.
   7. Add the appropriate amount of powder grout.
   8. Mix the grout for a minimum of 2 minutes until a very fluid but creamy uniform consistency is attained. Always maintain the correct working ratio, as per the manufacturer's instructions.
   9. Till the sock anchor using either the battery-operated grout gun or pressure pot with an air compressor. Limit the installation pressure to 44 psi.

10. Once the grout milk is seen running from the hole, stop the pumping and let it “relax” for a minimum of three minutes.
11. Clamp the pipe and remove the filling equipment.
12. Leave the exposed hose on the threaded sock anchor tube for two to three hours after installation prior to removal.
13. Patch the remaining hole with the specified patching compound, color-matched to the existing substrate.

G. Horizontal Reinforcement:
   1. Grind away existing mortar, 20 inches minimum on each side of the crack, 1-1/2 inch to 2 inches deep.
   2. Clean with water.
   3. Apply a bead of the manufacturer’s recommended grout.
   4. Insert the helical tie bar into the bead of the manufacturer’s recommended grout.
   5. Apply a bead of grout over the helical tie bar.
   6. If an additional helical tie bar is required, insert it into the bead of the manufacturer’s recommended grout.
   7. Apply a final bead of grout over the additional helical tie bar if required.
   8. Compact with an appropriate trowel.

3.04 FIELD QUALITY CONTROL

A. Site testing is encouraged for verification of helical or mechanical expansion anchor load capacity. Each construction site is unique and the appropriate use of this product is the responsibility of the engineers, architects, and other professionals who are familiar with the specific requirements of the project.
   1. Testing Agency: [Owner will engage] [Engage] a qualified testing agency to perform tests and inspections. Allow inspectors access to scaffolding and work areas as needed to perform tests and inspections. Re-testing of materials that fail to comply with specified requirements will be at the Contractor's expense.

END OF SECTION

SECTION 04 10 00 - MORTAR AND MASONRY GROUT FOR MASONRY

1. Part 1 - GENERAL

1.1. SECTION INCLUDES
   A. Mortar for manufactured stone.

1.2. ENVIRONMENTAL REQUIREMENTS
   A. Cold Weather Requirements: IMIAC - Recommended Practices and Guide Specifications for Cold Weather Masonry Construction.
   B. Hot Weather Requirements: IMIAC - Recommended Practices and Guide Specifications for Hot Weather Masonry Construction

2. PART 2 – PRODUCTS

2.1. MATERIALS
   A. Portland Cement: ASTM C150, Type I gray color.
   B. Premix Mortar: ASTM C387, using gray cement, Normal strength.
   C. Mortar Aggregate: ASTM C144, standard masonry type.
   D. Hydrated Lime: ASTM C207, Type N.
   E. Grout materials and proportions: ASTM C476.
   F. Water: Clean and potable.
   G. Waterproofing Admixture: W.R. Grace Co. “Dry Block”,, application rate as recommended by manufacturer for each specific application.

2.2. MORTAR MIXES
   A. Ready Mixed Mortar: (optional) ASTM C1142, Type S.
   B. Mortar for Non-load Bearing Walls and Partitions: (optional) ASTM C270, Type S or Type N using the Property Method.
   C. Pointing Mortar for Masonry: (optional) ASTM C270, Type S or Type N using the Property Method; with maximum 2 percent ammonium stearate or calcium stearate per cement weight.

2.3. MORTAR MIXING
   A. Thoroughly mix mortar ingredients in quantities needed for immediate use in accordance with ASTM C270.
   B. Add admixtures in accordance with manufacturer’s instructions.
   C. Do not use anti-freeze compounds to lower the freezing point of mortar.

2.4. MIX TESTS
   A. Test mortar and group and submit laboratory report of 3 cube tests.
   B. Testing or Mortar Mix: In accordance with ASTM C780.

3. PART 3 – EXECUTION

3.1. EXAMINATION AND PREPARATION
   A. Examine materials to be set and report irregularities to be corrected before beginning work.

3.2. INSTALLATION
   A. Install mortar in accordance with local code and standard practice.

3.3. SCHEDULES
   A. All masonry work = Type S mortar with Type S pointing mortar.

END OF SECTION 04 10 00

SECTION 042113 - BRICK MASONRY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

B. Face brick – Match existing face brick. Verify at job site.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

B. Samples: For each type and color of brick and colored mortar.

1.3 INFORMATIONAL SUBMITTALS

A. Material Certificates: For each type and size of product indicated.

1.4 QUALITY ASSURANCE

A. Masonry Standard: Comply with ACI 530.1/ASCE 6/TMS 602 unless modified by requirements in the Contract Documents.

B. Sample Panels: Build sample panels to verify selections made under sample submittals and to demonstrate aesthetic effects. Comply with requirements in Section 014000 "Quality Requirements" for mockups.

1. Build sample panels for each type of exposed unit masonry construction in sizes approximately 48 inches long by 48 inches by full thickness.

1.5 PROJECT CONDITIONS

A. Cold-Weather Requirements: Do not use frozen materials or materials mixed or coated with ice or frost. Do not build on frozen substrates. Remove and replace unit masonry damaged by frost or by freezing conditions. Comply with cold-weather construction requirements contained in ACI 530.1/ASCE 6/TMS 602.

1. Cold-Weather Cleaning: Use liquid cleaning methods only when air temperature is 40 deg F and higher and will remain so until masonry has dried, but not less than seven days after completing cleaning.

B. Hot-Weather Requirements: Comply with hot-weather construction requirements contained in ACI 530.1/ASCE 6/TMS 602.

PART 2 - PRODUCTS

2.1 MASONRY UNITS, GENERAL

A. Defective Units: Referenced masonry unit standards may allow a certain percentage of units to contain chips, cracks, or other defects exceeding limits stated in the standard. Do not use units where such defects will be exposed in the completed Work.

2.2 BRICK

A. General: Provide shapes indicated and as follows.

1. For ends of sills and caps and for similar applications that would otherwise expose unfinished brick surfaces, provide units without cores or frogs and with exposed surfaces finished.
2. Provide special shapes for applications where shapes produced by sawing would result in sawed surfaces being exposed to view.

B. Face Brick: Facing brick complying with ASTM C 216. Match existing Face brick and Glazed brick at job site.

1. Products: Subject to compliance with requirements, provide an Allowance of $950.00 per thousand brick and provide the following:

2. Grade: SW.
3. Type: FBS.
4. Initial Rate of Absorption: Less than 30 g/30 sq. in. per minute when tested per ASTM C 67.
5. Efflorescence: Provide brick that has been tested according to ASTM C 67 and is rated "not effloresced."
6. Size (Actual Dimensions): 3-5/8 inches wide by 2-1/4 inches high by 7-5/8 inches long.

2.3 MORTAR MATERIALS

A. Masonry Cement: ASTM C 91, Type N.

1. Products: Subject to compliance with requirements, provide products by one of the following:

a. Cemex S.A.B. de C.V.
b. Holcim (US) Inc.
c. Lafarge North America Inc.
d. Lehigh Cement Company.
e. National Cement Company, Inc.

B. Aggregate for Mortar: ASTM C 144; Natural sand or crushed stone.

C. Cold-Weather Admixture: Nonchloride, noncorrosive, accelerating admixture complying with ASTM C 494/C 494M, Type C, and recommended by manufacturer for use in masonry mortar of composition indicated.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Euclid Chemical Company (The); Accelguard 80.
b. Grace Construction Products; W.R. Grace & Co. -- Conn; Morset.
c. Sonneborn Products; Trimix-NCA.

2.4 REINFORCEMENT

A. Masonry Joint Reinforcement, General: ASTM A 951/A 951M.
1. 1. Interior Walls: Mill galvanized carbon steel.
2. 2. Exterior Walls: Hot-dip galvanized carbon steel.
3. 3. Wire Size for Side Rods: 0.148-inch diameter.
4. 4. Wire Size for Cross Rods: 0.148-inch diameter.
5. 5. Wire Size for Veneer Ties: 0.148-inch diameter.
6. 6. Spacing of Cross Rods, Tabs, and Cross Ties: Not more than 16 inches o.c.
7. 7. Provide in lengths of not less than 10 feet, with prefabricated corner and tee units.

B. Masonry-Joint Reinforcement for Single-Wythe Masonry: Ladder type with single pair of side rods.

1. Products: Subject to compliance with requirements, provide one of the following:
a. Hohmann & Benard, Inc; 220 Ladder-Mesh Reinforcement
b. Wire-Bond; Series 200 Ladder Mesh

C. Masonry Joint Reinforcement for Veneers Anchored with Seismic Masonry-Veneer Anchors: Ladder type, single 0.187-inch diameter, hot-dip galvanized, carbon-steel continuous wire.

1. Products: Subject to compliance with requirements, provide one of the following:
a. Hohmann & Benard, Inc; 270-2X-Hook with Welded Seismic Clip
b. Wire-Bond; Series 800 Ladder Level-Eye with Seismic Metal Clip

D. Adjustable (two-piece) type, either ladder or truss design, with one side rod at each face shell of backing wythe and with separate adjustable ties with high strength pintle. Pintle- and-eye connections having a maximum horizontal play of 1/16 inch (1.5 mm) and maximum vertical adjustment of 1-1/4 inches (32 mm). Structural performance is capable of withstanding a 100 lbf (445 N) minimum (as per BIA tech notes 44B) load in both tension and compression without deforming beyond 0.05 inch (1.3 mm). Size ties to extend at least halfway through facing wythe but with at least 5/8-inch (16-mm) cover on outside face.

1. Products: Subject to compliance with requirements, provide one of the following:
a. Hohmann & Benard, Inc; 270-2X Ladder Eye-Wire Reinforcement
b. Wire-Bond; Series 800 Ladder Level-Eye

2.5 TIES AND ANCHORS

A. Materials: Provide ties and anchors specified in this article that are made from materials that comply with the following unless otherwise indicated:

1. Hot-Dip Galvanized, Carbon-Steel Wire: ASTM A 82/A 82M; with ASTM A 153/A 153M, Class B-2 coating.
2. Steel Sheet, Galvanized after Fabrication: ASTM A 1008/A 1008M, Commercial Steel, with ASTM A 153/A 153M, Class B coating.

B. Wire Ties, General: Unless otherwise indicated, size wire ties to extend at least halfway through veneer but with at least 5/8-inch cover on outside face. Outer ends of wires are bent 90 degrees and extend 2 inches parallel to face of veneer.

C. Adjustable Anchors for Connecting to Structural Steel Framing: Provide anchors that allow vertical or horizontal adjustment but resist tension and compression forces perpendicular to plane of wall.

1. Anchor Section for Welding to Steel Frame: Crimped 1/4-inch diameter, hot-dip galvanized steel wire.
2. Tie Section: Triangular-shaped wire tie, sized to extend within 1 inch of masonry face, made from 0.187-inch diameter, hot-dip galvanized steel wire.
   a. Products: Subject to compliance with requirements, provide one of the following:
      1) Hohmann & Benard, Inc; 359 Weld-on Column Anchor
      2) Wire-Bond; 1000 Type l Weld-on Anchor

D. Adjustable Anchors for Connecting to Concrete: Provide anchors that allow vertical or horizontal adjustment but resist tension and compression forces perpendicular to plane of wall.

1. Connector Section: Dovetail tabs for inserting into dovetail slots in concrete and attached to tie section; formed from 0.060-inch thick, steel sheet, galvanized after fabrication.
2. Tie Section: Triangular-shaped wire tie, sized to extend within 1 inch of masonry face, made from 0.187-inch diameter, hot-dip galvanized steel wire.
3. Corrugated Metal Ties: Metal strips not less than 7/8 inch wide with corrugations having a wavelength of 0.3 to 0.5 inch and an amplitude of 0.06 to 0.10 inch made from 0.060-inch thick, steel sheet, galvanized after fabrication with dovetail tabs for inserting into dovetail slots in concrete and sized to extend to within 1 inch of masonry face.
   a. Products: Subject to compliance with requirements, provide one of the following:
      1) Hohmann & Benard, Inc; 345-BT- Flexible Tie
      2) Wire-Bond; 2102 Dovetail Triangular Tie

E. Adjustable Masonry-Veneer Anchors:

1. General: Provide anchors that allow vertical adjustment but resist tension and compression forces perpendicular to plane of wall, for attachment over sheathing to wood or metal studs, and as follows:

   a. Structural Performance Characteristics: Capable of withstanding a 100-lbf load in both tension and compression without deforming or developing play in excess of 0.05 inch.

2. Screw-Attached, Masonry-Veneer Anchors: Anchors masonry with minimal thermal bridging.

    a. Basis of Design: Subject to compliance requirements, provide one of the following:
        1) Dayton Superior Corporation, Dur-O-Wal Division. No longer available.
        2) Heckmann Building Products, Inc.; Pos-l-Tie Thermaclip System
        3) Hohmann & Barnard, Inc.; 2-Seal Thermal Wing Nut Anchor
        Wire-Bond; 4522 SureTie WS Anchor System (no thermal bridging found, see Test Method for the Thermal Performance of Building Assemblies by Means of Hot Box Apparatus.)

    b. Anchor Section: Barrel: Sabic Lexan 143 Polycarbonate. Wire Tie: ASTM A580 Stainless Steel 304, Tensile 102,500 – 150,000, Yield 70,000 psi. Washer is Polypropylene with carbon black UV stabilizer. Screw is ASTM A510 Carbon Steel. Screw Pull Out Values CMU Block: 476 lbs. Wood: 662 lbs. 18ga: 694 lbs. 16 ga: 896 lbs.
    c. Products: Subject to compliance with requirements, provide one of the following:
        1) Heckmann Building Products, Inc.; Original Pos-l-Tie Anchoring System
        2) Hohmann & Benard, Inc; 2-Seal Tie
        3) Wire-Bond; 4522 SureTie WS Anchor System

2.6 EMBEDDED FLASHING MATERIALS

A. Metal Flashing: Provide metal flashing complying with SMACNA's "Architectural Sheet Metal Manual," Section 076200 "Sheet Metal Flashing and Trim" and as follows:

1. Metal Drip Edge: Fabricate from stainless steel. Extend at least 3 inches into wall and 1/2 inch out from wall, with outer edge bent down 30 degrees and hemmed.
2. Metal Sealant Stop: Fabricate from stainless steel. Extend at least 3 inches into wall and out to exterior face of wall. At exterior face of wall, bend metal back on itself for 3/4 inch and down into joint 1/4 inch to form a stop for retaining sealant backer rod.

    a. Products: Subject to compliance with requirements, provide one of the following:
        1) Hohmann & Benard, Inc; DP – Drip Plates/Edges
        2) Wire-Bond; 4165 Drip Edge Flashing

B. Flexible Flashing: Use one of the following unless otherwise indicated:

1. Stainless Steel Flashing: Composite self-adhering flashing consisting of 2 mil Type 304 stainless steel sheet bonded on one side to a polymer fabric with a permanent clear PSA adhesive and a removable silicone-coated release liner. The total thickness of the composite material, including the release liner, is 12 mils. Type: ASTM A240/A240M.

    a. Products: Subject to compliance with requirements, provide one of the following:
        1) Wire-Bond; 4160 BOND-N-FLASH SA
        2) York Manufacturing, Inc; York 304 SA SS

2. Non-Asphaltic Flashing: Composite self-adhering flashing consisting of a woven coated membrane bonded to a polyethylene film with a custom formulated, high-content Butyl adhesive. The overall thickness shall be not less than 0.040 inch.

   a. Products: Subject to compliance with requirements, provide one of the following:
      1) Hohmann & Benard, Inc; TEXTROFLASH
      2) Wire-Bond; 4160 BOND-N-FLASH SA

3. Rubberized-Asphalt Flashing: Composite flashing self-adhering product consisting of a pliable, adhesive rubberized-asphalt compound, bonded to a high-density, cross-laminated polyethylene film to produce an overall thickness of not less than 0.040 inch.

   a. Products: Subject to compliance with requirements, provide one of the following:

      1) Carlisle Coatings & Waterproofing Inc; CCW-705-TWF Thru-Wall Flashing.
      2) Grace Construction Products; W.R. Grace & Co. -- Conn; Perm-A-Barrier Wall Flashing.
      3) Hohmann & Barnard, Inc; Textroflash.
      4) Meadows, W.R.,Inc; Air-Shield Thru-Wall Flashing.
      5) Williams Products, Inc; Everlastic MF-40.
      6) Wire-Bond; 4120 Aqua Flash 500
      7) Termination Bar: Install per flashing manufacturer guidelines at wall flashing location by each manufacturers listed above.

4. EPDM Flashing: Sheet flashing product made from ethylene-propylene-diene terpolymer, complying with ASTM D 4637, 0.040 inch thick.

   a. Products: Subject to compliance with requirements, provide one of the following:

      1) Carlisle Coatings & Waterproofing Inc; Pre-Kleened EPDM Thru-Wall Flashing.
      2) Firestone Specialty Products; FlashGuard.
      3) Wire-Bond; 4192 EPDM Thru-Wall Flashing

C. Size: Width as required. Masonry through-wall flashing shall extend the full width of the cavity and project not less than 6 inches above the top of the cavity drainage material. Secure the top edge of flashing with a continuous termination bar and seal with manufacturer's approved sealant.

D. Termination Bars for Flexible Flashing: [Aluminum] [Stainless steel] bars 1/8 inch by 1 inch.

   a) Products: Subject to compliance with requirements, provide one of the following:
      1) Hohmann & Benard, Inc; T1 Termination Bar
      2) Wire-Bond; 4200 Termination Bar

E. Solder and Sealants for Sheet Metal Flashings: As specified in Section 076200 "Sheet Metal Flashing and Trim."

F. Adhesives, Primers, and Seam Tapes for Flashings: Flashing manufacturer's standard products or products recommended by flashing manufacturer for bonding flashing sheets to each other and to substrates.

2.7 MISCELLANEOUS MASONRY ACCESSORIES

A. Compressible Filler: Premolded filler strips complying with ASTM D 1056, Grade 2A1; compressible up to 35 percent; formulated from neoprene, urethane or PVC.

B. Bond-Breaker Strips: Asphalt-saturated, organic roofing felt complying with ASTM D 226, Type I (No. 15 asphalt felt).

C. Weep/Vent Products:

1. Cellular Plastic Weep/Vent: One-piece, flexible extrusion made from UV-resistant polypropylene copolymer, full height and width of joint and depth 1/8 inch less than depth of outer wythe, in color selected from manufacturer's standard.

a. Products: Subject to compliance with requirements, provide one of the following:

1) Advanced Building Products Inc; Mortar Maze weep vent.
2) BLOK-LOK Limited; Cell-Vent.
3) Heckmann Building Products, Inc; No. 85 Cell Vent.
4) Hohmann & Barnard, Inc; Quadro-Vent.
5) Wire-Bond; 3601 Cell Vent

D. Cavity Drainage Material: Free-draining mesh, made from polymer strands that will not degrade within the wall cavity.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Advanced Building Products Inc; Mortar Break.
b. Hohmann & Barnard, Inc; Mortar Trap
c. Mortar Net USA, Ltd; Mortar Net.
d. Wire-Bond; C3611D Cavity Net DT

2. Provide the following configuration:

a. Strips, full-depth of cavity air space and 10 inches high, with dovetail shaped notches 7 inches deep.

2.8 MASONRY CLEANERS

A. Proprietary Acidic Cleaner: Manufacturer's standard-strength cleaner designed for removing mortar/grout stains, efflorescence, and other new construction stains from new masonry without discoloring or damaging masonry surfaces. Use product expressly approved for intended use by cleaner manufacturer and manufacturer of masonry units being cleaned.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Diedrich Technologies, Inc.
b. EaCo Chem, Inc.
c. PROSOCO, Inc.

2.9 MORTAR MIXES

A. General: Do not use admixtures, including pigments, air-entraining agents, accelerators, retarders, water-repellent agents, antifreeze compounds, or other admixtures unless otherwise indicated.

1. Do not use calcium chloride in mortar.
2. Use masonry cement mortar unless otherwise indicated.
3. Add cold-weather admixture (if used) at same rate for all mortar that will be exposed to view, regardless of weather conditions, to ensure that mortar color is consistent.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Use full-size units without cutting if possible. If cutting is required to provide a continuous pattern or to fit adjoining construction, cut units with motor-driven saws; provide clean, sharp, unchipped edges. Allow units to dry before laying unless wetting of units is specified. Install cut units with cut surfaces and, where possible, cut edges concealed.

B. Select and arrange units for exposed unit masonry to produce a uniform blend of colors and textures.

C. Wetting of Brick: Wet brick before laying if initial rate of absorption exceeds 30 g/30 sq. in. per minute when tested per ASTM C 67. Allow units to absorb water so they are damp but not wet at time of laying.

3.2 TOLERANCES

A. Dimensions and Locations of Elements:

1. For dimensions in cross section or elevation do not vary by more than plus 1/2 inch or minus 1/4 inch.
2. For location of elements in plan do not vary from that indicated by more than plus or minus 1/2 inch.
3. For location of elements in elevation do not vary from that indicated by more than plus or minus 1/4 inch in a story height or 1/2 inch total.

B. Lines and Levels:

1. For bed joints and top surfaces of bearing walls do not vary from level by more than 1/4 inch in 10 feet, or 1/2 inch maximum.
2. For conspicuous horizontal lines, such as lintels, sills, parapets, and reveals, do not vary from level by more than 1/8 inch in 10 feet, 1/4 inch in 20 feet, or 1/2 inch maximum.

3. For vertical lines and surfaces do not vary from plumb by more than 1/4 inch in 10 feet, 3/8 inch in 20 feet, or 1/2 inch maximum.
4. For conspicuous vertical lines, such as external corners, door jambs, reveals, and expansion and control joints, do not vary from plumb by more than 1/8 inch in 10 feet, 1/4 inch in 20 feet, or 1/2 inch maximum.
5. For lines and surfaces do not vary from straight by more than 1/4 inch in 10 feet, 3/8 inch in 20 feet, or 1/2 inch maximum.

C. Joints:

1. For bed joints, do not vary from thickness indicated by more than plus or minus 1/8 inch, with a maximum thickness limited to 1/2 inch; do not vary from bed-joint thickness of adjacent courses by more than 1/8 inch.
2. For exposed head joints, do not vary from thickness indicated by more than plus or minus 1/8 inch. Do not vary from adjacent bed-joint and head-joint thicknesses by more than 1/8 inch.

3.3 LAYING MASONRY WALLS

A. Lay out walls in advance for accurate spacing of surface bond patterns with uniform joint thicknesses and for accurate location of openings, movement-type joints, returns, and offsets. Avoid using less-than-half-size units, particularly at corners, jambs, and, where possible, at other locations.

B. Bond Pattern for Exposed Masonry: Unless otherwise indicated, lay exposed masonry in running bond; do not use units with less than nominal 4-inch horizontal face dimensions at corners or jambs.

C. Built-in Work: As construction progresses, build in items specified in this and other Sections. Fill in solidly with masonry around built-in items.

D. Fill space between steel frames and masonry solidly with mortar unless otherwise indicated.

3.4 MORTAR BEDDING AND JOINTING

A. Lay hollow brick as follows:

1. With face shells fully bedded in mortar and with head joints of depth equal to bed joints.
2. With entire units, including areas under cells, fully bedded in mortar at starting course on footings.

B. Lay solid masonry units with completely filled bed and head joints; butter ends with sufficient mortar to fill head joints and shove into place. Do not deeply furrow bed joints or slush head joints.

C. Tool exposed joints slightly concave when thumbprint hard, using a jointer larger than joint thickness unless otherwise indicated.

3.5 ANCHORING MASONRY TO STRUCTURAL STEEL AND CONCRETE

A. Anchor masonry to structural steel and concrete where masonry abuts or faces structural steel or concrete to comply with the following:

1. Provide an open space not less than 1/2 inch wide between masonry and structural steel or concrete unless otherwise indicated. Keep open space free of mortar and other rigid materials.
2. Anchor masonry with anchors embedded in masonry joints and attached to structure.
3. Space anchors as indicated, but not more than 24 inches o.c. vertically and 36 inches o.c. horizontally.

3.6 ANCHORING MASONRY VENEERS

A. Anchor masonry veneers to wall framing with masonry-veneer anchors to comply with the following requirements:

1. Fasten screw-attached anchors through sheathing to wall framing with metal fasteners of type indicated. Use two fasteners unless anchor design only uses one fastener.
2. Embed tie sections in masonry joints.
3. Locate anchor sections to allow maximum vertical differential movement of ties up and down.
4. Space anchors as indicated, but not more than 16 inches o.c. vertically and 32 inches o.c. horizontally with not less than 1 anchor for each 3.5 sq. ft. of wall area. Install additional anchors within 12 inches of openings and at intervals, not exceeding 36 inches, around perimeter.

3.7 FLASHING, WEEP HOLES, CAVITY DRAINAGE, AND VENTS

A. General: Install embedded flashing and weep holes in masonry at shelf angles, lintels, ledges, other obstructions to downward flow of water in wall, and where indicated. Install vents at shelf angles, ledges, and other obstructions to upward flow of air in cavities, and where indicated.

B. Install flashing as follows unless otherwise indicated:

1. Prepare masonry surfaces so they are smooth and free from projections that could puncture flashing. Where flashing is within mortar joint, place through-wall flashing on sloping bed of mortar and cover with mortar. Before covering with mortar, seal penetrations in flashing with adhesive, sealant, or tape as recommended by flashing manufacturer.
2. At lintels and shelf angles, extend flashing a minimum of 6 inches into masonry at each end. At heads and sills, extend flashing 6 inches at ends and turn up not less than 2 inches to form end dams.
3. Install metal drip edges beneath flexible flashing at exterior face of wall. Stop flexible flashing 1/2 inch back from outside face of wall and adhere flexible flashing to top of metal drip edge.

4. Install metal flashing termination beneath flexible flashing at exterior face of wall. Stop flexible flashing 1/2 inch back from outside face of wall and adhere flexible flashing to top of metal flashing termination.

C. Install weep holes in head joints in exterior wythes of first course of masonry immediately above embedded flashing and as follows:

1. Use specified weep/vent products to form weep holes.
2. Space weep holes 24 inches o.c. unless otherwise indicated.

D. Place cavity drainage material in cavities to comply with configuration requirements for cavity drainage material in "Miscellaneous Masonry Accessories" Article.

E. Install vents in head joints in exterior wythes at spacing indicated. Use specified weep/vent products to form vents.

1. Close cavities off vertically and horizontally with blocking in manner indicated. Install through-wall flashing and weep holes above horizontal blocking.

3.8 FIELD QUALITY CONTROL

A. Testing and Inspecting: Owner will engage special inspectors to perform tests and inspections and prepare reports. Allow inspectors access to scaffolding and work areas, as needed to perform tests and inspections. Retesting of materials that fail to meet specified requirements shall be done at Contractor's expense.

B. Inspections: Level 1 special inspections according to the "International Building Code."

1. Begin masonry construction only after inspectors have verified proportions of site-prepared mortar.

C. Mortar Aggregate Ratio Test (Proportion Specification): For each mix provided, according to ASTM C 780.

3.9 CLEANING

A. In-Progress Cleaning: Clean unit masonry as work progresses by dry brushing to remove mortar fins and smears before tooling joints.

B. Final Cleaning: After mortar is thoroughly set and cured, clean exposed masonry as follows:

1. Test cleaning methods on sample wall panel; leave one-half of panel uncleaned for comparison purposes
2. Protect adjacent surfaces from contact with cleaner.
3. Wet wall surfaces with water before applying cleaners; remove cleaners promptly by rinsing surfaces thoroughly with clear water.
4. Clean brick by bucket-and-brush hand-cleaning method described in "BIA Technical Notes 20."
5. Clean masonry with a proprietary acidic cleaner applied according to manufacturer's written instructions.

6. Clean concrete masonry by cleaning method indicated in NCMA TEK 8-2A applicable to type of stain on exposed surfaces.

3.10 MASONRY WASTE DISPOSAL

A. Waste Disposal as Fill Material: Dispose of clean masonry waste, including excess or soil-contaminated sand, waste mortar, and broken masonry units, by crushing and mixing with fill material as fill is placed.

1. Do not dispose of masonry waste as fill within 18 inches of finished grade.

B. Excess Masonry Waste: Remove excess clean masonry waste that cannot be used as fill, as described above, and other masonry waste, and legally dispose of off Owner's property.

END OF SECTION 042113

SECTION 061000 - ROUGH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Wood blocking, cants and nailers.
2. Wood furring and grounds.
3. Plywood backing panels.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of process and factory-fabricated product.

1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements
2. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements.

1.3 INFORMATIONAL SUBMITTALS

A. Material Certificates: For dimension lumber specified to comply with minimum allowable unit stresses. Indicate species and grade selected for each use and design values approved by the ALSC Board of Review.

B. Evaluation Reports: For the following, from ICC-ES:

1. Wood-preservative-treated wood.
2. Fire-retardant-treated wood.
3. Engineered wood products.
4. Shear panels.
5. Power-driven fasteners.
6. Powder-actuated fasteners.
7. Expansion anchors.
8. Metal framing anchors.

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS, GENERAL

A. Lumber: DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, provide lumber that complies with the applicable rules of any rules-writing agency

certified by the ALSC Board of Review. Provide lumber graded by an agency certified by the ALSC Board of Review to inspect and grade lumber under the rules indicated.

1. Factory mark each piece of lumber with grade stamp of grading agency.
2. For exposed lumber indicated to receive a stained or natural finish, mark grade stamp on end or back of each piece.
3. Provide dressed lumber, S4S, unless otherwise indicated.

B. Maximum Moisture Content of Lumber: 15 percent for 2-inch nominal thickness or less, 19 percent for more than 2-inch nominal unless otherwise indicated.

C. Engineered Wood Products: Provide engineered wood products acceptable to authorities having jurisdiction and for which current model code research or evaluation reports exist that show compliance with building code in effect for Project.

1. Allowable Design Stresses: Provide engineered wood products with allowable design stresses, as published by manufacturer, that meet or exceed those indicated. Manufacturer's published values shall be determined from empirical data or by rational engineering analysis and demonstrated by comprehensive testing performed by a qualified independent testing agency.

2.2 WOOD-PRESERVATIVE-TREATED LUMBER

A. Preservative Treatment by Pressure Process: AWPA U1; Use Category UC2 for interior construction not in contact with the ground, Use Category UC3b for exterior construction not in contact with the ground, and Use Category UC4a for items in contact with the ground.

1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium. Do not use inorganic boron (SBX) for sill plates.

B. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Do not use material that is warped or that does not comply with requirements for untreated material.

C. Mark lumber with treatment quality mark of an inspection agency approved by the ALSC Board of Review.

D. Application: Treat items indicated on Drawings, and the following:

1. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.
2. Wood sills, sleepers, blocking, furring, stripping and similar concealed members in contact with masonry or concrete.
3. Wood framing and furring attached directly to the interior of below-grade exterior masonry or concrete walls.
4. Wood framing members that are less than 18 inches above the ground in crawlspaces or unexcavated areas.
5. Wood floor plates that are installed over concrete slabs-on-grade.

2.3 FIRE-RETARDANT-TREATED MATERIALS

A. General: Where fire-retardant-treated materials are indicated, use materials complying with requirements in this article, that are acceptable to authorities having jurisdiction, and with fire-test-response characteristics specified as determined by testing identical products per test method indicated by a qualified testing agency.

B. Fire-Retardant-Treated Lumber and Plywood by Pressure Process: Products with a flame spread index of 25 or less when tested according to ASTM E 84, and with no evidence of significant progressive combustion when the test is extended an additional 20 minutes, and with the flame front not extending more than 10.5 feet beyond the centerline of the burners at any time during the test.

1. Exterior Type: Treated materials shall comply with requirements specified above for fire-retardant-treated lumber and plywood by pressure process after being subjected to accelerated weathering according to ASTM D 2898. Use for exterior locations and where indicated.
2. Interior Type A: Treated materials shall have a moisture content of 28 percent or less when tested according to ASTM D 3201 at 92 percent relative humidity. Use where exterior type is not indicated.

C. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Kiln-dry plywood after treatment to a maximum moisture content of 15 percent.

D. Identify fire-retardant-treated wood with appropriate classification marking of qualified testing agency.

E. Application: Treat items indicated on Drawings, and the following:

1. Lumber located in Roof construction.

2.4 MISCELLANEOUS LUMBER

A. General: Provide miscellaneous lumber indicated and lumber for support or attachment of other construction, including the following:

1. Blocking.
2. Nailers.
3. Cants.
4. Furring.
5. Grounds.

B. For items of dimension lumber size, provide Construction or No. 2 grade lumber of any species.

C. For concealed boards, provide lumber with 15 percent maximum moisture content and any of the following species and grades:

1. Mixed southern pine; No. 2 grade; SPIB.
2. Eastern softwoods; No. 2 Common grade; NeLMA.
3. Northern species; No. 2 Common grade; NLGA.

4. Western woods; Construction or No. 2 Common grade; WCLIB or WWPA.

2.5 PLYWOOD BACKING PANELS

A. Equipment Backing Panels: DOC PS 1, Exterior, AC in thickness indicated or, if not indicated, not less than 3/4-inch nominal thickness.

2.6 FASTENERS

A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.

1. Where rough carpentry is exposed to weather, in ground contact, pressure-preservative treated, or in area of high relative humidity, provide fasteners of Type 304 stainless steel.

B. Power-Driven Fasteners: NES NER-272.

C. Bolts: Steel bolts complying with ASTM A 307, Grade A; with ASTM A 563 hex nuts and, where indicated, flat washers.

2.7 METAL FRAMING ANCHORS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Cleveland Steel Specialty Co.
2. KC Metals Products, Inc.
3. Phoenix Metal Products, Inc.
4. Simpson Strong-Tie Co., Inc.
5. USP Structural Connectors.

B. Allowable Design Loads: Provide products with allowable design loads, as published by manufacturer, that meet or exceed those of products of manufacturers listed. Manufacturer's published values shall be determined from empirical data or by rational engineering analysis and demonstrated by comprehensive testing performed by a qualified independent testing agency.

C. Galvanized-Steel Sheet: Hot-dip, zinc-coated steel sheet complying with ASTM A 653/A 653M, G60 coating designation.

1. Use for interior locations unless otherwise indicated.

D. Hot-Dip, Heavy-Galvanized Steel Sheet: ASTM A 653/A 653M; structural steel (SS), high-strength low-alloy steel Type A (HSLAS Type A), or high-strength low-alloy steel Type B (HSLAS Type B); G185 coating designation; and not less than 0.036 inch thick.

1. Use for wood-preservative-treated lumber and where indicated.

2.8 MISCELLANEOUS MATERIALS

A. Flexible Flashing: Composite, self-adhesive, flashing product consisting of a pliable, butyl rubber compound, bonded to a high-density polyethylene film, aluminum foil, or spunbonded polyolefin to produce an overall thickness of not less than 0.025 inch.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Set rough carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit rough carpentry to other construction; scribe and cope as needed for accurate fit. Locate furring, nailers, blocking, grounds and similar supports to comply with requirements for attaching other construction.

B. Metal Framing Anchors: Install metal framing anchors to comply with manufacturer's written instructions. Install fasteners through each fastener hole.

C. Do not splice structural members between supports unless otherwise indicated.

D. Comply with AWPA M4 for applying field treatment to cut surfaces of preservative-treated lumber.

E. Where wood-preservative-treated lumber is installed adjacent to metal decking, install continuous flexible flashing separator between wood and metal decking.

F. Securely attach rough carpentry work to substrate by anchoring and fastening as indicated, complying with the following:

1. NES NER-272 for power-driven fasteners.
2. Table 2304.9.1, "Fastening Schedule," in ICC's International Building Code.
3. Table R602.3(1), "Fastener Schedule for Structural Members," and Table R602.3(2), "Alternate Attachments," in ICC's International Residential Code for One- and Two-Family Dwellings.

3.2 PROTECTION

A. Protect wood that has been treated with inorganic boron (SBX) from weather. If, despite protection, inorganic boron-treated wood becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

B. Protect rough carpentry from weather. If, despite protection, rough carpentry becomes sufficiently wet that moisture content exceeds that specified, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION 061000

SECTION 061600 - SHEATHING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Wall sheathing.
2. Sheathing joint and penetration treatment.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated plywood complies with requirements.
2. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated plywood complies with requirements.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Test-Response Characteristics: For assemblies with fire-resistance ratings, provide materials and construction identical to those of assemblies tested for fire resistance per ASTM E 119 by a testing and inspecting agency acceptable to authorities having jurisdiction.

1. Fire-Resistance Ratings: Indicated by design designations from UL's "Fire Resistance Directory." or GA-600, "Fire Resistance Design Manual."

2.2 WALL SHEATHING

A. Glass-Mat Gypsum Wall Sheathing: ASTM C 1177/1177M.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Georgia-Pacific Gypsum LLC; 5/8” DensGlass exterior sheathing or comparable product by one of the following:

a. Certainteed.
b. James Hardie Building Products, Inc.
c. National Gypsum Company.
d. United States Gypsum Company.+

2.3 FASTENERS

A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.

1. For wall sheathing, provide fasteners with hot-dip zinc coating complying with ASTM A 153/A 153M.

2.4 SHEATHING JOINT-AND-PENETRATION TREATMENT MATERIALS

A. Sealant for Glass-Mat Gypsum Sheathing: Elastomeric, medium-modulus, neutral-curing silicone joint sealant compatible with joint substrates formed by gypsum sheathing and other materials, recommended by sheathing manufacturer for application indicated and complying with requirements for elastomeric sealants specified in Section 079200 "Joint Sealants."

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Do not use materials with defects that impair quality of sheathing or pieces that are too small to use with minimum number of joints or optimum joint arrangement. Arrange joints so that pieces do not span between fewer than three support members.

B. Cut panels at penetrations, edges, and other obstructions of work; fit tightly against abutting construction unless otherwise indicated.

C. Securely attach to substrate by fastening as indicated, complying with the following:

1. NES NER-272 for power-driven fasteners.
2. Table 2304.9.1, "Fastening Schedule," in ICC's "International Building Code."

D. Coordinate wall sheathing installation with flashing and joint-sealant installation so these materials are installed in sequence and manner that prevent exterior moisture from passing through completed assembly.

E. Do not bridge building expansion joints; cut and space edges of panels to match spacing of structural support elements.

3.2 GYPSUM SHEATHING INSTALLATION

A. Comply with GA-253 and with manufacturer's written instructions.

1. Fasten gypsum sheathing to cold-formed metal framing with screws.
2. Install boards with a 3/8-inch gap where non-load-bearing construction abuts structural elements.
3. Install boards with a 1/4-inch gap where they abut masonry or similar materials that might retain moisture, to prevent wicking.

B. Seal sheathing joints according to sheathing manufacturer's written instructions.

1. Apply elastomeric sealant to joints and fasteners and trowel flat. Apply sufficient amount of sealant to completely cover joints and fasteners after troweling. Seal other penetrations and openings.
2. Apply glass-fiber sheathing tape to glass-mat gypsum sheathing joints and apply and trowel silicone emulsion sealant to embed entire face of tape in sealant. Apply sealant to exposed fasteners with a trowel so fasteners are completely covered. Seal other penetrations and openings.

END OF SECTION 061600

SECTION 062023 - INTERIOR FINISH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior plywood paneling.
2. Closet shelving and clothes rods.
3. Interior wood railings.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of process and factory-fabricated product.

B. Samples: For each type of paneling.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

A. Lumber: DOC PS 20.

1. Factory mark each piece of lumber with grade stamp of inspection agency indicating grade, species, moisture content at time of surfacing, and mill.

a. For exposed lumber, mark grade stamp on end or back of each piece.

B. Softwood Plywood: DOC PS 1.

2.2 PANELING

A. Hardwood Veneer Plywood Paneling: Manufacturer's stock hardwood plywood panels complying with HPVA HP-1, made without urea-formaldehyde adhesive.

1. Manufacturers: Subject to compliance with requirements, provide products by one manufacturer:
1. Face Grade: HPVA grade AA.
2. Back Grade: HPVA grades 1 or 2.
3. Face Veneer Cut: Rotary-cut white birch, Rotary-cut red oak or Rotary-cut white oak, as selected by Architect.
4. Panel Face Veneer Matching: Whole piece veneer.
5. Thickness: 1/2 inch.
6. Finish: Stain as per Section 099300 “Staining and Transparent Finishing.”

7. Metal Reveal Trim: As manufactured by Fry Reglet or equal.
   a. Vertical Trim: Fry Reglet MWR5050
   b. Inside Corner Trim: Fry Reglet MWCISC50
   c. Outside Corner Trim: Fry Reglet MWCK50
   d. Mounting Accessories: Provide all mounting accessories, as necessary for a complete installation and as recommend by manufacturer.
   e. Finish: Clear anodized or color anodized, as selected by Architect from manufacturer's full range of standard colors.

2.3 CLOSET SHELVING AND CLOTHES RODS

A. Shelving: Made from the following material, 3/4 inch thick.

1. Softwood Boards: Douglas fir-larch, Douglas fir south, or hem-fir; Superior or C & Btr finish; NLGA, WCLIB, or WWPA; or southern pine, B & B finish; SPIB; kiln dried.

B. Shelf Cleats: 3/4-by-5-1/2-inch boards with hole and notch to receive clothes rods, as specified above for shelving.

C. Shelf Brackets with Rod Support: BHMA A156.16, B04051; prime-painted formed steel.

D. Shelf Brackets without Rod Support: BHMA A156.16, B04041; prime-painted formed steel.

E. Clothes Rods: 1-1/2-inch diameter, clear, kiln-dried Douglas fir or southern pine.

2.4 WOOD RAILINGS

A. Interior Railings: Clear, kiln-dried red oak.

1. Finish: Stain as per Section 099300 "Staining and Transparent Finishing."

2.5 MISCELLANEOUS MATERIALS

A. Glue: Aliphatic-resin, polyurethane, or resorcinol wood glue recommended by manufacturer for general carpentry use.

1. Wood glue shall have a VOC content of 30 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

B. Paneling Adhesive: Comply with paneling manufacturer's written recommendations for adhesives.

1. Adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

PART 3 - EXECUTION

3.1 PREPARATION

A. Before installing interior finish carpentry, condition materials to average prevailing humidity in installation areas for a minimum of 24 hours, unless longer conditioning is recommended by manufacturer.

3.2 INSTALLATION, GENERAL

A. Install interior finish carpentry level, plumb, true, and aligned with adjacent materials. Use concealed shims where necessary for alignment.

1. Scribe and cut interior finish carpentry to fit adjoining work. Refinish and seal cuts as recommended by manufacturer.
2. Countersink fasteners, fill surface flush, and sand unless otherwise indicated.
3. Install to tolerance of 1/8 inch in 96 inches for level and plumb. Install adjoining interior finish carpentry with 1/32-inch maximum offset for flush installation and 1/16-inch maximum offset for reveal installation.

3.3 STANDING AND RUNNING TRIM INSTALLATION

A. Install with minimum number of joints practical, using full-length pieces from maximum lengths of lumber available. [Cope] [Miter] at returns, miter at outside corners, and cope at inside corners to produce tight-fitting joints with full-surface contact throughout length of joint. Use scarf joints for end-to-end joints.

3.4 PANELING INSTALLATION

A. Plywood Paneling: Select and arrange panels on each wall to minimize noticeable variations in grain character and color between adjacent panels. Leave 1/4-inch gap to be covered with trim at top, bottom, and openings. Install with uniform tight joints between panels.

1. Attach panels to supports with manufacturer's recommended panel adhesive and fasteners. Space fasteners and adhesive as recommended by panel manufacturer.
2. Conceal fasteners to greatest practical extent.

B. Hardboard Paneling: Install according to manufacturer's written recommendations. Leave 1/4-inch gap to be covered with trim at top, bottom, and openings. Butt adjacent panels with moderate contact. Use fasteners with prefinished heads matching paneling color.

C. Board Paneling: Arrange in random-width pattern suggested by manufacturer unless boards or planks are of uniform width.

1. Install in full lengths without end joints.
2. Stagger end joints in random pattern to uniformly distribute joints on each wall.

3. Select and arrange boards on each wall to minimize noticeable variations in grain character and color between adjacent boards. Install with uniform tight joints between boards.
4. Fasten paneling by face nailing, setting nails, and filling over nail heads.
5. Fasten paneling with trim screws, set below face and filled.
6. Fasten paneling by blind nailing through tongues.

3.5 SHELVING AND CLOTHES ROD INSTALLATION

A. Cut shelf cleats at ends of shelves about 1/2 inch less than width of shelves and sand exposed ends smooth.

B. Install shelf cleats by fastening to framing or backing with finish nails or trim screws, set below face and filled. Space fasteners not more than 16 inches o.c.

C. Install shelf brackets according to manufacturer's written instructions, spaced not more than 32 inches o.c. Fasten to framing members, blocking, or metal backing, or use toggle bolts or hollow wall anchors.

D. Cut shelves to neatly fit openings with only enough gap to allow shelves to be removed and reinstalled. Install shelves, fully seated on cleats, brackets, and supports.

3.6 RAILING INSTALLATION

A. Railings: Secure wall rails with metal brackets. Fasten freestanding railings to newel posts and to trim at walls with countersunk-head wood screws or rail bolts, and glue. Assemble railings at goosenecks, easements, and splices with rail bolts and glue.

END OF SECTION 062023

SECTION 064116 - PLASTIC-LAMINATE-FACED ARCHITECTURAL CABINETS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Plastic-laminate-faced architectural cabinets.
2. Wood furring, blocking, shims, and hanging strips for installing plastic-laminate-faced architectural cabinets unless concealed within other construction before cabinet installation.

B. Related Requirements:

1. Section 123623.13 "Plastic-Laminate-Clad Countertops."

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product, including panel products, high-pressure decorative laminate, adhesive for bonding plastic laminate and cabinet hardware and accessories.

B. Shop Drawings: Show location of each item, dimensioned plans and elevations, large-scale details, attachment devices, and other components.

C. Samples:

1. Plastic laminates, for each color, pattern, and surface finish.
2. Thermoset decorative panels, for each color, pattern, and surface finish.

1.3 QUALITY ASSURANCE

A. Fabricator Qualifications: 5 years documented experience in the successful fabrication of plastic-laminate-faced architectural cabinets for commercial building projects.

B. Installer Qualifications: Fabricator of products.

1.4 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install cabinets until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature and relative humidity at occupancy levels during the remainder of the construction period.

PART 2 - PRODUCTS

2.1 ARCHITECTURAL CABINET FABRICATORS

A. Fabricators: Subject to compliance with requirements, provide products by one of the following:

1. Insight Inc. Cooktown Road, Ruston, LA 318-255-8789

2. Tippen's Specialty Millwork 211 Hood Street, West Monroe, LA 318-387-5973

3. Bayou Wood Products 1315 Hwy 15, West Monroe, LA 318-397-0000

4. Douglas Cabinet Company.

2.2 PLASTIC-LAMINATE-FACED ARCHITECTURAL CABINETS

A. Quality Standard: Unless otherwise indicated, comply with the "Architectural Woodwork Standards" for grades of architectural plastic-laminate cabinets indicated for construction, finishes, installation, and other requirements.

B. Grade: Custom.

C. Type of Construction: Frameless.

D. Cabinet, Door, and Drawer Front Interface Style: Flush overlay.

E. High-Pressure Decorative Laminate: NEMA LD 3, grades as indicated or if not indicated, as required by woodwork quality standard.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Abet Laminati, Inc.
b. Formica Corporation.
c. Lamin-Art, Inc.
d. Panolam Industries International, Inc.
e. Wilsonart International; Div. of Premark International, Inc.
f. Nevamar.

F. Laminate Cladding for Exposed Surfaces:

1. Horizontal Surfaces: Grade HGS.
2. Postformed Surfaces: Grade HGP.
3. Vertical Surfaces: Grade HGS.
4. Pattern Direction: As requested by Architect.

G. Materials for Semiexposed Surfaces:

1. Surfaces Other Than Drawer Bodies: High-pressure decorative laminate, NEMA LD 3, Grade VGS.
2. Drawer Sides and Backs: Thermoset decorative panels with PVC or polyester edge banding.
3. Drawer Bottoms: Thermoset decorative panels.

H. Dust Panels: 1/4-inch (6.4-mm) plywood or tempered hardboard above compartments and drawers unless located directly under tops.

I. Colors, Patterns, and Finishes: Provide materials and products that result in colors and textures of exposed laminate surfaces complying with the following requirements:

1. As indicated by laminate manufacturer's designations.
2. Match Architect's sample.
3. As selected by Architect from laminate manufacturer's full range in the following categories:

    a. Solid colors, [gloss] or [matte] finish.
    b. Solid colors with core same color as surface, [gloss] or [matte] finish.
    c. Wood grains, [gloss] or [matte] finish.
    d. Patterns, [gloss] or [matte] finish.
    e. Several colors and finishes will be selected by Architect. See interior elevations on drawings.

2.3 WOOD MATERIALS

A. Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of woodwork and quality grade specified unless otherwise indicated.

1. Wood Moisture Content: 5 to 10 percent.

B. Composite Wood and Agrifiber Products: Provide materials that comply with requirements of referenced quality standard for each type of woodwork and quality grade specified unless otherwise indicated.

1. Medium-Density Fiberboard: ANSI A208.2, Grade 130, made with binder containing no urea formaldehyde.
2. Softwood Plywood: DOC PS 1, medium-density overlay.
3. Veneer-Faced Panel Products (Hardwood Plywood): HPVA HP-1, made with adhesive containing no urea formaldehyde.
4. Thermoset Decorative Panels: Particleboard or medium-density fiberboard finished with thermally fused, melamine-impregnated decorative paper and complying with requirements of NEMA LD 3, Grade VGL, for test methods 3.3, 3.4, 3.6, 3.8, and 3.10.

2.4 CABINET HARDWARE AND ACCESSORIES

A. General: Provide cabinet hardware and accessory materials associated with architectural cabinets.

B. Butt Hinges: 2-3/4-inch, five-knuckle steel hinges made from 0.095-inch thick metal, and as follows:

1. Semiconcealed Hinges for Flush Doors: BHMA A156.9, B01361.
2. Semiconcealed Hinges for Overlay Doors: BHMA A156.9, B01521.

C. Frameless Concealed Hinges (European Type): BHMA A156.9, B01602, [170] degrees of opening[, self-closing].

D. Back-Mounted Pulls: BHMA A156.9, B02011.

E. Wire Pulls: Back mounted, solid metal, 4 inches long, 5/16 inch in diameter.

F. Catches: Magnetic catches, BHMA A156.9, B03141.

G. Adjustable Shelf Standards and Supports: BHMA A156.9, B04071; with shelf rests, B04081.

H. Shelf Rests: BHMA A156.9, B04013; metal, two-pin type with shelf hold-down clip.

I. Drawer Slides: BHMA A156.9.

1. Grade 1 and Grade 2: Side mounted and extending under bottom edge of drawer; [full-extension type; zinc-plated steel with polymer rollers.
2. Grade 1HD-100 and Grade 1HD-200: Side mounted; full-extension type; zinc-plated-steel ball-bearing slides.
3. For drawers not more than 3 inches high and not more than 24 inches wide, provide Grade 1.
4. For drawers more than 3 inches high but not more than 6 inches high and not more than 24 inches wide, provide Grade 1.
5. For drawers more than 6 inches high or more than 24 inches wide, provide Grade 1HD-100.
6. For computer keyboard shelves, provide Grade 1.
7. For trash bins not more than 20 inches high and 16 inches wide, provide Grade 1HD-100.

J. Door Locks: BHMA A156.11, E07121.

K. Drawer Locks: BHMA A156.11, E07041.

L. Door and Drawer Silencers: BHMA A156.16, L03011.

M. Exposed Hardware Finishes: For exposed hardware, provide finish that complies with BHMA A156.18 for BHMA finish number indicated.

1. Dark, Oxidized, Satin Bronze, Oil Rubbed: BHMA 613 for bronze base; BHMA 640 for steel base; match Architect's sample.
2. Bright Brass, Clear Coated: BHMA 605 for brass base; BHMA 632 for steel base.
3. Bright Brass, Vacuum Coated: BHMA 723 for brass base; BHMA 729 for zinc-coated-steel base.
4. Satin Brass, Blackened, Bright Relieved, Clear Coated: BHMA 610 for brass base; BHMA 636 for steel base.
5. Satin Chromium Plated: BHMA 626 for brass or bronze base; BHMA 652 for steel base.

6. Bright Chromium Plated: BHMA 625 for brass or bronze base; BHMA 651 for steel base.
7. Satin Stainless Steel: BHMA 630.

2.5 MISCELLANEOUS MATERIALS

A. Furring, Blocking, Shims, and Hanging Strips: Softwood or hardwood lumber, kiln dried to less than 15 percent moisture content.

B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide metal expansion sleeves or expansion bolts for post-installed anchors. Use nonferrous-metal or hot-dip galvanized anchors and inserts at inside face of exterior walls and at floors.

C. Adhesives: Do not use adhesives that contain urea formaldehyde.

D. Adhesive for Bonding Plastic Laminate: Unpigmented contact cement.

1. Adhesive for Bonding Edges: Hot-melt adhesive or adhesive specified above for faces.

2.6 FABRICATION

A. Complete fabrication, including assembly and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.

B. Shop-cut openings to maximum extent possible to receive hardware, appliances, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

PART 3 - EXECUTION

3.1 PREPARATION

A. Before installation, condition cabinets to average prevailing humidity conditions in installation areas.

3.2 INSTALLATION

A. Grade: Install cabinets to comply with same grade as item to be installed.

B. Install cabinets level, plumb, true, and straight. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches.

C. Scribe and cut cabinets to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.

D. Anchor cabinets to anchors or blocking built in or directly attached to substrates. Secure with countersunk, concealed fasteners and blind nailing. Use fine finishing nails or finishing screws for exposed fastening, countersunk and filled flush with woodwork.

E. Cabinets: Install without distortion so doors and drawers fit openings properly and are accurately aligned. Adjust hardware to center doors and drawers in openings and to provide unencumbered operation. Complete installation of hardware and accessory items as indicated.

1. Install cabinets with no more than 1/8 inch in 96-inch sag, bow, or other variation from a straight line.
2. Fasten wall cabinets through back, near top and bottom, and at ends not more than 16 inches o.c. with No. 10 wafer-head screws sized for not less than 1-1/2-inch penetration into wood framing, blocking, or hanging strips, No. 10 wafer-head sheet metal screws through metal backing or metal framing behind wall finish or No. 10 wafer-head, self-drilling screws sized for not less than 1-1/2-inch penetration into concrete masonry units, blocking, or hanging strips

END OF SECTION 064116

SECTION 066400 - PLASTIC PANELING

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes plastic sheet paneling.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Samples: For plastic paneling and trim accessories.

1.3 QUALITY ASSURANCE

A. Testing Agency: Acceptable to authorities having jurisdiction.

PART 2 - PRODUCTS

2.1 PLASTIC SHEET PANELING

A. Glass-Fiber-Reinforced Plastic Paneling: Gelcoat-finished, glass-fiber-reinforced plastic panels complying with ASTM D 5319. Panels shall be USDA accepted for incidental food contact.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. Crane Composites, Inc.
    b. Glasteel.
    c. Marlite.

2. Surface-Burning Characteristics: As follows when tested by a qualified testing agency according to ASTM E 84. Identify products with appropriate markings of applicable testing agency.

    a. Flame-Spread Index: 25 or less.
    b. Smoke-Developed Index: 450 or less.

3. Nominal Thickness: Not less than 0.075 inch.
4. Surface Finish: Molded pebble texture.
5. Color: As selected by Architect from manufacturer's full range.

2.2 ACCESSORIES

A. Trim Accessories: Manufacturer's standard one-piece vinyl extrusions designed to retain and cover edges of panels. Provide division bars, inside corners, outside corners and caps as needed to conceal edges.

1. Color: As selected by Architect from manufacturer's full range.

B. Adhesive: As recommended by plastic paneling manufacturer and with a VOC content of 50 g/L or less.

C. Sealant: Mildew-resistant, single-component, neutral-curing silicone sealant recommended by plastic paneling manufacturer and complying with requirements in Section 079200 "Joint Sealants."

1. Sealant shall have a VOC content of 250 g/L or less.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean substrates of substances that could impair adhesive bond, including oil, grease, dirt, and dust.

B. Condition panels by unpacking and placing in installation space before installation according to manufacturer's written recommendations.

C. Lay out paneling before installing. Locate panel joints to provide equal panels, at ends of walls and panel runs, not less than half the width of full panels.

3.2 INSTALLATION

A. Install plastic paneling according to manufacturer's written instructions.

B. Install panels in a full spread of adhesive.

C. Install trim accessories with adhesive.

D. Fill grooves in trim accessories with sealant before installing panels, and bed inside corner trim in a bead of sealant.

E. Maintain uniform space between panels and wall fixtures. Fill space with sealant.

F. Remove excess sealant and smears as paneling is installed. Clean with solvent recommended by sealant manufacturer and then wipe with clean dry cloths until no residue remains.

END OF SECTION 066400

SECTION 071900 - WATER REPELLENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes penetrating water-repellent treatments for the following vertical and horizontal surfaces:

1. Clay brick masonry (face brick).

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

B. Samples: For each type of water repellent and substrate indicated.

1.3 INFORMATIONAL SUBMITTALS

A. Product certificates.

1.4 QUALITY ASSURANCE

A. Preinstallation Conference: Conduct conference at Project site.

PART 2 - PRODUCTS

2.1 PENETRATING WATER REPELLENTS

A. Silane/Siloxane-Blend, Penetrating Water Repellent: Clear, silane and siloxane blend with 400 g/L or less of VOCs.

1. Products: Subject to compliance with requirements, provide one of the following:

a. BASF Construction Chemicals, LLC; MasterProtect H 177.
b. Euclid Chemical Company (The), an RPM company; Chemstop WB Regular/Heavy Duty.
c. PROSOCO, Inc.; Siloxane PD or Siloxane WB Concentrate.
d. SaverSystems; MasonrySaver Water Repellent for Brick.
e. Sika Corporation, Inc.; Sikagard 701W.
f. Tnemec Inc.; Dur A Pell 10.

PART 3 - EXECUTION

3.1 General

A. Apply water repellent to all vertical and horizontal surfaces of the following materials, exposed to the exterior:

1. Clay brick masonry (face brick/thin brick)

3.2 EXAMINATION

A. Examine substrates, areas, and conditions, with Applicator present, for compliance with requirements and conditions affecting performance of the Work.

1. Verify that surfaces are clean and dry according to water-repellent manufacturer's requirements. Check moisture content in representative locations by method recommended by manufacturer.
2. Inspect for previously applied treatments that may inhibit penetration or performance of water repellents.
3. Verify that there is no efflorescence or other removable residues that would be trapped beneath the application of water repellent.
4. Verify that required repairs are complete, cured, and dry before applying water repellent.

B. Test pH level according to water-repellent manufacturer's written instructions to ensure chemical bond to silica-containing or siliceous minerals.

3.3 PREPARATION

A. Cleaning: Before application of water repellent, clean substrate of substances that could impair penetration or performance of product according to water-repellent manufacturer's written instructions.

B. Coordination with Mortar Joints: Do not apply water repellent until pointing mortar for joints adjacent to surfaces receiving water-repellent treatment has been installed and cured.

C. Coordination with Sealant Joints: Do not apply water repellent until sealants for joints adjacent to surfaces receiving water-repellent treatment have been installed and cured.

1. Water-repellent work may precede sealant application only if sealant adhesion and compatibility have been tested and verified using substrate, water repellent, and sealant materials identical to those required.

3.4 APPLICATION

A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect the substrate before application of water repellent and to instruct Applicator on the product and application method to be used.

B. Apply a heavy-saturation coating of water repellent, on surfaces indicated for treatment, using low-pressure spray to the point of saturation. Remove excess material; do not allow material to puddle beyond saturation. Comply with manufacturer's written instructions for application procedure unless otherwise indicated.

1. Precast Concrete and Cast Stone: At Contractor's option, first application of water repellent on units may be completed before installing them. Mask mortar and sealant bond surfaces to prevent water repellent from migrating onto joint surfaces.

C. Apply a second saturation coating, repeating first application. Comply with manufacturer's written instructions for limitations on drying time between coats and after rainstorm wetting of surfaces between coats. Consult manufacturer's technical representative if written instructions are not applicable to Project conditions.

3.5 CLEANING

A. Immediately clean water repellent from adjoining surfaces and surfaces soiled or damaged by water-repellent application as work progresses. Correct damage to work of other trades caused by water-repellent application.

B. Comply with manufacturer's written cleaning instructions.

END OF SECTION 071900

SECTION 072100 - THERMAL INSULATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Glass-fiber blanket insulation.
2. Mineral-wool blanket insulation.
3. Spray polyurethane foam insulation @ CMU walls
4. 1 ½" extruded polystyrene unfaced insulation bd.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

1.3 INFORMATIONAL SUBMITTALS

A. Product test reports.

B. Research/evaluation reports.

PART 2 - PRODUCTS

2.1 RIGID INSULATION BOARD

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following.

1. Owens Corning
2. Johns Manville
3. Knauf Insulation
4. CertainTeed Corporation

B. Extruded Polystyrene (XPS) Cavity Wall Insulation Board: Complies with ASTM C578, and manufactured using carbon black technology.

Type and Compressive Resistance: Type IV, 25 psi (173 kPa), minimum.
Flame Spread Index (FSI): Class A - 0 to 25, when tested in accordance with ASTM E84.
Smoke Developed Index (SDI): 450 or less, when tested in accordance with ASTM E84.
Type and Thermal Resistance, R-value (RSI-value): Type IV, 5.6 (0.98), minimum, per 1 inch (25.4 mm) thickness at 75 degrees F (24 degrees C) mean temperature.

Complies with fire resistance requirements indicated on drawings as part of an exterior non-load-bearing exterior wall assembly when tested in accordance with NFPA 285.

Board Size: 15-3/4 inches by 96 inches.

Board Thickness: 1 1/2 inches.

Board Edges: Square.

Type and Water Absorption: Type IV, 0.3 percent by volume, maximum, by total immersion.

2.2 GLASS-FIBER BLANKET INSULATION

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. CertainTeed Corporation.
2. Guardian Building Products, Inc.
3. Johns Manville.
4. Knauf Insulation.
5. Owens Corning.

B. Unfaced, Glass-Fiber Blanket Insulation: ASTM C 665, Type I; with maximum flame-spread and smoke-developed indexes of 25 and 50, respectively, per ASTM E 84; passing ASTM E 136 for combustion characteristics.

1. Interior Partitions: Provide in unfaced, glass-fiber blanket insulation in stud cavity of interior partitions, as indicated by Drawings.
2. Exterior Walls: Provide in unfaced, glass-fiber blanket insulation in stud cavity of all exterior stud wall, as follows:

   a. 3-5/8 inch Studs: 3-1/2 inches thick, R-15.
   b. 6 inch Studs: 5-1/2 inches thick, R-21.

3. Ceiling insulation: Provide above all ceilings 6” R-21 unfaced Batt insulation.

2.3 CONCRETE MASONRY UNIT (CMU) INSULATION

A. Foam Fill Insulation: Foamed-in-place aminoplast foam insulation, Class A building material with maximum flame-spread and smoke-developed indexes of 25 and 450, respectively, per ASTM E 84, minimum R-Value of 4.0 per inch, minimum Dry-Density of 0.7lbs per cubic foot and minimum Wet-Density of 2.5lbs per cubic foot.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Tailored Chemical Products, Inc.; Core-Fill 500
   b. cfiFOAM, Inc.; Core Foam

2. Basis-of-design product: Tailored Chemical Products, Inc.; Core-Fill 500

2.4 SPRAY POLYURETHANE FOAM INSULATION

A. Closed-Cell Polyurethane Foam Insulation: ASTM C 1029, Type II, with maximum flame-spread and smoke-developed indexes of 75 and 450, respectively, per ASTM E 84.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. BASF Corporation.
b. BaySystems NorthAmerica, LLC.
c. Dow Chemical Company (The).
d. Gaco Western Inc.

2. Minimum density of 1.5 lb/cu. ft., thermal resistivity of 6.2 deg F x h x sq. ft./Btu x in. at 75 deg F.

3. Provide polyurethane foam insulation manufacturer’s standard Thermal Barrier coating, complying with the International Building Code, 2012 edition.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Comply with insulation manufacturer's written instructions applicable to products and applications indicated.

B. Install insulation that is undamaged, dry, and unsoiled and that has not been left exposed to ice, rain, or snow at any time.

C. Extend insulation to envelop entire area to be insulated. Cut and fit tightly around obstructions and fill voids with insulation. Remove projections that interfere with placement.

D. Provide sizes to fit applications indicated and selected from manufacturer's standard thicknesses, widths, and lengths. Apply single layer of insulation units to produce thickness indicated unless multiple layers are otherwise shown or required to make up total thickness.

3.2 INSTALLATION OF INSULATION BELOW STEEL DECK

A. Spray-Applied Insulation: Apply spray-applied insulation according to manufacturer's written instructions. Do not apply insulation until installation of pipes, ducts and conduits scheduled to be surface mounted to deck is completed, electrical boxes, and other items not indicated to receive insulation are masked.

B. Miscellaneous Voids: Install insulation in miscellaneous voids and cavity spaces where required to prevent gaps in insulation using the following materials:

1. Spray Polyurethane Insulation: Apply according to manufacturer's written instructions.

3.3 INSTALLATION OF INSULATION FOR FRAMED CONSTRUCTION

A. Apply insulation units to substrates by method indicated, complying with manufacturer's written instructions. If no specific method is indicated, bond units to substrate with adhesive or use mechanical anchorage to provide permanent placement and support of units.

B. Glass-Fiber Insulation: Install in cavities formed by framing members according to the following requirements:

1. Use insulation widths and lengths that fill the cavities formed by framing members. If more than one length is required to fill the cavities, provide lengths that will produce a snug fit between ends.
2. Place insulation in cavities formed by framing members to produce a friction fit between edges of insulation and adjoining framing members.
3. Maintain 3-inch clearance of insulation around recessed lighting fixtures not rated for or protected from contact with insulation.
4. Install eave ventilation troughs between roof framing members in insulated attic spaces at vented eaves.
5. For metal-framed wall cavities where cavity heights exceed 96 inches, support unfaced blankets mechanically and support faced blankets by taping flanges of insulation to flanges of metal studs.

C. Miscellaneous Voids: Install insulation in miscellaneous voids and cavity spaces where required to prevent gaps in insulation using the following materials:

1. Loose-Fill Insulation: Compact to approximately 40 percent of normal maximum volume equaling a density of approximately 2.5 lb/cu. ft..

END OF SECTION 072100

SECTION 072726 - FLUID-APPLIED AIR & WATER-RESISTIVE BARRIER SYSTEM

PART 1 – GENERAL

1.1 SUMMARY:

A. Work of this section includes window and door flashing, air and water-resistive barrier membrane system, and accessory materials for application to exterior building envelope substrates as indicated on the drawings.

B. Related work:
1. Concrete.
2. Masonry.
3. Sheathing.
4. Exterior wall finish materials.
5. Flashings.
6. Joint sealants.
7. Doors and frames.
8. Storefronts.
9. Curtain walls.
10. Windows.
11. Stucco.

1.2 PERFORMANCE REQUIREMENTS:

A. Performance requirements: Comply with the specified performance requirements and characteristics as herein specified.

B. Performance description:

1. The building envelope shall be constructed with a continuous, air and water-resistive barrier to control water and air leakage into and out of the conditioned space.
2. Joints, penetrations and paths of water and air infiltration shall be made watertight and airtight.
3. System shall be capable of withstanding positive and negative combined wind, stack and HVAC pressures on the envelope without damage or displacement.
4. System shall be installed in an airtight and flexible manner, allowing for the relative movement of systems due to thermal and moisture variations.

1.3 SUBMITTALS:

A. Product data: Submit manufacturer’s product data including membrane and accessory material types, technical and test data, composition, descriptions and properties, installation instructions and substrate preparation requirements.

B. Shop Drawings: Provide Installation Guideline Illustrations. Submittals shall be submitted to the Architect electronically.

1.4 QUALITY ASSURANCE:

A. Applicable standards, as referenced herein: ASTM International (ASTM).

B. Manufacturer’s qualifications: Air and water-resistive barrier systems shall be manufactured and marketed by a firm with a minimum of ten (10) years experience in the production and sales of air

and water-resistive barrier system. Manufacturers proposed for use, but not named in these specifications, shall submit evidence of ability to meet all requirements specified, and include a list of projects of similar design and complexity completed within the past five years.

C. Installer's qualifications: The installer shall demonstrate qualifications to perform the work of this section by submitting the following:

1. Verification that installer has been trained by and is approved to perform work as herein specified by air and water-resistive barrier system manufacturer.
2. A firm experienced in applying similar materials on similar size and scoped projects.
3. Evidence of proper equipment and trained field personnel to successfully complete the project.

D. Inspection and testing: Cooperate and coordinate with the Owner's inspection and testing agency. Do not cover installed products or assemblies until they have been inspected, tested and approved.

E. Sole source: Obtain materials from a single manufacturer.

F. This material shall be installed behind all exterior finishes such as brick, block, EIFS, and metal panels, etc.

G. Product shall be installed by a Louisiana Licensed Waterproofing Contractor.

H. Regulations: Provide products which comply with all state and local regulations controlling use of volatile organic compounds (VOC).

I. Install mock-up using approved weather barrier system including membrane, flashing, joint and detailing compound and related weather barrier accessories according to weather barrier manufacture's current printed instructions and recommendations.

1. Mock-up shall be 10 feet by 10 feet and shall be inspected by the architect prior to work continuing.
2. Mock-up substrate: Match wall assembly construction, including window opening.
3. Mock-up may remain as part of the final work.

J. Pre-installation conference: Prior to beginning installation of air and water-resistive barrier system, hold a pre-installation conference to review work to be accomplished.

1. Contractor, Architect, installing subcontractor, membrane system manufacturer's representative, and all subcontractors who have materials penetrating membrane system or finishes covering membrane system shall be present.
2. Contractor shall notify Architect at least seven days prior to time for conference.
3. Contractor shall record minutes of meeting and distribute to attending parties.
4. Agenda: As a minimum discuss:
   a. Surface preparation.
   b. Substrate condition and pretreatment.
   c. Minimum curing period.
   d. Special details and sheet flashing.
   e. Sequence of construction, responsibilities, and schedule for subsequent operations.
   f. Installation procedures.
   g. Inspection procedures.
   h. Protection and repair procedures.
   i. Review and approval of all glazing applications.

DELIVERY, STORAGE, AND HANDLING:

K. Deliver materials and products in labeled packages. Store and handle in strict compliance with manufacturer's instructions and recommendations. Protect from damage, weather, excessive temperatures and construction operations. Remove damaged material from site and dispose of in accordance with applicable regulations.

L. Protect air and water-resistive barrier components from freezing and extreme heat.

M. Sequence deliveries to avoid delays, and to minimize on-site storage.

1.5 PROJECT CONDITIONS:

A. Weather conditions: Perform work only when existing and forecasted weather conditions are within the limits established by the manufacturer of the materials used.
   1. Apply at surface and ambient temperatures recommended by the manufacturer. See manufacturer's product data sheets for best practices.
   2. Proceed with installation only when the substrate construction and preparation work are complete and in condition to receive the membrane system.
   3. Exposure limitations: Schedule work to ensure that air and water-resistive barrier system is covered and protected from UV exposure within 180 days of installation. If air and water-resistive barrier membrane system cannot be covered within 180 days after installation, apply temporary UV protection as recommended by membrane manufacturer.

1.6 WARRANTY:

A. Manufacturer's warranty requirements: Submit manufacturer's written warranty stating that installed air and water-resistive barrier materials are watertight, free from defects in material and workmanship, and agreeing to replace defective materials and components.

B. Warranty period: Ten years from Date of Substantial Completion.

PART 2 – PRODUCTS

2.1 MANUFACTURER:

A. PROSOCO, Inc.
B. Sto Corp.
C. DuPont Building Innovations.
D. Carlisle Coatings & Waterproofing.
E. Parex USA.

2.2 WATER BASED PRIMER FOR RAW GYPSUM BOARD EDGES:

A. Acceptable product: PROSOCO R-GUARD Primer or approved equal

B. Description: Primer consolidates and seals the cut edges of gypsum wall boards where they are exposed in rough openings for windows and doors. The sealed edge makes a compatible surface

for easy application of Joint & Seam Filler fiber-reinforced fill coat and seam treatment for through-wall components. Primer brushes or sprays on easily and is usually dry in 30 minutes.

C. Characteristics:
1. Form: milky blue liquid, mild odor
2. Specific Gravity: 1.01
3. pH: 8.5
4. Weight per Gallon: 8.41 pounds
5. Active Content: 18 percent
6. Total Solids: 18 percent ASTM-D-2369
7. Volatile Organic Content (VOC): less than 100 grams per Liter
8. Flash point: greater than 212 degrees Fahrenheit (greater than 100 degrees Celsius) ASTM-D-3278
9. Freeze Point: 32 degrees Fahrenheit (0 degrees Celsius)
10. Shelf Life: 1 year in tightly sealed, unopened container

2.3 JOINT & SEAM FILLER FIBER REINFORCED FILL COAT AND SEAM FILLER:

A. Acceptable product: PROSOCO R-GUARD Joint & Seam Filler or approved equal

B. Description: Joint & Seam Filler is a high modulus, gun-grade, crack and joint filler, adhesive and detailing compound that combines the best silicone and polyurethane properties. This single-component, 99% solids, fiber-reinforced, Silyl-Terminated-Poly-Ether (STPE) is easy to gun, spread and tool.

C. Characteristics:
1. Thickness: Apply according to manufacturer's instructions. See product data sheet.
2. Hardness: Shore A, 45-50 when tested in accordance with ASTM C661.
3. Water vapor permeability: Minimum 14 perms when tested in accordance with ASTM E-96.
4. Tensile strength: 225 psi when tested in accordance with ASTM D412.
5. Lap shear strength: 275 psi when tested in accordance with ASTM D1002.
6. Elongation at break: 275% when tested in accordance with ASTM D412.
7. Peel strength: 30 pli when tested in accordance with ASTM D1781.
8. Shrinkage: None.
9. Form: pale red, gun-grade sealant
10. Specific gravity: 1.40 to 1.50
11. pH: not applicable
12. Weight per gallon: 11.8 pounds
13. Active content: 99 percent
14. Total solids: 99 percent
15. Volatile organic content (VOC): 30 grams per Liter, maximum
16. Flash point: no data
17. Freeze point: no date
18. Shelf life: 1 year in tightly sealed, unopened container

2.4 LIQUID-APPLIED FLASHING MEMBRANE

A. Acceptable product: PROSOCO R-GUARD Flashing or approved equal

B. Description: Flashing is a gun-grade waterproofing, adhesive and detailing compound that combines the best of silicone and polyurethane properties. This single component, 99% solids, Silyl-Terminated-Poly-Ether (STPE) is easy to gun, spread and tool to produce a highly durable, seamless, elastomeric flashing membrane in rough openings of structural walls.

C. Characteristics:
1. Thickness: Apply according to manufacturer's instructions.
2. Water vapor permeability: Minimum 14 perms when tested in accordance with ASTM E96.
3. Water penetration (cyclical static air pressure difference): No uncontrolled water penetration when tested in accordance with ASTM E547.
4. Hardness: Shore A, 40-45 when tested in accordance with ASTM C661.
5. Tensile strength: 180 psi when tested in accordance with ASTM D412.
6. Elongation at break: 400% when tested in accordance with ASTM D412.
7. Peel strength: 25 pli when tested in accordance with ASTM D1781.
8. Form: Brick Red, Gun Grade Sealant.
9. Specific gravity: 1.45 to 1.60
10. pH: not applicable
11. Weight per gallon: 12.5 pounds
12. Active content: 99 percent
13. Total solids: 99 percent
14. Volatile organic content (VOC): 30 grams per Liter, maximum
15. Flash point: no data
16. Freeze point: no data
17. Shelf life: 1 year in tightly sealed, unopened container

2.5 SPRAY WRAP AIR AND WATER-RESISTIVE BARRIER

A. Acceptable product: PROSOCO R-GUARD Spray Wrap or approved equal

Note: All Air & Water Resistive Barriers must be installed by a waterproofing.

B. Description: Spray Wrap is a fluid-applied air and water-resistive barrier that stops air and water leakage in cavity wall, masonry veneer construction, as well as in stucco, EIFS and most other building wall assemblies. Once on the substrate, the easily applied liquid quickly dries into a rubberized, highly durable, water-resistant, vapor-permeable membrane.

C. Characteristics:
1. Thickness: Apply according to manufacturer's instructions. See product data sheet.
2. Air infiltration: Less than 0.004 cfm per square foot (0.02 L/s/sq m) when tested in accordance with ASTM E2178 or ASTM E283.
3. Air Barrier Assembly: pass when tested in accordance with ASTM E-2357.
4. Water vapor permeability: 10.5 perms when tested in accordance with ASTM E96.
5. Structural performance: Air and water-resistive barrier system shall withstand positive and negative wind pressure loading when tested in accordance with ASTM E330.
6. Water penetration (static pressure): No uncontrolled water penetration when tested in accordance with ASTM E331.
7. Flexibility: No cracking or de-lamination using 1/8 inch mandrel at 14 degrees Fahrenheit before and after aging when tested in accordance with ASTM D522.
8. Tensile strength: Greater than 15 psi or exceeds strength of substrate when tested in accordance with ASTM C297.
9. Nail Sealability: pass when tested in accordance with ASTM D1970.
10. Surface burning: pass when tested in accordance with ASTM E84.
11. Form: light red viscous liquid, mild odor
12. Specific gravity: less than 1.0
13. pH: 7.5 to 10.0
14. Weight per gallon: 12.7 pounds
15. Active content: no data
16. Total solids: 62 percent by volume, ASTM-D-2369
17. Volatile organic content (VOC): less than 100 grams per Liter
18. Flash point: greater than 200 degrees Fahrenheit (greater than 93 degrees Celsius)

19. Freeze point: 32 degrees Fahrenheit (0 degrees Celsius)
20. Shelf life: 1 year in tightly sealed, unopened container

2.6 AIR AND WATERPROOF SEALANT FOR WINDOWS AND DOORS:

A. Acceptable product: PROSOCO R-GUARD Weather Barrier or approved equal

B. Description: Weather Barrier is a medium modulus sealant that combines the best silicone and polyurethane properties. This single component, 98% solids Silyl-Terminated-Poly-Ether (STPE) is easy to gun and tool in all weather conditions. Weather Barrier® cures quickly to produce a durable, high performance, high movement elastomeric interior air sealant

C. Characteristics:
1. Hardness: Shore A, 20-25 when tested in accordance with ASTM C661.
2. Tensile strength: 110 psi when tested in accordance with ASTM D412.
3. Elongation at break: 1300% when tested in accordance with ASTM D412.
4. Peel strength: 30 pli when tested in accordance with ASTM D1781.
5. Type: Type S, Grade NS, Class 50 when tested in accordance with ASTM C920.
6. Shrinkage: None.
7. Form: heavy white paste, mild odor
8. Specific gravity: 1.3 to 1.4
9. pH: not applicable
10. Weight per gallon: 11.648 pounds
11. Active content: 98 percent
12. Total solids: 98 percent
13. Volatile organic content (VOC): 30 grams per Liter, maximum
14. Flash point: greater than 200 degrees Fahrenheit (greater than 93 degrees Celsius)
15. Freeze point: not applicable
16. Shelf life: 1 year in tightly sealed, unopened container

D. Backer rod: Compressible, closed cell rod stock as recommended by manufacturer for compatibility with sealant. Provide size and shape of rod to control joint depth.

PART 3 - EXECUTION

3.1 EXAMINATION:

A. Verify that surfaces and conditions are ready to accept the Work of this section. Notify design professionals in writing of any discrepancies. Commencement of the Work or any parts thereof shall mean acceptance of the prepared substrates.

B. All surfaces must be sound, clean and free of grease, dirt, excess mortar or other contaminants. Fill or bridge damaged surfaces, voids or gaps larger than one-half (1/2) inch with mortar, wood, metal, sheathing or other suitable material, as necessary. Fill voids and gaps measuring one-half (1/2) inch or less with Joint & Seam Filler as necessary to ensure continuity.
1. Surfaces to receive Spray Wrap, MVP, TMVP and VB may be dry or damp. Do not apply to surfaces which are sufficiently wet to transfer water to the skin when touched. Surfaces must be protected from rain for 2 hours following application.
2. Surfaces to receive, Joint & Seam Filler, and Weather Barrier may be dry, damp or wet to the touch. Brush away any standing water which may be present before application. The products will tolerate rain immediately after application

C. Where curing materials are used they must be clear resin based without oil, wax or pigments

D. Condition materials to room temperature prior to application to facilitate extrusion and handling.

3.2 SURFACE PREPARATION:

A. Air, water-resistive and waterproofing membrane and accessories may be applied to green concrete 16 hours after removal of forms.

B. Refer to manufacturer's product data sheets for requirements for condition of and preparation of substrates.
   1. Surfaces shall be sound and free of voids, spalled areas, loose aggregate and sharp protrusions.
   2. Remove contaminants such as grease, oil and wax from exposed surfaces.
   3. Remove dust, dirt, loose stone and debris.
   4. Use repair materials and methods that are acceptable to manufacturer of the air and water-resistive barrier system.
   5. The product line includes several options for preparing structural walls to receive the primary air and water resistive barrier. Refer to manufacturer's product data sheets and Installation Guidelines for additional information.

C. Exterior sheathing:
   1. Ensure that sheathing is properly installed with ends, corners and edges properly fastened.
   2. Mechanical fasteners used to secure sheathing boards or penetrate sheathing boards shall be set flush with sheathing, fastened and spotted with Joint & Seam Filler and fastened into solid backing.
   3. Consolidate and seal the cut edges of gypsum wall boards exposed in rough openings for windows and doors at corners. The treated edge provides a suitable surface for application of Joint & Seam Filler fiber-reinforced coat and seam treatment.

D. Masonry and concrete substrates:
   1. Masonry head and bed joints should be fully filled and tooled.
   2. Mechanically remove loose mortar fins, mortar accumulations and protrusions, and debris.

3.3 INSTALLATION OF JOINT TREATMENT (PREPARE):

A. Apply Joint & Seam Filler for seams, joints, cracks, gaps, primed rough gypsum edges at sheathing, rough openings:
   1. Fill or repair cracks larger than one-half inch.
   2. Fill surface defects and over driven fasteners with Joint & Seam Filler.
   3. Using a dry knife, trowel or spatula, tool and spread the product. Spread one inch beyond seam at each side to manufacturer's recommended thickness. See product data sheet.
   4. Allow to skin before installing other waterproofing or air barrier components.
   5. Apply in accordance with manufacturer's Application Guideline illustrations.

3.4 FLASHING AT WINDOWS, DOORS, OPENINGS AND PENETRATIONS (PREPARE):

A. Apply Flashing over surfaces prepared with Joint & Seam Filler to seal and waterproof rough openings:
   1. Apply a thick bead of Flashing over any visible gaps in the prepared rough opening.
   2. Immediately press and spread the wet product into gaps.
   3. Allow treated surface to skin.
   4. Starting at the top, apply a thick bead of Flashing in a zigzag pattern to the structural wall surrounding the rough opening.

5. Spread the wet product to create an opaque, monolithic flashing membrane which surrounds the rough opening and extends 4 to 6 inches over the face of the structural wall. Apply and spread additional product as needed to create an opaque, monolithic flashing membrane free of voids and pin holes.
6. Apply additional product in a zigzag pattern over a structural framing inside the rough opening.
7. Apply Flashing within temperature and weather limitations as required by manufacturer.
8. Apply Flashing to perimeters, sills and adjacent sheathing and building face, in accordance with manufacturer's product data sheet and Installation Guidelines illustrations.
9. Extend flashing onto building face 4 to 6 inches.
10. Install preparation products in accordance with manufacturer's Application Guideline illustrations.

3.5 AIR & WATER-RESISTIVE BARRIER INSTALLATION (PROTECT)

A. Apply appropriate air and water-resistive barrier to a clean, dry substrate (clean, dry, and/or damp substrates use waterproofing air-barrier membrane), within temperature and weather limitations as required by manufacturer.
   1. Apply to recommended thickness. Proper thickness is achieved when coating is opaque.
   2. Allow product to cure and dry.
   3. Inspect membrane before covering. Repair any punctures, translucent or damaged areas by applying additional material.
   4. Specifier Note: If air or surface temperature exceed 95 degrees Fahrenheit (35 degrees Celsius), apply to shaded surfaces and before daytime air and surface temperatures reach their peak.
   5. On CMU wall construction back roll as necessary to ensure there are no pinholes, voids or gaps in the membrane.

3.6 FLASHING TRANSITIONS (TRANSITION)

A. Apply Joint & Seam Filler and Flashing as a liquid flashing membrane to waterproof the transitions in rough opening and between dissimilar materials.
   1. Fill any voids between the top of the flashing leg and the vertical wall with R-GUARD Joint & Seam Filler. Tool to direct water from the vertical wall to the flashing.
   2. Apply a generous bead of Flashing to the top edge of the flashing leg.
   3. Spread the wet products to create a monolithic "cap-flash" flashing membrane extending 2 inches up the vertical face of the structural wall and 1 inch over the flashing membrane extending. Apply additional product as needed to achieve a void and pinhole free surface. This "liquid termination bar" helps secure the flashing and ensures positive drainage from the wall surface to the flashing.
   4. Allow treated surfaces to skin before installing other wall assembly, waterproofing or air barrier components.

3.7 AIR AND WEATHER BARRIER SEALANT FOR WINDOWS AND DOORS INSTALLATION

A. Install Weather Barrier with professional grade caulking gun in continuous beads without air gaps or air pockets.
   1. Apply Weather Barrier to a clean, dry or damp surface
   2. Install Backer rod: Compressible, closed cell rod stock as recommended by manufacturer for compatibility with sealant. Provide size and shape of rod to control joint depth
   3. Install Weather Barrier to provide uniform, continuous ribbons without gaps or air pockets, with complete wetting of the joint bond surfaces.
   4. Tool sealant immediately to ensure complete wetting of joint bond surface and to produce a smooth, concave joint profile flush with the edges of the adjacent surfaces. Where horizontal and vertical surfaces meet, tool sealant to create a slight cove so as to not trap moisture or debris.

5. Do not allow materials to overflow onto adjacent surfaces. Prevent staining of adjacent surfaces.
6. Remove excess and misplaced materials as work progresses. Clean the adjoining surfaces to remove misplaced materials, without damage to adjacent surfaces or finishes.

END OF SECTION

SECTION 074213.13 - FORMED METAL WALL PANELS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Concealed-fastener, lap-seam metal wall panels.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: Include fabrication and installation layouts of metal panels; details of edge conditions, joints, panel profiles, corners, anchorages, attachment system, trim, flashings, closures, and accessories; and special details.

C. Samples: For each type of metal panel indicated.

1.4 INFORMATIONAL SUBMITTALS

A. Product test reports.

B. Warranties: Samples of special warranties.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.

B. UL-Certified, Portable Roll-Forming Equipment: UL-certified, portable roll-forming equipment capable of producing metal panels warranted by manufacturer to be the same as factory-formed products. Maintain UL certification of portable roll-forming equipment for duration of work.

1.7 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of metal panel systems that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

B. Special Warranty on Panel Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace metal panels that show evidence of deterioration of factory-applied finishes within specified warranty period.

1. Finish Warranty Period: [20] [10] <Insert number> years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Structural Performance: Provide metal panel systems capable of withstanding the effects of the loads, as required by the International Building Code 2012 edition, based on testing according to ASTM E 1592:

B. Air Infiltration: Air leakage of not more than 0.06 cfm/sq. ft. when tested according to ASTM E 283 at the following test-pressure difference:

1. Test-Pressure Difference: 1.57 lbf/sq. ft..

C. Water Penetration under Static Pressure: No water penetration when tested according to ASTM E 331 at the following test-pressure difference:

1. Test-Pressure Difference: 2.86 lbf/sq. ft..

D. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.

1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.

E. Fire-Resistance Ratings: Comply with ASTM E 119; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Indicate design designations from UL's "Fire Resistance Directory" or from the listings of another qualified testing agency.

2.2 CONCEALED-FASTENER, LAP-SEAM METAL WALL PANELS

A. General: Provide factory-formed metal panels designed to be field assembled by lapping and interconnecting side edges of adjacent panels and mechanically attaching through panel to supports using concealed fasteners in side laps. Include accessories required for weathertight installation.

B. Concealed-Fastener Metal Wall Panels: Formed to match existing metal wall panels on existing adjacent building.

1. Metallic-Coated Steel Sheet: Zinc-coated (galvanized) steel sheet complying with ASTM A 653/A 653M, G90 coating designation, or aluminum-zinc alloy-coated steel sheet complying with ASTM A 792/A 792M, Class AZ50 coating designation; structural quality. Prepainted by the coil-coating process to comply with ASTM A 755/A 755M.

    a. Nominal Thickness: 0.028 inch.
    b. Exterior Finish: Two-coat fluoropolymer.
    c. Color: Match existing metal wall panel on existing adjacent building.

2. Panel Coverage: Match existing metal wall panel on existing adjacent building.
3. Panel Height: Match existing metal wall panel on existing adjacent building.
4. Panel Type: Metal Wall Panel 3

2.3 MISCELLANEOUS MATERIALS

A. Miscellaneous Metal Subframing and Furring: ASTM C 645, cold-formed, metallic-coated steel sheet, ASTM A 653/A 653M, G90 coating designation or ASTM A 792/A 792M, Class AZ50 aluminum-zinc-alloy coating designation unless otherwise indicated. Provide manufacturer's standard sections as required for support and alignment of metal panel system.

B. Panel Accessories: Provide components required for a complete, weathertight panel system including trim, copings, fasciae, mullions, sills, corner units, clips, flashings, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal panels unless otherwise indicated.

1. Closures: Provide closures at eaves and rakes, fabricated of same metal as metal panels.
2. Backing Plates: Provide metal backing plates at panel end splices, fabricated from material recommended by manufacturer.
3. Closure Strips: Closed-cell, expanded, cellular, rubber or crosslinked, polyolefin-foam or closed-cell laminated polyethylene; minimum 1-inch thick, flexible closure strips; cut or premolded to match metal panel profile. Provide closure strips where indicated or necessary to ensure weathertight construction.

C. Flashing and Trim: Provide flashing and trim formed from same material as metal panels as required to seal against weather and to provide finished appearance. Locations include, but are not limited to, bases, drips, sills, jambs, corners, endwalls, framed openings, rakes, fasciae, parapet caps, soffits, reveals, and fillers. Finish flashing and trim with same finish system as adjacent metal panels.

D. Panel Fasteners: Self-tapping screws designed to withstand design loads. Provide exposed fasteners with heads matching color of metal panels by means of plastic caps or factory-applied coating. Provide EPDM or PVC sealing washers for exposed fasteners.

E. Panel Sealants: Provide sealant type recommended by manufacturer that are compatible with panel materials, are nonstaining, and do not damage panel finish.

1. Sealant Tape: Pressure-sensitive, 100 percent solids, gray polyisobutylene compound sealant tape with release-paper backing; 1/2 inch wide and 1/8 inch thick.
2. Joint Sealant: ASTM C 920; as recommended in writing by metal panel manufacturer.
3. Butyl-Rubber-Based, Solvent-Release Sealant: ASTM C 1311.

2.4 FABRICATION

A. General: Fabricate and finish metal panels and accessories at the factory, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.

B. On-Site Fabrication: Subject to compliance with requirements of this Section, metal panels may be fabricated on-site using UL-certified, portable roll-forming equipment if panels are of same profile and warranted by manufacturer to be equal to factory-formed panels. Fabricate according to equipment manufacturer's written instructions and to comply with details shown.

C. Provide panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of panel.

D. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's recommendations and recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to design, dimensions, metal, and other characteristics of item indicated.

2.5 FINISHES

A. Panels and Accessories:

1. Two-Coat Fluoropolymer: AAMA 62. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in color coat.
2. Concealed Finish: White or light-colored acrylic or polyester backer finish.

PART 3 - EXECUTION

3.1 PREPARATION

A. Miscellaneous Supports: Install subframing, furring, and other miscellaneous panel support members and anchorages according to ASTM C 754 and metal panel manufacturer's written recommendations.

3.2 METAL PANEL INSTALLATION

A. Lap-Seam Metal Panels: Fasten metal panels to supports with fasteners at each lapped joint at location and spacing recommended by manufacturer.

1. Lap ribbed or fluted sheets one full rib. Apply panels and associated items true to line for neat and weathertight enclosure.
2. Provide metal-backed washers under heads of exposed fasteners bearing on weather side of metal panels.
3. Locate and space exposed fasteners in uniform vertical and horizontal alignment. Use proper tools to obtain controlled uniform compression for positive seal without rupture of washer.
4. Install screw fasteners with power tools having controlled torque adjusted to compress washer tightly without damage to washer, screw threads, or panels. Install screws in predrilled holes.
5. Flash and seal panels with weather closures at perimeter of all openings.

B. Watertight Installation:

1. Apply a continuous ribbon of sealant or tape to seal lapped joints of metal panels, using sealant or tape as recommend by manufacturer on side laps of nesting-type panels; and elsewhere as needed to make panels watertight.
2. Provide sealant or tape between panels and protruding equipment, vents, and accessories.
3. At panel splices, nest panels with minimum 6-inch end lap, sealed with sealant and fastened together by interlocking clamping plates.

C. Accessory Installation: Install accessories with positive anchorage to building and weathertight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.

D. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that are permanently watertight.

3.3 CLEANING

A. Remove temporary protective coverings and strippable films, if any, as metal panels are installed, unless otherwise indicated in manufacturer's written installation instructions. On completion of metal panel installation, clean finished surfaces as recommended by metal panel manufacturer. Maintain in a clean condition during construction.

END OF SECTION 074213.13

SECTION 076200 - SHEET METAL FLASHING AND TRIM

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Manufactured reglets with counter-flashing.
2. Formed wall sheet metal fabrications.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For sheet metal flashing and trim.

1. Include plans, elevations, sections, and attachment details.
2. Distinguish between shop- and field-assembled work.
3. Include identification of finish for each item.
4. Include pattern of seams and details of termination points, expansion joints and expansion-joint covers, direction of expansion, roof-penetration flashing, and connections to adjoining work.

C. Samples: For each exposed product and for each color and texture specified.

1.4 INFORMATIONAL SUBMITTALS

A. Product certificates.

B. Product test reports.

C. Sample warranty.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.6 QUALITY ASSURANCE

A. Fabricator Qualifications: Employs skilled workers who custom fabricate sheet metal flashing and trim similar to that required for this Project and whose products have a record of successful in-service performance.

1. For copings and roof edge flashings that are SPRI ES-1 tested, shop shall be listed as able to fabricate required details as tested and approved.

B. Mockups: Build mockups to verify selections made under Sample submittals to demonstrate aesthetic effects and to set quality standards for fabrication and installation.

1. Build mockup of typical roof edge and eave, including fascia and fascia trim, approximately 2 feet long.

1.7 WARRANTY

A. Special Warranty on Finishes: Manufacturer agrees to repair finish or replace sheet metal flashing and trim that shows evidence of deterioration of factory-applied finishes within specified warranty period.

1. Finish Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. General: Sheet metal flashing and trim assemblies shall withstand wind loads, structural movement, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Completed sheet metal flashing and trim shall not rattle, leak, or loosen, and shall remain watertight.

B. Sheet Metal Standard for Flashing and Trim: Comply with NRCA's "The NRCA Roofing Manual" and SMACNA's "Architectural Sheet Metal Manual" requirements for dimensions and profiles shown unless more stringent requirements are indicated.

C. SPRI Wind Design Standard: Manufacture and install roof edge flashings tested according to SPRI ES-1 and capable of resisting the following design pressure:

1. Design Pressure: As required by the International Building Code.

D. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 SHEET METALS

A. General: Protect mechanical and other finishes on exposed surfaces from damage by applying strippable, temporary protective film before shipping.

B. Aluminum Sheet: ASTM B 209, alloy as standard with manufacturer for finish required, with temper as required to suit forming operations and performance required.

1. Exposed Coil-Coated Finish:

a. Three-Coat Fluoropolymer: AAMA 620. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in both color coat and clear topcoat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

2. Color: As selected by Architect from manufacturer's full range.

C. Metallic-Coated Steel Sheet: Provide zinc-coated (galvanized) steel sheet according to ASTM A 653/A 653M, G90 coating designation or aluminum-zinc alloy-coated steel sheet according to ASTM A 792/A 792M, Class AZ50 coating designation, Grade 40; prepainted by coil-coating process to comply with ASTM A 755/A 755M.

1. Exposed Coil-Coated Finish:

a. Three-Coat Fluoropolymer: AAMA 621. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in both color coat and clear topcoat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

2. Color: As selected by Architect from manufacturer’s full range.

2.3 UNDERLAYMENT MATERIALS

A. Synthetic Underlayment: Laminated or reinforced, woven polyethylene or polypropylene, synthetic roofing underlayment; bitumen free; slip resistant; suitable for high temperatures over 220 deg F; and complying with physical requirements of ASTM D 226/D 226M for Type I and Type II felts.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Atlas Roofing Corporation; Summit.
b. Engineered Coated Products; Nova-Seal II.
c. Kirsch Building Products, LLC; Sharkskin Comp.
d. SDP Advanced Polymer Products Inc; Palisade.

B. Slip Sheet: Rosin-sized building paper, 3 lb/100 sq. ft. minimum.

2.4 MISCELLANEOUS MATERIALS

A. General: Provide materials and types of fasteners, solder, protective coatings, sealants, and other miscellaneous items as required for complete sheet metal flashing and trim installation and as recommended by manufacturer of primary sheet metal[or manufactured item] unless otherwise indicated.

B. Fasteners: Self-tapping screws, self-locking rivets and bolts, and other suitable fasteners designed to withstand design loads and recommended by manufacturer of primary sheet metal or manufactured item.

1. General: Blind fasteners or self-drilling screws, gasketed, with hex-washer head.

a. Exposed Fasteners: Heads matching color of sheet metal using factory-applied coating. Provide metal-backed EPDM or PVC sealing washers under heads of exposed fasteners bearing on weather side of metal.
b. Blind Fasteners: High-strength aluminum or stainless-steel rivets suitable for metal being fastened.
c. Spikes and Ferrules: Same material as gutter; with spike with ferrule matching internal gutter width.

2. Fasteners for Aluminum Sheet: Aluminum or Series 300 stainless steel.
3. Fasteners for Stainless-Steel Sheet: Series 300 stainless steel.
4. Fasteners for Zinc-Coated (Galvanized) or Aluminum-Zinc Alloy-Coated Steel Sheet: Series 300 stainless steel or hot-dip galvanized steel according to ASTM A 153/A 153M or ASTM F 2329.

C. Solder:

1. For Stainless Steel: ASTM B 32, Grade Sn60, with acid flux of type recommended by stainless-steel sheet manufacturer.
2. For Zinc-Coated (Galvanized) Steel: ASTM B 32, Grade Sn50, 50 percent tin and 50 percent lead or Grade Sn60, 60 percent tin and 40 percent lead with maximum lead content of 0.2 percent.

D. Sealant Tape: Pressure-sensitive, 100 percent solids, polyisobutylene compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape 1/2 inch wide and 1/8 inch thick.

E. Elastomeric Sealant: ASTM C 920, elastomeric silicone polymer sealant; of type, grade, class, and use classifications required to seal joints in sheet metal flashing and trim and remain watertight.

F. Butyl Sealant: ASTM C 1311, single-component, solvent-release butyl rubber sealant; polyisobutylene plasticized; heavy bodied for hooked-type expansion joints with limited movement.

G. Epoxy Seam Sealer: Two-part, noncorrosive, aluminum seam-cementing compound, recommended by aluminum manufacturer for exterior nonmoving joints, including riveted joints.

2.5 MANUFACTURED REGLETS

A. Reglets: Units of type, material, and profile required, formed to provide secure interlocking of separate reglet and counterflashing pieces, and compatible with flashing indicated with factory-mitered and -welded corners and junctions and with interlocking counterflashing on exterior face, of same metal as reglet.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Fry Reglet Corporation.
   b. Heckmann Building Products, Inc.
   c. Hickman, W. P. Company.
   d. Hohmann & Barnard, Inc.

2. Material: Stainless steel, 0.019 inch thick, Aluminum, 0.024 inch thick or Galvanized steel, 0.022 inch thick.
3. Finish: With manufacturer's standard color coating. Colors selected by Architect.

2.6 FABRICATION, GENERAL

A. General: Custom fabricate sheet metal flashing and trim to comply with details shown and recommendations in cited sheet metal standard that apply to design, dimensions, geometry, metal thickness, and other characteristics of item required. Fabricate sheet metal flashing and trim in shop to greatest extent possible.

1. Obtain field measurements for accurate fit before shop fabrication.
2. Form sheet metal flashing and trim to fit substrates without excessive oil canning, buckling, and tool marks; true to line, levels, and slopes; and with exposed edges folded back to form hems.
3. Conceal fasteners and expansion provisions where possible. Do not use exposed fasteners on faces exposed to view.

B. Expansion Provisions: Form metal for thermal expansion of exposed flashing and trim.

1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with butyl sealant concealed within joints.
2. Use lapped expansion joints only where indicated on Drawings.

C. Sealant Joints: Where movable, nonexpansion-type joints are required, form metal to provide for proper installation of elastomeric sealant according to cited sheet metal standard.

D. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal.

E. Fabricate cleats and attachment devices of sizes as recommended by cited sheet metal standard for application, but not less than thickness of metal being secured.

F. Seams: Fabricate nonmoving seams with flat-lock seams. Form seams and seal with elastomeric sealant unless otherwise recommended by sealant manufacturer for intended use. Rivet joints where necessary for strength.

G. Seams for Aluminum: Fabricate nonmoving seams with flat-lock seams. Form seams and seal with epoxy seam sealer. Rivet joints where necessary for strength.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. General: Anchor sheet metal flashing and trim and other components of the Work securely in place, with provisions for thermal and structural movement. Use fasteners, solder, protective coatings, separators, sealants, and other miscellaneous items as required to complete sheet metal flashing and trim system.

1. Install sheet metal flashing and trim true to line, levels, and slopes. Provide uniform, neat seams with minimum exposure of solder, welds, and sealant.
2. Install sheet metal flashing and trim to fit substrates and to result in watertight performance. Verify shapes and dimensions of surfaces to be covered before fabricating sheet metal.
3. Space cleats not more than 12 inches apart. Attach each cleat with at least two fasteners. Bend tabs over fasteners.
4. Install exposed sheet metal flashing and trim with limited oil canning, and free of buckling and tool marks.
5. Torch cutting of sheet metal flashing and trim is not permitted.

B. Metal Protection: Where dissimilar metals contact each other, or where metal contacts pressure-treated wood or other corrosive substrates, protect against galvanic action or corrosion by painting contact surfaces with bituminous coating or by other permanent separation as recommended by sheet metal manufacturer or cited sheet metal standard.

1. Coat concealed side of uncoated-aluminum and stainless-steel sheet metal flashing and trim with bituminous coating where flashing and trim contact wood, ferrous metal, or cementitious construction.
2. Underlayment: Where installing sheet metal flashing and trim directly on cementitious or wood substrates, install underlayment and cover with slip sheet.

C. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at maximum of 10 feet with no joints within 24 inches of corner or intersection.

1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with sealant concealed within joints.
2. Use lapped expansion joints only where indicated on Drawings.

D. Fasteners: Use fastener sizes that penetrate substrate not less than recommended by fastener manufacturer to achieve maximum pull-out resistance.

E. Conceal fasteners and expansion provisions where possible in exposed work and locate to minimize possibility of leakage. Cover and seal fasteners and anchors as required for a tight installation.

F. Seal joints as required for watertight construction. Prepare joints and apply sealants to comply with requirements in Section 079200 "Joint Sealants."

G. Soldered Joints: Clean surfaces to be soldered, removing oils and foreign matter. Pre-tin edges of sheets with solder to width of 1-1/2 inches; however, reduce pre-tinning where pre-tinned surface would show in completed Work.

1. Do not solder metallic-coated steel and aluminum sheet.
2. Do not use torches for soldering.
3. Heat surfaces to receive solder, and flow solder into joint. Fill joint completely. Completely remove flux and spatter from exposed surfaces.
4. Stainless-Steel Soldering: Tin edges of uncoated sheets, using solder for stainless steel and acid flux. Promptly remove acid flux residue from metal after tinning and soldering. Comply with solder manufacturer's recommended methods for cleaning and neutralization.
5. Copper Soldering: Tin edges of uncoated sheets, using solder for copper.

H. Rivets: Rivet joints in uncoated aluminum where necessary for strength.

3.2 ROOF FLASHING INSTALLATION

A. General: Install sheet metal flashing and trim to comply with performance requirements, sheet metal manufacturer's written installation instructions and cited sheet metal standard. Provide concealed fasteners where possible, and set units true to line, levels, and slopes. Install work with laps, joints, and seams that are permanently watertight and weather resistant.

B. Roof Edge Flashing: Anchor to resist uplift and outward forces according to recommendations in cited sheet metal standard unless otherwise indicated. Interlock bottom edge of roof edge flashing with continuous cleat anchored to substrate.

C. Counterflashing: Coordinate installation of counterflashing with installation of base flashing. Insert counterflashing in reglets or receivers and fit tightly to base flashing. Extend counterflashing 4 inches over base flashing. Lap counterflashing joints minimum of 4 inches.

D. Roof-Penetration Flashing: Coordinate installation of roof-penetration flashing with installation of roofing and other items penetrating roof. Seal with butyl sealant and clamp flashing to pipes that penetrate roof.

3.3 WALL FLASHING INSTALLATION

A. General: Install sheet metal wall flashing to intercept and exclude penetrating moisture according to cited sheet metal standard unless otherwise indicated. Coordinate installation of

wall flashing with installation of wall-opening components such as windows, doors, and louvers.

B. Opening Flashings in Frame Construction: Install continuous head, sill, jamb and similar flashings to extend 4 inches beyond wall openings.

3.4 CLEANING AND PROTECTION

A. Clean exposed metal surfaces of substances that interfere with uniform oxidation and weathering.

B. Clean and neutralize flux materials. Clean off excess solder.

C. Clean off excess sealants.

D. Remove temporary protective coverings and strippable films as sheet metal flashing and trim are installed unless otherwise indicated in manufacturer's written installation instructions.

END OF SECTION 076200

SECTION 077100 - ROOF SPECIALTIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Copings.
2. Roof-edge flashings.
3. Roof-edge drainage systems.
4. Reglets and counterflashings.

1.2 PERFORMANCE REQUIREMENTS

A. SPRI Wind Design Standard: Manufacture and install copings and roof-edge flashings tested according to SPRI ES-1 and capable of resisting the following design pressures:

1. Design Pressure: As required by the International Building Code 2012 edition.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: For roof specialties. Include plans, elevations, expansion-joint locations, keyed details, and attachments to other work. Distinguish between plant- and field-assembled work.

C. Samples: For each exposed product and for each color and texture specified.

1.4 INFORMATIONAL SUBMITTALS

A. Product test reports.

B. Warranty: Sample of special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.6 QUALITY ASSURANCE

A. Preinstallation Conference: Conduct conference at Project site.

1.7 WARRANTY

A. Special Warranty on Painted Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace roof specialties that show evidence of deterioration of factory-applied finishes within 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 EXPOSED METALS

A. Zinc-Coated (Galvanized) Steel Sheet: ASTM A 653/A 653M, G90 coating designation.

1. Manufacturer: Mcelroy Metals
2. Surface: Smooth, flat finish.
3. Exposed Coil-Coated Finishes: Prepainted by the coil-coating process to comply with ASTM A 755/A 755M. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

a. Two-Coat Fluoropolymer: AAMA 621. System consisting of primer and fluoropolymer color topcoat containing not less than 70 percent PVDF resin by weight.

1) Color: As selected by Architect from manufacturer’s full range.

2.2 CONCEALED METALS

A. Zinc-Coated (Galvanized) Steel Sheet: ASTM A 653/A 653M, G90 coating designation.

2.3 UNDERLAYMENT MATERIALS

A. Felt: ASTM D 226, Type II (No. 30), asphalt-saturated organic felt, nonperforated.

B. Self-Adhering, High-Temperature Sheet: Minimum 30 to 40 mils thick, consisting of slip-resisting polyethylene-film top surface laminated to layer of butyl or SBS-modified asphalt adhesive, with release-paper backing; cold applied. Provide primer when recommended by underlayment manufacturer.

1. Thermal Stability: ASTM D 1970; stable after testing at 240 deg F.
2. Low-Temperature Flexibility: ASTM D 1970; passes after testing at minus 20 deg F.

C. Polyethylene Sheet: 6-mil thick polyethylene sheet complying with ASTM D 4397.

2.4 MISCELLANEOUS MATERIALS

A. General: Provide materials and types of fasteners, protective coatings, sealants, and other miscellaneous items required by manufacturer for a complete installation.

B. Fasteners: Manufacturer's recommended fasteners, suitable for application and designed to meet performance requirements. Furnish the following unless otherwise indicated:

1. Exposed Penetrating Fasteners: Gasketed screws with hex washer heads matching color of sheet metal.
2. Fasteners for Copper Sheet: Copper, hardware bronze, or passivated Series 300 stainless steel.
3. Fasteners for Aluminum: Aluminum or Series 300 stainless steel.
4. Fasteners for Stainless-Steel Sheet: Series 300 stainless steel.
5. Fasteners for Zinc-Coated (Galvanized) Steel Sheet: Series 300 stainless steel or hot-dip zinc-coated steel according to ASTM A 153/A 153M or ASTM F 2329.

C. Elastomeric Sealant: ASTM C 920, elastomeric polymer sealant of type, grade, class, and use classifications required by roofing-specialty manufacturer for each application.

D. Butyl Sealant: ASTM C 1311, single-component, solvent-release butyl rubber sealant; polyisobutylene plasticized; heavy bodied for hooked-type expansion joints with limited movement.

E. Bituminous Coating: Cold-applied asphalt emulsion complying with ASTM D 1187.

F. Asphalt Roofing Cement: ASTM D 4586, asbestos free, of consistency required for application.

2.5 COPINGS

A. Copings: Manufactured coping system consisting of formed-metal coping cap in section lengths not exceeding 12 feet, concealed anchorage; corner units, end cap units, and concealed splice plates with same finish as coping caps.

1. Coping-Cap Material: Zinc-coated steel, nominal thickness as required to meet performance requirements but not less than 24 gauge.

a. Finish: Two-coat fluoropolymer.
b. Color: Colonial Red.

2. Corners: Factory mitered and mechanically clinched and sealed watertight.
3. Coping-Cap Attachment Method: Face leg hooked to continuous cleat with back leg fastener exposed, fabricated from coping-cap material.
4. Snap-on-Coping Anchor Plates: Concealed, galvanized-steel sheet, 12 inches wide, with integral cleats.
5. Face Leg Cleats: Concealed, continuous galvanized-steel sheet.

2.6 ROOF-EDGE FLASHINGS

A. Roof-Edge Fascia and: Manufactured, two-piece, roof-edge fascia consisting of compression-clamped metal fascia cover in section lengths not exceeding 12 feet and a continuous formed galvanized-steel sheet, 0.028 inch thick, minimum, with extended vertical leg terminating in a drip-edge cleat. Provide matching corner units.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Mcelroy Metals.

2. Fascia Cover: Fabricated from the following exposed metal:
   a. Zinc-Coated Steel: Nominal thickness as required to meet performance requirements but not less than 24 gauge.

3. Corners: Factory mitered and mechanically clinched and sealed watertight.
4. Splice Plates: Exposed, of same material, finish, and shape as fascia cover.
5. Special Fabrications: Radiussed sections, Arched sections, Bullnose fascia cover, Cornice fascia cover and Cove fascia cover, as indicated by drawings.
6. Fascia Accessories: Fascia extenders with continuous hold-down cleats and Wall cap.

2.7 ROOF-EDGE DRAINAGE SYSTEMS

A. Gutters: Manufactured in uniform section lengths not exceeding 12 feet, with matching corner units, ends, outlet tubes, and other accessories. Elevate back edge at least 1 inch above front edge. Furnish flat-stock gutter straps, gutter brackets, expansion joints, and expansion-joint covers fabricated from same metal as gutters.

   1. Fabricate from the following exposed metal:

      a. Zinc-Coated Steel: Nominal 0.028-inch thickness.

   2. Gutter Profile: As indicated according to SMACNA's "Architectural Sheet Metal Manual."
   3. Corners: Factory mitered and mechanically clinched and sealed watertight.
   4. Gutter Supports: Straps.
   5. Gutter Accessories: Continuous hinged leaf guard of solid metal designed to shed leaves.

B. Downspouts: Plain rectangular complete with machine-crimped elbows, manufactured from the following exposed metal. Furnish with metal hangers, from same material as downspouts, and anchors.
   1. Zinc-Coated Steel: Nominal 0.034-inch thickness.

C. Zinc-Coated Steel Finish: Two-coat fluoropolymer.

   1. Color: As selected by Architect from manufacturer's full range.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. General: Install roof specialties according to manufacturer's written instructions. Anchor roof specialties securely in place, with provisions for thermal and structural movement. Use fasteners, solder, protective coatings, separators, sealants, and other miscellaneous items as required to complete roof-specialty systems.

1. Install roof specialties level, plumb, true to line and elevation; with limited oil-canning and without warping, jogs in alignment, buckling, or tool marks.
2. Provide uniform, neat seams with minimum exposure of solder and sealant.
3. Install roof specialties to fit substrates and to result in watertight performance. Verify shapes and dimensions of surfaces to be covered before manufacture.
4. Torch cutting of roof specialties is not permitted.
5. Install underlayment with adhesive for temporary anchorage. Apply in shingle fashion to shed water, with lapped joints of not less than 2 inches. Roll laps of self-adhering sheet underlayment with roller; cover within 14 days.

B. Metal Protection: Protect metals against galvanic action by separating dissimilar metals from contact with each other or with corrosive substrates by painting contact surfaces with bituminous coating or by other permanent separation as recommended by manufacturer.
1. Underlayment: Where installing metal flashing directly on cementitious or wood substrates, install a course of self-adhering, high-temperature sheet underlayment.

C. Expansion Provisions: Allow for thermal expansion of exposed roof specialties.

1. Space movement joints at a maximum of 12 feet with no joints within 18 inches corners or intersections unless otherwise shown on Drawings.
2. When ambient temperature at time of installation is between 40 and 70 deg F set joint members for 50 percent movement each way. Adjust setting proportionately for installation at higher ambient temperatures.

D. Fastener Sizes: Use fasteners of sizes that will penetrate wood blocking or sheathing not less than 3/4 inch for wood screws (nails are not acceptable) and substrate not less than recommended by fastener manufacturer to achieve maximum pull-out resistance.

E. Seal joints with sealant as required by roofing-specialty manufacturer.

F. Seal joints as required for watertight construction. Place sealant to be completely concealed in joint. Do not install sealants at temperatures below 40 deg F.

3.2 COPING INSTALLATION

A. Install cleats, anchor plates, and other anchoring and attachment accessories and devices with concealed fasteners.

B. Anchor copings to meet performance requirements.

1. Interlock face and back leg drip edges of snap-on coping cap into cleated anchor plates anchored to substrate at manufacturer's required spacing that meets performance requirements.
2. Interlock face leg drip edge into continuous cleat anchored to substrate at manufacturer's required spacing that meets performance requirements. Anchor back leg of coping with screw fasteners and elastomeric washers at manufacturer's required spacing that meets performance requirements.

3.3 ROOF-EDGE FLASHING INSTALLATION

A. Install cleats, cants, and other anchoring and attachment accessories and devices with concealed fasteners.

B. Anchor roof edgings with manufacturer's required devices, fasteners, and fastener spacing to meet performance requirements.

3.4 ROOF-EDGE DRAINAGE-SYSTEM INSTALLATION

A. General: Install components to produce a complete roof-edge drainage system according to manufacturer's written instructions.

B. Gutters: Join and seal gutter lengths. Allow for thermal expansion. Attach gutters to firmly anchored gutter supports spaced not more than 30 inches apart. Attach ends with rivets and seal with sealant to make watertight. Slope to downspouts.

1. Install gutter with expansion joints at locations indicated but not exceeding 50 feet apart. Install expansion joint caps.
2. Install continuous leaf guards on gutters with noncorrosive fasteners, hinged to swing open for cleaning gutters.

C. Downspouts: Join sections with manufacturer's standard telescoping joints. Provide hangers with fasteners designed to hold downspouts securely to walls and 1 inch away from walls; locate fasteners at top and bottom and at approximately 60 inches o.c.

3.5 CLEANING AND PROTECTION

A. Clean exposed metal surfaces of substances that interfere with uniform oxidation and weathering.

B. Clean and neutralize flux materials. Clean off excess solder and sealants.

C. Remove temporary protective coverings and strippable films as roof specialties are installed.

END OF SECTION 077100

SECTION 077200 - ROOF ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Roof curbs.
2. Equipment supports.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of roof accessory indicated.

B. Shop Drawings: For roof accessories.

C. Samples: For each exposed product and for each color and texture specified.

1.3 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Roof plans, drawn to scale, and coordinating penetrations and roof-mounted items.

B. Warranty: Sample of special warranty.

1.4 CLOSEOUT SUBMITTALS

A. Operation and maintenance data.

1.5 WARRANTY

A. Special Warranty on Painted Finishes: Manufacturer's standard form in which manufacturer agrees to repair finishes or replace roof accessories that show evidence of deterioration of factory-applied finishes within 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 METAL MATERIALS

A. Zinc-Coated (Galvanized) Steel Sheet: ASTM A 653/A 653M, G90 coating designation.

1. Mill-Phosphatized Finish: Manufacturer's standard for field painting.

2. Factory Prime Coating: Where field painting is indicated, apply pretreatment and white or light-colored, factory-applied, baked-on epoxy primer coat, with a minimum dry film thickness of 0.2 mil.
3. Exposed Coil-Coated Finish: Two-coat fluoropolymer finish; AAMA 621; system consisting of primer and fluoropolymer color topcoat containing not less than 70 percent PVDF resin by weight.

B. Aluminum Extrusions and Tubes: ASTM B 221, manufacturer's standard alloy and temper for type of use, finished to match assembly where used, otherwise mill finished.

2.2 MISCELLANEOUS MATERIALS

A. General: Provide materials and types of fasteners, protective coatings, sealants, and other miscellaneous items required by manufacturer for a complete installation.

B. Fasteners: Roof accessory manufacturer's recommended fasteners suitable for application and metals being fastened. Match finish of exposed fasteners with finish of material being fastened. Provide nonremovable fastener heads to exterior exposed fasteners.

C. Sealants: As recommended by roof accessory manufacturer for installation indicated.

2.3 ROOF CURBS

A. Roof Curbs, General: Provide roof curbs, as specified by this Section, unless otherwise specified by Division 23 “HVAC.”

B. Roof Curbs: Internally reinforced roof-curb units with integral spring-type vibration isolators and capable of supporting superimposed live and dead loads, including equipment loads and other construction indicated on Drawings; with welded or mechanically fastened and sealed corner joints, stepped integral metal cant raised the thickness of roof insulation and integrally formed deck-mounting flange at perimeter bottom.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

    a. AES Industries, Inc.
    b. Curbs Plus, Inc.
    c. Custom Solution Roof and Metal Products.
    d. Greenheck Fan Corporation.
    e. LM Curbs.
    f. Metallic Products Corp.
    g. Milcor Inc.; Commercial Products Group of Hart & Cooley, Inc.
    h. Pate Company (The).
    i. Roof Products, Inc.
    j. Safe Air of Illinois.
    k. Thybar Corporation.
    l. Vent Products Co., Inc.

C. Material: Zinc-coated (galvanized) steel sheet, 0.080 inch thick, but not less than required to support superimposed live and dead load, including equipment loads.

1. Finish: Two-coat fluoropolymer.
2. Color: As selected by Architect from manufacturer's full range.

D. Construction:

1. Insulation: Factory insulated with 1-1/2-inch glass-fiber board insulation.
2. Liner: Same material as curb, of manufacturer's standard thickness and finish.
3. Factory-installed wood nailer at top of curb, continuous around curb perimeter.
4. On ribbed or fluted metal roofs, form deck-mounting flange at perimeter bottom to conform to roof profile.
5. Fabricate curbs to minimum height of 8 inches, above finished roof, unless otherwise indicated to be fabricated taller.
6. Top Surface: Level around perimeter with roof slope accommodated by sloping the deck-mounting flange.
7. Sloping Roofs: Where roof slope exceeds 1:48, fabricate curb with perimeter curb height tapered to accommodate roof slope so that top surface of perimeter curb is level. Equip unit with water diverter or cricket on side that obstructs water flow.

PART 3 - EXECUTION

3.1 INSTALLATION

A. General: Verify dimensions of roof openings for roof accessories. Install roof accessories according to manufacturer's written instructions.

1. Install roof accessories level, plumb, true to line and elevation, and without warping, jogs in alignment, excessive oil canning, buckling, or tool marks.
2. Anchor roof accessories securely in place so they are capable of resisting indicated loads.
3. Use fasteners, separators, sealants, and other miscellaneous items as required to complete installation of roof accessories and fit them to substrates.
4. Install roof accessories to resist exposure to weather without failing, rattling, leaking, or loosening of fasteners and seals.

B. Metal Protection: Protect metals against galvanic action by separating dissimilar metals from contact with each other or with corrosive substrates by painting contact surfaces with bituminous coating or by other permanent separation as recommended by manufacturer.

1. Underlayment: Where installing roof accessories directly on cementitious or wood substrates, install a course of felt underlayment and cover with a slip sheet, or install a course of polyethylene sheet.

C. Seal joints with sealant as required by roof accessory manufacturer.

3.2 REPAIR AND CLEANING

A. Galvanized Surfaces: Clean field welds, bolted connections, and abraded areas and repair galvanizing according to ASTM A 780.

B. Replace roof accessories that have been damaged or that cannot be successfully repaired by finish touchup or similar minor repair procedures.

END OF SECTION 077200

SECTION 078413 - PENETRATION FIRESTOPPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Penetrations in fire-resistance-rated walls.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

B. Product Schedule: For each penetration firestopping system. Include location and design designation of qualified testing and inspecting agency.

1. Where Project conditions require modification to a qualified testing and inspecting agency's illustration for a particular penetration firestopping condition, submit illustration, with modifications marked, approved by penetration firestopping manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly.

1.3 INFORMATIONAL SUBMITTALS

A. Installer Certificates: From Installer indicating penetration firestopping has been installed in compliance with requirements and manufacturer's written recommendations.

B. Product test reports.

1.4 QUALITY ASSURANCE

A. Fire-Test-Response Characteristics: Penetration firestopping shall comply with the following requirements:

1. Penetration firestopping tests are performed by UL, FM Global or other qualified testing agency acceptable to authorities having jurisdiction.
2. Penetration firestopping is identical to those tested per testing standard referenced in "Penetration Firestopping" Article. Provide rated systems bearing marking of qualified testing and inspection agency.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Hilti, Inc.
2. Johns Manville.
3. RectorSeal Corporation.
4. Specified Technologies Inc.
5. 3M Fire Protection Products.
6. USG Corporation.

2.2 PENETRATION FIRESTOPPING

A. Provide penetration firestopping that is produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of construction penetrated. Penetration firestopping systems shall be compatible with one another, with the substrates forming openings, and with penetrating items if any.

B. Penetrations in Fire-Resistance-Rated Walls: Ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg.

1. F-Rating: Not less than the fire-resistance rating of constructions penetrated.

C. Penetrations in Horizontal Assemblies: Ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg.

1. F-Rating: At least 1 hour, but not less than the fire-resistance rating of constructions penetrated.
2. T-Rating: At least 1 hour, but not less than the fire-resistance rating of constructions penetrated except for floor penetrations within the cavity of a wall.

D. Exposed Penetration Firestopping: Provide products with flame-spread and smoke-developed indexes of less than 25 and 450, respectively, as determined per ASTM E 84.

E. VOC Content: Penetration firestopping sealants and sealant primers shall comply with the following limits for VOC content when calculated according to 40 CFR 59, Subpart D (EPA Method 24):

1. Sealants: 250 g/L.
2. Sealant Primers for Nonporous Substrates: 250 g/L.
3. Sealant Primers for Porous Substrates: 775 g/L.

F. Accessories: Provide components for each penetration firestopping system that are needed to install fill materials and to maintain ratings required. Use only those components specified by

penetration firestopping manufacturer and approved by qualified testing and inspecting agency for firestopping indicated.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for opening configurations, penetrating items, substrates, and other conditions affecting performance of the Work.

B. Install penetration firestopping to comply with manufacturer's written installation instructions and published drawings for products and applications indicated.

C. Install forming materials and other accessories of types required to support fill materials during their application and in the position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.

1. After installing fill materials and allowing them to fully cure, remove combustible forming materials and other accessories not indicated as permanent components of firestopping.

D. Install fill materials for firestopping by proven techniques to produce the following results:

1. Fill voids and cavities formed by openings, forming materials, accessories, and penetrating items as required to achieve fire-resistance ratings indicated.
2. Apply materials so they contact and adhere to substrates formed by openings and penetrating items.
3. For fill materials that will remain exposed after completing the Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

3.2 IDENTIFICATION

A. Identify penetration firestopping with preprinted metal or plastic labels. Attach labels permanently to surfaces adjacent to and within 6 inches of firestopping edge so labels will be visible to anyone seeking to remove penetrating items or firestopping. Use mechanical fasteners or self-adhering-type labels with adhesives capable of permanently bonding labels to surfaces on which labels are placed. Include the following information on labels:

1. The words "Warning - Penetration Firestopping - Do Not Disturb. Notify Building Management of Any Damage."
2. Contractor's name, address, and phone number.
3. Designation of applicable testing and inspecting agency.
4. Date of installation.
5. Manufacturer's name.
6. Installer's name.

3.3 FIELD QUALITY CONTROL

A. Owner will engage a qualified testing agency to perform tests and inspections.

B. Where deficiencies are found or penetration firestopping is damaged or removed because of testing, repair or replace penetration firestopping to comply with requirements.

C. Proceed with enclosing penetration firestopping with other construction only after inspection reports are issued and installations comply with requirements.

END OF SECTION 078413

SECTION 079200 - JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Silicone joint sealants.
2. Urethane joint sealants.
3. Preformed joint sealants.

1.2 PRECONSTRUCTION TESTING

A. Preconstruction Compatibility and Adhesion Testing: Submit to joint-sealant manufacturers eight samples of materials that will contact or affect joint sealants. Use ASTM C 1087 or manufacturer's standard test method to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of joint sealants to joint substrates.

B. Preconstruction Field-Adhesion Testing: Before installing sealants, field test their adhesion to Project joint substrates. Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C 1193 or Method A, Tail Procedure, in ASTM C 1521.

1.3 ACTION SUBMITTALS

A. Product Data: For each joint-sealant product indicated.

B. Samples: For each kind and color of joint sealant required.

C. Joint-Sealant Schedule: Include the following information:

1. Joint-sealant application, joint location, and designation.
2. Joint-sealant manufacturer and product name.
3. Joint-sealant formulation.
4. Joint-sealant color.

1.4 INFORMATIONAL SUBMITTALS

A. Product test reports.

B. Preconstruction compatibility and adhesion test reports.

C. Preconstruction field-adhesion test reports.

D. Field-adhesion test reports.

E. Warranties.

1.5 QUALITY ASSURANCE

A. Preinstallation Conference: Conduct conference at Project site.

1.6 WARRANTY

A. Special Installer's Warranty: Manufacturer's standard form in which Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

A. VOC Content of Interior Sealants: Sealants and sealant primers used inside the weatherproofing system shall comply with the following limits for VOC content when calculated according to 40 CFR 59, Subpart D (EPA Method 24):

1. Architectural Sealants: 250 g/L.
2. Sealant Primers for Nonporous Substrates: 250 g/L.
3. Sealant Primers for Porous Substrates: 775 g/L.

B. Liquid-Applied Joint Sealants: Comply with ASTM C 920 and other requirements indicated for each liquid-applied joint sealant specified, including those referencing ASTM C 920 classifications for type, grade, class, and uses related to exposure and joint substrates.

1. Suitability for Immersion in Liquids. Where sealants are indicated for Use I for joints that will be continuously immersed in liquids, provide products that have undergone testing according to ASTM C 1247. Liquid used for testing sealants is deionized water, unless otherwise indicated.

C. Stain-Test-Response Characteristics: Where sealants are specified to be nonstaining to porous substrates, provide products that have undergone testing according to ASTM C 1248 and have not stained porous joint substrates indicated for Project.

2.2 SILICONE JOINT SEALANTS

A. Mildew-Resistant, Neutral-Curing Silicone Joint Sealant: ASTM C 920.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. BASF Building Systems.
    b. Dow Corning Corporation.
    c. GE Advanced Materials - Silicones.
    d. May National Associates, Inc.
    e. Pecora Corporation.
    f. Polymeric Systems, Inc.
    g. Schnee-Morehead, Inc.
    h. Sika Corporation; Construction Products Division.
    i. Tremco Incorporated.

2. Type: Single component (S).
3. Grade: Nonsag (NS).
4. Class: 2.
5. Uses Related to Exposure: Traffic (T) or Nontraffic (NT), as applicable to exposure.

2.3 URETHANE JOINT SEALANTS

A. Urethane Joint Sealant: ASTM C 920.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. BASF Building Systems.
    b. Bostik, Inc.
    c. Lymtal, International, Inc.
    d. May National Associates, Inc.
    e. Pacific Polymers International, Inc.
    f. Pecora Corporation.
    g. Polymeric Systems, Inc.
    h. Schnee-Morehead, Inc.
    i. Sika Corporation; Construction Products Division.
    j. Tremco Incorporated.

2. Type: Multicomponent (M).
3. Grade: Nonsag (NS).
4. Class: 25.
5. Uses Related to Exposure: Traffic (T) or Nontraffic (NT), as applicable to exposure.

2.4 PREFORMED JOINT SEALANTS

A. Preformed Foam Joint Sealant : Manufacturer's standard preformed, precompressed, open-cell foam sealant manufactured from urethane foam with minimum density of 10 lb/cu. ft. and impregnated with a nondrying, water-repellent agent. Factory produce in precompressed sizes

in roll or stick form to fit joint widths indicated; coated on one side with a pressure-sensitive adhesive and covered with protective wrapping.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Dayton Superior Specialty Chemicals.
    b. EMSEAL Joint Systems, Ltd.
    c. Sandell Manufacturing Co.
    d. Schul International, Inc.
    e. Willseal USA, LLC.

2.5 JOINT SEALANT BACKING

A. Cylindrical Sealant Backings: ASTM C 1330, Type C (closed-cell material with a surface skin), Type O (open-cell material) or any of the preceding types, as approved in writing by joint-sealant manufacturer for joint application indicated, and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.

B. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer.

2.6 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions.

1. Remove laitance and form-release agents from concrete.
2. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants.

B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.2 INSTALLATION

A. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.

B. Install sealant backings of kind indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.

1. Do not leave gaps between ends of sealant backings.
2. Do not stretch, twist, puncture, or tear sealant backings.
3. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.

C. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.

D. Install sealants using proven techniques that comply with the following and at the same time backings are installed:

1. Place sealants so they directly contact and fully wet joint substrates.
2. Completely fill recesses in each joint configuration.
3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.

E. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.

1. Remove excess sealant from surfaces adjacent to joints.
2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
3. Provide concave joint profile per Figure 8A in ASTM C 1193, unless otherwise indicated.

F. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.3 FIELD QUALITY CONTROL

A. Field-Adhesion Testing: Field test joint-sealant adhesion to joint substrates as follows:

1. Extent of Testing: Test completed and cured sealant joints as follows:

a. Perform 10 tests for the first 1000 feet of joint length for each kind of sealant and joint substrate.
b. Perform 1 test for each 1000 feet of joint length thereafter or 1 test per each floor per elevation.

2. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C 1193 or Method A, Tail Procedure, in ASTM C 1521.

B. Evaluation of Field-Adhesion Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

END OF SECTION 079200

SECTION 081113 - HOLLOW METAL DOORS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes hollow-metal work.

1.2 DEFINITIONS

A. Minimum Thickness: Minimum thickness of base metal without coatings according to NAAMM-HMMA 803 or SDI A250.8.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: Include elevations, door edge details, frame profiles, metal thicknesses, preparations for hardware, and other details.

C. Samples for Initial Selection: For units with factory-applied color finishes.

D. Samples for Verification: For each type of exposed finish required.

E. Schedule: Prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings.

1.4 INFORMATIONAL SUBMITTALS

A. Product test reports.

1.5 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of hollow metal door and frame systems that fail in materials or workmanship within specified warranty period.

1. Warranty Period: One year from substantial completion.

1.6 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Ceco Door Products; an Assa Abloy Group company.
2. Curries Company; an Assa Abloy Group company
3. Steelcraft; an Ingersoll-Rand company.

1.7 REGULATORY REQUIREMENTS

A. Fire-Rated Assemblies: Complying with NFPA 80 and listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction for fire-protection ratings indicated, based on testing at positive pressure according to NFPA 252 or UL 10C.

1. Smoke- and Draft-Control Assemblies: Provide an assembly with gaskets listed and labeled for smoke and draft control by a qualified testing agency acceptable to authorities having jurisdiction, based on testing according to UL 1784 and installed in compliance with NFPA 105.

B. Fire-Rated, Borrowed-Light Assemblies: Complying with NFPA 80 and listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction for fire-protection ratings indicated, based on testing according to NFPA 257 or UL 9.

1.8 INTERIOR FRAMES

A. Standard-Duty Doors and Frames: SDI A250.8, Level 1.

1. Physical Performance: Level C according to SDI A250.4.

2. Frames:

a. Materials: Metallic-coated, cold-rolled steel sheet, minimum thickness of 0.042 inch.
b. Construction: Full profile welded.

3. Exposed Finish: Factory primed.

1.9 EXTERIOR HOLLOW-METAL DOORS AND FRAMES

A. Heavy-Duty Doors and Frames: SDI A250.8, Level 2.

1. Physical Performance: Level B according to SDI A250.4.
2. Doors:

a. Type: As indicated in the Door and Frame Schedule.
b. Thickness: 1-3/4 inches.
c. Face: Metallic-coated steel sheet, minimum thickness of 0.042 inch, with minimum A40 coating.
d. Edge Construction: Seamless.
e. Core: Manufacturer's standard insulation material.

3. Thermal-Rating: Provide doors fabricated with thermal-resistance value (R-value) of not less than 2.1 deg F x h x sq. ft./Btu when tested according to ASTM C 1363.

4. Frames:

   a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum A40 coating.
   b. Construction: Full profile welded.

5. Exposed Finish: Factory Primed.

1.10 FRAME ANCHORS

A. Jamb Anchors:

1. Masonry Type: Adjustable strap-and-stirrup or T-shaped anchors to suit frame size, not less than 0.042 inch thick, with corrugated or perforated straps not less than 2 inches wide by 10 inches long; or wire anchors not less than 0.177 inch thick.
2. Stud-Wall Type: Designed to engage stud, welded to back of frames; not less than 0.042 inch thick.
3. Post-installed Expansion Type for In-Place Concrete or Masonry: Minimum 3/8-inch diameter bolts with expansion shields or inserts. Provide pipe spacer from frame to wall, with throat reinforcement plate, welded to frame at each anchor location.

B. Floor Anchors: Formed from same material as frames, minimum thickness of 0.042 inch, and as follows:

1. Monolithic Concrete Slabs: Clip-type anchors, with two holes to receive fasteners.

1.11 MATERIALS

A. Cold-Rolled Steel Sheet: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B; suitable for exposed applications.

B. Hot-Rolled Steel Sheet: ASTM A 1011/A 1011M, Commercial Steel (CS), Type B; free of scale, pitting, or surface defects; pickled and oiled.

C. Metallic-Coated Steel Sheet: ASTM A 653/A 653M, Commercial Steel (CS), Type B.

D. Frame Anchors: ASTM A 879/A 879M, Commercial Steel (CS), 04Z coating designation; mill phosphatized.

1. For anchors built into exterior walls, steel sheet complying with ASTM A 1008/A 1008M or ASTM A 1011/A 1011M, hot-dip galvanized according to ASTM A 153/A 153M, Class B.

E. Inserts, Bolts, and Fasteners: Hot-dip galvanized according to ASTM A 153/A 153M.

F. Power-Actuated Fasteners in Concrete: From corrosion-resistant materials.

G. Grout: ASTM C 476, except with a maximum slump of 4 inches, as measured according to ASTM C 143/C 143M.

H. Glazing: Section 088000 "Glazing."

1.12 FABRICATION

A. Fabricate hollow-metal work to be rigid and free of defects, warp, or buckle. Accurately form metal to required sizes and profiles, with minimum radius for metal thickness. Where practical, fit and assemble units in manufacturer's plant. To ensure proper assembly at Project site, clearly identify work that cannot be permanently factory assembled before shipment.

B. Hollow-Metal Doors:

1. Exterior Doors: Provide weep-hole openings in bottoms of exterior doors to permit moisture to escape. Seal joints in top edges of doors against water penetration.
2. Astragals: Provide overlapping astragal on one leaf of pairs of doors where required by NFPA 80 for fire-performance rating or where indicated.

C. Hollow-Metal Frames: Where frames are fabricated in sections due to shipping or handling limitations, provide alignment plates or angles at each joint, fabricated of same thickness metal as frames.

1. Sidelight and Transom Bar Frames: Provide closed tubular members with no visible face seams or joints, fabricated from same material as door frame. Fasten members at crossings and to jambs by butt welding.
2. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
3. Grout Guards: Weld guards to frame at back of hardware mortises in frames to be grouted.
4. Floor Anchors: Weld anchors to bottoms of jambs with at least four spot welds per anchor; however, for slip-on drywall frames, provide anchor clips or countersunk holes at bottoms of jambs.
5. Jamb Anchors: Provide number and spacing of anchors as follows:

a. Masonry Type: Locate anchors not more than 16 inches from top and bottom of frame. Space anchors not more than 32 inches o.c., to match coursing, and as follows:

1) Two anchors per jamb up to 60 inches high.
2) Three anchors per jamb from 60 to 90 inches high.
3) Four anchors per jamb from 90 to 120 inches high.
4) Four anchors per jamb plus one additional anchor per jamb for each 24 inches or fraction thereof above 120 inches high.

b. Stud-Wall Type: Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:

1) Three anchors per jamb up to 60 inches high.
2) Four anchors per jamb from 60 to 90 inches high.
3) Five anchors per jamb from 90 to 96 inches high.
4) Five anchors per jamb plus one additional anchor per jamb for each 24 inches or fraction thereof above 96 inches high.

c. Postinstalled Expansion Type: Locate anchors not more than 6 inches from top and bottom of frame. Space anchors not more than 26 inches o.c.

6. Door Silencers: Except on weather-stripped frames, drill stops to receive door silencers.

a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.

D. Hardware Preparation: Factory prepare hollow-metal work to receive templated mortised hardware; include cutouts, reinforcement, mortising, drilling, and tapping according to SDI A250.6, the Door Hardware Schedule, and templates.

1. Reinforce doors and frames to receive non-templated, mortised, and surface-mounted door hardware.
2. Comply with applicable requirements in SDI A250.6 and BHMA A156.115 for preparation of hollow-metal work for hardware.

E. Stops and Moldings: Provide stops and moldings around glazed lites. Form corners of stops and moldings with mitered hairline joints.

1. Single Glazed Lites: Provide fixed stops and moldings welded on secure side of hollow-metal work.
2. Provide fixed frame moldings on outside of exterior and on secure side of interior doors and frames.
3. Provide loose stops and moldings on inside of hollow-metal work.
4. Coordinate rabbet width between fixed and removable stops with glazing and installation types indicated.

1.13 STEEL FINISHES

A. Prime Finish: Clean, pre-treat, and apply manufacturer's standard primer.

1. Shop Primer: SDI A250.10.

B. Field Finish: Paint as specified for Steel Substrates in Section 099600 “High Performance Coatings”

1. Color and Gloss: As selected by Architect.

1.14 ACCESSORIES

A. Mullions and Transom Bars: Join to adjacent members by welding or rigid mechanical anchors.

B. Grout Guards: Formed from same material as frames, not less than 0.016 inch thick.

PART 2 - EXECUTION

2.1 INSTALLATION

A. Hollow-Metal Frames: Install hollow-metal frames of size and profile indicated. Comply with SDI A250.11 or NAAMM-HMMA 840 as required by standards specified.

1. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces, leaving surfaces smooth and undamaged.

    a. At fire-rated openings, install frames according to NFPA 80.
    b. Where frames are fabricated in sections because of shipping or handling limitations, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces.
    c. Install frames with removable stops located on secure side of opening.
    d. Install door silencers in frames before grouting.
    e. Remove temporary braces necessary for installation only after frames have been properly set and secured.
    f. Check plumb, square, and twist of frames as walls are constructed. Shim as necessary to comply with installation tolerances.
    g. Field apply bituminous coating to backs of frames that will be filled with grout containing anti-freezing agents.

2. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor, and secure with post-installed expansion anchors.

    a. Floor anchors may be set with power-actuated fasteners instead of post-installed expansion anchors if so indicated and approved on Shop Drawings.

3. Metal-Stud Partitions: Solidly pack un-faced fiber-glass insulation inside frames.
4. In-Place Concrete or Masonry Construction: Secure frames in place with post-installed expansion anchors. Countersink anchors, and fill and make smooth, flush, and invisible on exposed faces.
5. Installation Tolerances: Adjust hollow-metal door frames for squareness, alignment, twist, and plumb to the following tolerances:

    a. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
    b. Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.
    c. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
    d. Plumbness: Plus or minus 1/16 inch, measured at jambs at floor.

B. Hollow-Metal Doors: Fit hollow-metal doors accurately in frames, within clearances specified below. Shim as necessary.

1. Non-Fire-Rated Steel Doors:

a. Between Door and Frame Jambs and Head: 1/8 inch plus or minus 1/32 inch.
b. Between Edges of Pairs of Doors: 1/8 inch to 1/4 inch plus or minus 1/32 inch.
c. At Bottom of Door: 5/8 inch plus or minus 1/32 inch.
d. Between Door Face and Stop: 1/16 inch to 1/8 inch plus or minus 1/32 inch.

2. Fire-Rated Doors: Install doors with clearances according to NFPA 80.
3. Smoke-Control Doors: Install doors and gaskets according to NFPA 105.

C. Glazing: Comply with installation requirements in Section 088000 "Glazing" and with hollow-metal manufacturer's written instructions.

1. Secure stops with countersunk flat- or oval-head machine screws spaced uniformly not more than 9 inches o.c. and not more than 2 inches o.c. from each corner.

2.2 ADJUSTING AND CLEANING

A. Final Adjustments: Check and readjust operating hardware items immediately before final inspection. Leave work in complete and proper operating condition. Remove and replace defective work, including hollow-metal work that is warped, bowed, or otherwise unacceptable.

B. Remove grout and other bonding material from hollow-metal work immediately after installation.

C. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.

D. Metallic-Coated Surface Touchup: Clean abraded areas and repair with galvanizing repair paint according to manufacturer's written instructions.

E. Touchup Painting: Cleaning and touchup painting of abraded areas of paint are specified in painting Sections.

END OF SECTION 081113

SECTION 083313 - COILING COUNTER DOORS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Counter doors.

B. Related Requirements:

1. Section 055000 "Metal Fabrications" for miscellaneous steel supports.

1.2 ACTION SUBMITTALS

A. Product Data: For each type and size of coiling counter door and accessory.

B. Shop Drawings: For each installation and for special components not dimensioned or detailed in manufacturer's product data.

1. Include points of attachment and their corresponding static and dynamic loads imposed on structure.
2. Show locations of controls, locking devices, detectors or replaceable fusible links, and other accessories.
3. Include diagrams for power, signal, and control wiring.

C. Samples: For each exposed product and for each color and texture specified.

1.3 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.4 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer for both installation and maintenance of units required for this Project.

PART 2 - PRODUCTS

2.1 COUNTER DOOR ASSEMBLY

A. Counter Door: Coiling counter door formed with curtain of interlocking metal slats.

1. Basis-of-Design Product: Subject to compliance with requirements, provide Overhead door Corporation; Model 650 or comparable product by one of the following:

    a. ACME Rolling Doors.
    b. Alpine Overhead Doors, Inc.
    c. C.H.I. Overhead Doors.
    d. Cookson Company.
    e. Overhead Door Corporation.
    f. Raynor.
    g. Wayne-Dalton Corp.

B. Door Curtain Material: Galvanized steel.

C. Door Curtain Slats: Flat profile slats of 1-1/2-inch center-to-center height.

D. Bottom Bar: Manufacturer's standard continuous channel or tubular shape, fabricated hot-dip galvanized steel and finished to match door.

E. Curtain Jamb Guides: Aluminum with exposed finish matching curtain slats. Provide continuous integral wear strips to prevent metal-to-metal contact and to minimize operational noise.

F. Hood: Match curtain material and finish.

1. Mounting: Face of wall.

G. Sill Configuration: No sill.

H. Locking Devices: Equip door with locking device assembly and chain lock keeper.

1. Locking Device Assembly: Cremone type, both jamb sides locking bars, operable from inside and outside with cylinders.

I. Manual Door Operator: Chain-hoist operator.

J. Door Finish:
1. Baked-Enamel or Powder-Coated Finish: Color as selected by Architect from manufacturer's full range.

2.2 DOOR CURTAIN MATERIALS AND CONSTRUCTION

A. Door Curtains: Fabricate coiling counter-door curtain of interlocking metal slats in a continuous length for width of door without splices. Unless otherwise indicated, provide slats of thickness and mechanical properties recommended by door manufacturer for performance, size, and type of door indicated, and as follows:

1. Metal Interior Curtain-Slat Facing: Match metal of exterior curtain-slat face.

B. Curtain Jamb Guides: Manufacturer's standard angles or channels and angles of same material and finish as curtain slats unless otherwise indicated, with sufficient depth and strength to retain

curtain, to allow curtain to operate smoothly, and to withstand loading. Slot bolt holes for guide adjustment. Provide removable stops on guides to prevent overtravel of curtain.

1. Removable Posts and Jamb Guides: Manufacturer's standard.

2.3 HOODS

A. General: Form sheet metal hood to entirely enclose coiled curtain and operating mechanism at opening head. Contour to fit end brackets to which hood is attached. Roll and reinforce top and bottom edges for stiffness. Form closed ends for surface-mounted hoods and fascia for any portion of between-jamb mounting that projects beyond wall face. Equip hood with intermediate support brackets as required to prevent sagging.

2.4 LOCKING DEVICES

A. Locking Device Assembly: Fabricate with cylinder lock, spring-loaded dead bolt, operating handle, cam plate, and adjustable locking bars to engage through slots in tracks.

1. Lock Cylinders: Cylinders standard with manufacturer and keyed to building keying system.
2. Keys: Three for each cylinder.

B. Chain Lock Keeper: Suitable for padlock.

2.5 COUNTERBALANCING MECHANISM

A. General: Counterbalance doors by means of manufacturer's standard mechanism with an adjustable-tension, steel helical torsion spring mounted around a steel shaft and contained in a spring barrel connected to top of curtain with barrel rings. Use grease-sealed bearings or self-lubricating graphite bearings for rotating members.

B. Brackets: Manufacturer's standard mounting brackets of either cast iron or cold-rolled steel plate.

2.6 MANUAL DOOR OPERATORS

A. General: Equip door with manual door operator by door manufacturer.

B. Chain-Hoist Operator: Consisting of endless steel hand chain, chain-pocket wheel and guard, and gear-reduction unit with a maximum 25-lbf force for door operation. Provide alloy-steel hand chain with chain holder secured to operator guide.

C. Crank Operator: Consisting of crank and crank gearbox, steel crank drive shaft, and gear-reduction unit, of type indicated. Size gears to require not more than [25-lbf (111-N)] [30-lbf (133-N)] <Insert value> force to turn crank. Fabricate gearbox to be oil tight and to completely enclose operating mechanism. Provide manufacturer's standard crank-locking device.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install coiling counter doors and operating equipment complete with necessary hardware, anchors, inserts, hangers, and equipment supports; according to manufacturer's written instructions and as specified.

B. Adjust hardware and moving parts to function smoothly so that doors operate easily, free of warp, twist, or distortion. Lubricate bearings and sliding parts as recommended by manufacturer.

3.2 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain coiling counter doors.

END OF SECTION 083313

SECTION 084113 - ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Exterior and interior storefront framing.
2. Exterior and interior manual-swing entrance doors.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: Include plans, elevations, sections, full-size details, and attachments to other work.

1. Show connection to and continuity with adjacent thermal, weather, air, and vapor barriers.

C. Samples: For each exposed finish required.

D. Entrance Door Hardware Schedule: Prepared by or under supervision of supplier, detailing fabrication and assembly of entrance door hardware, as well as procedures and diagrams.

1.4 INFORMATIONAL SUBMITTALS

A. Energy Performance Certificates: NFRC-certified energy performance values from manufacturer.

B. Product test reports.

C. Field quality-control reports.

D. Sample warranties.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.

B. Testing Agency Qualifications: Qualified according to ASTM E 699 for testing indicated.

C. Product Options: Information on Drawings and in Specifications establishes requirements for aesthetic effects and performance characteristics of assemblies. Aesthetic effects are indicated by dimensions, arrangements, alignment, and profiles of components and assemblies as they relate to sightlines, to one another, and to adjoining construction.

1. Do not change intended aesthetic effects, as judged solely by Architect, except with Architect's approval. If changes are proposed, submit comprehensive explanatory data to Architect for review.

1.7 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of aluminum-framed entrances and storefronts that do not comply with requirements or that fail in materials or workmanship within specified warranty period.

1. Warranty Period: 10 years from date of Substantial Completion.

B. Special Finish Warranty: Standard form in which manufacturer agrees to repair finishes or replace aluminum that shows evidence of deterioration of factory-applied finishes within specified warranty period.

1. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. General Performance: Comply with performance requirements specified, as determined by testing of aluminum-framed entrances and storefronts representing those indicated for this Project without failure due to defective manufacture, fabrication, installation, or other defects in construction.

1. Aluminum-framed entrances and storefronts shall withstand movements of supporting structure including, but not limited to, story drift, twist, column shortening, long-term creep, and deflection from uniformly distributed and concentrated live loads.
2. Failure also includes the following:

a. Thermal stresses transferring to building structure.
b. Glass breakage.
c. Noise or vibration created by wind and thermal and structural movements.
d. Loosening or weakening of fasteners, attachments, and other components.
e. Failure of operating units.

B. Structural Loads: As required by the International Building Code, 2012 edition.

C. Deflection of Framing Members: At design wind pressure, as follows:

1. Deflection Normal to Wall Plane: Limited to 1/175 of clear span for spans up to 13 feet 6 inches and to 1/240 of clear span plus 1/4 inch for spans greater than 13 feet 6 inches or an amount that restricts edge deflection of individual glazing lites to 3/4 inch, whichever is less.
2. Deflection Parallel to Glazing Plane: Limited to 1/360 of clear span or 1/8 inch, whichever is smaller.

    a. Operable Units: Provide a minimum 1/16-inch clearance between framing members and operable units.

3. Cantilever Deflection: Where framing members overhang an anchor point, as follows:

    a. Perpendicular to Plane of Wall: No greater than 1/240 of clear span plus 1/4 inch for spans greater than 11 feet 8-1/4 inches or 1/175 times span, for spans less than 11 feet 8-1/4 inches.

D. Structural: Test according to ASTM E 330 as follows:

1. When tested at positive and negative wind-load design pressures, assemblies do not evidence deflection exceeding specified limits.
2. When tested at 150 percent of positive and negative wind-load design pressures, assemblies, including anchorage, do not evidence material failures, structural distress, or permanent deformation of main framing members exceeding 0.2 percent of span.
3. Test Durations: As required by design wind velocity, but not less than 10 seconds.

E. Air Infiltration: Test according to ASTM E 283 for infiltration as follows:

1. Fixed Framing and Glass Area:

    a. Maximum air leakage of 0.06 cfm/sq. ft. at a static-air-pressure differential of 1.57 lbf/sq. ft..

2. Entrance Doors:

    a. Pair of Doors: Maximum air leakage of 1.0 cfm/sq. ft. at a static-air-pressure differential of 1.57 lbf/sq. ft.
    b. Single Doors: Maximum air leakage of 1.0 cfm/sq. ft. at a static-air-pressure differential of 1.57 lbf/sq. ft.

F. Water Penetration under Static Pressure: Test according to ASTM E 331 as follows:

1. No evidence of water penetration through fixed glazing and framing areas when tested according to a minimum static-air-pressure differential of 20 percent of positive wind-load design pressure, but not less than 10 lbf/sq. ft.

G. Energy Performance: Certify and label energy performance according to NFRC as follows:

1. Thermal Transmittance (U-factor): Fixed glazing and framing areas shall have U-factor of not more than 0.44 Btu/sq. ft. x h x deg F as determined according to NFRC 100.
2. Solar Heat Gain Coefficient: Fixed glazing and framing areas shall have a solar heat gain coefficient of no greater than 0.35 as determined according to NFRC 200.
3. Condensation Resistance: Fixed glazing and framing areas shall have an condensation resistance factor of no less than 62 for frames and 68 for glass as determined according to AAMA Specification 1503.

H. Thermal Movements: Allow for thermal movements resulting from ambient and surface temperature changes:

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 MANUFACTURERS

A. Basis-of-Design: Subject to compliance with requirements, provide Kawneer Co., Inc; Trifab VG 451T.

1. Old Castle Phone: 1.866.653.2278
2. YKK AP America Inc. 5300 Hollister St. Suite 320 Houston, Texas 77040 Phone: 713.329.9551.

2.3 FRAMING

A. Framing Members: Manufacturer's extruded- or formed-aluminum framing members of thickness required and reinforced as required to support imposed loads.

1. Construction: Thermally broken.
2. Frame Size: 2 inches by 4-1/2 inches.
3. Glazing System: Retained mechanically with gaskets on four sides.
4. Glazing Plane: Center.
5. Finish: As selected by Architect from the following:

    a. AA-M10C21A44/AA-M45C22A44, AAMA 611, Architectural Class 1, Clear anodic finish.
    b. Full range of manufacturer’s standard AA-M10C21A44/AA-M45C22A44, AAMA 611, Architectural Class 1, Color anodic finishes.
    c. Full range of manufacturer’s standard AAMA 2605, 70% PVDF, Fluoropolymer Coatings.
    d. Custom color AAMA 2605, 70% PVDF, Fluoropolymer Coating.

6. Fabrication Method: Field-fabricated stick system.

B. Backer Plates: Manufacturer's standard, continuous backer plates for framing members, if not integral, where framing abuts adjacent construction.

C. Brackets and Reinforcements: Manufacturer's standard high-strength aluminum with nonstaining, nonferrous shims for aligning system components.

D. Materials:

1. Aluminum: Alloy and temper recommended by manufacturer for type of use and finish indicated.

    a. Sheet and Plate: ASTM B 209.
    b. Extruded Bars, Rods, Profiles, and Tubes: ASTM B 221.
    c. Extruded Structural Pipe and Tubes: ASTM B 429/B 429M.
    d. Structural Profiles: ASTM B 308/B 308M.

2. Steel Reinforcement: Manufacturer's standard zinc-rich, corrosion-resistant primer complying with SSPC-PS Guide No. 12.00; applied immediately after surface preparation and pretreatment. Select surface preparation methods according to recommendations in SSPC-SP COM, and prepare surfaces according to applicable SSPC standard.

    a. Structural Shapes, Plates, and Bars: ASTM A 36/A 36M.
    b. Cold-Rolled Sheet and Strip: ASTM A 1008/A 1008M.
    c. Hot-Rolled Sheet and Strip: ASTM A 1011/A 1011M.

2.4 ENTRANCE DOOR SYSTEMS

A. Basis-of-Design: Subject to compliance with requirements, provide Kawneer Co., Inc; Series 500 Wide Stile.

1. Door Construction: 2- to 2-1/4-inch overall thickness, with minimum 0.125-inch thick, extruded-aluminum tubular rail and stile members. Mechanically fasten corners with reinforcing brackets that are deeply penetrated and fillet welded or that incorporate concealed tie rods.

    a. Thermal Construction: High-performance plastic connectors separate aluminum members exposed to the exterior from members exposed to the interior.

2. Door Design: Medium stile; 3-1/2-inch nominal width.
3. Glazing Gaskets: Manufacturer’s standard compression type, replaceable, extruded EPDM rubber.

2.5 ENTRANCE DOOR HARDWARE

A. Entrance Door Hardware: Hardware not specified in this Section is specified in Section 087100 "Door Hardware."

B. General: Provide entrance door hardware for each entrance door to comply with requirements in this Section.

1. Entrance Door Hardware Sets: Provide quantity, item, size, finish or color indicated, and products complying with BHMA standard referenced.
2. Sequence of Operation: Provide electrified door hardware function, sequence of operation, and interface with other building control systems indicated.
3. Opening-Force Requirements:

a. Egress Doors: Not more than 15 lbf to release the latch and not more than 30 lbf to set the door in motion and not more than 15 lbf to open the door to its minimum required width.
b. Accessible Interior Doors: Not more than 5 lbf to fully open door.

C. Designations: Requirements for design, grade, function, finish, size, and other distinctive qualities of each type of entrance door hardware are indicated in "Entrance Door Hardware Sets" Article. Products are identified by using entrance door hardware designations as follows:

1. Named Manufacturers' Products: Manufacturer and product designation are listed for each door hardware type required for the purpose of establishing minimum requirements. Manufacturers' names are abbreviated in "Entrance Door Hardware Sets" Article.
2. References to BHMA Standards: Provide products complying with these standards and requirements for description, quality, and function.

D. Butt Hinges: BHMA A156.1, Grade 1, radius corner.

1. Nonremovable Pins: Provide set screw in hinge barrel that, when tightened into a groove in hinge pin, prevents removal of pin while entrance door is closed.
2. Exterior Hinges: Stainless steel, with stainless-steel pin.
3. Quantities:

a. For doors up to 87 inches high, provide three hinges per leaf.
b. For doors more than 87 and up to 120 inches high, provide four hinges per leaf.

E. Mortise Auxiliary Locks: BHMA A156.5, Grade 1.

F. Automatic and Self-Latching Flush Bolts: BHMA A156.3, Grade 1.

G. Panic Exit Devices: BHMA A156.3, Grade 1, listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for panic protection, based on testing according to UL 305.

H. Cylinders: As specified in Section 087100 "Door Hardware."

1. Keying: Master key system. Permanently inscribe each key with a visual key control number and include notation "DO NOT DUPLICATE".

I. Strikes: Provide strike with black-plastic dust box for each latch or lock bolt; fabricated for aluminum framing.

J. Operating Trim: BHMA A156.6.

K. Closers: BHMA A156.4, Grade 1, with accessories required for a complete installation, sized as required by door size, exposure to weather, and anticipated frequency of use; adjustable to comply with field conditions and requirements for opening force.

L. Concealed Overhead Holders: BHMA A156.8, Grade 1.

M. Door Stops: BHMA A156.16, Grade 1, floor or wall mounted, as appropriate for door location indicated, with integral rubber bumper.

N. Weather Stripping: Manufacturer's standard replaceable components.

O. Weather Sweeps: Manufacturer's standard exterior-door bottom sweep with concealed fasteners on mounting strip.

P. Silencers: BHMA A156.16, Grade 1.

Q. Thresholds: BHMA A156.21, raised thresholds beveled with a slope of not more than 1:2, with maximum height of 1/2 inch.

2.6 GLAZING

A. Glazing: Comply with Section 088000 "Glazing."

B. Glazing Gaskets: Manufacturer's standard sealed-corner pressure-glazing system of black, resilient elastomeric glazing gaskets, setting blocks, and shims or spacers.

C. Glazing Sealants: As recommended by manufacturer.

D. Sealants used inside the weatherproofing system shall have a VOC content of 250 g/L.

2.7 FABRICATION

A. Form or extrude aluminum shapes before finishing.

B. Weld in concealed locations to greatest extent possible to minimize distortion or discoloration of finish. Remove weld spatter and welding oxides from exposed surfaces by descaling or grinding.

C. Fabricate components that, when assembled, have the following characteristics:

1. Profiles that are sharp, straight, and free of defects or deformations.
2. Accurately fitted joints with ends coped or mitered.
3. Physical and thermal isolation of glazing from framing members.
4. Accommodations for thermal and mechanical movements of glazing and framing to maintain required glazing edge clearances.
5. Provisions for field replacement of glazing from interior.
6. Fasteners, anchors, and connection devices that are concealed from view to greatest extent possible.

D. Mechanically Glazed Framing Members: Fabricate for flush glazing without projecting stops.

E. Entrance Door Frames: Reinforce as required to support loads imposed by door operation and for installing entrance door hardware.

F. Entrance Doors: Reinforce doors as required for installing entrance door hardware.

G. Entrance Door Hardware Installation: Factory install entrance door hardware to the greatest extent possible. Cut, drill, and tap for factory-installed entrance door hardware before applying finishes.

H. After fabrication, clearly mark components to identify their locations in Project according to Shop Drawings.

PART 3 - EXECUTION

3.1 INSTALLATION

A. General:

1. Comply with manufacturer's written instructions.
2. Do not install damaged components.
3. Fit joints to produce hairline joints free of burrs and distortion.
4. Rigidly secure nonmovement joints.
5. Install anchors with separators and isolators to prevent metal corrosion and electrolytic deterioration and to prevent impeding movement of moving joints.
6. Seal perimeter and other joints watertight unless otherwise indicated.

B. Metal Protection:

1. Where aluminum is in contact with dissimilar metals, protect against galvanic action by painting contact surfaces with materials recommended by manufacturer for this purpose or by installing nonconductive spacers.
2. Where aluminum is in contact with concrete or masonry, protect against corrosion by painting contact surfaces with bituminous paint.

C. Set continuous sill members and flashing in full sealant bed as specified in Section 079200 "Joint Sealants" to produce weathertight installation.

D. Install components plumb and true in alignment with established lines and grades.

E. Install operable units level and plumb, securely anchored, and without distortion. Adjust weather-stripping contact and hardware movement to produce proper operation.

F. Install glazing as specified in Section 088000 "Glazing."

G. Entrance Doors: Install doors to produce smooth operation and tight fit at contact points.

1. Exterior Doors: Install to produce weathertight enclosure and tight fit at weather stripping.
2. Field-Installed Entrance Door Hardware: Install surface-mounted entrance door hardware according to entrance door hardware manufacturers' written instructions using concealed fasteners to greatest extent possible.

END OF SECTION 084113

Finish Hardware Specification

10/2/2025 11:22

for

Lenwil Elementary School Cafeteria Renovation
112 Arrant Road
West Monroe, LA 71292

Architect:	TBA Studio , LA USA
Supplier:	Twin City Door & Hardware Inc. 3109 Concordia Ave. Monroe, LA 71201 (318)323-8474 Fax: (318)323-8447 Phone:
Job Number:	VD10225
Date:	October 02, 2025

Finish Hardware Specification

Lenwil Elementary School Cafeteria Renovation

10/2/2025 11:22

Job Number: VD10225



Finish Hardware Specification

Lenwil Elementary School Cafeteria Renovation

10/2/2025 11:22

Job Number: VD10225

Based On:

Hinge - (4-1/2 Std Wt(.134))	IVES (IVES)
Cylinder - Rim	Schlage Lock Company (SCH)
Mortise Lockset	Schlage Lock Company (SCH)
Mortise Privacy	Schlage Lock Company (SCH)
Exit Device - Rim	Von Duprin, Inc. (VDI)
Deadlock - Cylindrical	Schlage Lock Company (SCH)
Core	Schlage Lock Company (SCH)
Push Plate	Rockwood (ROC)
Pull Plate	Rockwood (ROC)
Closer	LCN (LCN)
Kick Plate	Rockwood (ROC)
Wall Stop	Rockwood (ROC)
Floor Stop	Rockwood (ROC)
Weatherstrip	Pemko (PEM)
Sweep	Pemko (PEM)
Threshold	Pemko (PEM)
Silencer	Rockwood (ROC)

Finish Hardware Specification

Lenwil Elementary School Cafeteria Renovation

10/2/2025 11:22

Job Number: VD10225

Hardware Finishes:

Finish	Finish Description
626	Satin chromium plated over nickel
689	Aluminum painted
Alum	Aluminum
Gray	Gray
US26D	Satin chromium plated over nickel
US32D	Satin stainless steel

Finish Hardware Specification

Lenwil Elementary School Cafeteria Renovation

10/2/2025 11:22

Job Number: VD10225

Door List

Door#	Hardware Set#
101	1
102	2
103	1
104	1
105	3
106	4
107	4
108	3
110	4
111	4
112	5
113	6
114	7
115	8
116	4
117	5
118	6
119	6

Lenwil Elementary School Cafeteria Renovation

10/2/2025 11:22

Job Number: VD10225

Finish Hardware Specification

Hardware Set#: 1

Single: 101, 103, 104

Qty	UOM	Manf	Item Type	Item Series/Description	Finish
3.0	EA	IVES	Hinge - (4-1/2 Std Wt(.134))	5BB1 4 1/2 x 4 1/2 NRP	US32D
1.0	EA	SCH	Cylinder - Rim	20-057	626
1.0	EA	VDI	Exit Device - Rim	98L x 996L(#06) x 299 x 3-0	US26D
1.0	EA	LCN	Closer	4040XP.SCUSH.689.TBSRT	689
1.0	EA	ROC	Kick Plate	K1050 10 x 34 4BE CSK TEK	US32D
1.0	EA	PEM	Weatherstrip	306AV 36x84 Tek	Alum
1.0	EA	PEM	Sweep	345AV 36" Tek	Alum
1.0	EA	PEM	Threshold	2005AV 36" WS/PA	Alum

Hardware Set#: 2

Single: 102

Qty	UOM	Manf	Item Type	Item Series/Description	Finish
3.0	EA	IVES	Hinge - (4-1/2 Std Wt(.134))	5BB1 4 1/2 x 4 1/2 NRP	US32D
1.0	EA	SCH	Cylinder - Rim	20-057	626
1.0	EA	VDI	Exit Device - Rim	98L x 996L(#06) x 299 x 4-0	US26D
1.0	EA	LCN	Closer	4040XP.SCUSH.689.TBSRT	689
1.0	EA	ROC	Kick Plate	K1050 10 x 34 4BE CSK TEK	US32D
1.0	EA	PEM	Weatherstrip	306AV 36x84 Tek	Alum
1.0	EA	PEM	Sweep	345AV 36" Tek	Alum
1.0	EA	PEM	Threshold	2005AV 36" WS/PA	Alum

Lenwil Elementary School Cafeteria Renovation

10/2/2025 11:22

Job Number: VD10225

Finish Hardware Specification

Hardware Set#: 3

Single: 105, 108

Qty	UOM	Manf	Item Type	Item Series/Description	Finish
3.0	EA	IVES	Hinge - (4-1/2 Std Wt(.134))	5BB1 4 1/2 x 4 1/2	US26D
1.0	EA	ROC	Push Plate	70C TEK	US32D
1.0	EA	ROC	Pull Plate	102x70C TEK	US32D
1.0	EA	LCN	Closer	4040XP.EDA.689.TBSRT	689
1.0	EA	ROC	Kick Plate	K1050 10 x 34 4BE CSK TEK	US32D
1.0	EA	ROC	Floor Stop	470	US26D
3.0	EA	ROC	Silencer	608	Gray

Hardware Set#: 4

Single: 106, 107, 110, 111, 116

Qty	UOM	Manf	Item Type	Item Series/Description	Finish
3.0	EA	IVES	Hinge - (4-1/2 Std Wt(.134))	5BB1 4 1/2 x 4 1/2	US26D
1.0	EA	SCH	Deadlock - Cylindrical	B563T x 12-288 x 10-094 x ICC x 50-231	626
1.0	EA	SCH	Core	23-030	626
1.0	EA	ROC	Push Plate	70C TEK	US32D
1.0	EA	ROC	Pull Plate	102x70C TEK	US32D
1.0	EA	LCN	Closer	4040XP.EDA.689.TBSRT	689
1.0	EA	ROC	Kick Plate	K1050 10 x 34 4BE CSK TEK	US32D
1.0	EA	ROC	Floor Stop	470	US26D
3.0	EA	ROC	Silencer	608	Gray

Lenwil Elementary School Cafeteria Renovation

10/2/2025 11:22

Job Number: VD10225

Finish Hardware Specification

Hardware Set#: 5

Single: 112, 117

Qty	UOM	Manf	Item Type	Item Series/Description	Finish
3.0	EA	IVES	Hinge - (4-1/2 Std Wt(.134))	5BB1 4 1/2 x 4 1/2	US26D
1.0	EA	SCH	Mortise Lockset	L9050T x 06N x 10-072 x 1-3/4" DR x 1-3/16" LIP x ICC x 50-231	626
1.0	EA	SCH	Core	23-030	626
1.0	EA	LCN	Closer	4040XP.EDA.689.TBSRT	689
1.0	EA	ROC	Kick Plate	K1050 10 x 34 4BE CSK TEK	US32D
1.0	EA	ROC	Wall Stop	407	US32D
3.0	EA	ROC	Silencer	608	Gray

Hardware Set#: 6

Single: 113, 118, 119

Qty	UOM	Manf	Item Type	Item Series/Description	Finish
3.0	EA	IVES	Hinge - (4-1/2 Std Wt(.134))	5BB1 4 1/2 x 4 1/2	US26D
1.0	EA	SCH	Mortise Lockset	L9080T x 06N x 10-072 x 1-3/4" DR x 1-3/16" LIP x ICC x 50-231	626
1.0	EA	SCH	Core	23-030	626
1.0	EA	LCN	Closer	4040XP.EDA.689.TBSRT	689
1.0	EA	ROC	Kick Plate	K1050 10 x 34 4BE CSK TEK	US32D
1.0	EA	ROC	Wall Stop	407	US32D
3.0	EA	ROC	Silencer	608	Gray

Lenwil Elementary School Cafeteria Renovation

10/2/2025 11:22

Job Number: VD10225

Finish Hardware Specification

Hardware Set#: 7

Single: 114

Qty	UOM	Manf	Item Type	Item Series/Description	Finish
3.0	EA	IVES	Hinge - (4-1/2 Std Wt(.134))	5BB1 4 1/2 x 4 1/2	US26D
1.0	EA	SCH	Mortise Lockset	L9070T x 06N x 10-072 x 1-3/4" DR x 1-3/16" LIP x ICC x 50-231	626
1.0	EA	SCH	Core	23-030	626
1.0	EA	LCN	Closer	4040XP.EDA.689.TBSRT	689
1.0	EA	ROC	Kick Plate	K1050 10 x 34 4BE CSK TEK	US32D
1.0	EA	ROC	Wall Stop	407	US32D
3.0	EA	ROC	Silencer	608	Gray

Hardware Set#: 8

Single: 115

Qty	UOM	Manf	Item Type	Item Series/Description	Finish
3.0	EA	IVES	Hinge - (4-1/2 Std Wt(.134))	5BB1 4 1/2 x 4 1/2	US26D
1.0	EA	SCH	Mortise Privacy	L9044 x 06N x 10-072 x OS-OCC x 1-3/4" DR x 1-3/16" LIP	626
1.0	EA	SCH	Core	23-030	626
1.0	EA	LCN	Closer	4040XP.EDA.689.TBSRT	689
1.0	EA	ROC	Kick Plate	K1050 10 x 34 4BE CSK TEK	US32D
1.0	EA	ROC	Wall Stop	407	US32D
3.0	EA	ROC	Silencer	608	Gray

SECTION 088000 - GLAZING

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes glazing for the following products and applications, including those specified in other Sections where glazing requirements are specified by reference to this Section:

1. Doors.
2. Storefront framing.
3. Glazed entrances.
4. Interior borrowed lites.

1.2 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design glass, including comprehensive engineering analysis according to ASTM E 1300 and ICC's 2012 International Building Code by a qualified professional engineer, using the following design criteria:

1. Design Wind Pressures: As required by ICC’s 2012 International Building Code.
2. Vertical Glazing: For glass surfaces sloped 15 degrees or less from vertical, design glass to resist design wind pressure based on glass type factors for short-duration load.
3. Sloped Glazing: For glass surfaces sloped more than 15 degrees from vertical, design glass to resist each of the following combinations of loads:

    a. Outward design wind pressure minus the weight of the glass. Base design on glass type factors for short-duration load.
    b. Inward design wind pressure plus the weight of the glass plus half of the design snow load. Base design on glass type factors for short-duration load.
    c. Half of the inward design wind pressure plus the weight of the glass plus the design snow load. Base design on glass type factors for long-duration load.
4. Differential Shading: Design glass to resist thermal stresses induced by differential shading within individual glass lites.

1.3 PRECONSTRUCTION TESTING

A. Preconstruction Adhesion and Compatibility Testing: Test each glazing material type, tape sealant, gasket, glazing accessory, and glass-framing member for adhesion to and compatibility with elastomeric glazing sealants.

1. Testing will not be required if data are submitted based on previous testing of current sealant products and glazing materials matching those submitted.

1.4 ACTION SUBMITTALS

A. Product Data: For each glass product and glazing material indicated.

B. Glass Samples: For each type of glass product other than clear monolithic vision glass; 12 inches square.

C. Glazing Schedule: List glass types and thicknesses for each size opening and location. Use same designations indicated on Drawings.

D. Delegated-Design Submittal: For glass indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1.5 INFORMATIONAL SUBMITTALS

A. Preconstruction adhesion and compatibility test report.

1.6 QUALITY ASSURANCE

A. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below, unless more stringent requirements are indicated. Refer to these publications for glazing terms not otherwise defined in this Section or in referenced standards.

1. GANA Publications: GANA's "Laminated Glazing Reference Manual" and GANA's "Glazing Manual."
2. IGMA Publication for Insulating Glass: SIGMA TM-3000, "North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial and Residential Use."

B. Safety Glazing Labeling: Where safety glazing labeling is indicated, permanently mark glazing with certification label of the SGCC or another certification agency acceptable to authorities having jurisdiction. Label shall indicate manufacturer's name, type of glass, thickness, and safety glazing standard with which glass complies.

C. Fire-Protection-Rated Glazing Labeling: Permanently mark fire-protection-rated glazing with certification label of a testing agency acceptable to authorities having jurisdiction. Label shall indicate manufacturer's name, test standard, whether glazing is for use in fire doors or other openings, whether or not glazing passes hose-stream test, whether or not glazing has a temperature rise rating of 450 deg F, and the fire-resistance rating in minutes.

D. Insulating-Glass Certification Program: Permanently marked either on spacers or on at least one component lite of units with appropriate certification label of IGCC.

1.7 WARRANTY

A. Manufacturer's Special Warranty for Coated-Glass Products: Manufacturer's standard form in which coated-glass manufacturer agrees to replace coated-glass units that deteriorate within specified warranty period. Deterioration of coated glass is defined as defects developed from normal use that are not attributed to glass breakage or to maintaining and cleaning coated glass

contrary to manufacturer's written instructions. Defects include peeling, cracking, and other indications of deterioration in coating.

1. Warranty Period: 10 years from date of Substantial Completion.

B. Manufacturer's Special Warranty on Laminated Glass: Manufacturer's standard form in which laminated-glass manufacturer agrees to replace laminated-glass units that deteriorate within specified warranty period. Deterioration of laminated glass is defined as defects developed from normal use that are not attributed to glass breakage or to maintaining and cleaning laminated glass contrary to manufacturer's written instructions. Defects include edge separation, delamination materially obstructing vision through glass, and blemishes exceeding those allowed by referenced laminated-glass standard.

1. Warranty Period: 10 years from date of Substantial Completion.

C. Manufacturer's Special Warranty on Insulating Glass: Manufacturer's standard form in which insulating-glass manufacturer agrees to replace insulating-glass units that deteriorate within specified warranty period. Deterioration of insulating glass is defined as failure of hermetic seal under normal use that is not attributed to glass breakage or to maintaining and cleaning insulating glass contrary to manufacturer's written instructions. Evidence of failure is the obstruction of vision by dust, moisture, or film on interior surfaces of glass.

1. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 GLASS PRODUCTS, GENERAL

A. Thickness: Where glass thickness is indicated, it is a minimum. Provide glass lites in thicknesses as needed to comply with requirements indicated.

B. Strength: Provide fully tempered glass is indicated, provide Kind FT heat-treated float glass.

C. Thermal and Optical Performance Properties: Provide glass with performance properties specified, as indicated in manufacturer's published test data, based on procedures indicated below:

1. U-Factors: Center-of-glazing values, according to NFRC 100 and based on LBL's WINDOW 5.2 computer program, expressed as Btu/sq. ft. x h x deg F.
2. Solar Heat-Gain Coefficient and Visible Transmittance: Center-of-glazing values, according to NFRC 200 and based on LBL's WINDOW 5.2 computer program.
3. Visible Reflectance: Center-of-glazing values, according to NFRC 300.

2.2 GLASS PRODUCTS

A. Float Glass: ASTM C 1036, Type I, Quality-Q3, Class I (clear) unless otherwise indicated.

2.3 INSULATING GLASS

A. Manufacturers: Subject to compliance with requirements, provide products indicated on drawings.

B. Insulating-Glass Units: Factory-assembled units consisting of sealed lites of glass separated by a dehydrated interspace, qualified according to ASTM E 2190, and complying with other requirements specified.

2.4 GLAZING GASKETS

A. Dense Compression Gaskets: Molded or extruded gaskets of profile and hardness required to maintain watertight seal, made from one of the following:

1. Neoprene complying with ASTM C 864.
2. EPDM complying with ASTM C 864.
3. Silicone complying with ASTM C 1115.
4. Thermoplastic polyolefin rubber complying with ASTM C 1115.

B. Soft Compression Gaskets: Extruded or molded, closed-cell, integral-skinned neoprene, EPDM, silicone or thermoplastic polyolefin rubber gaskets complying with ASTM C 509, Type II, black; of profile and hardness required to maintain watertight seal.

1. Application: Use where soft compression gaskets will be compressed by inserting dense compression gaskets on opposite side of glazing or pressure applied by means of pressure-glazing stops on opposite side of glazing.

2.5 GLAZING SEALANTS

A. General:

1. Compatibility: Provide glazing sealants that are compatible with one another and with other materials they will contact, including glass products, seals of insulating-glass units, and glazing channel substrates, under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
2. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.
3. Sealants used inside the weatherproofing system, shall have a VOC content of not more than 250 g/L when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
4. Colors of Exposed Glazing Sealants: As selected by Architect from manufacturer's full range.

2.6 GLAZING TAPES

A. Back-Bedding Mastic Glazing Tapes: Preformed, butyl-based, 100 percent solids elastomeric tape; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer

rod as recommended in writing by tape and glass manufacturers for application indicated; and complying with ASTM C 1281 and AAMA 800 for products indicated below:

1. AAMA 804.3 tape, where indicated.
2. AAMA 806.3 tape, for glazing applications in which tape is subject to continuous pressure.
3. AAMA 807.3 tape, for glazing applications in which tape is not subject to continuous pressure.

B. Expanded Cellular Glazing Tapes: Closed-cell, PVC foam tapes; factory coated with adhesive on both surfaces; and complying with AAMA 800 for the following types:

1. AAMA 810.1, Type 1, for glazing applications in which tape acts as the primary sealant.
2. AAMA 810.1, Type 2, for glazing applications in which tape is used in combination with a full bead of liquid sealant.

2.7 MISCELLANEOUS GLAZING MATERIALS

A. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.

B. Setting Blocks: Elastomeric material with a Shore, Type A durometer hardness of 85, plus or minus 5.

C. Spacers: Elastomeric blocks or continuous extrusions of hardness required by glass manufacturer to maintain glass lites in place for installation indicated.

D. Edge Blocks: Elastomeric material of hardness needed to limit glass lateral movement (side walking).

E. Cylindrical Glazing Sealant Backing: ASTM C 1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.

F. Perimeter Insulation for Fire-Resistive Glazing: Product that is approved by testing agency that listed and labeled fire-resistant glazing product with which it is used for application and fire-protection rating indicated.

2.8 MONOLITHIC-GLASS TYPES

A. Glass Type (Exterior Hollow Metal doors): Clear fully tempered float glass.

1. Thickness: 1/2 inch.
2. Low-E.
3. Visible Light Transmittance: 35%
4. Summer Daytime U-Factor 0.27 maximum.
5. Winter Night Time U-Value: 0.29 maximum.
6. Solar Heat Gain Coefficient: 0.25 maximum.

B. Provide safety glazing labeling.

C. Glass Type (Interior Hollow Metal doors): Clear fully tempered float glass.

1. Thickness: 1/4 inch.
2. Provide safety glazing labeling.

D. Glass Type (Interior Aluminum Entrances and Storefronts): Clear Fully tempered float glass.

1. Thickness: 1/4 inch.
2. Provide safety glazing labeling.

E. Glass Type (Interior Borrowed Lites): Clear Fully tempered float glass.

1. Thickness: 1/4 inch.
2. Provide safety glazing labeling.

F. Heat strengthen 7/16” glass in aluminum framing with level 1 bullet resistant Glass see drawings for location.

2.9 INSULATING-GLASS TYPES

A. Glass Type (Exterior Storefront Glazing): Low-e-coated, tinted insulating glass Vitro Architectural Glass (formerly PPG Glass); Solar Gray.

1. Overall Unit Thickness: 1 inch.
2. Thickness of Each Glass Lite: 0.25 inches.
3. Outdoor Lite: Tinted fully tempered float glass.
4. Tint Color: Gray.
5. Interspace Content: Air.
6. Indoor Lite: Clear fully tempered float glass.
7. Low-E Coating: Sputtered on second surface.
8. Visible Light Transmittance: 35 percent minimum.
9. Winter Nighttime U-Factor: 0.29 maximum.
10. Summer Daytime U-Factor: 0.27 maximum.
11. Solar Heat Gain Coefficient: 0.25 maximum.

PART 3 - EXECUTION

3.1 GLAZING, GENERAL

A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.

B. Adjust glazing channel dimensions as required by Project conditions during installation to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances.

C. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass is glass with edge damage or other imperfections that, when installed, could weaken glass and impair performance and appearance.

D. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.

E. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.

F. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.

G. Provide spacers for glass lites where length plus width is larger than 50 inches.

H. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and according to requirements in referenced glazing publications.

3.2 TAPE GLAZING

A. Position tapes on fixed stops so that, when compressed by glass, their exposed edges are flush with or protrude slightly above sightline of stops.

B. Install tapes continuously, but not necessarily in one continuous length. Do not stretch tapes to make them fit opening.

C. Cover vertical framing joints by applying tapes to heads and sills first and then to jambs. Cover horizontal framing joints by applying tapes to jambs and then to heads and sills.

D. Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant approved by tape manufacturer.

E. Apply heel bead of elastomeric sealant.

F. Center glass lites in openings on setting blocks and press firmly against tape by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.

G. Apply cap bead of elastomeric sealant over exposed edge of tape.

3.3 GASKET GLAZING (DRY)

A. Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.

B. Insert soft compression gasket between glass and frame or fixed stop so it is securely in place with joints miter cut and bonded together at corners.

C. Installation with Drive-in Wedge Gaskets: Center glass lites in openings on setting blocks and press firmly against soft compression gasket by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended by gasket manufacturer.

D. Installation with Pressure-Glazing Stops: Center glass lites in openings on setting blocks and press firmly against soft compression gasket. Install dense compression gaskets and pressure-glazing stops, applying pressure uniformly to compression gaskets. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended by gasket manufacturer.

E. Install gaskets so they protrude past face of glazing stops.

3.4 SEALANT GLAZING (WET)

A. Install continuous spacers, or spacers combined with cylindrical sealant backing, between glass lites and glazing stops to maintain glass face clearances and to prevent sealant from extruding into glass channel and blocking weep systems until sealants cure. Secure spacers or spacers and backings in place and in position to control depth of installed sealant relative to edge clearance for optimum sealant performance.

B. Force sealants into glazing channels to eliminate voids and to ensure complete wetting or bond of sealant to glass and channel surfaces.

C. Tool exposed surfaces of sealants to provide a substantial wash away from glass.

3.5 CLEANING AND PROTECTION

A. Protect exterior glass from damage immediately after installation by attaching crossed streamers to framing held away from glass. Do not apply markers to glass surface. Remove nonpermanent labels and clean surfaces.

B. Protect glass from contact with contaminating substances resulting from construction operations. If, despite such protection, contaminating substances do come into contact with glass, remove substances immediately as recommended in writing by glass manufacturer.

C. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains; remove as recommended in writing by glass manufacturer.

D. Remove and replace glass that is broken, chipped, cracked, or abraded or that is damaged from natural causes, accidents, and vandalism, during construction period.

END OF SECTION 088000

SECTION 090561.13 – MOISTURE VAPOR EMISSION CONTROL

PART 1 – GENERAL

1.1 SUMMARY

A. Section includes application of polymer-based, high-solids, water-based moisture control and primer system for underlayments.
B. Related Requirements:
1. Section 03 35 00 – Concrete Finishing.
2. Section 03 54 16 – Hydraulic Cement Underlayment.
3. Section 09 65 00 – Resilient Flooring.

1.2 REFERENCES

A. ASTM F1869 – Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride.
B. ASTM F2170 – Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs.
C. ASTM F3010 – Two-Component Vapor-Permeability Systems.
D. ASTM F3513 – One-Component Vapor-Permeability Systems.

1.3 SUBMITTALS

A. Product Data: Manufacturer’s technical data and installation instructions.
B. Safety Data Sheets (SDS).
C. Certification of compliance with ASTM standards.

1.4 QUALITY ASSURANCE

A. Manufacturer qualifications: 10 years minimum producing moisture mitigation systems.
B. Installer qualifications: Minimum 2 years experience with resinous flooring systems.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials in unopened containers with manufacturer’s labels intact.
B. Store between 50°F and 90°F. Protect from freezing.

1.6 FIELD CONDITIONS

A. Do not install when ambient or substrate temperature is below 50°F.
B. Substrate temperature must be at least 5°F above dew point.

1.6 FIELD CONDITIONS

A. Do not install when ambient or substrate temperature is below 50°F.
B. Substrate temperature must be at least 5°F above dew point.

PART 2 – PRODUCTS

2.1 BASIS OF DESIGN: Subject to compliance with requirements, provide Planiseal Max by Mapei Corporation 1144 East Newport Center Drive Deerfield, FL. 33442 Ph. 1.888.876.2734 or by one of the following.

A. Koster American Corp. Ph. 757.425.1206
B. Maxxon Corp. 1.800.238.8461 or 1.800.878.5586

2.2 MATERIALS

A. One-component, high-solids, water-based, polymer moisture mitigation coating with textured surface.
B. Color: Burgundy.
C. VOC Content: <50 g/L.

2.3 PERFORMANCE REQUIREMENTS

A. Moisture vapor emission: Up to 25 lb/1000 ft²/24 h (ASTM F1869).
B. Relative humidity: Up to 100% (ASTM F2170).
C. pH resistance: Up to 14.
D. Water vapor permeance: <0.1 perms (ASTM E96).

2.4 PACKAGING

A. 4-gallon (15.1 L) pails.

PART 3 – EXECUTION

3.1 EXAMINATION

A. Verify substrate is structurally sound, porous, and free of contaminants.
B. Verify moisture and pH testing is complete.

3.2 SURFACE PREPARATION
A. Mechanically prepare substrate to ICRI CSP 1 minimum.
B. Clean surface of dust and debris before application.

3.3 APPLICATION
A. Mix: Stir gently before use.
B. Apply two coats by roller at 200 ft²/gal per coat.
C. Allow 30 minutes between coats, dry to touch.
D. Allow 1–2 hours cure time before applying underlayment or adhesive.

3.4 PROTECTION
A. Protect finished surface from traffic until covered with subsequent flooring.

3.5 CLEANING
A. Clean tools with water immediately after use.

END OF SECTION

SECTION 092216 - NON-STRUCTURAL METAL FRAMING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Non-load-bearing steel framing systems for interior gypsum board assemblies.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Test-Response Characteristics: Provide materials and construction identical to those tested according to ASTM E 119.

2.2 FRAMING SYSTEMS

A. General: Where structural drawings/notes indicate a thicker base-metal thickness (heavier gauge) or wider flange, the structural drawings/notes shall govern.

B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Allied Studco, Inc.
2. ClarkDietrich Building Systems.
3. Marino Ware Industries.
4. The Steel Network, Inc.
5. Unimast Incorporated.
6. Delta Metal Products.

C. Interior Partition Steel Studs and Runners: ASTM C 645. Use either steel studs and runners or dimpled steel studs and runners of equivalent minimum base-metal thickness.

1. Minimum Base-Metal Thickness: 0.0205 inch.
2. Flange: 1-1/4 inch.
3. Web Width: As indicated on drawings.

D. Exterior Wall Steel Studs and Runners: ASTM C 645. Use either steel studs and runners or dimpled steel studs and runners of equivalent minimum base-metal thickness.

1. Minimum Base-Metal Thickness: 0.0312 inch.
2. Flange: 1-1/4 inch.
3. Web Width: As indicated on drawings.

E. Cold-Rolled Channel Bridging: Steel, 0.053 inch minimum base-metal thickness, with minimum 1/2-inch wide flanges.

1. Depth: 1-1/2 inches.
2. Clip Angle: Not less than 1-1/2 by 1-1/2 inches, 0.068-inch thick, galvanized steel.

2.3 AUXILIARY MATERIALS

A. Fasteners for Metal Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Installation Standard: ASTM C 754.

1. Gypsum Board Assemblies: Also comply with requirements in ASTM C 840 that apply to framing installation.

B. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.

C. Install bracing at terminations in assemblies.

D. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.

3.2 INSTALLING FRAMED ASSEMBLIES

A. Install framing system components according to spacing indicated, but not less than spacing required by referenced installation standards for assembly types.

B. Where studs are installed directly against exterior masonry walls or dissimilar metals at exterior walls, install isolation strip between studs and exterior wall.

C. Install studs so flanges within framing system point in same direction.

D. Install tracks (runners) at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings, except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts penetrating partitions above ceiling.

1. Door Openings: Screw vertical studs at jambs to jamb anchor clips on door frames; install runner track section (for cripple studs) at head and secure to jamb studs.

    a. Install two studs at each jamb unless otherwise indicated.
    b. Install cripple studs at head adjacent to each jamb stud, with a minimum 1/2-inch clearance from jamb stud to allow for installation of control joint in finished assembly.
    c. Extend jamb studs through suspended ceilings and attach to underside of overhead structure.

2. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.

E. Installation Tolerance: Install each framing member so fastening surfaces vary not more than 1/8 inch from the plane formed by faces of adjacent framing.

END OF SECTION 092216

SECTION 092900 - GYPSUM BOARD

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior gypsum board.
2. Texture finishes.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Samples:

1. Textured Finishes: 24-inch by 24-inch for each textured finish indicated and on same backing indicated for Work.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Resistance-Rated Assemblies: For fire-resistance-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 119 by an independent testing agency.

B. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 90 and classified according to ASTM E 413 by an independent testing agency.

2.2 INTERIOR GYPSUM BOARD

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Certainteed.
2. James Hardie Building Products, Inc.
3. National Gypsum Company.
4. Temple-Inland.
5. United States Gypsum Company.
6. ClarkDietrich Building Systems.

B. Gypsum Board, Type X: ASTM C 1396/C 1396M.

1. Thickness: 5/8 inch.
2. Long Edges: Tapered.

C. Gypsum Ceiling/Furr-down Board: ASTM C 1396/C 1396M.

1. Thickness: 1/2 inch.
2. Long Edges: Tapered.

2.3 TRIM ACCESSORIES

A. Interior Trim: ASTM C 1047.

1. Material: Galvanized or aluminum-coated steel sheet, rolled zinc, plastic, or paper-faced galvanized steel sheet.

2.4 JOINT TREATMENT MATERIALS

A. General: Comply with ASTM C 475/C 475M.

B. Joint Tape:

1. Interior Gypsum Board: Paper.

C. Joint Compound for Interior Gypsum Board: For each coat use formulation that is compatible with other compounds applied on previous or for successive coats.

2.5 AUXILIARY MATERIALS

A. Steel Drill Screws: ASTM C 1002, unless otherwise indicated.

B. Thermal Insulation: As specified in Section 072100 "Thermal Insulation."

2.6 TEXTURE FINISHES

A. Primer: As recommended by textured finish manufacturer.

B. Non-Aggregate Finish: Pre-mixed, vinyl texture finish for spray application.

1. Products: Subject to compliance with requirements, provide one of the following:

a. CertainTeed Corp.; ProRoc Easi-Tex Spray Texture.
b. National Gypsum Company; Perfect Spray EM Texture.
c. USG Corporation; BEADEX FasTex Wall and Ceiling Spray Texture.

2. Texture: As selected by Architect.

PART 3 - EXECUTION

3.1 APPLYING AND FINISHING PANELS

A. Comply with ASTM C 840.

B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.

C. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments, except floors. Provide 1/4- to 1/2-inch wide spaces at these locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.

D. Install trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.
   1. Control Joints: Install control joints, according to ASTM C 840 and in specific locations approved by Architect for visual effect.

E. Pre-fill open joints and damaged surface areas.

F. Apply joint tape over gypsum board joints, except for trim products specifically indicated as not intended to receive tape.

G. Texture Finish Application: Prepare and apply primer to gypsum panels and other surfaces receiving texture finishes. Mix and apply finish using powered spray equipment, to produce a uniform texture, matching approved mockup, and free of starved spots or other evidence of thin application or of application patterns.

H. Protect adjacent surfaces from drywall compound and texture finishes and promptly remove from floors and other non-drywall surfaces. Repair surfaces stained, marred, or otherwise damaged during drywall application.

I. Remove and replace panels that are wet, moisture damaged, and mold damaged.

END OF SECTION 092900

SECTION 093000 - TILING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Ceramic tile.
2. Stone thresholds.
3. Waterproof membrane.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

B. Samples:

1. Each type and composition of tile and for each color and finish required.
2. Assembled samples, with grouted joints, for each type and composition of tile and for each color and finish required.
3. Stone thresholds in 4 inch lengths.

1.3 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match and are from same production runs as products installed and that are packaged with protective covering and identified with labels describing contents.

1. Tile and Trim Units: Furnish quantity of full-size units equal to 3 percent of amount installed for each type, composition, color, pattern, and size indicated.

1.4 QUALITY ASSURANCE

A. Mockups: Build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Build mockup of each type of floor tile installation.
2. Build mockup of each type of wall tile installation.
3. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

PART 2 - PRODUCTS

2.1 TILE PRODUCTS

A. ANSI Ceramic Tile Standard: Provide Standard grade tile that complies with ANSI A137.1 for types, compositions, and other characteristics indicated.

B. FloorScore Compliance: Tile for floors shall comply with requirements of FloorScore Standard.

1. Basis-of-Design Product: Subject to compliance with requirements, provide **Crossville** or comparable products by one of the following.
   a. American Olean
   b. Concept Surfaces
   c. Daltile

All Colors are subject to approval by architect.

Porcelain Floor Tile (PFT -1)– Crossville (Shades 2.0)

1. Size: 12” inch by 24” inch.
2. Finish: UPS
3. Grout: Laticrete
4. Trim Units: As indicated on drawings or required.

Ceramic Wall Tile (CWT-1) – Crossville (Moonstruck)

1. Size: 12” inch by 24” inch
2. Finish: PO
3. Grout: Laticrete
4. Trim Units: As indicated on drawings.
5. Schluter strip at base of wall. Schluter-DILEX-PHK PVC, cove-shaped profile 3/8” radius as indicated by drawings. Full range of color options.

C. General: Fabricate to sizes and profiles indicated or required to provide transition between adjacent floor finishes.

1. Bevel edges at 1:2 slope, with lower edge of bevel aligned with or up to 1/16 inch above adjacent floor surface. Finish bevel to match top surface of threshold. Limit height of threshold to 1/2 inch or less above adjacent floor surface.

D. Marble Thresholds: ASTM C 503, with a minimum abrasion resistance of 10 per ASTM C 1353 or ASTM C 241 and with honed finish.

1. Description: Uniform, fine- to medium-grained white stone with gray veining.

2.2 WATERPROOF MEMBRANE

A. General: Manufacturer's standard product, selected from the following, that complies with ANSI A118.10 and is recommended by the manufacturer for the application indicated.

B. Fluid-Applied Membrane: Liquid-latex rubber or elastomeric polymer.

1. Products: Subject to compliance with requirements, [provide one of the following]

   a. Bostik, Inc.; Durabond D-222 Duraguard Membrane.
   b. C-Cure; Pro-Red Waterproofing Membrane 63.
   c. Custom Building Products; Redgard Waterproofing and Crack Prevention Membrane.
   d. Laticrete International, Inc.; Latapoxy 24hr HydroProofing.
   e. MAPEI Corporation; Mapelastic HPG.
   f. TEC, a subsidiary of H. B. Fuller Company; HydraFlex - Waterproofing Crack Isolation Membrane.

2.3 SETTING MATERIALS

A. Latex-Portland Cement Mortar (Thin Set): ANSI A118.4.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Bonsal American; an Oldcastle company.
   b. Bostik, Inc.
   c. C-Cure.
   d. Custom Building Products.
   e. Laticrete International, Inc.
   f. MAPEI Corporation.
   g. Mer-Kote Products, Inc.
   h. TEC; a subsidiary of H. B. Fuller Company.

2. Prepackaged, dry-mortar mix to which only water must be added.
3. For wall applications, provide nonsagging mortar.

2.4 GROUT MATERIALS

A. Water-Cleanable Epoxy Grout: ANSI A118.3, with a VOC content of 65 g/L or less when calculated according to 40 CFR 59, Subpart D.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

   a. Boiardi Products; a QEP company.
   b. Bonsal American; an Oldcastle company.
   c. Bostik, Inc.
   d. C-Cure.

e. Custom Building Products.
f. Laticrete International, Inc.
g. MAPEI Corporation.

2.5 MISCELLANEOUS MATERIALS

A. Trowelable Underlayments and Patching Compounds: Latex-modified, portland cement-based formulation provided or approved by manufacturer of tile-setting materials for installations indicated.

B. Grout Sealer: Manufacturer's standard product for sealing grout joints and that does not change color or appearance of grout.

1. Products: Subject to compliance with requirements, provide one of the following:

a. Bonsal American, an Oldcastle company; Grout Sealer.
b. Bostik, Inc.; CeramaSeal Grout & Tile Sealer.
c. C-Cure; Penetrating Sealer 978.
d. Custom Building Products; Surfaceguard Sealer.
e. MAPEI Corporation; KER 004, Keraseal Penetrating Sealer for Unglazed Grout and Tile.
f. TEC, a subsidiary of H. B. Fuller Company; TA-256 Penetrating Silicone Grout Sealer.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions where tile will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of installed tile.

1. Verify that substrates for setting tile are firm, dry, clean, free of coatings that are incompatible with tile-setting materials including curing compounds and other substances that contain soap, wax, oil, or silicone; and comply with flatness tolerances required by ANSI A108.01 for installations indicated.

3.2 PREPARATION

A. Fill cracks, holes, and depressions in concrete substrates for tile floors installed with thin-set mortar with trowelable leveling and patching compound specifically recommended by tile-setting material manufacturer.

B. Blending: For tile exhibiting color variations, use factory blended tile or blend tiles at Project site before installing.

C. Field-Applied Temporary Protective Coating: If indicated under tile type or needed to prevent grout from staining or adhering to exposed tile surfaces, precoat them with continuous film of temporary protective coating, taking care not to coat unexposed tile surfaces.

3.3 INSTALLATION

A. Comply with TCA's "Handbook for Ceramic Tile Installation" for TCA installation methods specified in tile installation schedules. Comply with parts of the ANSI A108 Series "Specifications for Installation of Ceramic Tile" that are referenced in TCA installation methods, specified in tile installation schedules, and apply to types of setting and grouting materials used.

1. For the following installations, follow procedures in the ANSI A108 Series of tile installation standards for providing 95 percent mortar coverage:

    a. Tile floors in wet areas.

B. Extend tile work into recesses and under or behind equipment and fixtures to form complete covering without interruptions unless otherwise indicated. Terminate work neatly at obstructions, edges, and corners without disrupting pattern or joint alignments.

C. Accurately form intersections and returns. Perform cutting and drilling of tile without marring visible surfaces. Carefully grind cut edges of tile abutting trim, finish, or built-in items for straight aligned joints. Fit tile closely to electrical outlets, piping, fixtures, and other penetrations so plates, collars, or covers overlap tile.

D. Provide manufacturer's standard trim shapes where necessary to eliminate exposed tile edges.

E. Jointing Pattern: Lay tile in grid pattern unless otherwise indicated. Lay out tile work and center tile fields in both directions in each space or on each wall area. Lay out tile work to minimize the use of pieces that are less than half of a tile. Provide uniform joint widths unless otherwise indicated.

F. Joint Widths: Unless otherwise indicated or otherwise recommended by tile manufacturer, install tile with the following joint widths:

1. Wall Tile: 1/16 inch.
2. Floor Tile: 1/16 inch.

G. Lay out tile wainscots to dimensions indicated or to next full tile beyond dimensions indicated.

H. Expansion Joints: Provide expansion joints and other sealant-filled joints, including control, contraction, and isolation joints, where indicated. Form joints during installation of setting materials, mortar beds, and tile. Do not saw-cut joints after installing tiles.

1. Where joints occur in concrete substrates, locate joints in tile surfaces directly above them.
2. Prepare joints and apply sealants to comply with requirements in Section 079200 "Joint Sealants."

I. Stone Thresholds: Install stone thresholds in same type of setting bed as adjacent floor unless otherwise indicated.

J. Grout Sealer: Apply grout sealer to cementitious grout joints in tile floors and tile floor wall bases according to grout-sealer manufacturer's written instructions. As soon as grout sealer has penetrated grout joints, remove excess sealer and sealer from tile faces by wiping with soft cloth.

K. Install waterproofing to comply with ANSI A108.13 and manufacturer's written instructions to produce waterproof membrane of uniform thickness and bonded securely to substrate.

END OF SECTION 093000

SECTION 095100 – ACOUSTICAL CEILING SOUNDSCAPES BLADES LINEAR ACOUSTICAL PANELS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

Drawings and general conditions of Contract, including General and Supplementary Conditions and Divisions-1 Specification sections apply to work of this section.

1.2 SUMMARY

A. Section Includes:
   1. Linear acoustical ceiling and wall panels
   2. Exposed grid suspension system
   3. Wire hangers, fasteners, main runners, cross tees, wall angle moldings and accessories

B. Related Sections:
   1. Section 09 50 00 – Ceilings
   2. Section 09 51 13 – Acoustical Panel Ceilings
   3. Section 09 53 00 – Acoustical Ceiling Suspension Assemblies
   4. Section 09 54 00 – Specialty Ceilings
   5. Section 09 54 33 – Decorative Panel Ceilings
   6. Section 09 54 53 – Fiberglass Reinforced Panel Ceilings

C. Alternates
   1. Prior Approval: Unless otherwise provided for in the Contract documents, proposed product substitutions may be submitted no later than TEN (10) working days prior to the date established for receipt of bids. Acceptability of a proposed substitution is contingent upon the Architect's review of the proposal for acceptability and approved products will be set forth by the Addenda. If included in a Bid are substitute products that have not been pre-approved by the architect and included in the Addenda, the originally specified products shall be provided without additional compensation.
   2. Submittals that do not provide adequate data for the product evaluation will not be considered. The proposed substitution must meet all requirements of this section, including but not necessarily limited to, the following: Single source materials suppliers; Underwriters' Laboratories Classified Acoustical performance; Panel design, size, composition, color, and finish; Suspension system component profiles and sizes; Compliance with the referenced standards.

1.3 REFERENCES

A. American Society for Testing and Materials (ASTM):
   1. ASTM A 1008 Standard Specification for Steel, Sheet, Cold Rolled, Carbon, Structural, High-Strength Low-Alloy and High-Strength Low-Alloy with Improved Formability
   2. ASTM A 641 Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire

3. ASTM A 653 Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) by the Hot-Dip Process
4. ASTM C 423 Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method
5. ASTM C 635 Standard Specification for Metal Suspension Systems for Acoustical Tile and Lay-in Panel Ceilings
6. ASTM C 636 Recommended Practice for Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-in Panels
7. ASTM D 3273 Standard Test Method for Resistance to Growth of Mold on the Surface of Interior Coatings in an Environmental Chamber
8. ASTM E 84 Standard Test Method for Surface Burning Characteristics of Building Materials
9. ASTM E 580 Installation of Metal Suspension Systems in Areas Requiring Moderate Seismic Restraint
10. ASTM E 1111 Standard Test Method for Measuring the Interzone Attenuation of Ceilings Systems
11. ASTM E 1414 Standard Test Method for Airborne Sound Attenuation Between Rooms Sharing a Common Ceiling Plenum
12. ASTM E 1264 Classification for Acoustical Ceiling Products

B. NFPA 286 Standard Methods of Fire Tests for Evaluating Contribution of Wall and Ceiling Interior Finish to Room Fire Growth
C. ASHRAE Standard 62.1-2004, “Ventilation for Acceptable Indoor Air Quality”
D. ICC ESR 1308 International Code Council Evaluation Report Independent Evaluation of Armstrong Suspension Components for Seismic Installations
E. International Building Code
F. ASCE 7 American Society of Civil Engineers, Minimum Design Loads for Buildings and Other Structures
G. International Code Council-Evaluation Services - AC 156 Acceptance Criteria for Seismic Qualification Testing of Non-structural Components
H. LEED - Leadership in Energy and Environmental Design is a set of rating systems for the design, construction, operation, and maintenance of green buildings

1.4 SYSTEM DESCRIPTION

A. Discontinuous

1.5 SUBMITTALS

A. Product Data: Submit manufacturer's technical data for each type of acoustical ceiling unit and suspension system required.
B. Samples: Minimum 6" x 6" submittal sample of specified blade color; 8 inch long sample of suspension system, including main runner and cross tee.
C. Shop Drawings: Layout and details of acoustical ceilings show locations of items, which are to be coordinated with, or supported by the ceilings.
D. Acoustical Certifications: Manufacturer's certifications that products comply with specified requirements, including laboratory reports showing compliance with specified tests and standards. For acoustical performance, each carton of material must carry an approved independent laboratory classification, such as Underwriter's Laboratory (UL) of NRC.
    1. If the material supplied by the acoustical subcontractor does not have an independent laboratory classification of acoustical performance on every carton, subcontractor shall be required to send material from every production run appearing on the job to an independent or NVLAP approved laboratory for testing, at the architect's or owner's discretion. All products not conforming to manufacturer's current published values must be removed, disposed of, and replaced with complying product at the expense of the Contractor performing the work.

1.6 SUSTAINABLE MATERIALS

A. Transparency: Manufacturers will be given preference when they provide documentation to support sustainable requirements for the following: Material ingredient transparency, Removal of Red List Ingredients per LBCV3, Life Cycle impact information, Low-Emitting Materials, and Clean Air performance.
    1. End of Life Programs/Recycling: Where applicable, manufacturers that provide the option for recycling of their products into new products at end-of-life through take-back programs will be preferred.
    2. Products meeting LEED V4 requirements including:
        i. Storage & Collection of Recyclables
        ii. Construction and Demolition Waste Management Planning
        iii. Building Life-Cycle Impact Reduction
        iv. Building Product Disclosure and Optimization Environmental Product Declarations
        v. Building Product Disclosure and Optimization Sourcing of Raw Materials
        vi. Building Product Disclosure and Optimization Material Ingredients
        vii. Construction and Demolition Waste Management

1.7 QUALITY ASSURANCE

A. Single-Source Responsibility: Provide acoustical panel units and grid components by a single manufacturer.
B. Fire Performance Characteristics: Identify acoustical ceiling components with appropriate markings of applicable testing and inspecting organization.

1. Surface Burning Characteristics: Class A as follows, tested per ASTM E84 and CAN/ULC S102:
    a. Flame Spread: 25 or less
    b. Smoke Developed: 50 or less

C. Handle acoustical blades carefully to avoid scratching or denting units in any way.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Deliver acoustical ceiling units to project site in original, unopened packages and store them in a fully enclosed space where they will be protected against damage from moisture, direct sunlight, surface contamination, and other causes.
B. Before installing acoustical ceiling units, permit them to reach room temperature and a stabilized moisture content.
C. Handle acoustical ceiling units carefully to avoid chipping edges or damaged units in any way.

1.9 PROJECT CONDITIONS

A. Space Enclosure:
All ceiling products and suspension systems must be installed and maintained in accordance with Armstrong written installation instructions for that product in effect at the time of installation and best industry practice. Prior to installation, the ceiling product must be kept clean and dry, in an environment that is between 32°F (0°C) and 120°F (49°C) and not subject to Abnormal Conditions. Abnormal conditions include exposure to chemical fumes, vibrations, moisture from conditions such as building leaks or condensation, excessive humidity, or excessive dirt or dust buildup.

HumiGuard Plus Ceilings: Installation of the products shall be carried out where the temperature is between 32°F (0° C) and 120°F (49° C). It is not necessary for the area to be enclosed or for HVAC systems to be functioning. All wet work (plastering, concrete, etc.) must be complete and dry. The ceilings must be maintained to avoid excessive dirt or dust buildup that would provide a medium for microbial growth on ceiling panels. Microbial protection does not extend beyond the treated surface as received from the factory and does not protect other materials that contact the treated surface such as supported insulation materials.

1.10 WARRANTY

A. Blades: Submit a written warranty executed by the manufacturer, agreeing to repair or replace acoustical panels that fail within the warranty period. Failures include, but are not limited to:
    1. Blade Panels: Sagging and warping as a result of defects in materials or factory workmanship.
    2. Grid System: Rusting and manufacturer's defects
B. Warranty Period:
    1. Blades: One (1) year from date of substantial completion
    2. Suspension System: Ten (10) years from date of substantial completion
C. The Warranty shall not deprive the Owner of other rights the Owner may have under other provisions of the Contract Documents and will be in addition to and run concurrent with other warranties made by the Contractor under the requirements of the Contract Documents.

1.11 MAINTENANCE

A. Extra Materials: Deliver extra materials to Owner. Furnish extra materials described below that match products installed. Packaged with protective covering for storage and identified with appropriate labels.
    1. Acoustical Ceiling Units: Furnish quality of full-size units equal to 5.0 percent of amount installed.
    2. Exposed Suspension System Components: Furnish quantity of each exposed suspension component equal to 2.0 percent of amount installed.

Part 2 - PRODUCTS

2.1. MANUFACTURERS

1) Basis of Design SoundScapes Blades
    a) Armstrong World Industries Inc.
    b) Certain Teed
2) Suspension System
    a) Armstrong World Industries Inc.
    b) Certain Teed

2.2.1 SoundScapes Blades:

1. Surface Texture: Fine
2. Composition: Fiberglass
3. Color: Color shall be selected by Architect from manufacturers standard colors and including custom colors.
4. Size & Design: Double Wave size as shown on drawings
5. Edge Profile: Square
6. Recycled Content: 43%
7. Acoustics: Sound absorption up to 1.80 Noise Reduction Coefficient (NRC) ASTM C 423 dependent on blade depth and spacing:
8. Panel Depth 10” and 12” o.c.
9. Flame Spread: ASTM E 1264; Class A (UL)
10. Dimensional Stability: HumiGuard Plus; Anti-Microbial, inherent

11. Basis of Design: Furnish and Install SoundScapes Blades as manufactured by Armstrong World Industries or comparable products by one of the following.

12. a. Certain Teed
13. b. Kanopi

14. Products shall comply with the Build America, Buy America Act (BABA)

2.2.2 Individual Suspension:

1. Aircraft Cable: Acceptable product as manufactured by Armstrong World Industries
    a. Item 6655L8CR - 4-Point Hanging Kit (4 per bag)
    b. Item 625530 - Extended Hanging Aircraft Cables (30' length, 4 per bag). For use with Item 6655L8CR when longer cables are needed.

2.3.1 METAL SUSPENSION SYSTEMS

A. Direct-to-Grid Suspension Acceptable Product: Listed Below as manufactured by Armstrong World Industries, Inc. Items are available in custom colors; contact ASQuote@armstrongceilings.com.

a. Prelude XL in coordinating finishes manufactured by Armstrong World Industries:

7301 _ _ _ 12' HD Main Beam

XL7342 _ _ _ 4' Cross Tee

XL7328 _ _ _ 2' Cross Tee

7800 _ _ _ 12’ Angle Molding

b. 360° painted Black (BL) or White (WH) as manufactured by Armstrong World Industries:

730136 12’ HD Main Beam
XL734036 4’ Cross Tee
XL732036 2’ Cross Tee
780036 12’ Angle Molding

c. 360° painted made to order colors (RAL) as manufactured by Armstrong World Industries:

56418 12’ HD Main Beam
56421 4’ Cross Tee
56419 2’ Cross Tee
7800 12’ Angle Molding

B. Direct-Attach Acceptable Product: AXM34STR3 _ _ 10' Straight Wall Molding (360º Paint Recommended)
C. Wire for Hangers and Ties: ASTM A 641, Class 1 zinc coating, soft annealed, with a yield stress load of at least time three design load, but not less than 12 gauge.
D. Accessories (based on selection)
AX4STR3_ _ 10’ Axiom Classics 4” Straight Trim (360º Paint Recommended)
ARBRKT Adjustable Hanger Bracket
6459BL Black Rigid Attachment Clip
STAC Single Tee Adapter Clip
E. Seismic Accessories Required (based on “Seismic Design Category”)

PART 3 - EXECUTION

3.1 EXAMINATION

A. Do not proceed with installation until all wet work such as concrete, terrazzo, plastering and painting has been completed and thoroughly dried out, unless expressly permitted by manufacturer's printed recommendations. (Exception: HumiGuard Max Ceilings)

3.2 PREPARATION

A. Coordination: Furnish layouts for preset inserts, clips, and other ceiling anchors whose installation is specified in other sections.

1. Furnish concrete inserts and similar devices to other trades for installation well in advance of time needed for coordination of other work.

3.3 INSTALLATION

A. Install SoundScapes Blades per Armstrong World Industries installation instructions.
B. For areas having seismic requirements, consult with the Authority Having Jurisdiction or Building Code to determine the local requirements and following the manufacturers seismic guidelines found in the manufacturers Installation instructions.
C. Install suspension system per ASTM C636 unless otherwise noted in the manufactures Installation Instructions.

3.4 ADJUSTING AND CLEANING

A. Replace damaged and broken blades.
B. Clean exposed surfaces of blades, including trim, and suspension members comply with manufacturer's instructions for cleaning and touch up of minor finish damage.
C. Remove and replace work that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION

SECTION 095113 - ACOUSTICAL PANEL CEILINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes acoustical panels and exposed suspension systems for ceilings.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Samples: For each exposed product and for each color and texture specified.

1.4 INFORMATIONAL SUBMITTALS

A. Product test reports.

B. Evaluation reports.

C. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.6 QUALITY ASSURANCE

A. Testing Agency Qualifications: Qualified according to NVLAP.

B. Mockups: Build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Build mockup of typical ceiling area as shown on Drawings.
2. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame-Spread Index: Comply with ASTM E 1264 for Class A materials.
2. Smoke-Developed Index: 450 or less.

2.2 ACOUSTICAL PANEL CEILINGS, GENERAL

A. Acoustical Panel Standard: Comply with ASTM E 1264.

B. Metal Suspension System Standard: Comply with ASTM C 635.

C. Attachment Devices: Size for five times the design load indicated in ASTM C 635, Table 1, "Direct Hung," unless otherwise indicated. Comply with seismic design requirements.

2.3 ACOUSTICAL PANELS (ACT)

A. Basis-of-Design Product : Subject to compliance with requirements, provide Armstrong World Industries, Inc.; 1728 “Fine Fissured” or comparable product by one of the following:

1. CertainTeed Corp.
2. Chicago Metallic Corporation.
3. Tectum Inc.
4. USG Interiors, Inc.; Subsidiary of USG Corporation.

B. Color: White.

C. LR: 0.85.

D. NRC: 0.70, Type E-400 mounting according to ASTM E 795.

E. CAC: 35.

F. Edge/Joint Detail: Square.

G. Thickness: 3/4 inch.

H. Modular Size: 24 by 24 inches.

2.4 METAL SUSPENSION SYSTEM

A. Basis-of-Design Product: Subject to compliance with requirements, provide Armstrong World Industries, Inc.; “Prelude Plus XL Fire Guard” or comparable product by one of the following:

1. CertainTeed Corp.
2. Chicago Metallic Corporation.
3. USG Interiors, Inc.; Subsidiary of USG Corporation.

B. 15/16" Tee System, Capped, Double-web, Steel Suspension System: Main and cross runners roll formed from cold-rolled steel sheet; hot-dip galvanized according to ASTM A 653/A 653M, not less than G30 coating designation; with prefinished 15/16 inch wide metal caps on flanges.

1. Structural Classification: Heavy-duty system.
2. End Condition of Cross Runners: Override (stepped) type.
3. Face Design: Flat, flush.
4. Cap Material: aluminum cold-rolled sheet.
5. Cap Finish: Baked Polyester painted, white.

C. Roll-Formed, Sheet-Metal Edge Moldings and Trim: Type and profile indicated or, if not indicated, manufacturer's standard moldings for edges and penetrations that comply with seismic design requirements; formed from sheet metal of same material, finish, and color as that used for exposed flanges of suspension-system runners.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install acoustical panel ceilings to comply with ASTM C 636/C 636M and seismic design requirements indicated, according to manufacturer's written instructions and CISCA's "Ceiling Systems Handbook."

B. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders, and comply with layout shown on reflected ceiling plans.

1. Arrange directionally patterned acoustical panels as indicated on reflected ceiling plans.

END OF SECTION 095113

SECTION 096513 - RESILIENT BASE AND ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Resilient base.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Samples: For each exposed product and for each color and texture specified, not less than 4 inches long.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. FloorScore Compliance: Resilient base shall comply with requirements of FloorScore certification.

2.2 THERMOPLASTIC-RUBBER BASE

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Burke Flooring (Flexco).
2. Nora Rubber Products.
3. Roppe Corp.

B. Product Standard: ASTM F 1861, Type TP (rubber, thermoplastic).

C. Thickness: 0.125 inch.

D. Height: As indicated on Drawings.

E. Lengths: Coils in manufacturer's standard length.

F. Outside Corners: Preformed.

G. Inside Corners: Preformed.

H. Colors: Up to four (4) as selected by Architect from manufacturer's full range, within same Collection/Series as indicated on drawings.

2.3 RUBBER STAIR ACCESSORIES

A. Fire-Test-Response Characteristics: As determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.

1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

B. Basis-of-Design Product: Subject to compliance with requirements, Johnsonite; Stairwell Management VIRTR-RD or comparable product by one of the following:

1. AB; American Biltrite.
2. Armstrong World Industries, Inc.
3. Burke Mercer Flooring Products, Division of Burke Industries Inc.
4. Flexco.
5. Johnsonite; A Tarkett Company.
6. Roppe Corporation, USA.

C. Stair Treads: ASTM F 2169.

1. Type: Rubber with integrated riser.
2. Class: 2 (pattern; embossed, grooved, or ribbed).
3. Group: 2 (with contrasting color for the visually impaired).

D. Landing Tile: Matching treads; produced by same manufacturer as treads and recommended by manufacturer for installation with treads.

E. Locations: Provide rubber stair accessories in areas indicated.

F. Colors and Patterns: As selected by Architect from full range of industry colors.

2.4 INSTALLATION MATERIALS

A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.

B. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.

1. Adhesives shall have a VOC content of 50 g/L or less.

PART 3 - EXECUTION

3.1 PREPARATION

A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.

B. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.

C. Do not install resilient products until they are the same temperature as the space where they are to be installed.

D. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

3.2 RESILIENT BASE INSTALLATION

A. Comply with manufacturer's written instructions for installing resilient base.

B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.

C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.

D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.

E. Do not stretch resilient base during installation.

F. On masonry surfaces or other similar irregular substrates, fill voids along top edge of resilient base with manufacturer's recommended adhesive filler material.

G. Preformed Corners: Install preformed corners before installing straight pieces.

H. Job-Formed Corners: Job-formed corners are not acceptable

3.3 CLEANING AND PROTECTION

A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.

B. Cover resilient products subject to wear and foot traffic until Substantial Completion.

END OF SECTION 096513

SECTION 096519 - RESILIENT TILE FLOORING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Solid vinyl floor tile.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For each type of floor tile. Include floor tile layouts, edges, columns, doorways, enclosing partitions, built-in furniture, cabinets, and cutouts.

1. Show details of special patterns.

C. Samples: Full-size units of each color and pattern of floor tile required.

1.3 CLOSEOUT SUBMITTALS

A. Maintenance data.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Test-Response Characteristics: For resilient tile flooring, as determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.

1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

B. FloorScore Compliance: Resilient tile flooring shall comply with requirements of FloorScore certification.

2.2 Vinyl Composite Tile (VCT - 1)

A. Basis-of-Design: Subject to compliance with requirements, provide Armstrong Imperial Texture 12”x12” products or comparable products by one of the following:
1. Armstrong
2. Johnsonite
3. Tarkett

B. Color: As selected by Architect from manufacturer's full range, within series/collection.

2.3 Vinyl Composite Tile (VCT - 2)

A. Basis-of-Design: Subject to compliance with requirements, provide Armstrong Imperial Texture 12"x12" products or comparable products by one of the following:
1. Armstrong
2. Johnsonite
3. Tarkett

B. Color: As selected by Architect from manufacturer's full range, within series/collection.

2.4 INSTALLATION MATERIALS

A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by floor tile manufacturer for applications indicated.

B. Adhesives: Water-resistant type recommended by floor tile and adhesive manufacturers to suit floor tile and substrate conditions indicated.

1. Adhesives shall comply with the following limits for VOC content:

a. Tile Adhesives: 50 g/L or less.
b. Rubber Floor Adhesives: 60 g/L or less.

PART 3 - EXECUTION

3.1 PREPARATION

A. Prepare substrates according to floor tile manufacturer's written instructions to ensure adhesion of resilient products.

B. Concrete Substrates: Prepare according to ASTM F 710.

1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by floor tile manufacturer. Do not use solvents.
3. Alkalinity and Adhesion Testing: Perform tests recommended by floor tile manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 9 pH.
4. Moisture Testing: Proceed with installation only after substrates pass testing according to floor tile manufacturer's written recommendations, but not less stringent than the following:

a. Perform anhydrous calcium chloride test according to ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours.
b. Perform relative humidity test using in situ probes according to ASTM F 2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level.

C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.

D. Do not install floor tiles until they are the same temperature as the space where they are to be installed.

E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient floor tile.

3.2 FLOOR TILE INSTALLATION

A. Comply with manufacturer's written instructions for installing floor tile.

B. Lay out floor tiles from center marks established with principal walls, discounting minor offsets, so tiles at opposite edges of room are of equal width. Adjust as necessary to avoid using cut widths that equal less than one-half tile at perimeter.

1. Lay tiles in pattern indicated.

C. Match floor tiles for color and pattern by selecting tiles from cartons in the same sequence as manufactured and packaged, if so numbered. Discard broken, cracked, chipped, or deformed tiles.

1. Lay tiles in pattern of colors and sizes indicated.

D. Scribe, cut, and fit floor tiles to butt neatly and tightly to vertical surfaces and permanent fixtures including built-in furniture, cabinets, pipes, outlets, and door frames.

E. Extend floor tiles into toe spaces, door reveals, closets, and similar openings. Extend floor tiles to center of door openings.

F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on floor tiles as marked on substrates. Use chalk or other nonpermanent marking device.

G. Install floor tiles on covers for telephone and electrical ducts, building expansion-joint covers, and similar items in finished floor areas. Maintain overall continuity of color and pattern between pieces of tile installed on covers and adjoining tiles. Tightly adhere tile edges to substrates that abut covers and to cover perimeters.

H. Adhere floor tiles to flooring substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.

3.3 CLEANING AND PROTECTION

A. Comply with manufacturer's written instructions for cleaning and protecting floor tile.

B. Floor Polish for LVT: Remove soil, adhesive, and blemishes from floor tile surfaces before applying liquid floor polish.

1. Apply two coat(s).

C. Cover floor tile until Substantial Completion.

END OF SECTION 096519

SECTION 097700 - SPECIAL WALL SURFACES

PART 1 GENERAL

1.1 SECTION INCLUDES

1. Pre-manufactured panel system including mounting hardware and specified accessories.

1.2 RELATED SECTIONS

1. Section 06100 - Rough Carpentry; furring, blocking, and other carpentry work that is not exposed to view.

2. Section 06402 - Interior Architectural Woodwork; for interior woodwork other than wall systems not included in this section.

3. Section 09260 - Gypsum Board Assemblies; for metal support systems not included in this section.

1.3 REFERENCES

1. American Society for Testing and Materials (ASTM) E84 - Standard Test Method for Surface Burning Characteristics of Building Materials.
   a) Class 1/A - Flame Spread 0-25, Smoke Developed 450 or less.
2. Architectural Woodwork Institute (AWI) Quality Standards.
3. National Electrical Manufacturer’s Association (NEMA)

1.4 SUBMITTALS

1. Submit under provisions of Section 01300.

2. Product Data: Manufacturer's Safety Data Sheets (MSDS) on each product to be used, including:
   a) Preparation instructions and recommendations.
   b) Storage and handling requirements and recommendations.
   c) Installation methods.

3. Shop Drawings: Shop drawings in sufficient detail to show fabrication, installation, anchorage, and interface of the work of this Section with adjacent work.

4. Selection Samples: For each finish product specified, one complete set of color samples representing manufacturer's standard range of available colors and patterns including custom colors.

1.5 QUALITY ASSURANCE

1. Manufacturer Qualifications:
   a) Firm experienced in successful production of wall systems similar to that indicated for the Project, with sufficient production capacity to produce required units without causing delay in the work.

b) Provide certificate signed by panel manufacturer certifying that products comply with specified requirements.

2. Installer Qualifications: Demonstrate successful experience in installing architectural woodwork similar in type and quality to those required for this project.

1.6 DELIVERY, STORAGE, AND HANDLING

1. Do not deliver wall system until painting, wet work, grinding, and similar operations that could damage, soil, or deteriorate wall system have been completed in installation areas as specified by AWI 1700-G-3.

2. If panels are stored prior to installation, store them flat in completely enclosed areas, out of the weather. If panels must be stored in other than installation areas, store only in areas where environmental conditions comply with manufacturers recommendations. Do not expose panels to continuous direct sunlight, nor to extremes in temperature and humidity. Store products in manufacturer's packaging until ready for installation.

3. Store and dispose of solvent-based materials, and materials used with solvent-based materials, in accordance with requirements of local authorities having jurisdiction.

1.7 PROJECT CONDITIONS

1. Do not deliver or install wall system until building is enclosed, wet work is complete and HVAC system is operating and will maintain temperature and relative humidity at occupancy levels during the remainder of the construction period as specified by AWI 1700-G-3.

2. Do not install wall system until normal lighting conditions exist. Normal lighting conditions are described as those in place when the project is finished. This includes, but not limited to, design lighting (wall washers, spotlights and flood lights, and similar fixtures) and natural lighting.

3. Wall, ceilings, floors, and openings must be level, plumb, straight, in-line and square as specified by AWI 1700-G-3.

4. Optional for use with Glass panels.

   Sub wall must be flat and dry and conform to ML/SFA 540 Specifications. Vertical alignment (plumbness) of wall shall be within $1/960^{th}$ (1/8” in 10 ft.) of the span. Horizontal alignment (levelness) of the walls shall be within $1/960^{th}$ (1/8” in 10ft.) of their respective heights. Squareness of walls shall not be more than 1/8” out of square within the length of the wall. All corners, window mullions, are door frames must be plumb and level.

5. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results, both during installation and subsequent occupancy. Do not install products under environmental conditions outside manufacturer's absolute limits. Panels shall be conditioned in the environment in which they will be installed for a minimum of 72 hours prior to installation. The recommended environment is 60^0 to 80^0 F and 35% to 55% relative humidity.

6. Manufacturer warrants any product it has manufactured and sold against defects in materials or workmanship for a period of one year from the date of original purchase and acceptance

for use. This warranty extends to products assembled / installed and used in the manner intended and does not cover damage or failure caused by misuse, abuse or accidents, exposure to extreme temperature, improper installation, improper maintenance, and exposure to water or excessive humidity or excessive moisture.

PART 2 PRODUCTS

2.1 MANUFACTURERS

1. Basis of Design: ： Subject to compliance with requirements, provide Panel Specialists, Inc.; 3115 Range Rd., Temple, TX 76504. ASD. Toll Free Tel: (800) 947-9422. Tel: (254) 774-9800. Fax: (254) 598-3222. Email: psiwalls@panelspec.com. Web: http://www.panelspec.com. Or by one of the following.

   a. Surface Materials: 6655 Parkland Blvd. Solon, OH. 44139 Tele. (440) 248-0000

   b. Wall Panel Systems Inc.: 1815 Rustin Ave., Suite A Riverside, CA. 92507 Tele. (877) 333-4977.

2. Requests for substitutions will be considered in accordance with provisions of Section 016000.

2.2 PANEL SYSTEMS

1. Provide prefinished decorative panels where shown on the drawings, as specified herein, and as needed for a complete and proper installation.

2. Comply with applicable requirements of "Architectural Woodwork Quality Standards" in the production and installation of the wall panel system as published by the Architectural Woodwork Institute (AWl) unless otherwise indicated.

3. Panel System: #310 as manufactured by Panel Specialists inc. A progressive panel system with an exposed divider molding creating a 1/16 inch (1.5mm) horizontal and vertical reveal between edge banded panels.

   a) Panel Thickness: 7/16 inches (11.1 mm).
   b) Horizontal Reveal: System to provide a reveal of 1/16 inch (1.5mm) between panels.
   c) Vertical Reveal: System to provide a reveal of 1/16 inch (1.5mm) between panels.
   d) Panel Edge Finish: Panel edges to be finished with .018-inch (.5mm) PVC edge banding or wood veneer, except as noted in material specifications.
   e) Panel Finish: Refer to Room Finish Schedule and drawings. Colors selected by Architect including custom colors.

   f) Molding: All moldings to be .062” thick (at structural areas) 6063 alloy aluminum with T5 temper.
      a) Divider Moldings
         1. #302a 1/16 in.(1.5mm) wide Divider Molding
         2. #410 H Divider Molding available for use with marker boards, resilient tack board, and other specialty panels

      b) ½” Wide Edge Trims & 1” Corners
         1. #304 ½” Edge Trim Molding

2. #304A ½" Edge Trim Molding (2-piece)

3. #103-90 1" Rounded 90° Outside Corner
4. #103-135 135 ^{O} Outside Corner
5. #304-90 End Cap for top and bottom of 90° outside corner
6. #304-135 End Cap for top and bottom of 135° outside corner

g) Finishes:
   a) Panel Face: Compact Laminate Phenolic Panels
      1. Finish #1: HPL Color as selected
   b) Panel Face Pattern Direction:
      1. Horizontal or Vertical selected by Architect.
   c) Panel Edge Banding:
      1. 5mm PVC Platinum
   d) Aluminum Molding Finish:
      1. Clear Anodized

2.3 MATERIALS

1. High Pressure Decorative Laminates

   a) High Pressure Laminate (VGS, VGF.) and non-decorative backers (BKV) used to surface wall panels systems shall be manufactured to meet or exceed the National Electrical Manufacturing Association (NEMA LD3-2005) for thickness, performance properties and appearance.

2. Custom Graphic High-Pressure Laminate (HDP-10 AND HDP-9. We will have 2 different Custom graphics)

   a) Custom High-Pressure Laminate (CHPL) and non-decorative backers (BKV) used to surface wall panels systems shall be manufactured to meet or exceed the National Electrical Manufacturing Association (NEMA LD3-2005) for thickness, performance properties and appearance.

   b) Images can be either photographs or graphic images in a format in accordance with the manufacturer's artwork requirements described on their website.

PART 3 EXECUTION

3.1 EXAMINATION

1. Do not begin installation until substrates have been properly prepared according to AWI 1700-G-3.

2. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

3.2 FIELD DIMENSIONS

1. Where wall system is indicated to be fitted to other constructions, check actual dimensions of other constructions by accurate field measurements before manufacturing wall system; show recorded measurements on final shop drawings. Coordinate manufacturing schedule with construction progress to avoid delay of work.

2. Where field measurements cannot be made without delaying the work, guarantee dimensions and proceed with manufacture of wall system without field measurements coordinate other construction to ensure that actual dimensions correspond to guaranteed dimensions.

3.3 PREPARATION

1. Panels must be acclimated to ambient temperature and humidity conditions in accordance with manufacturer’s specifications prior to installation. Refer to PSI installation guide for proper, handling, storage, and acclimation procedures.

2. Clean surfaces thoroughly prior to installation.

3. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.

3.4 INSTALLATION

1. Install in accordance with manufacturer's instructions.

2. When interior paneling is on an exterior wall or in a wet area, provide a barrier sheet of plastic film between the outside wall and the panels in order to prevent condensation affecting the stability of the panels.

3. Field cutting of all wall systems should be accomplished using carbide tools. All face penetrations and cutouts should have a minimal 1/8-inch (3 mm) radius in corners according to NEMA Standards Publication LD 3-2005.

4. All wall systems should receive an "S" bead of panel mastic on the back of the panel during installation.

5. For vertical applications, wall systems shall be mechanically fastened to horizontal metal furring strapping spaced 24 inches (610 mm) O.C. Furring straps shall be no less than 18-ga 3-1/2 inches (89 mm) wide, continuously. Metal strapping to be installed to the drywall studs prior to the application of the gypsum board by the framing contractor. For panels installed with a horizontal orientation, strapping is recommended but not necessary

3.5 PROTECTION

1. Protect installed products until completion of project.

2. Touch-up, repair or replace damaged products before Substantial Completion.

END OF SECTION

SECTION 099000 – PAINTING AND COATING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Surface preparation.

B. Field application of paints, stains, and varnishes.

C. Scope: Finish all interior and exterior surfaces exposed to view, unless fully factory-finished and unless otherwise indicated, including the following:

D. Do Not Paint or Finish the Following Items:
1. Items fully factory-finished unless specifically so indicated; materials and products having factory-applied primers are not considered factory finished.
2. Items indicated to receive other finishes.
3. Items indicated to remain unfinished.
4. Fire rating labels, equipment serial number and capacity labels, and operating parts of equipment.
5. Floors, unless specifically so indicated.
6. Glass.
7. Concealed pipes, ducts, and conduits.

E. See Schedule of finishes included in this Section.

1.02 RELATED REQUIREMENTS

A. Section 02581 - Traffic Paint: Pavement markings.

B. Section 03356 - Concrete Floor Finishing.

C. Section 055000 - Metal Fabrications: Shop-primed items.

D. Section 06100 - Rough Carpentry: Exposed telephone and electrical panel boards.

E. Section 06200 - Finish Carpentry.

F. Section 07620 - Sheet Metal Flashing and Trim.

G. Section 08111 - Standard Steel Doors.

H. Section 08112 - Standard Steel Frames.

I. Section 08331 - Overhead Coiling Doors.

J. Section 08675 - Steel Sliding Fire Windows.

K. Section 09260 - Gypsum Board Assemblies.

L. Section 09290 - Glass Fiber Reinforced Units.

M. Division 15 - Mechanical: Painted identification.

N. Division 16 - Electrical: Painted identification.

1.03 REFERENCE STANDARDS

A. 40 CFR 59, Subpart D - National Volatile Organic Compound Emission Standards for Architectural Coatings; U.S. Environmental Protection Agency; current edition.

B. ASTM D16 - Standard Terminology for Paint, Related Coatings, Materials, and Applications; 2012.

C. ASTM D4442 - Standard Test Methods for Direct Moisture Content Measurement of Wood and Wood-Base Materials; 2007.

1.04 DEFINITIONS

A. Conform to ASTM D 16 for interpretation of terms used in this section.

1.05 SUBMITTALS

A. See Section 013000 - Administrative Requirements, for submittal procedures.

B. Product Data: Provide data on all finishing products, including VOC content.

C. Samples: Submit two painted samples, illustrating selected colors for each color and system selected with specified coats cascaded. Submit on aluminum sheet, 6 x 6 inch in size.

D. Manufacturer's Instructions: Indicate special surface preparation procedures.

E. Maintenance Data: Submit data on cleaning, touch-up, and repair of painted and coated surfaces.

1.06 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the products specified, with minimum three years documented experience.

B. Applicator Qualifications: Company specializing in performing the type of work specified with minimum three years' experience.

1.07 REGULATORY REQUIREMENTS

A. Conform to applicable code for flame and smoke rating requirements for products and finishes.

1.08 MOCK-UP

A. See Section 014000 - Quality Requirements, for general requirements for mock-up.

B. Provide panel, 4 feet long by 4 feet wide, illustrating specified paint colors, texture, and finish. See architect for color selections. All colors must be approved by the owner. The painted panels shall remain on the job site protected from the weather.

C. Provide door and frame assembly illustrating paint coating color, texture, and finish.

D. Locate where directed.

E. Mock-up may remain as part of the work.

1.09 DELIVERY, STORAGE, AND HANDLING

A. Deliver products to site in sealed and labeled containers; inspect to verify acceptability.

B. Container Label: Include manufacturer's name, type of paint, brand name, lot number, brand code, coverage, surface preparation, drying time, cleanup requirements, color designation, and instructions for mixing and reducing.

C. Paint Materials: Store at minimum ambient temperature of 45 degrees F and a maximum of 90 degrees F, in ventilated area, and as required by manufacturer's instructions.

1.10 FIELD CONDITIONS

A. Do not apply materials when surface and ambient temperatures are outside the temperature ranges

required by the paint product manufacturer.

B. Follow manufacturer's recommended procedures for producing best results, including testing of substrates, moisture in substrates, and humidity and temperature limitations.

C. Do not apply exterior coatings during rain or snow, or when relative humidity is outside the humidity ranges required by the paint product manufacturer.

D. Minimum Application Temperatures for Latex Paints: 45 degrees F for interiors; 50 degrees F for exterior; unless required otherwise by manufacturer's instructions.

E. Minimum Application Temperature for Varnish Finishes: 65 degrees F for interior or exterior, unless required otherwise by manufacturer's instructions.

F. Provide lighting level of 80 ft candles measured mid-height at substrate surface.

1.11 EXTRA MATERIALS

A. See Section 016000 - Product Requirements, for additional provisions.

B. Supply 1 gallon of each color; store where directed.

C. Label each container with color in addition to the manufacturer's label.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Provide all paint and coating products used in any individual system from the same manufacturer; no exceptions.

i) Sherwin-Williams is the basis of design. Up to 8 colors to be selected by architect.

B. Approved Manufacturers:

i) Benjamin Moore

ii) Behr

iii) PPG

iv) Kelly-Moore

C. Primer Sealers: Same manufacturer as top coats.

D. Block Fillers: Same manufacturer as top coats.

2.02 PAINTS AND COATINGS - GENERAL

A. Paints and Coatings: Ready mixed, unless intended to be a field-catalyzed coating.
1. Provide paints and coatings of a soft paste consistency, capable of being readily and uniformly dispersed to a homogeneous coating, with good flow and brushing properties, and capable of drying or curing free of streaks or sags.
2. Supply each coating material in quantity required to complete entire project's work from a single production run.
3. Do not reduce, thin, or dilute coatings or add materials to coatings unless such procedure is specifically described in manufacturer's product instructions.

B. Primers: Where the manufacturer offers options on primers for a particular substrate, use primer categorized as "best" by the manufacturer.

C. Volatile Organic Compound (VOC) Content:

1. Provide coatings that comply with the most stringent requirements specified in the following:
   a. 40 CFR 59, Subpart D--National Volatile Organic Compound Emission Standards for Architectural Coatings.
2. Determination of VOC Content: Testing and calculation in accordance with 40 CFR 59, Subpart D (EPA Method 24), exclusive of colorants added to a tint base and water added at project site; or other method acceptable to authorities having jurisdiction.

2.03 PAINT SYSTEMS – EXTERIOR

A. Wood: Unprimed, Latex, 3 Coat:
   1. One coat of SW B42W8041, Exterior Latex Wood Primer.
   2. Semi-gloss: Two coats of SW A89-Series, SuperPaint Exterior Satin.

B. Drywall, Unprimed, Latex, 3 Coat:
   1. One coat of SW B51-450 Series, Multi-Purpose Interior/Exterior Latex Primer.
   2. Semi-gloss: Two coats of SW A89-Series, SuperPaint Exterior Satin.

C. Masonry/Concrete, Opaque Paint System, Latex, 3 Coat:
   1. One coat of SW LX2W50, Loxon Concrete & Masonry Primer.
   2. Flat: Two coats of SW A89-Series, SuperPaint Exterior Satin.

D. CMU, Opaque Waterproofing System, Latex, 3 Coat:
   1. One coat SW CF1W50, ConFlex Block Filler.
   2. Flat: Two coats of SW CF11W51 Series, ConFlex XL Elastomeric Smooth.

E. Ferrous Metals, (doors, frames, & handrails), Primed, Latex, 2 Coat:
   1. Touch-up with SW B66-1300 Series, Pro-Cryl Universal Water Based Primer.
   2. Semi-gloss: Two coats of B53-1150 Series, WB Alkyd Urethane Enamel Semi-Gloss.

F. Galvanized Metals, Latex, 3 Coat:
   1. One coat of SW B66-1300 Series, Pro-Cryl Universal Water Based Primer.
   2. Gloss: Two coats of SW B66-1661 Series, Pro Industrial DTM Acrylic Eg-Shel.

G. Aluminum, Unprimed, Latex, 3 Coat:
   1. One coat of SW B66-1300 Series, Pro-Cryl Universal Water Based Primer.
   2. Semi-gloss: Two coats of SW B66-1661 Series, Pro Industrial DTM Acrylic Eg-Shel.

H. Architectural PVC, Plastic, Fiberglass: Unprimed, Latex, 3 Coat:
   1. One coat of SW B51W1150, Extreme Bond Interior/Exterior Bonding Primer.
   2. Semi-gloss: Two coats of SW A89-Series, SuperPaint Exterior Satin.

I. Traffic Marking Paint Latex, 2 Coat:
   1. Two Coats Setfast Low VOC Acrylic Traffice Marking Paint, TM Series; White Yellow, Red, or Black.

2.04 PAINT SYSTEMS – INTERIOR

A. Gypsum Board/Plaster Ceilings, Latex Flat Finish, 3 Coat:
   1. One coat of B28W2600, ProMar 200 Zero VOC Interior Latex Primer.
   2. Flat: Two coats of B30-2600 Series, ProMar 200 Zero VOC Interior Latex Flat.

B. Gypsum Board/Plaster Walls, Latex-Acrylic Semi-Gloss Finish, 3 Coat:
   1. One coat of B28W2600, ProMar 200 Zero VOC Interior Latex Primer.
   2. Semi-gloss: Two coats of B31-2600 Series, ProMar 200 Zero VOC Interior Latex Semi-Gloss.

Alternate for upgrade Scuff Resistant Semi-Gloss:
1. One coat of B28W2600, ProMar 200 Zero VOC Interior Latex Primer.
2. Eggshell: Two coats of SW K46-1150 Series, Pre-Catalyzed Waterbased Semi-Gloss.

C. Concrete/Masonry, Opaque, Latex, 3 Coat:
1. One coat of SW LX2W50, Loxon Concrete & Masonry Primer.
2. Flat: Two coats of SW B3-2600 Series, ProMar 200 Zero VOC Interior Latex Semi-Gloss.

D. Ferrous Metals (doors, frames, & handrails), Unprimed, Latex, 3 Coat:
1. One coat of SW B66-1300 Series, Pro-Cryl Universal Water Based Primer.
2. Semi-gloss: Two coats of B53-1150 Series, WB Alkyd Urethane Enamel Semi-Gloss.

E. Galvanized Metals, Latex, 3 Coat:
1. One coat of SW B66-1300 Series, Pro-Cryl Universal Water Based Primer.
2. Semi-gloss: Two coats of B66-1661 Series, Pro Industrial DTM Acrylic Eg-Shel.

F. Aluminum, Unprimed, Latex, 3 Coat:
1. One coat etching primer: SW B71Y1, DTM Wash Primer.
2. Semi-gloss: Two coats of B66-1661 Series, Pro Industrial DTM Acrylic Eg-Shel.

G. Concrete/Masonry, Epoxy Enamel, 3 Coat: (typically wet areas)
1. One coat of SW LX2W50, Loxon Concrete & Masonry Primer.
2. Gloss: Two coats of SW B73V300 Series, Waterborne Catalyzed Epoxy Gloss.

H. CMU, Pre-Catalyzed Epoxy Finish Semi-Gloss, Latex, 3 Coat:
1. One coat SW CF1W50, ConFlex Block Filler.
2. Eg-shel: Two coats of SW K46-1150 Series, Pre-Catalyzed Waterbased Semi-Gloss.

I. Wood, Opaque, Latex, 3 Coat:
1. One coat of SW B28W8111, Premium Wall & Wood Interior Latex Primer
2. Semi-Gloss: Two coats of SW K46-1150 Series, Pre-Catalyzed Waterbased Semi-Gloss.

J. Wood, Transparent, Varnish, Stain:
1. One coat of Minwax Performance Series Tintable Interior Stain 7150/7151.
2. One coat Minwax Performance Fast-Dry, Sanding Sealer 81580.
3. Satin: Two coats of Minwax Performance Series Fast-Dry Varnish 9150/9151 Series.

K. Fabrics/Insulation Jackets, Latex, 3 Coat:
1. One coat of SW B66-310 Series, Pro-Cryl Universal Water Based Primer.
2. Semi-gloss: Two coats of B66-1661 Series, Pro Industrial DTM Acrylic Eg-Shel.

L. Metal Decking DryFall Finish, Latex Flat, 2 Coat:
1. Flat: Two coats of B42W181, Pro Industrial Waterborne Acrylic DryFall Flat.
(possible primer if rusting is present)

M. Metal Decking DryFall Finish, Latex Eg-Shel, 2 Coat:
1. Eg-Shel: Two coats of B42W82, Pro Industrial Waterborne Acrylic DryFall Eg-Shel.
(possible primer if rusting is present)

N. Epoxy Floor Coating, 3 Coat:
1. One coat of SW B70V8100, ArmorSeal 8100 Water Based Epoxy Floor Coating.
(reduce with one pint of water per gallon)
2. Satin or Gloss: Two coats of B70-8100/8160 Series ArmorSeal 8100 Water Based Epoxy Floor Coating.

O. Resinous / Industrial Coatings for Concrete Floors.

High Performance Flooring Coatings – Sherwin-Williams

2.05 ACCESSORY MATERIALS

A. Accessory Materials: Provide all primers, sealers, cleaning agents, cleaning cloths, sanding materials, and clean-up materials required to achieve the finishes specified whether specifically indicated or not; commercial quality.

B. Patching Material: Latex filler.

C. Fastener Head Cover Material: Latex filler.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that surfaces are ready to receive work as instructed by the product manufacturer.

B. Examine surfaces scheduled to be finished prior to commencement of work. Report any condition that may potentially affect proper application.

C. Test shop-applied primer for compatibility with subsequent cover materials.

D. Measure moisture content of surfaces using an electronic moisture meter. Do not apply finishes unless moisture content of surfaces are below the following maximums:
1. Gypsum Wallboard: 12 percent.
2. Plaster and Stucco: 12 percent.
3. Masonry, Concrete, and Concrete Unit Masonry: 12 percent.
4. Interior Wood: 15 percent, measured in accordance with ASTM D4442.
5. Exterior Wood: 15 percent, measured in accordance with ASTM D4442.
6. Concrete Floors and Traffic Surfaces: 8 percent.

3.02 PREPARATION

A. Clean surfaces thoroughly and correct defects prior to coating application.

B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.

C. Remove surface appurtenances, including electrical plates, hardware, light fixture trim, escutcheons, and fittings, prior to preparing surfaces or finishing.

D. Surfaces: Correct defects and clean surfaces which affect work of this section. Remove or repair existing coatings that exhibit surface defects.

E. Seal surfaces that might cause bleed through or staining of topcoat.

F. Remove mildew from impervious surfaces by scrubbing with solution of tetra-sodium phosphate and bleach. Rinse with clean water and allow surface to dry.

G. Concrete and Unit Masonry Surfaces to be Painted: Remove dirt, loose mortar, scale, salt or alkali powder, and other foreign matter. Remove oil and grease with a solution of tri-sodium phosphate; rinse well and allow to dry. Remove stains caused by weathering of corroding metals with a solution of sodium metasilicate after thoroughly wetting with water. Allow to dry.

H. Gypsum Board Surfaces to be Painted: Fill minor defects with filler compound. Spot prime defects after repair.

I. Plaster Surfaces to be Painted: Fill hairline cracks, small holes, and imperfections with latex

patching plaster. Make smooth and flush with adjacent surfaces. Wash and neutralize high alkali surfaces.

J. Insulated Coverings to be Painted: Remove dirt, grease, and oil from canvas and cotton.

K. Concrete Floors and Traffic Surfaces to be Painted: Remove contamination, acid etch, and rinse floors with clear water. Verify required acid-alkali balance is achieved. Allow to dry.

L. Aluminum Surfaces to be Painted: Remove surface contamination by steam or high pressure water. Remove oxidation with acid etch and solvent washing. Apply etching primer immediately following cleaning.

M. Galvanized Surfaces to be Painted: Remove surface contamination and oils and wash with solvent. Apply coat of etching primer.

N. Uncorroded Uncoated Steel and Iron Surfaces to be Painted: Remove grease, mill scale, weld splatter, dirt, and rust. Where heavy coatings of scale are evident, remove by hand wire brushing or sandblasting; clean by washing with solvent. Apply a treatment of phosphoric acid solution, ensuring weld joints, bolts, and nuts are similarly cleaned. Prime paint entire surface; spot prime after repairs.

O. Shop-Primed Steel Surfaces to be Finish Painted: Sand and scrape to remove loose primer and rust. Feather edges to make touch-up patches inconspicuous. Clean surfaces with solvent. Prime bare steel surfaces. Re-prime entire shop-primed item.

P. Interior Wood Surfaces to Receive Opaque Finish: Wipe off dust and grit prior to priming. Seal knots, pitch streaks, and sappy sections with sealer. Fill nail holes and cracks after primer has dried; sand between coats. Back prime concealed surfaces before installation.

Q. Interior Wood Surfaces to Receive Transparent Finish: Wipe off dust and grit prior to sealing, seal knots, pitch streaks, and sappy sections with sealer. Fill nail holes and cracks after sealer has dried; sand lightly between coats. Prime concealed surfaces with gloss varnish reduced 25 percent with thinner.

R. Metal Doors to be Painted: Prime metal door top and bottom edge surfaces.

3.03 APPLICATION

A. Apply products in accordance with manufacturer's instructions.

B. Where adjacent sealant is to be painted, do not apply finish coats until sealant is applied.

C. Do not apply finishes to surfaces that are not dry. Allow applied coats to dry before next coat is applied.

D. Apply each coat to uniform appearance.

E. Sand wood and metal surfaces lightly between coats to achieve required finish.

F. Vacuum clean surfaces of loose particles. Use tack cloth to remove dust and particles just prior to applying next coat.

G. Wood to Receive Transparent Finishes: Tint fillers to match wood. Work fillers into the grain before set. Wipe excess from surface.

H. Reinstall electrical cover plates, hardware, light fixture trim, escutcheons, and fittings removed prior to finishing.

3.04 FINISHING MECHANICAL AND ELECTRICAL EQUIPMENT

A. Refer to Division 15 and Division 16 for schedule of color coding of equipment, duct work, piping, and conduit.

B. Paint shop-primed equipment, where indicated.

C. Remove unfinished louvers, grilles, covers, and access panels on mechanical and electrical components and paint separately.

D. Reinstall electrical cover plates, hardware, light fixture trim, escutcheons, and fittings removed prior to finishing.

3.05 CLEANING

A. Collect waste material that could constitute a fire hazard, place in closed metal containers, and remove daily from site.

3.06 SCHEDULE - SURFACES TO BE FINISHED

A. Do Not Paint or Finish the Following Items:
   1. Items fully factory-finished unless specifically noted.
   2. Fire rating labels, equipment serial number and capacity labels.
   3. Stainless steel items.

B. Paint the surfaces described 1 coat.

C. Mechanical and Electrical: Use paint systems defined for the substrates to be finished.
   1. Paint all insulated and exposed pipes occurring in finished areas to match background surfaces, unless otherwise indicated.
   2. Paint shop-primed items occurring in finished areas.
   3. Paint interior surfaces of air ducts and convector and baseboard heating cabinets that are visible through grilles and louvers with one coat of flat black paint to visible surfaces.
   4. Paint dampers exposed behind louvers, grilles, and convector and baseboard cabinets to match face panels.

END OF SECTION

SECTION 099600 - HIGH-PERFORMANCE COATINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes surface preparation and application of high-performance coating systems (paint) on the following substrates:

1. Interior Substrates:

a. Concrete masonry units (CMU).
b. Steel.
c. Gypsum board.
d. Concrete floors

2. Exterior Substrates:

a. Steel.

1.2 DEFINITIONS

A. Gloss Level 6: 70 to 85 units at 60 degrees, according to ASTM D 523.

B. Gloss Level 7: More than 85 units at 60 degrees, according to ASTM D 523.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated. Include preparation requirements and application instructions.

B. Samples: For each type of coating system and in each color and gloss of topcoat indicated. Provide panel, 4 feet long by 4 feet wide, illustrating specified colors, texture, and finish. See architect for color selections. All colors must be approved by the owner. The painted panels shall remain on the job site protected from the weather.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Coatings: 5 percent, but not less than 1 gal. of each material and color applied.

1.5 QUALITY ASSURANCE

A. Mockups: Apply mockups of each coating system indicated to verify preliminary selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Architect will select one surface to represent surfaces and conditions for application of each coating system specified in Part 3.

a. Wall and Ceiling Surfaces: Provide samples of at least 2 sq. ft.
b. Other Items: Architect will designate items or areas required.

2. Final approval of color selections will be based on mockups.

a. If preliminary color selections are not approved, apply additional mockups of additional colors selected by Architect at no added cost to Owner.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Products: Subject to compliance with requirements, provide products by one of the following:

1. Tnemec
2. Dupont
3. Sherwin-Williams
4. Corotech

2.2 HIGH-PERFORMANCE COATINGS, GENERAL

A. MPI Standards: Provide products that comply with MPI standards indicated and are listed in "MPI Approved Products List."

B. Material Compatibility:

1. Provide materials for use within each coating system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
2. For each coat in a coating system, provide products recommended in writing by manufacturers of topcoat for use in coating system and on substrate indicated.
3. Provide products of same manufacturer for each coat in a coating system.

C. VOC Content: Products shall comply with VOC limits of authorities having jurisdiction and, for interior coatings applied at project site, the following VOC limits, exclusive of colorants added to a tint base, when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

1. Flat Paints and Coatings: 50 g/L.
2. Nonflat Paints and Coatings: 150 g/L.
3. Primers, Sealers, and Undercoaters: 200 g/L.
4. Anti-Corrosive and Anti-Rust Paints Applied to Ferrous Metals: 250 g/L.

5. Zinc-Rich Industrial Maintenance Primers: 340 g/L.
6. Pre-Treatment Wash Primers: 420 g/L.
7. Floor Coatings: 100 g/L.
8. Shellacs, Clear: 730 g/L.
9. Shellacs, Pigmented: 550 g/L.

9. Shellacs, Pigmented: 550 g/L.

D. Colors: As selected by Architect from manufacturer's full range and as necessary to match existing.

2.3 BLOCK FILLERS

A. Block Filler, Cementitious Acrylic:

1. Basis-of-Design Product: Tnemec; Series 130 “Envirofill”.

B. Block Filler, Polyamine Epoxy:

1. Basis-of-Design Product: Tnemec; Series 215 “Surfacing Epoxy”.

2.4 INTERIOR PRIMERS/SEALERS

A. Primer Sealer, Vinyl Acrylic, Interior:

1. Basis-of-Design Product: Tnemec; Series 51 “PVA Sealer”.

2.5 METAL PRIMERS

A. Primer, Rust-Inhibitive:

1. Tnemec; Series 10 “Tnemec Primers”.

2.6 EPOXY COATINGS

A. Polyamidoamine Epoxy, Satin:

1. Basis-of-Design Product: Tnemec; Series N69 “Hi-Build Epoxoline”.

2.7 ACRYLIC COATINGS

A. Acrylic Polymer, water-based, Semi-gloss:

1. Basis-of-Design Product: Tnemec; Series 1029 “Enduratone”.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

1. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:

    a. Concrete: 12 percent.
    b. Masonry (Clay and CMU): 12 percent.
    c. Wood: 15 percent.
    d. Gypsum Board: 12 percent.

B. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers.

C. Proceed with coating application only after unsatisfactory conditions have been corrected.

1. Beginning coating application constitutes Contractor's acceptance of substrates and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual" applicable to substrates indicated.

B. Clean substrates of substances that could impair bond of coatings, including dust, dirt, oil, grease, and incompatible paints and encapsulants.

1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce coating systems indicated.

3.3 APPLICATION

A. Apply high-performance coatings according to manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual."

B. Apply coatings to produce surface films without cloudiness, spotting, holidays, laps, brush marks, runs, sags, ropiness, or other surface imperfections. Produce sharp glass lines and color breaks.

3.4 CLEANING AND PROTECTION

A. Protect work of other trades against damage from coating operation. Correct damage by cleaning, repairing, replacing, and recoating, as approved by Architect, and leave in an undamaged condition.

B. At completion of construction activities of other trades, touch up and restore damaged or defaced coated surfaces.

3.5 EXTERIOR HIGH-PERFORMANCE COATING SCHEDULE

A. Steel Substrates:

1. Acrylic System, new steel, exterior, exposed to view:

    a. Prime Coat: Primer, rust-inhibitive.
    b. Intermediate Coat: Acrylic Polymer, semi-gloss.
    c. Topcoat: Acrylic Polymer, semi-gloss.

2. Acrylic System, new steel, exterior, not exposed to view:

    a. Prime Coat: Primer, rust-inhibitive.

3. Interior Concrete is to receive a single coat of Latex. Prime wall before adding final coat of Latex.

3.6 INTERIOR HIGH-PERFORMANCE COATING SCHEDULE

A. CMU Substrates:

1. Acrylic System:

    a. Block Filler: Block filler, epoxy.
    b. Intermediate Coat: Acrylic Polymer, semi-gloss.
    c. Topcoat: Acrylic Polymer, semi-gloss.

2. Epoxy-Modified Latex System:

    a. Block Filler: Block filler, latex, interior/exterior[, MPI #4].
    b. Intermediate Coat: Epoxy-modified latex, interior, gloss (Gloss Level 6)[, MPI #115].
    c. Topcoat: Epoxy-modified latex, interior, gloss (Gloss Level 6)[, MPI #115].

B. Gypsum Board Substrates:

1. Acrylic System:

    a. Prime Coat: Primer sealer, vinyl acrylic, interior.
    b. Intermediate Coat: Acrylic Polymer, semi-gloss.
    c. Topcoat: Acrylic Polymer, semi-gloss.

C. Steel Substrates:

1. Acrylic System, new steel, interior, exposed to view:

    a. Prime Coat: Primer, rust-inhibitive.
    b. Intermediate Coat: Acrylic Polymer, semi-gloss.
    c. Topcoat: Acrylic Polymer, semi-gloss.

2. Acrylic System, new steel, interior, not exposed to view:

    a. Prime Coat: Primer, rust-inhibitive.

D. Interior Concrete Floor

1. Dur-A-Flex system exposed interior concrete floors in kitchen area see drawings for finish schedule.

a. Poly-Crete MDB – Prepare floors as required by manufacture.

END OF SECTION 099600

SECTION 101416 - PLAQUES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes plaques.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For plaques.

1. Include fabrication and installation details and attachments to other work.
2. Show plaque mounting heights, locations of supplementary supports to be provided by others, and accessories.
3. Show message list, typestyles, graphic elements, and layout for each plaque at least half size.

C. Samples: For each exposed product and for each color and texture specified.

D. Plaque Schedule: Use same designations specified or indicated on Drawings or in a plaque or sign schedule.

1.3 INFORMATIONAL SUBMITTALS

A. Sample warranty.

1.4 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.5 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of plaques that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

2.2 PLAQUES

A. Cast Plaque: Plaque with background texture, border, and characters having uniform faces, sharp corners, and precisely formed lines and profiles; and as follows:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. A. R. K. Ramos Signage Systems.
b. Gemini Incorporated.
c. Metal Arts; Division of L & H Mfg. Co.
d. Metallic Arts.

2. Plaque Material: Cast bronze.
3. Plaque Thickness: 0.50 inch.
4. Size: See drawings
5. Finishes:

a. Integral Metal Finish: As selected by Architect from full range of industry finishes.

6. Background Texture: As selected by Architect from manufacturer's full range.
7. Integrally Cast Border Style: Raised flat band.
8. Mounting: Concealed studs.

2.3 MATERIALS

A. Bronze Castings: Lead-free alloy.

2.4 ACCESSORIES

A. Fasteners and Anchors: Manufacturer's standard as required for secure anchorage of plaques, noncorrosive and compatible with each material joined, and complying with the following:

1. Use concealed fasteners and anchors unless indicated to be exposed.
2. For exterior exposure, furnish stainless-steel devices unless otherwise indicated.
3. Exposed Metal-Fastener Components, General:

a. Fabricated from same basic metal and finish of fastened metal unless otherwise indicated.

4. Plaque Mounting Fasteners:

a. Concealed Studs: Concealed (blind), threaded studs welded or brazed to back of plaque, screwed into back of plaque, or screwed into tapped lugs cast integrally into back of plaque, unless otherwise indicated.

2.5 FABRICATION

A. General: Provide manufacturer's standard plaques according to requirements indicated.

1. Provide welds and brazes behind finished surfaces without distorting or discoloring exposed side. Clean exposed welded and brazed connections of flux, and dress exposed and contact surfaces.
2. Conceal connections if possible; otherwise, locate connections where they are inconspicuous.
3. Provide rebates, lugs, and brackets necessary to assemble components and to attach to existing work. Drill and tap for required fasteners. Use concealed fasteners where possible; use exposed fasteners that match plaque finish.
4. Castings: Fabricate castings free of warp, cracks, blowholes, pits, scale, sand holes, and other defects that impair appearance or strength. Grind, wire brush, sandblast, and buff castings to remove seams, gate marks, casting flash, and other casting marks before finishing.

PART 3 - EXECUTION

3.1 INSTALLATION

A. General: Install plaques using mounting methods indicated and according to manufacturer's written instructions.

1. Install plaques level, plumb, true to line, and at locations and heights indicated, with plaque surfaces free of distortion and other defects in appearance.
2. Install plaques so they do not protrude or obstruct according to the accessibility standard.
3. Before installation, verify that plaque surfaces are clean and free of materials or debris that would impair installation.
4. Corrosion Protection: Coat concealed surfaces of exterior aluminum in contact with grout, concrete, masonry, wood, or dissimilar metals, with a heavy coat of bituminous paint.

B. Mounting Methods:

1. Concealed Studs: Using a template, drill holes in substrate aligning with studs on back of plaque. Remove loose debris from hole and substrate surface.

a. Masonry Substrates: Fill holes with adhesive. Leave recess space in hole for displaced adhesive. Place plaque in position and push until flush to surface, embedding studs in holes. Temporarily support plaque in position until adhesive fully sets.
b. Thin or Hollow Surfaces: Place plaque in position and flush to surface, install washers and nuts on studs projecting through opposite side of surface, and tighten.

C. Remove temporary protective coverings and strippable films as plaques are installed.

END OF SECTION 101416

SECTION 101423 - PANEL SIGNAGE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Room-identification signs.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For panel signs.

1. Include fabrication and installation details and attachments to other work.
2. Show sign mounting heights, locations of supplementary supports to be provided by others, and accessories.
3. Show message list, typestyles, graphic elements, including raised characters and Braille, and layout for each sign at least half size.

C. Samples: For each exposed product and for each color and texture specified.

D. Sign Schedule: Use same designations specified or indicated on Drawings or in a sign schedule.

1. Actual Room Names and Room Numbers to be used will be marked-up on shop drawings by the Construction Administrator, during the review process.

1.3 INFORMATIONAL SUBMITTALS

A. Sample warranty.

1.4 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.5 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of signs that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Accessibility Standard: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines for Buildings and Facilities and ICC A117.1 for signs.

2.2 SIGNS

A. Custom Panel Sign: Sign with smooth, uniform surfaces; with message and characters having uniform faces, sharp corners, and precisely formed lines and profiles; and as follows:

1. Illuminated Panel Sign: Interior and Backlighted construction with LED lighting including transformers, insulators, and other accessories for operability, with provision for servicing and concealing connections to building electrical system. Use tight or sealed joint construction to prevent unintentional light leakage. Space lamps apart from each other and away from sign surfaces as needed to illuminate evenly.

    a. Power: As indicated on electrical Drawings.

2. Solid-Sheet Sign Acrylic sheet with finish specified in "Surface Finish and Applied Graphics" Subparagraph below and as follows:

    a. Surface-Applied Graphics: Applied photo image.
    b. Etched and Filled Graphics: Sign face etched or routed to receive enamel-paint infill.
    c. Inset, Cutout Characters: Sign face routed to receive push-through acrylic graphics.

3. Sign-Panel Perimeter: Finish edges smooth.

    a. Edge Condition: Square cut.
    b. Corner Condition in Elevation: Custom.

4. Frame: Entire perimeter with continuous edge retainers.

    a. Material: Aluminum.
    b. Profile: Custom.
    c. Corner Condition in Elevation: Custom.
    d. Finish and Color: As selected by Architect from manufacturer's full range.

5. Mounting: Projecting from wall with concealed anchors.
6. Surface Finish and Applied Graphics:
    a. Photo-Image Graphics: Manufacturer's standard multicolor, 600-dpi halftone or dot-screen image.
    b. Overcoat: Manufacturer's standard.

B. Room-Identification Sign (Provide at each entry door to all rooms:

1. Basis-of-Design Product: 2/90 Sign Systems; Slide Modular Sign System or equal.

2. Mounting: Manufacturer's standard method for substrates indicated.

2.3 ACCESSORIES

A. Fasteners and Anchors: Manufacturer's standard as required for secure anchorage of signage, noncorrosive and compatible with each material joined, and complying with the following:

1. Use concealed fasteners and anchors unless indicated to be exposed.
2. For exterior exposure, furnish stainless-steel devices unless otherwise indicated.
3. Exposed Metal-Fastener Components, General:

    a. Fabricated from same basic metal and finish of fastened metal unless otherwise indicated.

4. Sign Mounting Fasteners:

    a. Concealed Studs: Concealed (blind), threaded studs welded or brazed to back of sign material or screwed into back of sign assembly, unless otherwise indicated.
    b. Projecting Studs: Threaded studs with sleeve spacer, welded or brazed to back of sign material or screwed into back of sign assembly, unless otherwise indicated.
    c. Through Fasteners: Exposed metal fasteners matching sign finish, with type of head indicated, installed in predrilled holes.

B. Adhesives: As recommended by sign manufacturer and that comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

C. Two-Face Tape: Manufacturer's standard high-bond, foam-core tape, 0.045 inch thick, with adhesive on both sides.

PART 3 - EXECUTION

3.1 INSTALLATION

A. General: Install signs using mounting methods indicated and according to manufacturer's written instructions.

1. Install signs level, plumb, true to line, and at locations and heights indicated, with sign surfaces free of distortion and other defects in appearance.
2. Install signs so they do not protrude or obstruct according to the accessibility standard.
3. Before installation, verify that sign surfaces are clean and free of materials or debris that would impair installation.
4. Corrosion Protection: Coat concealed surfaces of exterior aluminum in contact with grout, concrete, masonry, wood, or dissimilar metals, with a heavy coat of bituminous paint.

B. Mounting Methods (as applicable):

1. Concealed Studs: Using a template, drill holes in substrate aligning with studs on back of sign. Remove loose debris from hole and substrate surface.

    a. Masonry Substrates: Fill holes with adhesive. Leave recess space in hole for displaced adhesive. Place sign in position and push until flush to surface, embedding studs in holes. Temporarily support sign in position until adhesive fully sets.
    b. Thin or Hollow Surfaces: Place sign in position and flush to surface, install washers and nuts on studs projecting through opposite side of surface, and tighten.

2. Projecting Studs: Using a template, drill holes in substrate aligning with studs on back of sign. Remove loose debris from hole and substrate surface.

    a. Masonry Substrates: Fill holes with adhesive. Leave recess space in hole for displaced adhesive. Place spacers on studs, place sign in position, and push until spacers are pinched between sign and substrate, embedding the stud ends in holes. Temporarily support sign in position until adhesive fully sets.
    b. Thin or Hollow Surfaces: Place spacers on studs, place sign in position with spacers pinched between sign and substrate, and install washers and nuts on stud ends projecting through opposite side of surface, and tighten.

3. Through Fasteners: Drill holes in substrate using predrilled holes in sign as template. Countersink holes in sign if required. Place sign in position and flush to surface. Install through fasteners and tighten.
4. Brackets: Remove loose debris from substrate surface and install backbar or bracket supports in position so that signage is correctly located and aligned.
5. Adhesive: Clean bond-breaking materials from substrate surface and remove loose debris. Apply linear beads or spots of adhesive symmetrically to back of sign and of suitable quantity to support weight of sign after cure without slippage. Keep adhesive away from edges to prevent adhesive extrusion as sign is applied and to prevent visibility of cured adhesive at sign edges. Place sign in position, and push to engage adhesive. Temporarily support sign in position until adhesive fully sets.
6. Two-Face Tape: Clean bond-breaking materials from substrate surface and remove loose debris. Apply tape strips symmetrically to back of sign and of suitable quantity to support weight of sign without slippage. Keep strips away from edges to prevent visibility at sign edges. Place sign in position, and push to engage tape adhesive.

C. Remove temporary protective coverings and strippable films as signs are installed.

SECTION 102800 - TOILET, BATH, AND LAUNDRY ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Public-use washroom accessories.
2. Under-lavatory guards.
3. Custodial accessories.
4. Hand dryers

B. Owner-Furnished Material.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

B. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required.

1. Identify locations using room designations indicated.
2. Identify products using designations indicated.

1.3 INFORMATIONAL SUBMITTALS

A. Warranty: Sample of special warranty.

1.4 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.5 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

1.6 WARRANTY

A. Special Mirror Warranty: Manufacturer's standard form in which manufacturer agrees to replace mirrors that develop visible silver spoilage defects and that fail in materials or workmanship within specified warranty period.

1. Warranty Period: 15 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PUBLIC-USE WASHROOM ACCESSORIES

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. American Specialties, Inc.
2. Bobrick Washroom Equipment, Inc.
3. Bradley Corporation.
4. Saniflow Corp.
5. World Dryer

B. Grab Bar:

1. Basis-of-Design Product: ASI 164 Satin Finish.
2. Mounting: Flanges with concealed fasteners.
3. Material: Stainless steel, 0.05 inch thick.

a. Finish: Smooth, No. 4 finish (satin) on ends and slip-resistant texture in grip area.

4. Outside Diameter: 1-1/2 inches.
5. Configuration and Length: As indicated on Drawings.

C. Mirror Unit:

1. Basis-of-Design Product: ASI #0600 B1836 Tempered Glass Welder-Frame mirror.
2. Frame: Stainless-steel angle, 3/4” inch thick.

a. Corners: Welded and ground smooth.

3. Hangers: Produce rigid, tamper- and theft-resistant installation, using method indicated below.

a. One-piece, galvanized-steel, wall-hanger device with spring-action locking mechanism to hold mirror unit in position with no exposed screws or bolts.
b. Wall bracket of galvanized steel, equipped with concealed locking devices requiring a special tool to remove.

4. Size: 18x36

D. Soap Dispenser: FURNISHED BY OWNER INSTALLED BY CONTRACTOR

E. Toilet Tissue Dispenser: FURNISHED BY OWNER INSTALLED BY CONTRACTOR

2.2 WARM-AIR DRYERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. American Specialties, Inc.
2. Bobrick Washroom Equipment, Inc.
3. Bradley Corporation.
4. World Dryer Corporation.

B. Warm-Air Dryer:

1. Basis-of-Design Product: Excel Dryer Corporation; ThinAir Hand Dryer series.
2. Mounting: Surface mounted.
3. Operation: Electronic-sensor activated with timed power cut-off switch.
4. Electrical Requirements: 110-120 V, 7-7.8A, 750-920 W.
5. Finish: Brushed Stainless Steel
6. Noise Reduction Nozzle

2.3 UNDER-LAVATORY GUARDS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Plumberex Specialty Products, Inc.
2. Truebro by IPS Corporation.

B. Under-lavatory Guard:

1. Basis-of-Design Product: Truebro LA Guard 2.
2. Description: Insulating pipe covering for supply and drain piping assemblies that prevent direct contact with and burns from piping; allow service access without removing coverings.
3. Material and Finish: Antimicrobial, molded plastic, white.

2.4 CUSTODIAL ACCESSORIES

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. American Specialties, Inc.
2. Bobrick Washroom Equipment, Inc.
3. Bradley Corporation.

B. Mop and Broom Holder:

1. Basis-of-Design Product: ASI 0796-3 Mop Rack Surface mounted.
2. Description: Unit with 3 serrated rubber cam for grasping.
3. Length: 26 inches
4. Mop/Broom Holders: Three, spring-loaded, rubber hat, cam type.
5. Material and Finish: 20 Ga. Type 304 Stainless steel, No. 4 finish (satin). Projects 1/2" from wall.

2.5 FABRICATION

A. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of six keys to Owner's representative.

2.6 SHOWER CURTAIN

A. Vinyl Shower Curtain: Bobrick, Bradley or ASI - Opaque, matte white vinyl 0.008" (0.2mm) thick, containing antibacterial and flame-retardant agents. Nickel-plated brass grommets along top, one every 6" (150mm). bottom and sides are hemmed. Provide stainless steel curtain hooks. Install stainless steel curtain rod with concealed mounting. Verify size on drawings.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.

B. Grab Bars: Install to withstand a downward load of at least 250 lbf, when tested according to ASTM F 446.

END OF SECTION 102800

SECTION 104413 - FIRE PROTECTION CABINETS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes fire-protection cabinets for portable fire extinguishers.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For fire-protection cabinets.

1.3 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.4 COORDINATION

A. Coordinate size of fire-protection cabinets to ensure that type and capacity of fire extinguishers indicated are accommodated.

B. Coordinate sizes and locations of fire-protection cabinets with wall depths.

PART 2 - PRODUCTS

2.1 FIRE-PROTECTION CABINET

A. Basis-of-Design Product : Subject to compliance with requirements, provide JL Industries, Inc.; 1537 “Clear VU FX2” or comparable product by one of the following:

1. Larsen’s Manufacturing Co.

B. Cabinet Construction: Nonrated.

C. Cabinet Material: Cold-rolled steel sheet.

D. Semirecessed Cabinet: One-piece combination trim and perimeter door frame overlapping surrounding wall surface with exposed trim face and wall return at outer edge (backbend).

1. Rolled-Edge Trim: 3 inch backbend depth.

E. Cabinet Trim Material: Stainless-steel sheet.

F. Door Material: Stainless-steel sheet.

G. Door Style: Full acrylic bubble with frame.

H. Door Glazing: Molded acrylic bubble.

1. Acrylic Bubble Color: Clear, transparent.

I. Door Hardware: Manufacturer's standard door-operating hardware of proper type for cabinet type, trim style, and door material and style indicated.

J. Accessories:

1. Door Lock: Cam lock that allows door to be opened during emergency by pulling sharply on door handle.
2. Identification: Lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as indicated.

a. Identify fire extinguisher in fire-protection cabinet with the words "FIRE EXTINGUISHER."

1) Location: Applied to cabinet glazing.
2) Application Process: Diecut vinyl letters.
3) Lettering Color: Red.
4) Orientation: Vertical.

K. Materials:

1. Cold-Rolled Steel: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B.

a. Finish: Baked enamel or powder coat.
b. Color: White.

2. Stainless Steel: ASTM A 666, Type 304.

a. Finish: No. 4 directional satin finish.

2.2 FABRICATION

A. Fire-Protection Cabinets: Provide manufacturer's standard box (tub) with trim, frame, door, and hardware to suit cabinet type, trim style, and door style indicated.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Prepare recesses for semirecessed fire-protection cabinets as required by type and size of cabinet and trim style.

B. Install fire-protection cabinets in locations and at mounting heights indicated or, if not indicated, at heights acceptable to authorities having jurisdiction.

C. Fire-Protection Cabinets: Fasten cabinets to structure, square and plumb.

D. Identification: Apply vinyl lettering at locations indicated.

E. Adjust fire-protection cabinet doors to operate easily without binding. Verify that integral locking devices operate properly.

END OF SECTION 104413

SECTION 104413 – FIRST AID CABINETS

PART 1 – GENERAL

1.1 SUMMARY

A. Provide wall-mounted first aid cabinets fully stocked with ANSI/ISEA Z308.1 Class B compliant contents, sized to serve up to 200 occupants.
B. Cabinets shall be installed in areas to provide immediate access to medical supplies in case of injury or emergency. Verify the location of installation with owner.

1.2 RELATED SECTIONS

A. Section 08 71 00 – Door Hardware (if coordinated with lockable safety cabinets).
B. Section 09 90 00 – Painting and Coating (for wall finish compatibility).
C. Section 10 44 00 – Safety Specialties.

1.3 REFERENCES

A. ANSI/ISEA Z308.1 – Minimum Requirements for Workplace First Aid Kits and Supplies, Class B.
B. OSHA 29 CFR 1910.151 – Medical Services and First Aid.
C. NFPA 101 – Life Safety Code.
D. ADA Standards for Accessible Design – Reach ranges for operable parts.

1.4 SUBMITTALS

A. Product Data: Manufacturer’s catalog data and installation instructions.
B. Certificates of Compliance: Documenting that contents meet ANSI/ISEA Z308.1 Class B.
C. Warranty Documentation.
D. Operation and Maintenance Data: Manufacturer’s recommendations for restocking, replacement intervals, and maintenance.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver in manufacturer’s unopened packaging with contents intact, sterile items sealed, and expiration dates visible.
B. Store in a clean, dry, and secure location protected from humidity and extreme temperatures.

1.6 WARRANTY

A. Manufacturer’s standard warranty for material and workmanship, not less than one year.

PART 2 – PRODUCTS

2.1 BASIS OF DESIGN: Subject to compliance with requirements, provide First Aid Only Model 90577 Class B or comparable products by one of the following.

A. First Aid Only – Model No. 90577, ANSI Class B, 200+ Person Kit.
B. Medique Products – Large Industrial First Aid Cabinet, 200+ Person Capacity.
C. Cintas First Aid & Safety – Large Wall-Mounted First Aid Cabinet.

2.2 MATERIALS

A. Cabinet:
1. Steel construction with white baked enamel or powder-coated finish.
2. Size: Minimum 20 in. H x 15 in. W x 6 in. D.
3. Lockable door with positive latching hardware.
4. Adjustable shelves for organized storage.
5. Cabinet front labeled “FIRST AID” in bold red or green letters.
6. Wall-mounting hardware provided.

B. CONTENTS:

Provide ANSI/ISEA Z308.1 Class B minimum required items expanded for 200-person capacity, including but not limited to:
1. Adhesive bandages, 1” x 3”, 300 count.
2. Adhesive tape rolls, 6 count.
3. Sterile gauze pads, 3” x 3” and 4” x 4”, 50 count each.
4. Large trauma dressings, 5 count.
5. Triangular bandages with safety pins, 6 count.
6. Antiseptic wipes, 100 count.
7. Antibiotic ointment packets, 50 count.
8. Burn treatment gel packets, 25 count.
9. Instant cold packs, 6 count.
10. Eye wash bottles, 4 oz minimum, 2 count.
11. Eye pads, 10 count.
12. Scissors, 1 each.
13. Tweezers, 1 each.
14. CPR mask or shield with one-way valve, 1 each.
15. Exam gloves, nitrile, latex-free, 10 pair.
16. First aid instruction guide, 1 each.

C. PERFORMANCE:

1. Stocked to meet needs of up to 200 persons.
2. All items clearly labeled, individually packaged, and within manufacturer's expiration dates.
3. Contents organized for quick identification and access during emergencies.

PART 3 – EXECUTION

3.1 EXAMINATION

A. Verify walls are suitable to support cabinet weight when fully stocked.
B. Coordinate installation height and location with Owner and ADA accessibility standards.

3.2 INSTALLATION

A. Install cabinet in locations designated by Owner, typically near:
1. School nurse's office.
2. Gymnasium or athletic training areas.
3. Cafeteria or assembly spaces.
B. Mount cabinets securely to wall framing or blocking.
C. Install with operable parts not higher than 48 inches above finished floor.

3.3 FIELD QUALITY CONTROL

A. Inspect installed units to verify secure anchorage, proper labeling, and full stock.
B. Confirm expiration dates of all perishable items are valid beyond date of Substantial Completion.

3.4 ADJUSTING AND CLEANING

A. Remove protective coverings and clean surfaces upon completion.
B. Provide Owner with two sets of cabinet keys if lockable.

3.5 MAINTENANCE

A. Provide Owner with restocking list, recommended service intervals, and supplier contact.
B. Train Owner's staff (school nurse, maintenance, or safety officer) on inspection and replenishment procedures.

END OF SECTION

SECTION 104416 - FIRE EXTINGUISHERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes portable, hand-carried fire extinguishers and mounting brackets for fire extinguishers.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.3 INFORMATIONAL SUBMITTALS

A. Warranty: Sample of special warranty.

1.4 CLOSEOUT SUBMITTALS

A. Operation and maintenance data.

1.5 COORDINATION

A. Coordinate type and capacity of fire extinguishers with fire-protection cabinets to ensure fit and function.

1.6 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace fire extinguishers that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Six years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. NFPA Compliance: Fabricate and label fire extinguishers to comply with NFPA 10, "Portable Fire Extinguishers."

B. Fire Extinguishers: Listed and labeled for type, rating, and classification by an independent testing agency acceptable to authorities having jurisdiction.

2.2 PORTABLE, HAND-CARRIED FIRE EXTINGUISHERS

A. Fire Extinguishers: Type, size, and capacity for each fire-protection cabinet and mounting bracket indicated.

1. Basis-of-Design Product: Subject to compliance with requirements, provide JL Industries, Inc.; Cosmic 10E or comparable product by one of the following:
   a. Ansul Incorporated.
   b. Guardian Fire Equipment, Inc.
   c. Kidde Residential and Commercial Division; Subsidiary of Kidde plc.
   d. Larsens Manufacturing Company.

2. Instruction Labels: Include pictorial marking system complying with NFPA 10, Appendix B, and bar coding for documenting fire-extinguisher location, inspections, maintenance, and recharging.

2.3 MOUNTING BRACKETS

A. Basis-of-Design Product: Subject to compliance with requirements, provide JL Industries, Inc.; MB846A or comparable product by one of the following:

1. Ansul Incorporated.
2. Guardian Fire Equipment, Inc.
3. JL Industries, Inc.; a division of the Activar Construction Products Group.
4. Larsens Manufacturing Company.

B. Identification: Lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as indicated by Architect.

1. Identify bracket-mounted fire extinguishers with the words "FIRE EXTINGUISHER" in red letter decals applied to mounting surface.

   a. Orientation: Vertical.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Examine fire extinguishers for proper charging and tagging.

1. Remove and replace damaged, defective, or undercharged fire extinguishers.

B. Install fire extinguishers and mounting brackets in locations indicated and in compliance with requirements of authorities having jurisdiction.

1. Mounting Brackets: 48 inches above finished floor to top of fire extinguisher.

C. Mounting Brackets: Fasten mounting brackets to surfaces, square and plumb, at locations indicated.

END OF SECTION 104416

SECTION 105113 - METAL LOCKERS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Welded corridor lockers.

1.2 ACTION SUBMITTALS

A. Product data.

B. Shop Drawings: Include plans, elevations, sections, details, attachments to other work, and locker identification system and numbering sequence.

C. Samples: For each color specified.

1.3 INFORMATIONAL SUBMITTALS

A. Sample warranties.

1.4 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.5 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of metal lockers that fail in materials or workmanship, excluding finish, within specified warranty period.

1. Warranty Period for Welded Metal Lockers: [**Lifetime**] from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Accessibility Requirements: For lockers indicated to be accessible, comply with applicable provisions in [**ADA-ABA Accessibility Guidelines**].

2.2 WELDED CORRIDOR LOCKERS

A. Basis-of-Design Product: Subject to compliance with requirements, provide [**Double Tier Welded Lockers**] <**List Industries Inc.**> or comparable product by one of the following:

1. **Lyon LLC.**
2. **Penco Products.**
3. **DeBourgh Mfg. Co.**
4. **Hadrian Mfg. Inc.**

B. Doors: One piece; fabricated from 0.075-inch (1.90-mm) nominal-thickness steel sheet; formed into channel shape with double bend at vertical edges and with right-angle single bend at horizontal edges.

1. Reinforcement: Manufacturer's standard reinforcing angles, channels, or stiffeners for doors more than 12 inches wide; welded to inner face of doors.
2. Door Style:[**Unperforated panel.**]

C. Body: Assembled by welding body components together. Fabricate from unperforated steel sheet with thicknesses as follows:

1. Tops, Bottoms, and Sides: 0.060-inch (1.52-mm) nominal thickness.
2. Backs: 0.048-inch (1.21-mm) nominal thickness.
3. Shelves: 0.060-inch (1.52-mm) nominal thickness, with double bend at front and single bend at sides and back.

D. Frames: Channel formed; fabricated from 0.060-inch (1.52-mm) nominal-thickness steel sheet; lapped and factory welded at corners; with top and bottom main frames factory welded into vertical main frames. Form continuous, integral, full-height door strikes on vertical main frames.

E. Hinges:

1. Continuous Hinges: Manufacturer's standard, steel, full height.

F. Recessed Door Handle and Latch: Stainless-steel cup with integral door pull, recessed so locking device does not protrude beyond door face; pry and vandal resistant.

1. Single-Point Latching: Nonmoving latch hook [**designed to engage bolt of built-in combination or cylinder lock**] [**with steel padlock loop that projects through recessed cup and is finished to match metal locker body**]. Equip each door with one latch hook.

G. Locks: [**Combination padlocks**]

H. Identification Plates: Manufacturer's standard, etched, embossed, or stamped [**aluminum**] plates, with numbers and letters at least 3/8 inch (9 mm) high.

I. Hooks: Manufacturer's standard ball-pointed type, aluminum or steel; zinc plated.

J. Coat Rods: Manufacturer's standard.

K. Continuous Zee Base: Fabricated from, [**manufacturer's standard thickness, but not less than 0.060-inch (1.52-mm)**] nominal-thickness steel sheet.

1. Height: [**4 inches (102 mm)**].

L. Continuous Sloping Tops: Fabricated from 0.048-inch (1.21-mm) nominal-thickness steel sheet, with a pitch of approximately 20 degrees.

1. Closures: [**Vertical**]-end type.

M. Recess Trim: Fabricated from 0.048-inch (1.21-mm) nominal-thickness steel sheet.

N. Filler Panels: Fabricated from 0.048-inch (1.21-mm) nominal-thickness steel sheet.

O. Boxed End Panels: Fabricated from 0.048-inch (1.21-mm) nominal-thickness steel sheet.

P. Materials:

1. Metallic-Coated Steel Sheet: ASTM A 653/A 653M, Commercial Steel (CS), Type B; with A60 (ZF180) zinc-iron, alloy (galvannealed) coating designation.

Q. Finish: Baked enamel or powder coat.

1. Color: [**As selected by Architect from manufacturer's full range**].

2.3 FABRICATION

A. Fabricate metal lockers square, rigid, without warp, and with metal faces flat and free of dents or distortion. Make exposed metal edges safe to touch and free of sharp edges and burrs.

B. Fabricate each metal locker with an individual door and frame; individual top, bottom, and back; and common intermediate uprights separating compartments. Factory weld frame members of each metal locker together to form a rigid, one-piece assembly.

C. Equipment: Provide each locker with an identification plate and the following equipment:

1. Double-Tier Units: One double-prong ceiling hook and two single-prong wall hooks.
2. Coat Rods: [**For each compartment of each locker**]

D. Welded Construction: Factory preassemble metal lockers by welding all joints, seams, and connections; with no bolts, nuts, screws, or rivets used in assembly of main locker groups. Factory weld main locker groups into one-piece structures. Grind exposed welds flush.

E. Accessible Lockers: Fabricate as follows:

1. Where hooks, coat rods, or additional shelves are provided, locate no higher than 48 inches (1219 mm) above the floor.

F. Continuous Base: Formed into channel or zee profile for stiffness, and fabricated in lengths as long as practical to enclose base and base ends of metal lockers; finished to match lockers.

G. Continuous Sloping Tops: Fabricated in lengths as long as practical, without visible fasteners at splice locations; finished to match lockers.

H. Recess Trim: Fabricated with minimum 2-1/2-inch (64-mm) face width and in lengths as long as practical; finished to match lockers.

I. Filler Panels: Fabricated in an unequal leg angle shape; finished to match lockers. Provide slip-joint filler angle formed to receive filler panel.

J. Boxed End Panels: Fabricated with 1-inch- (25-mm-) wide edge dimension, and designed for concealing fasteners and holes at exposed ends of nonrecessed metal lockers; finished to match lockers.

K. Finished End Panels: Designed for concealing unused penetrations and fasteners, except for perimeter fasteners, at exposed ends of nonrecessed metal lockers; finished to match lockers.

L. Center Dividers: Full-depth, vertical partitions between bottom and shelf; finished to match lockers.

PART 3 - EXECUTION

3.1 INSTALLATION

A. General: Install lockers level, plumb, and true; shim as required, using concealed shims.

1. Anchor locker runs at ends and at intervals recommended by manufacturer, but not more than 36 inches (910 mm) o.c. Using concealed fasteners, install anchors through backup reinforcing plates, channels, or blocking as required to prevent metal distortion.
2. Anchor single rows of metal lockers to walls near top [**and bottom of lockers**].
3. Anchor back-to-back metal lockers to floor.

B. Welded Lockers: Connect groups together with standard fasteners, with no exposed fasteners on face frames.

C. Trim: Fit exposed connections of trim, fillers, and closures accurately together to form tight, hairline joints, with concealed fasteners and splice plates.

1. Attach recess trim to recessed metal lockers with concealed clips.
2. Attach filler panels with concealed fasteners.
3. Attach sloping-top units to metal lockers, with closures at exposed ends.

END OF SECTION 105113

SECTION 114000 – FOODSERVICE EQUIPMENT

PART 1 - GENERAL

1.1 GENERAL REQUIREMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 STANDARDS

A. Equipment and installation thereof shall meet all requirements of applicable portions of latest editions of Standards listed below.

1. American Society for Testing Materials (ASTM)
2. National Electrical Code (NEC)
3. American Gas Association (AGA)
4. Louisiana State Board of Health
5. National Sanitation Foundation (NSF)
6. Factory Mutual (FM)
7. Underwriters Laboratory (UL)
8. Occupational Safety and Health Administration (OSHA)
9. National Fire Protection Association (NFPA)
10. International Building Code (IBC)
11. American Disabilities Act (ADA)

1.3 DESCRIPTION OF WORK

A. Work in this Section includes the following:

1. Furnishing, delivery, un-crating, setting in place at locations indicated on Drawings. Installation to include mounting, leveling, adjusting, and cleaning all equipment specified herein.
2. Apply permanent foot/caster placement markings to building floor at all cooking equipment requiring coverage of fire suppression system in accordance with NFPA-96 codes.
3. All components required for a complete assembly to serve intended function when connected to mechanical and electrical services.
4. Coordination of all Work required for a complete installation with other trades and subcontractors.
5. Field verification of plumbing and electrical rough-ins by Food Service Equipment Contractor to ensure requirements and locations are correct. Said verification shall include all electrical characteristics (amperage, voltage, and phase) for all Existing, Contractor-Furnished, and Owner-Furnished Equipment. Field verification shall commence prior to release of equipment order and pouring of concrete slab by General Contractor.
6. Sink faucets, strainers, vacuum breakers, duo drains, lever handle drains and tailpieces specified under heading entitled Fabrication Standards.

7. Furnishing and mounting of all electrical starting switches, controls, light fixtures, and receptacles included in Itemized Equipment Specifications or as required for operation of equipment specified herein.
8. Cutting of all holes in equipment tops, shelves and bodies required for piping (gas, water and drains) and wiring.
9. Threaded hanger rods with brackets and turn buckles required to support Exhaust Hoods.
10. Threaded hanger rods with brackets and turn buckles required to support walk-in cooler and/or freezer ceiling panels (where applicable).

B. Related Work Specified Elsewhere:

1. Water/gas piping, line shut-off valves and final connections to equipment.
2. Drain piping, floor drains, floor sinks, “P” traps, grease traps and final connections to equipment.
3. Electrical wiring, overload protection devices, line-disconnect switches, and final connections to equipment.
4. Install cord/plug assemblies provided by Food Service Equipment Contractor.
5. Concrete pad for remote walk-in cooler/freezer condensing unit package located outside building.
6. Exhaust/supply fans (including magnetic starters/ductwork/roof curb) and welding exhaust ducts to exhaust duct collars of exhaust hoods to meet applicable fire codes.
7. Air balancing of exhaust/supply fans of Exhaust Hoods to meet project requirements.
8. Structural framing where required at hanger rod locations to support Exhaust Hoods and/or Walk-In Coolers and/or Freezers.
9. Wall blocking for support of wall-mounted equipment (where applicable).

1.4 DRAWINGS AND SPECIFICATIONS

A. Specifications and drawings shall be considered as a part of the Contract to be executed. Intent of said Drawings and Specifications is for all components required for a complete installation of food service equipment specified.

B. Should any error, omission or conflict occur in Drawings and Specifications, Contractor shall not avail himself of such error, omission or conflict but shall have same explained and adjusted prior to signing the Contract.

C. All addenda shall be considered as a part of original Contract Documents.

1.5 QUALITY AND WORKMANSHIP

A. All equipment shall be constructed in strict compliance with standards of National Sanitation Foundation and shall bear the NSF label. All equipment shall meet all standards set by state and local regulations.

B. All electrical equipment shall be approved by Underwriter's Laboratories and shall bear its seal of approval.

C. All electrical components of equipment shall meet requirements of National Electric Code.

D. All material shall be new (latest model at time of delivery) and of first quality. All equipment shall be installed in an undamaged condition. Where brands, materials, apparatus or equipment is specifically designated, no substitution shall be made without prior approval in writing.

E. Provide all Work in best manner in conformity with best standard practices. Employ qualified, efficient and skillful workers for installation in a first-class manner.

F. It is required that custom fabricated equipment be fabricated by a Food Service Equipment Fabricator who has plant, personnel and engineering facilities to design, detail and manufacture high quality equipment.

1.6 FOOD SERVICE EQUIPMENT CONTRACTOR QUALIFICATIONS

A. Contractor shall possess experience and ability to perform the necessary services for a complete and workmanlike installation of food service equipment.

B. Contractor experience shall include a minimum of five (5) years' experience as a successful Food Service Equipment Contractor and shall have successfully completed installation of at least five (5) comparable projects of similar size and nature.

C. Contractor's in-house capabilities shall include preparation of dimensioned mechanical/electrical rough-in Drawings, experienced personnel to coordinate with other trades the proper equipment installation, warranty services, and proper demonstration of equipment on operation, service and maintenance.

1.7 SUBMITTALS

A. Submittals shall include product data (manufacturer's specification sheets) of standard-manufactured equipment, shop drawings of custom-fabricated equipment and equipment modified to meet project requirements, and dimensioned mechanical and electrical rough-in drawings of equipment utility requirements. Partial submittals will be given no consideration.

1. Product data shall be submitted in electronic pdf format unless stated otherwise in Contract Documents and shall be in numerical order (by equipment item numbers). Each manufacturer's specification sheet shall be preceded with a type-written sheet that includes equipment description, quantity, brand/model number, accessories, and modifications to meet project requirements.
2. Shop drawings are not to be based upon reproduction of Contract Document drawings. Shop drawings shall be submitted in electronic pdf format unless stated otherwise in Contract Documents. Shop drawings for custom-fabricated equipment shall be drawn at a minimum scale of ¾" to the foot with cross-sections drawn at 1-1/2" to the foot. Sheet sizes shall be same size as sheet sizes of Contract Document drawings, not to exceed 30" x 42".
3. Equipment floor plan, mechanical, and electrical rough-in drawings are not to be based upon reproduction of Contract Document drawings. Drawings shall be submitted in electronic pdf format. Rough-in drawings shall show utility requirements of equipment specified, existing equipment to be re-used, future equipment (including vendor-furnished equipment), area clean-up floor drains, and electrical convenient outlets shown on Contract Document drawings. Rough-in requirements shall be accurately drawn to scale with

dimensions from centerline of columns or finished walls. Contractor shall be responsible for determining exact locations on building walls and floors and not connection points on equipment. Contractor shall visit project site to verify correct locations of utility stub-outs and floor recesses/block-outs prior to pouring of concrete slab and report discrepancies found to Architect and/or Consultant. Refer to certification requirements of Description of Work of this section.

4. Contractor shall be responsible for taking all field dimensions which affect equipment and installation thereof. At the time of taking field measurements and observation of existing conditions, Contractor shall report in writing to Architect all work performed by other trades which will prevent him from execution of his work required by Contract Documents and shall obtain Architect's instructions before proceeding with his work.

1.8 PROTECTION OF WORK AND MATERIALS

A. Contractor shall at all times cover and protect his Work, material and equipment to save same from damage. Contractor shall at all times exercise due care to protect the work of others. Cost of any repair or replacement of damaged Work, material and equipment shall be borne by Contractor.

1.9 BRANDS AND TRADE NAMES

A. Contractors are cautioned that only food service equipment and related items manufactured in accordance with Specifications will be acceptable. Where brand names and model numbers are specified, it is not intended that competition be limited, but to set standards of performance, design, capacity, durability and appearance. Bidders desiring to quote and/or supply brands of equipment other than those specified shall submit a written request to Architect with a copy to Consultant seven (7) days prior to bid date in order that such substitutions can be considered for approval and if approved, an addendum issued to all plan holders. It is understood that approval of substitutions does not relieve Contractor from furnishing equipment to meet intent and requirements of Specifications. Approval of substitutions does not relieve Contractor from additional costs of mechanical and electric utilities and other requirements not included in Contract Documents.

1.10 WARRANTIES

A. Contractor shall provide a one (1) Year Warranty from date of Substantial Completion or occupancy on all Work provided under these Specifications. Warranty shall cover replacement of defective material, transportation and labor, but does not include costs of replacement parts and labor caused by Owner's carelessness or misuse of equipment. An additional four (4) year warranty (labor included) shall be provided on all refrigeration compressors. Contractor shall provide a reputable and qualified service agency, located within fifty (50) miles of Project site, to provide immediate service for all refrigeration equipment.

PART 2 - PRODUCTS

2.1 CUSTOM FABRICATED EQUIPMENT MANUFACTURERS

A. Equipment manufacturers shall be Low Temp Industries, Inc.; Atlanta Custom Fabricators; and Stainless & Aluminum Fabrication, or a prior approved equivalent.

B. All fabricated equipment shall be manufactured by one (1) manufacturer to ensure uniformity in design and finish.

2.2 ELECTRICAL REQUIREMENTS

A. Refer to Drawings for specific requirements.

B. Fixtures wired for three-phase shall have loads balanced as equally as possible.

2.3 SWITCHES AND CONTROLS

A. A suitable control switch or starter of proper type in accordance with Underwriter's Code shall be supplied for each motorized appliance or electrically- heated unit.

B. Said switches and controls shall be mounted in recessed die-stamped stainless steel cups or otherwise indented to prevent damage.

2.4 METAL FABRICATION STANDARDS

A. Materials:

1. All stainless steel shall be type 302 or 304 with 18% chromium, 8% nickel and a maximum of 0.12% carbon. All sheets shall have a No. 4 finish with colors and finish uniform throughout.

B. Welding:

1. All welded parts shall be non-porous and free from imperfections, pits, cracks or discolorations.
2. Stainless steel joints and seams shall be heli-arc welded ground smooth and polished to a No. 4 finish. Tinning of welds is not acceptable. All welds shall be ground smooth and polished to original finish of metal.

C. Field Joints:

1. Field joints shall be located for practical construction with sizes convenient for shipping and entry into building spaces.
2. All field joints shall be fully (continuous) welded with same type metal, ground smooth and polished to original finish of metal.

D. Table and Counter Tops:

1. All tops, unless otherwise specified, shall be constructed of 14-gauge stainless steel. Exterior edges not adjacent to walls or other equipment shall be turned down on a 90-degree angle or rolled down 1-3/4" with corners bullnosed. Tops adjacent to walls shall be turned up 6" and back 1" (minimum) on a 90-degree angle to form a backsplash. Tops

adjacent to other equipment shall be flanged straight down 1-3/4". Sound deadening material shall be provided between frame members and stainless steel tops.

2. Edges of dishtable tops not adjacent to walls shall be turned up 3" and rolled down 1-1/2" with corners bullnosed. Dishtable tops adjacent to walls shall be turned up 10", back 2-1/2" on a 45-degree angle and down 2" to form a pipe chase. All horizontal edges and internal corners of dishtable tops shall be coved on a 5/8" minimum radius. Ends of backsplashes shall be closed, welded, ground smooth and polished.
3. Edges of preparation counter tops (with sinks) not adjacent to walls shall be turned up 7/8" on a 45-degree angle and turned down on a 90-degree angle or rolled down 2-5/8" to form a marine roll unless specified otherwise. Preparation counter tops (with sinks and cantilevered overshelf uprights) adjacent to walls shall be turned up 10", back 2-1/4" on a 45-degree angle and turned down 1" on 90-degree angle to form a backsplash with pipe chase. All horizontal edges and internal corners of preparation counter tops shall be coved on a 5/8" minimum radius. Ends of backsplashes shall be closed, welded, ground smooth and polished. Backsplashes of counter tops with sinks shall be pierced on 8" centers over sinks.
4. All tops shall be reinforced on the underside with 12-gauge (minimum) stainless steel hat channels running from front to back with center bracing where required to hold tops flat. Channels shall be stud welded and bolted to underside of tops with legs, bodies and drawer housings secured to channels so that bolts or rivets will not extend through work tops. Holes required for counter equipment shall be neatly die-punched with raised edges.

E. Backsplashes:

1. Backsplashes of table and countertop with 90-degree turnbacks adjacent to walls shall be turned down 1" at 90-degrees and secured to building walls with 4" long 14-gauge stainless steel "zee" clips on 36" centers. Cracks between backsplashes and building walls shall be sealed with clear silicone sealant.
2. Backsplashes of preparation counters and dishtables with 45-degree turnbacks adjacent to walls shall be turned down 1" at 135-degrees and secured to walls with 4" long 14-gauge stainless steel "zee" clips on 36" centers. Cracks between backsplashes and building walls shall be sealed with clear silicone sealant.

F. Open Bases:

1. Open bases shall be constructed of 1-5/8" OD 16-gauge stainless steel tubular uprights and crossbraces fully welded together, ground smooth and polished. Top of crossbraces shall be 12" above floor. Refer to Drawings for arrangement of crossbraces. Uprights shall be fitted at floor with adjustable, sanitary stainless steel bullet feet inserted into uprights with inside threads to eliminate any possibility of threading collecting dirt and other matter. Tops of legs shall be fitted into die-stamped fully enclosed stainless steel gussets equivalent to Component Hardware No. A20-0206-C welded to reinforcing channels on underside of stainless steel tops.
2. Tables 6'-0" long and under shall have four (4) legs, and tables 7'-0" long shall have six (6) legs. Legs shall be spaced not more than 5' 0" apart unless specified otherwise.

G. Undershelves:

1. All undershelves shall be constructed of 18-gauge stainless steel.

2. Undershelves on open base tables shall be sectional, removable and rolled down over crossbraces, unless specified in Itemized Equipment Specifications. Shelves adjacent to walls and other equipment shall turn up 2". Shelves shall be notched around table uprights and crossbraces, so that undershelves are easily removable. All edges of sections adjacent to each other shall be turned down 1" (minimum) for rigidity.

H. Elevated Shelves:

1. Elevated shelves shall be constructed of 16-gauge stainless steel and shall be turned down 1-1/2" on front and ends with sanitary semi-rolled edges with bullnosed corners. Rear sides of shelves shall be turned up 1-1/2".
2. Free-standing shelves, unless specified otherwise, shall be mounted on 1" OD stainless steel tubular uprights mounted to counter tops in a sanitary manner (tube inserts when accessible from bottom of counter). Wall mounted shelves shall be equipped with stainless steel angle wall brackets anchored to building wall.
3. Shelves, where specified to be mounted on cantilever brackets, shall be mounted on 1-5/8" diameter stainless steel tubular uprights welded to framing of table and counter tops.

I. Drawers:

1. All drawers shall be 20" x 20" x 5" deep unless specified otherwise. Removable pans shall be formed of one-piece die-stamped 18-gauge stainless steel with top edges flanged out 2". Faces of drawers shall be equivalent to Component Hardware No. J85-2000. Drawers shall operate on ball-bearing roller stainless steel extension slides to allow full opening and shall be fitted with adjustable stops to prevent drawers from being pulled out too far so they will drop down.
2. Drawers shall be completely enclosed in 18-gauge stainless steel housing attached to undersides of tops on open base tables and shall be attached to framework of cabinet base tables.

J. Casters:

1. Casters specified for open base tables shall be equivalent to Component Hardware Nos. C23-1250 (5” diameter non-braking) and C23-1251 (5” diameter braking).

K. Sinks:

1. Sinks shall be constructed of 14-gauge stainless steel having back, bottom and front formed of one (1) continuous sheet of metal with ends and partitions welded in place. All vertical and horizontal corners of sink compartments shall be coved with metal on a 5/8" (minimum) radius. No solder filleting will be acceptable. All edges of sink counter tops not adjacent to walls shall be turned up 7/8" on a 45-degree angle, and rolled down 2-5/8" to form a marine roll unless specified otherwise. Edges of sink counter tops adjacent to wall shall be turned up 10", back 2-1/4" on a 45-degree angle and down 2" to form a backsplash with pipe chase. All ends of backsplashes shall be closed, ground smooth and polished. Backsplashes shall be pierced on 8" centers over compartment dividers of two, three and four compartment sinks and over center of one compartment sinks unless specified otherwise. Bottom of each sink compartment shall be fitted with Component Hardware No. D50-7200 lever handle drain. Overflow drain assemblies when specified shall be Component Hardware No. D50-7215. Drains shall set into embossed openings in sink bottoms, gasketed and locked in place without use of rivets or bolts. Sinks shall be

mounted on 1-5/8" OD 16-gauge stainless steel legs with adjustable stainless steel feet (same as specified for open base tables). All sink partitions shall be 7/8" thick double wall construction. A model No. B-0231 T & S mixing faucet (12" spout) shall be mounted at center of each single compartment sink and over each partition of each multiple compartment sink. Preparation and utensil wash sinks shall be 12" and 14" deep respectively unless specified otherwise.

2. Sink inserts shall be constructed same as specified for sinks above with coved corners and 2" lever drains. Sink inserts shall be welded integral with stainless steel tops. Inserts unless otherwise specified, shall have a T & S model no. B-0222-059X faucet deck-mounted behind each compartment.

L. Item No. 1 Mixing Faucet W/Hose Threads – Division 22 (Plumbing)

M. Item No. 2 Air Curtain (One Required):

1. Mars Air Doors No. N248-1UA-SSS or approved equal with components/features/accessories as follows:

a. Stainless steel housing
b. One (1) micro-switch for automatic on/off operation

N. Item No. 3 Mobile Utility Carts (2) – Owner Furnished, Owner Installed

1. Piper No. 1-UCM-3 (23” wide x 39-1/4” long x 37-5/16” high) or approved equal, each with rotary bumpers and brakes

O. Item No. 4 Mixing Faucets w/Hose Threads (2) – Division 22 (Plumbing)

P. Item No. 5 Wall-Mount Hose Racks (Three Required):

1. T&S No. 002970-45, each mounted on building wall beneath mixing faucets

Q. Item No. 6 Hand Sinks (4) - Division 22 (Plumbing)

R. Item No. 7 Storage Shelving Unit – Owner Furnished, Owner Installed

1. Metro Super Erecta Brite series or approved equal with components/features/accessories as follows:

a. Five (5) 18” wide x 48” long zinc-plated adjustable wire shelves
b. 72” high zinc-plated tubular uprights with foot levelers

S. Item No. 8 Clothes Washer – Owner Furnished, Owner Installed

1. Whirlpool No. WTW5000DW or approved equal with 36” long cord/plug assembly

T. Item No. 9 Clothes Dryer – Owner Furnished, Owner Installed

1. Whirlpool No. WED5000DW or approved equal with 36” long NEMA 14-30P cord/plug assembly

U. Item No. 10 Floor Mop Sink – Division 22 (Plumbing)

V. Item No. 11 Chemical Dispenser - Not in Contract (By Vendor)

W. Item No. 12 Storage Shelving Units (12) – Owner Furnished, Owner Installed

1. Metro Super Erecta Brite series or approved equal, each with components/features/accessories as follows:

a. Five (5) 21” wide x 42” & 48” long (as indicated on drawings) zinc-plated adjustable wire shelves
b. 72” high zinc-plated tubular uprights with foot levelers

X. Item No. 13 Dunnage Racks (2) – Owner Furnished, Owner Installed

1. Cambro Nos. DRS360 or approved equal, as indicated on drawings

Y. Item No. 14 Walk-In Cooler/Freezer (One Required):

1. General: Walk-in shall be pre-fabricated modular construction, designed and constructed to allow for fast and easy field assembly, relocation, and modification by addition of modular panels. Walk-in and components thereof shall meet 2009 Energy Code Standards. Walk-in shall be installed and/or commissioned by a certified factory technician.
2. Project Requirements: Walk-in shall be floor type installed on existing interior building slab.
3. Size: Walk-in shall be 19’-3” wide x 15’-5” deep x 8’-6” high, arrangement indicated on drawings
4. Finishes: Exposed exterior wall and ceiling panels (including exposed floor and ceiling caps) shall be 20-gauge type 304 No. 3 finish stainless steel. Interior wall and ceiling panels shall be 26-gauge galvanized steel with mill-applied white enamel. Interior/exterior door/door panels shall be 20-gauge type 304 No. 3 finish stainless steel with 36” high kick plates. Unexposed wall and ceiling panels shall be 26-gauge galvanized steel. Exposed floor panels shall be foamed-in-place 1/8” thick aluminum diamond tread plate reinforced with ¾” thick marine plywood. Unexposed floor panels shall be 14-gauge galvanized steel.
5. Panel Construction: Panels shall consist of metal pans, formed to precise dimensions, with “foamed-in-place” urethane to permanently bond to inner metal surfaces to form strong rigid units. Standard wall, ceiling, and floor panels shall 11½”, 23", 34½”, 46", and 69" wide. Standard corner panels shall be 12" x 12" on 90-degree angle. Special fabricated panels shall be provided to meet project requirements. Panels shall be equipped with NSF-approved double-bead interior and exterior vinyl gaskets which are resistant to stains, grease, oil, mildew, and sunlight. Panels shall be equipped with cam-action locking mechanisms (hook and arm assemblies) securely mounted in matching panel locations to form air-tight and vapor-proof joints. Locking mechanism parts shall be equipped with urethane plugs and snap-in caps to match interior finish of panels.
6. Insulation: Insulation shall be 4" thick rigid, low ozone depleting HCPC 22 blown Class 1 urethane foam classified according to UL723 (ASTM-E-84) as tested by Underwriter’s Laboratories, Inc. Four (4) inch core material shall have a flame spread of 25 or less and a smoke density of 250. Insulation shall have a thermal conductivity (K Factor) of not more than 0.125 BTU/hr/sf per degree Fahrenheit/inch, on overall coefficient of heat transfer (U factor) of not more than .031, and R factor of 32. Pre-fabricated urethane foam panels shall be supplied with a Class 1 fire hazard classification according to

UL723 (ASTM-E-84) as tested by Underwriter's Laboratories, Inc. Panels shall have a flame spread rating of 25 or less with a certifying UL labels.

7. Entrance Doors and Door Panels: Refer to drawings for door locations and directions of door swings. Doors shall be 36" wide x 76" high, infitting flush-mounted type with one-piece perimeter PVC accordion-type removable gasket with magnetic core at top and side perimeters at doors. Adjustable wiper gaskets shall be mounted on bottom edge of doors. Door latches shall be high pressure zinc die cast with polished chrome finish with break-away inside safety release handles so that doors can be opened from inside, even if locked, and cylinder locks. Doors shall be equipped with Kason No. 1346 Performer adjustable hinge. Doors shall be equipped with positive-action hydraulic door closers to ensure positive closing of doors. Hinges of 36" wide doors shall be 9-inch modified strap, cam-lift, self-closing design with door lift-off capability, same type and finish as door latches. Rubber door stopper shall be installed on exterior front panel to prevent damage of panel by handle when door is opened to a full 180 degrees. Aluminum diamond treadplates (1/8" thick) shall be mounted on the lower 36" of interior and exterior door surfaces. Door panels shall be equipped with heavy reinforced steel "U" channel frame on entire door perimeter. Anti-sweat heater cables shall be run in breaker strips located behind removable heavy-gauge stainless steel trim for easy access to heater cables. Heater cables shall be run within heavy-gauge "U" channels of 12-gauge stainless steel (minimum) thresholds. Each door panel shall include a pre-wired Kason No. 11806LEDGU24 LED light fixture with globe and 11.5-watt lamp, 2½" diameter chrome face, and flush-mount dual-reading adjustable dial thermometer on exterior surface to provide temperature readings of minus 40-degrees F to plus 60-degrees F and minus 40-degrees C to 15-degrees C.
8. Pressure Relief Ports: Walk-in cooler and freezer rooms shall include 2-way heated pressure relief ports (vents) to equalize pressure between interior and exterior pressures caused by sudden temperature changes due to opening doors, loading of products, and/or defrosting of coils. Pressure relief port(s) quantities, sizing, and locations to be determined by walk-in manufacturer.
9. Ceiling Light Fixtures: Six (6) Kason No. 1810LC4000 48" long LED-light fixtures, each with two lamps (40-watt total) shall be furnished and installed by this Contractor. Junction box assemblies shall include threaded electrical conduit (urethane-filled), junction boxes (installed on top of ceiling panels), and 120-volt wiring to junction box.
10. Warranty: Walk-in panels shall include a ten (10) year factory warranty (including labor) for defects in materials and workmanship from date of Substantial Completion of project.
11. Trim Strips and Closure Panels: Trim strips to match finish of exposed exterior walk-in panels shall be furnished and installed in a workmanlike manner to conceal cracks between walk-in and building walls. Closure panels, constructed in accordance with drawings and project requirements, shall be mounted on top of walk-in to match exposed exterior walk-in panels. Where required for access to top of walk-in, removable closure panels are required. Trim strips and closure panels shall be constructed of 18-gauge stainless steel.
12. Temperature Alarm System: Each cooler/freezer room shall include one (1) flush-mounted Modularm No. 75LC multi-monitor, 3-button user interface, digital temperature indicator, built-in audible alarm, built-in dry contacts for remote notification capability of an audio and/or visual alarm condition, built-in transformer, built-in rechargeable battery with recharging circuitry, and built-in data/comm port for system expansion. System shall be provided with Energy Independence and Security Act compliant timing lighting control, Hi-Lo temperature alarm, panic alarm, and door ajar alarm. System shall include magnetic contacts for each door and low voltage IP-1 illuminated push button (to provide light switch and panic alarm functions) inside each cooler/freezer room by the door. The

IP-1 will remain lit at all times, even during a power failure. Multiple IP-1's shall be provided by each door in multi-door compartments to integrate with timed lighting function and to replace conventional 3-way light switching. Walk-in manufacturer shall furnish and install rigid conduit and wiring from each flush-mounted monitor mounted in door panels to top of ceiling panels (for field wiring to ceiling lights and specified components, by electrical contractor). Wiring to sensors within cooler/freezer rooms shall be furnished and installed by Food Service Equipment Contractor. System shall include low voltage MD-1 motion detector inside walk-in cooler and freezer rooms above the door for occupancy detection and automatic light control. Temperature sensors shall be located behind the evaporator coils to typify the average ambient temperature of the room. Sensor wiring shall be run above top of walk-in ceiling panels with penetrations (thoroughly sealed with silicone and foam urethane to prevent condensation) at sensor locations. Sensor wiring shall be secured to top of walk-in ceiling panels with continuous duct tape to prevent wiring damage.

13. Plastic Door Curtains: Exterior cooler/freezer entrance doors shall be equipped with Clear Vu stripless swinging door curtains manufactured by CCI Industries, Inc. (350-A Fischer Ave., Costa Mesa, CA 92626) Phone: (800) 854-5719.
14. Quality Standards: Walk-in shall be manufactured by Thermo-Kool, American Panel, or approved equal.

Z. Item No. 15 Walk-in Cooler/Freezer Remote Condensing Units (Two Required):

1. System shall be factory-assembled air-cooled system single-compressor type mounted with-in individual 304 stainless steel housings with one (1) (1-HP) compressor and one (1) evaporator coil for cooler, and one (1) (3-HP) compressor and one (1) evaporator coil for freezer. System shall include QRC refrigeration control feature for Intelligent Demand Defrost **and equipped with two pre-mounted and pre-wired leak sensors**. Food Service Equipment Contractor shall furnish and install **liquid line shut-off valves and suction line check valves (furnish by manufacturer)**, and all necessary valves, controls, oil separators, refrigerant tubing, refrigerant **R454A**, condensate drain lines, wall-mount condenser rack and accessories for a complete and neat workmanlike job in accordance with the best refrigeration practices. Refrigerant piping shall be pressure tested with nitrogen at 300 psi after condensing units and evaporator coils have been connected prior to charging with refrigerant and testing. All refrigerant lines subject to sweating shall be insulated with AP/Armaflex insulation (¾" minimum thickness for coolers and 1" thickness for freezers) with all joints sealed with glue as recommended by the manufacturer of the insulation. Duct tape at joints is not acceptable. Thickness of insulation shall be increased to 1-1/2" and 2" for cooler and freezer rooms respectively in poorly-ventilated confined areas to reduce probability of condensation of refrigerant lines. Refrigerant lines shall be rigid, type L copper with all joints soldered to meet the best refrigeration practices. Refrigerant lines shall be anchored to building structure with clamps and galvanized steel saddles as required. Condensate drain lines shall be rigid, type L copper securely fastened to walk-in panels with non-corrosive clamps (straps are not acceptable). Condensate drain lines installed in freezer rooms shall be tightly wrapped with spiral-installed heater tape. Condensate drain lines shall be generously sloped (1/2" per lineal foot minimum) to the bottom of walk-in rooms, extended through walk-in panel, through building walls (where applicable), and trapped outside walk-ins. All refrigeration systems shall be checked out to the Owner's satisfaction. This contractor shall provide an acceptable, local refrigeration service agency which shall provide 24-hour, 7-day warranty service. Coordinate final electrical connection requirements with General Contractor, final connections by Electrical Contractor.

AA. Item No. 16 Mobile Shelving Units (12) – Owner Furnished, Owner Installed

1. MetroSeal 3 series or approved equal, each with components/features/accessories as follows:

a. Four (4) 21” wide x 48” long epoxy-coated adjustable wire shelves
b. Four (4) 63” long epoxy-coated tubular uprights
c. Four (4) 5” diameter urethane swivel casters, two (2) with brakes

BB. Item No. 17 Dunnage Racks (7) – Owner Furnished, Owner Installed

1. Cambro Nos. DRS360 and DRS480 or approved equal, as indicated on drawings

CC. Item No. 18 Spare Number

DD. Item No. 19 Preparation Counter w/Sinks & Overshelf (One Required):

1. 60” wide x 11’-0” long x 36” high, arrangement indicated on drawings, custom fabricated stainless steel double-sided open base type with components/features/accessories as follows:

a. Marine roll top edges on front and ends
b. Two (2) 20” x 24” x 12” deep sinks
c. One (1) splash-mount faucet
d. Four (4) drawers
e. Undershelves, except at sinks 6” wide x full-length x 6” high enclosed backsplash
f. Four (4) NEMA 5-20R receptacles (2 on each side) mounted in backsplash
g. 15” wide x full-length stainless steel overshelf mounted on tubular uprights and cantilever brackets 24” above counter top
h. Flanged feet on end legs

EE. Item No. 20 Food Processor – Owner Furnished, Owner Installed

1. Robot Coupe No. R702N or approved equal with standard cutting plates

FF. Item No. 21 Slicer – Owner Furnished, Owner Installed

1. Hobart No. HS6-1 or approved equal

GG. Item No. 22 Mobile Stand – Owner Furnished, Owner Installed

1. Hobart No. CUTTER-TABLE4 stand with casters

HH. Item No. 23 Mobile Pan Racks (2) – Owner Furnished, Owner Installed

1. CresCor No. 207-1820 or approved equal, each with components/features/accessories as follows:

a. Vinyl corner bumpers
b. Casters w/brakes

II. Item No. 24 Baker’s Table w/Spice Shelf (One Required):

1. 30” wide x 84” long x 36” high, custom-fabricated stainless steel open base type with following:

    a. Tier of 3-drawers (located on left end)
    b. Open base to receive mobile ingredient bins
    c. 6” high rear splash
    d. 12” wide x 84” long 16-gauge stainless steel spice shelf mounted on stainless steel tubular uprights 15” above tabletop

JJ. Item No. 25 Mobile Ingredient Bins (2) – Owner Furnished, Owner Installed

1. Rubbermaid No. FG360288 or approved equal

KK. Item No. 26 60-Quart Mixer (One Required):

1. Hobart No. HL600 or approved equal with components/features/ accessories as follows:

    a. Standard 60-quart accessories including stainless steel bowl, bowl guard, “B” beater, “D” wire whip, and “ED” dough hook
    b. Bowl dolly
    c. 40-quart accessories including stainless steel bowl, “B” beater, “D” wire whip, and “ED” dough hook
    d. 48” long NEMA L15-20P cord/plug assembly

LL. Item No. 27 Mobile Proof Holding Cabinet – Owner Furnished, Owner Installed

1. CresCor No. 121-PH-UA-11D or approved equal with components/features/accessories as follows:

    a. Lexan doors
    b. Vinyl corner bumpers
    c. Casters w/brakes

MM. Item No. 28 Mobile Utensil Shelving Unit – Owner Furnished, Owner Installed

1. MetroSeal 3 series or approved equal with components/features/accessories as follows:

    a. Four (4) 24” wide x 48” long epoxy-coated adjustable wire shelves
    b. Four (4) 63” long epoxy-coated tubular uprights
    c. Four (4) 5” diameter urethane swivel casters, two (2) with brakes

NN. Item No. 29 3-Compartment Sink W/Overshelf (One Required):

1. 34" wide x 11'-0" long x 36" high, arrangement indicated on drawings, custom fabricated stainless steel open base type with components/ features/accessories as follows:

    a. Marine roll edges on front and left end
    b. 6” high rear splash
    c. Three (3) 20” x 28” (front to back) x 14” deep sink compartments
    d. One (1) splash-mount faucet

e. One (1) T&S Brass No. B-0133-ADF12-B splash-mounted pre-rinse spray unit with wall bracket and add-on faucet with 12” long swing nozzle, mounted above left-end sink compartment divider
f. Two (2) 36” long integral drainboards
g. 15” wide x 11’-0” long cantilevered overshelf 24” above sink rim with 2-bar pot rack per detail provided in drawings
h. Undershelves, except at sinks

OO. Item No. 30 Double Stack Convection Oven (One Required):

1. Blodgett No. DFG-100 (double-deck) or approved equal with components/ features/accessories as follows:

a. Stainless steel front, sides, top, rear enclosure panel, 6” legs, and solid doors
b. Common gas manifold for single gas connection

PP. Item No. 31 Double Stack Convection Oven (One Required):

1. Blodgett No. DFG-100 (double-deck) or approved equal with components/ features/accessories as follows:

a. Stainless steel front, sides, top, rear enclosure panel, 6” legs, and solid doors
b. Common gas manifold for single gas connection

QQ. Item No. 32 Convection Steamer (One Required):
1. Groen No. (2)GSSP-BL-5GS (double-stack) or approved equal with components/ features/accessories as follows:

a. Smart Steam water treatment system

RR. Item No. 33 40-Gallon Tilting Braising Pan (One Required):

1. Groen No. BPM-40GC or approved equal with components/features/accessories as follows:

a. Classic controls
b. No. N60346 double pantry faucet with 60” long spray hose and kettle filler
c. No. 150247 pan carrier
d. 72” long NEMA 5-15P cord/plug assembly

SS. Item No. 34 2-Burner Range w/Modular Stand (One Required):

1. Garland No. MST4T-E or approved equal with components/features/accessories as follows:

a. Stainless steel front, sides, and rear
b. Stainless steel open base stationary stand
c. Stainless steel front, front top rail, sides, rear side, 6” high flue riser, and modular stand (range to be securely bolted to stand with stainless steel bolts)
d. ¾” rear gas connection

TT. Item No. 35 Combi-Oven/Steamer (One Required):

1. Alto-Shaam No. 10-20G-PRO or approved equal with components/features/accessories as follows:

    a. Water filter system
    b. Spray hose
    c. Recessed door
    d. No. 5016084 stainless steel stand with pan slides and shelf

UU. Item No. 36 Utility Distribution System (One Required):

1. System shall be a U.L. Listed, modular, island-type energy distribution and control system manufactured in accordance with the latest edition of the National Electrical Code (NEC), National Manufacturer's Association (NEMA), National Fire Protection Association (NFPA) Pamphlet Nos. 96 and 54, Uniform Plumbing Code, ASME, and Occupational Safety and Health Administration (OSHA) using only U.L. Listed Bureau of Mines, and AGA and CGA certified components.
2. System shall be 12'-0" long x 8" wide and shall be completely pre-wired and pre-plumbed to final connection points for electric/hot water/cold water/gas for the equipment shown on the drawings. HORIZONTAL CHASE OF ISLAND-TYPE SYSTEM SHALL NOT EXCEED AN OVERALL HEIGHT (INCLUDING PEAKED TOP) OF 50" ABOVE FINISHED FLOOR.
3. Fixed riser, pedestal, end caps, and raceway exterior panels shall be constructed of 16-gauge type 304 stainless steel with a No. 4 finish. Removable panels shall be constructed of 18- and 20-gauge stainless steel. A watertight barrier shall be provided between electrical and plumbing compartments. Control tower pedestals shall be secured to the building floor with stainless steel, interior flanges. Housing of the raceway shall be equipped with neoprene bumper strips.
4. Electrical compartment shall be a completely enclosed, stainless steel housing accessible by removal of stainless steel screws.
5. Internal electrical main feeder(s) shall be cable bus type having balanced load and phases with branch circuit locations directly behind connection plates. Cable bus shall be manufactured from 100% copper and mounted on non-conductive insulators spaced at 48" (maximum) centers and equipped with connection lugs for main service. Field joints shall be connected by attaching cables to insulated terminals. Branch circuit wiring for each electrical connection shall be phase-identified and sized in accordance with circuit breaker's rated ampacity. A 12" long, 16-gauge, stainless steel connection plate shall be provided for each electrical connection and equipped with a point-of-use circuit breaker and grounding type receptacle having a specific NEMA, polarized configuration or pre-wired, flexible, seal-tite conduit. Connection plates shall be equipped with metallic labels with permanently lettered electrical characteristics. Plates shall be spaced on 12" centers and readily interchangeable by maintenance personnel to facilitate changes, additions, and deletions of equipment. Blank plates shall be provided for future equipment. A main electrical circuit breaker and disconnect shall be mounted in the control tower.
6. Plumbing compartment shall be isolated from the electrical compartment and all piping and disconnects shall be color-coded. Provide an additional capped nipple in each section for each plumbing service for future use. Field joints shall be securely by tightening unions.
7. Hot and cold water piping, including individual branch pipe connections, shall be hard temper type "L" copper tubing with copper sweat type solder fittings. All water lines

shall be covered with 3/8" thermal closed cell pipe insulation per ASTM-E90-C. Each branch connection shall be provided with a brass, double shut-off, quick-disconnect, and flexible hose connector consisting of brass bellows type, corrugated hose with braided stainless steel restrainer. Hoses shall be coated with Avtec Polytec material to provide a smooth surface for cleaning.

8. Gas piping shall be black iron pipe with welded threadolets to branch connections and drip-tee in the service riser. Each branch connection shall be equipped with a quarter-turn, ball-type shut-off valve; brass quick-disconnect; 2-wall, stainless steel, flexible hose connecter; and steel restraining cable. Hoses shall be coated with Avtec Polytec material to provide a smooth surface for cleaning.
9. System shall be equipped with quarter-turn shut-off valves for all main incoming services for gas and water.

    a. Two (2) end risers
    b. Two (2) floor pedestals
    c. Power shut-off device (shunt trip breaker)
    d. Exhaust Hood light switch, mounted on end riser panel adjacent to Manager's Office
    e. Exhaust/Supply fan control panel with fire system interface mounted in end riser adjacent to Manager's Office
    f. Water quick-disconnect hose assemblies for cooking equipment
    g. Gas quick-disconnect hose assemblies with shut-off valves for cooking equipment
    h. Electric cord/plug assemblies for cooking equipment

10. System shall be Avtec MID series or approved equal to meet above requirements.
11. Shop drawings are required for approval.
12. Refer to Contract Document drawings for utility requirements and locations thereof.

VV. Item No. 37 Exhaust Hood – By Division 23 (Mechanical):

WW. Item No. 38 Fire Suppression System – By Division 23 (Mechanical):

XX. Item No. 39 Stainless Steel Drain Trough w/Grate (One Required):

1. 19-1/2" wide x 36" long, custom-fabricated all-welded 14-gauge type 302/304 stainless steel in accordance with drawings. Trough shall be equipped with 5-1/2" diameter x 3-1/4" deep sump bowl with 3" long pipe sleeve sized to accommodate drain pipe (installed within sleeve) by plumbing contractor. Sump bowls shall be equipped with removable perforated stainless steel strainer baskets with perforated covers. Submit shop drawing for approval.
2. Troughs shall be equipped with 15-1/4" wide x 31-3/4" long x 1" thick McNichols No. MS-M-150-MINI-GRID (dark gray color) or IMC Teddy equal fire retardant removable molded fiberglass grates (9/32" thick bars on 3/4" x 3/4" spacings) with grit surface (one side only). Each grate shall be cut with a bar on all outside edges for a banded finished edge appearance. Grates shall be furnished by trough fabricator for fitting coordination purposes.
3. Submit shop drawing for approval.

YY. Item No. 40 Work Table w/Overhead Pot Rack (One Required):

1. 30” wide x 108” long x 36” high, custom-fabricated stainless steel open base type with components/features/accessories as follows:

    a. 102” long double bar table-mount overhead pot rack
    b. Two (2) drawers
    c. Undershelf

ZZ. Item No. 41 Pass-Thru Warmer (One Required):

1. Traulsen No. RHF232WP or approved equal with components/features/accessories as follows:

    a. Half-height stainless steel doors
    b. Twenty (20) sets of stainless steel universal pan slides
    c. 6” high stainless steel legs
    d. 48” long NEMA L14-20P cord/plug assembly

AAA. Item No. 42 Pass-Thru Refrigerator (One Required):

1. Traulsen No. RHT232NPUT or approved equal with components/features/accessories as follows:

    a. Half-height stainless steel doors
    b. Stainless steel rod-type pan slide assemblies for 18” x 26” pans
    c. 6” high stainless steel legs

BBB. Item No. 43 Mobile Tray Dispensers (2) – Owner Furnished, Owner Installed

1. Shelleymatic No. TT2-1014 or approved equal, each with perimeter bumpers to accommodate 10” x 14” compartment trays (verify exact size)

CCC. Item No. 44 Mobile Milk Cooler – Owner Furnished, Owner Installed

1. True No. TMC58S-SS-H (forced-air type), with corner bumpers

DDD. Item No. 45 Mobile Milk Cooler – Owner Furnished, Owner Installed

1. True No. TMC-34-S-DS-S (forced-air type), with corner bumpers

EEE. Item No. 46 Mobile Hot Food Counter (One Required):

1. 32” wide x 84” long x 34” high, LTI No. SPC-TW-DW-SS-20-04-60 (MOD) (stainless steel series) or approved equal with components/features/accessories as follows:

    a. Stainless steel base panels
    b. Four (4) hot food wells with drains, drain manifold, and shut-off valve with threaded hose connection
    c. Flat top space where indicated on drawings for silverware
    d. 60” long single-service buffet guard
    e. Hatco No. GRNH-54 (54” long) pre-wired infrared heat lamp
    f. 54” long pre-wired LED lights

g. Full-length solid-type fold-down tray slide
h. Line-up locks for adjacent counters
i. 60” long NEMA 14-30P cord/plug assembly
j. Stainless steel floor mounted outlet box with one (1) NEMA 14-30R for this counter and one (1) NEMA 14-20R for Item No. 47
k. 5” diameter swivel casters with brakes with 6” minimum clearance for floor-mounted outlet box
l. Shop drawing required for approval

FFF. Item No. 47 Mobile Hot/Cold Food Counter (One Required):

1. 32” wide x 60” long x 34” high, LTI No. SPC-ST-SS-60 (stainless steel series) or approved equal with components/features/accessories as follows:

a. Stainless steel base panels
b. One LTI No. DI-QSGT-42-G-H pre-wired drop-in hot/cold/frost-top shelf
c. One 60” long single-service buffet guard
d. One Hatco No. GRNH-48 pre-wired infrared heat lamp
e. 54” long pre-wired LED lights
f. Full-length solid-type stainless steel fold-down tray slide
g. Line-up locks for adjacent counters
h. 60” long NEMA 14-20P cord/plug assembly on end adjacent to Item No. 46
i. 5” diameter swivel casters with brakes with 6” minimum clearance for floor-mounted outlet box
j. Shop drawing required for approval

GGG. Item No. 48 Mobile Flat Top Counter w/Drop-In Ice Cream Freezer (One Required):

1. 32” wide x 50” long x 34” high, LTI No. SPC-ST-SS-50 (stainless steel series) or approved equal with components/features/accessories as follows:

a. Stainless steel base panels
b. 1” die-stamped recessed top to accommodate one (1) 18” x 26” sheet pan, lengthwise
c. Delfield No. N225P drop-in ice cream freezer with lexan cover
d. 30” long single-service buffet guard
e. 24” long pre-wired LED light
f. Full-length solid type fold-down tray slide
g. Line-up locks for adjacent counters
h. 60” long NEMA 5-20P cord/plug assembly
i. Stainless steel floor mounted outlet box with two (2) NEMA 5-20R and one (1) data receptacle for this item and Item No. 49
j. 5” diameter swivel casters with brakes with 6” minimum clearance for floor-mounted outlet box
k. Shop drawing required for approval

HHH. Item No. 49 Mobile Cashier Counter (One Required):

1. 32” wide x 28” long x 34” high, LTI No. 30-CSE (stainless steel series) or approved equal with components/features/accessories as follows:

a. Stainless steel base panels
b. 2” diameter holes in top for computer cables/cord/plug assemblies
c. Solid-type fold-down tray slide
d. 8” wide pull-out stainless steel shelf to accommodate computer keyboard
e. Line-up locks for adjacent counter
f. Flush-mounted NEMA 5-20R in counter base with 48” long NEMA 5-20P cord/plug assembly
g. 5” diameter swivel casters with brakes with 6” minimum clearance for floor-mounted outlet box
h. Shop drawing required for approval

III. Item No. 50 POS Computer – By Others

JJJ. Item No. 51 Spare Number

KKK. Item No. 52 Pass-Thru Window Shelf w/Frame & Roll-Down Counter Door (One Required):

1. Custom fabricated all-welded stainless steel in accordance with drawings to include components/features/accessories as follows:

a. 14-gauge stainless steel frame and window sill to fit 48” wide x 37” high wall opening (verify) 35” above finished floor
b. Stainless steel matching trim on Dishroom side
c. Cookson No. ESC20 roll-down counter door (less sill to fit within window frame) between jambs unit with stainless steel hood, curtain and door guides
d. Shop drawings for door required

LLL. Item No. 53 Soiled Dishtable (One Required):

1. 30” wide x 34” high x length and arrangement indicated on drawings, custom fabricated stainless steel open base type with components/features/ accessories as follows:

a. 6” wide x 60” long scrap trough equipped with one (1) Fisher No. 2905 trough water inlet (mounted in end of scrap trough), one (1) vacuum breaker, and “silver-saver” strap (installed in bottom of trough at pre-rinse sink)
b. 20” x 20” x 6” deep pre-rinse sink with cut-out for scrap trough, removable stainless steel rack guide, and 6-1/2” diameter disposer sink adapter
c. T & S Brass No. B-0133/B-0109 pre-rinse spray unit
d. Stainless steel bracket for disposer control panel
e. Open base for mobile equipment at pass-thru window

MMM. Item No. 54 Disposer (One Required):

1. Salvajor No. 300-SA-6-ARSS-LD or approved equal with components/features/ accessories as follows:

a. 6-1/2” sink collar
b. No. ARSS-LD control panel

NNN. Item No. 55 Dishwasher (One Required):

1. Hobart No. CL44EN or approved equal with components/features/accessories as follows:

    a. Left-to-right operation
    b. Regulated electric tank heat
    c. Single-point electric connection (for tank heat and motors)
    d. Booster heater
    e. Two (2) exhaust duct connections with dampers
    f. Vent fan control

OOO. Item No. 56 Dishwasher Pant Leg Exhaust Duct (One Required):

1. All-welded 18-gauge all-welded stainless steel construction in accordance with drawings to fit dishwasher with components/features/accessories as follows:

    a. Stainless steel duct extension to 6” above finished floor
    b. Stainless steel ceiling trim

PPP. Item No. 57 Clean Dishtable (One Required):

1. 30” wide x 34” high x length and arrangement indicated on drawings, custom fabricated stainless steel open base type with components/features/ accessories as follows:
    a. 48” long undershelf
    b. Table limit switch

QQQ. Item No. 58 Mobile Condiment Counter (One Required):

1. 32” wide x 74” long x 34” high, LTI No. SPC-ST-SS-74 (stainless steel series) or approved equal with components/features/accessories as follows:

    a. Stainless steel base panels with undershelf
    b. Hinged doors for storage below counter top
    c. Full-length solid type fold-down tray slide
    d. 5” diameter swivel casters with brakes with 6” minimum clearance for floor-mounted outlet box

RRR. Shop drawing required for approval Item No. 59 Ice Machine (Cuber) w/Storage Bin – Owner Furnished, Owner Installed

1. Manitowoc No. IDT0500A (air-cooled) or approved equal with components/ features/accessories as follows:

    a. No. D570 ice storage bin
    b. Manufacturer-recommended water filter for ice production capacity

SSS. Item No. 60 Student Hand Wash Sink - Division 22 (Plumbing)

PART 3 - EXECUTION

3.1 ERECTION

A. Equipment specified herein shall be erected and set in place at location as indicated on Drawings. Equipment shall be fabricated so that it can be handled through finished openings or arrangements otherwise made with General Contractor. Equipment specified shall be located on floors as indicated on Drawings. A competent foreman shall be provided as supervisor of erections and installations.

3.2 ADJUSTMENT OF EQUIPMENT

A. Contractor shall adjust all equipment after erection and installation to satisfaction of Owner.

B. Contractor shall confirm in writing that all equipment is operational and in working condition prior to demonstration.

3.3 CLEANING OF EQUIPMENT

A. Clean up all debris caused by workmen immediately upon completion of Work in the area, and clean equipment after all others have completed their Work in the area.

3.4 DEMONSTRATION OF EQUIPMENT

A. Upon acceptance by Owner, provide full instructions to Owner's designated representative on proper methods of care, operation and maintenance of equipment.

B. Three (3) operating instructions, warranty cards/certificates and parts manuals on equipment in loose leaf hard cover binders shall be presented to Architect at this time. Operation and maintenance manuals shall be organized for easy reference by maintenance personnel, including index tabs of equipment item numbers.

END OF SECTION 114000

SECTION 123661 - SIMULATED STONE COUNTERTOPS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Solid-surface-material countertops and backsplashes.

1.2 ACTION SUBMITTALS

A. Product Data: For countertop materials.

B. Shop Drawings: For countertops. Show materials, finishes, edge and backsplash profiles, methods of joining, and cutouts for plumbing fixtures.

C. Samples: For each type of material exposed to view.

1.3 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of simulated stone countertop systems that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

B. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace simulated stone materials that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Ten years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOLID-SURFACE-MATERIAL COUNTERTOPS

A. Basis Of Design: Provide countertops with the following front and backsplash style. Solid Surface Countertop shall be **Wilsonart Iron Falls**

1. Front: 3/4-inch.
2. Backsplash: Straight, slightly eased at corner.
3. Endsplash: Matching backsplash.

B. Countertops: 3/4-inch thick, solid surface material with front edge built up with same material

C. Backsplashes: 3/4-inch thick, solid surface material.

2.2 COUNTERTOP MATERIALS

A. Particleboard: ANSI A208.1, Grade M-2-Exterior Glue.

B. Plywood: Exterior softwood plywood complying with DOC PS 1, Grade C-C Plugged, touch sanded.

C. Solid Surface Material: Homogeneous solid sheets of filled plastic resin complying with ANSI SS1.

1. Manufacturers: Subject to compliance with requirements, provide products indicated by the drawings or comparable products by one of the following:

   a. Avonite Surfaces.
   b. Dupont Co.
   c. Formica Corporation.
   d. Wilsonart International.

2. Type: Provide Standard Type or Veneer Type made from material complying with requirements for Standard Type, as indicated unless Special Purpose Type is indicated.
3. Colors and Patterns: As selected by Architect from manufacturer's full range.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Fasten countertops by screwing through corner blocks of base units into underside of countertop. Align adjacent surfaces and, using adhesive in color to match countertop, form seams to comply with manufacturer's written instructions. Carefully dress joints smooth, remove surface scratches, and clean entire surface.

END OF SECTION 123661

SECTION 21 13 13 - WET-PIPE SPRINKLER SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
1. Pipes, fittings, and specialties.
2. Cover system for sprinkler piping.
3. Specialty valves.
4. Sprinklers.
5. Alarm devices.
6. Control panels.
7. Pressure gages.

B. Furnish all materials, labor, tools, equipment and working plans to install and place into operation the complete Fire Protection System (Automatic Wet Pipe Sprinkler System) for the entire building in accordance with the attached plans and as specified herein.

C. All work shall meet requirements of the latest edition of the National Fire Protection Association (NFPA), Louisiana State Fire Marshal.

D. Prior to start of the design of the fire protection system, the contractor shall coordinate and complete the “Owner’s Information Certificate” form required by the State Fire Marshal. The form can be found at the State Fire Marshal’s website http://www.dps.louisiana.gov/sfm. The form shall identify special occupancies and commodity classifications and shall be given to the fire protection system designer before the start of design.

E. Sprinkler contractor shall visit site and familiarize himself with all existing conditions, examine plans and specifications to determine building conditions and coordinate with work being performed by other trades. Contractor shall make note that all calculations and plans required by the State Fire Marshal shall be provided by Sprinkler Contractor.

F. Each bidder shall be licensed to perform sprinkler work in the State of Louisiana and shall be recognized by Property Insurance Association of Louisiana as a reliable sprinkler contractor.

G. Sprinkler Contractor shall include in his price all offsets required in order to avoid conflict with ductwork, lights, grilles, air boxes, etc. All offsets shall be made above intersecting ducts or pipes in order to minimize trapping of water. Contractor shall coordinate installation of his piping with all other trades to assure that they can all fit in the space provided. In general, sprinkler piping shall be run at maximum height above finished floor or between joists in order

to minimize conflict with different trades. In areas where joists are exposed, lines shall be run at bottom of roof deck, between or through joists.

H. Contractor shall make note that sprinkler piping layout and sprinkler head locations are diagrammatic and all spaces shall have proper number of heads and proper pipe size in contractor's price.

I. Contractor shall also obtain latest flow data for local utility company and assure himself prior to bid that adequate pressures and flow are available for the system he intends to provide.

1.3 REQUEST FOR APPEAL

A. The Contractor shall be required to complete any and all “Appeals” to the State Fire Marshal’s Office required to clear review comments associated with shop drawings. The Contractor shall be required to complete the Appeal Forms and provide associated appeal costs for appeals associated with the project.
   1. Example of Appeals including but not limited to: Sprinkler head type below stands, Low Suction Control Valve required by DHH on Fire Pump applications, etc.

1.4 DEFINITIONS

A. Standard-Pressure Sprinkler Piping: Wet-pipe sprinkler system piping designed to operate at working pressure of 175-psig maximum.

1.5 PAINTING

A. All painting shall be by the general contractor's painting sub-contractor. All pipe, pipe covering, equipment, supports, hangers, etc. Exposed in the building or equipment room shall be painted. This contractor shall prepare the surface of the material to receive the first coat of paint.

B. All subsequent coatings shall be prepared by the painting sub-contractor. Requirements covering paints, workmanship and preparation of surfaces as stated in the architectural specifications shall govern. Colors shall be approved by the architect. All piping shall be color-coded.

C. All piping shall be color coded per the following:
   1. Fire Protection Piping (Exposed in Building) Red (Color to be selected by Architect)

1.6 ACTION SUBMITTALS

A. Product Data: For each type of product.
   1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

B. Shop Drawings: For wet-pipe sprinkler systems.

1. Include plans, elevations, sections, and attachment details.
2. Include diagrams for power, signal, and control wiring.
3. Shop drawings shall be prepared by the contractor before commencing fire protection installation. The shop drawings shall be detailed as required by the State Fire Marshal's Office and submitted through the Architect to the following for approval:
   a. State Fire Marshal.
   b. Local Fire Prevention Bureau.
4. Provide review application fee as required by the State Fire Marshal. Contractor shall pay all applicable fees required for the project thru completion of project.
5. All shop drawings plans and elevations shall be made at 1/8" scale and arranged same as contract drawings.
6. Provide scaled site plan.

C. Delegated-Design Submittal: For wet-pipe sprinkler systems indicated to comply with performance requirements and design criteria, including analysis data signed by the qualified NICET certified designer responsible for their preparation.

1.7 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Sprinkler systems, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Domestic water piping
2. Items penetrating finished ceiling including the following:

   a. Lighting fixtures.

B. Qualification Data: For qualified Installer and NICET designer.

C. Approved Sprinkler Piping Drawings: Working plans, prepared according to NFPA 13, that have been approved by authorities having jurisdiction, including hydraulic calculations if applicable.

D. Fire-hydrant flow test report.

E. Field Test Reports and Certificates: Indicate and interpret test results for compliance with performance requirements and as described in NFPA 13. Include "Contractor's Material and Test Certificate for Aboveground Piping."

F. Field quality-control reports.

1.8 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For wet-pipe sprinkler systems and specialties to include in emergency, operation, and maintenance manuals.

1.9 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
   1. Sprinkler Cabinets: Finished, wall-mounted, steel cabinet with hinged cover, and with space for minimum of six spare sprinklers plus sprinkler wrench. Include number of sprinklers required by NFPA 13 and sprinkler wrench. Include separate cabinet with sprinklers and wrench for each type of sprinkler used on Project.

1.10 QUALITY ASSURANCE

A. Installer Qualifications:
   1. Installer's responsibilities include designing, fabricating, and installing sprinkler systems and providing professional engineering services needed to assume engineering responsibility. Base calculations on results of fire-hydrant flow test.
      a. Engineering Responsibility: Preparation of working plans, calculations, and field test reports by a qualified designer.
      b. The contractor shall be a qualified fire protection contractor, licensed by the State of Louisiana and directly engaged in the installation of automatic fire sprinkler systems and other fire protection equipment.

B. Welding Qualifications: Qualify procedures and operators according to 2010 ASME Boiler and Pressure Vessel Code.

1.11 FIELD CONDITIONS

A. Interruption of Existing Sprinkler Service: Do not interrupt sprinkler service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary sprinkler service according to requirements indicated:
   1. Notify Architect no fewer than two days in advance of proposed interruption of sprinkler service.
   2. Do not proceed with interruption of sprinkler service without Architect's written permission.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Sprinkler system equipment, specialties, accessories, installation, and testing shall comply with the following:
   1. NFPA 13.

B. Standard-Pressure Piping System Component: Listed for 175-psig minimum working pressure.

C. Delegated Design: Engage a qualified designer to design wet-pipe sprinkler systems.
   1. Conduct a fire-hydrant flow test and indicate the following conditions:
      a. Date:
      b. Time:

c. Performed by:
d. Location of Residual Fire Hydrant R:
e. Location of Flow Fire Hydrant F:
f. Static Pressure at Residual Fire Hydrant R:
g. Measured Flow at Flow Fire Hydrant F:
h. Residual Pressure at Residual Fire Hydrant R:

2. Sprinkler system design shall be approved by authorities having jurisdiction.
   a. Margin of Safety for Available Water Flow and Pressure: 10 percent, including losses through water-service piping, valves, and backflow preventers.
   b. Sprinkler Occupancy Hazard Classifications as per NFPA.
3. Minimum Density for Automatic-Sprinkler Piping Design as per NFPA:
4. Maximum Protection Area per Sprinkler: According to UL listing.

2.2 STEEL PIPE AND FITTINGS

A. Standard-Weight, SCHEDULE 40 Black-Steel Pipe: ASTM A 53/A 53M, Type E, Grade B. Pipe ends may be factory or field formed to match joining method.

B. Schedule 10, Black-Steel Pipe: ASTM A 135/A 135M or ASTM A 795/A 795M, Schedule 10 in NPS 4 to NPS 5; and NFPA 13-specified wall thickness in NPS 6 to NPS 10, plain end.

C. Black-Steel Pipe Nipples: ASTM A 733, made of ASTM A 53/A 53M, standard-weight, seamless steel pipe with threaded ends.

D. Galvanized- and Uncoated-Steel Couplings: ASTM A 865/A 865M, threaded.

E. Malleable- or Ductile-Iron Unions: UL 860.

F. Cast-Iron Flanges: ASME 16.1, Class 125.

G. Steel Flanges and Flanged Fittings: ASME B16.5, Class 150.
   1. Pipe-Flange Gasket Materials: EPDM rubber gasket.
      a. Class 125 and Class 250, Cast-Iron, Flat-Face Flanges: Full-face gaskets.
      b. Class 150 and Class 300, Ductile-Iron or -Steel, Raised-Face Flanges: Ring-type gaskets.
   2. Metal, Pipe-Flange Bolts and Nuts: Carbon steel unless otherwise indicated.

H. Steel Welding Fittings: ASTM A 234/A 234M and ASME B16.9.
   1. Welding Filler Metals: Comply with AWS D10.12M/D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.

I. Grooved-Joint, Steel-Pipe Appurtenances:
   1. Pressure Rating: 175-psig minimum.
   2. Galvanized Painted Uncoated Grooved-End Fittings for Steel Piping: ASTM A 47/A 47M, malleable-iron casting or ASTM A 536, ductile-iron casting, with dimensions matching steel pipe.
   3. Grooved-End-Pipe Couplings for Steel Piping: AWWA C606 and UL 213 rigid pattern, unless otherwise indicated, for steel-pipe dimensions. Include ferrous housing sections, EPDM-rubber gasket, and bolts and nuts.

2.3 SPECIALTY VALVES

A. Listed in UL's "Fire Protection Equipment Directory" or FM Global's "Approval Guide."

B. Pressure Rating:
1. Standard-Pressure Piping Specialty Valves: 175-psig minimum.

C. Body Material: Cast or ductile iron.

D. Size: Same as connected piping.

E. End Connections: Flanged or grooved.

2.4 SPRINKLERS

A. Manufacturers shall be one of the following:
1. Viking Corporation.
2. Reliable Automatic Sprinkler Co.
3. Grinnel.
4. Tyco Fire & Building Products.

B. Listed in UL's "Fire Protection Equipment Directory" or FM Global's "Approval Guide."

C. Pressure Rating for Residential Sprinklers: 175-psig maximum.

D. Pressure Rating for Automatic Sprinklers: 175-psig minimum.

E. Automatic Sprinklers with Heat-Responsive Element:
1. Early-Suppression, Fast-Response Applications: UL 1767.
2. Nonresidential Applications: UL 199.
3. Residential Applications: UL 1626.
4. Characteristics: Nominal 1/2-inch orifice with Discharge Coefficient K of 5.6, and for "Ordinary" temperature classification rating unless otherwise indicated or required by application.

F. Open Sprinklers with Heat-Responsive Element Removed: UL 199.
1. Nominal Orifice: 1/2 inch, with discharge coefficient K between 5.3 and 5.8.

G. Sprinkler Finishes: Chrome plated.

H. Sprinkler Escutcheons: Materials, types, and finishes for the following sprinkler mounting applications. Escutcheons for concealed, flush, and recessed-type sprinklers are specified with sprinklers.
1. Ceiling Mounting: Chrome-plated steel, one piece, flat.
2. Sidewall Mounting: Chrome-plated steel, one piece, flat.

I. Sprinkler Guards:
1. Standard: UL 199.
2. Type: Wire cage with fastening device for attaching to sprinkler.

2.5 ALARM DEVICES

A. Alarm-device types shall match piping and equipment connections.

B. Water-Motor-Operated Alarm:
1. Standard: UL 753.
2. Type: Mechanically operated, with Pelton wheel.
3. Alarm Gong: Cast aluminum with red-enamel factory finish.
4. Size: 8-1/2-inches diameter.
5. Components: Shaft length, bearings, and sleeve to suit wall construction.
6. Inlet: NPS 3/4.
7. Outlet: NPS 1 drain connection.

C. Electrically Operated Alarm Bell:
1. Standard: UL 464.
2. Type: Vibrating, metal alarm bell.
3. Size: [6-inch minimum-] [8-inch minimum-] [10-inch] diameter.
4. Finish: Red-enamel factory finish, suitable for outdoor use.
5. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application

D. Water-Flow Indicators:
1. Standard: UL 346.
2. Water-Flow Detector: Electrically supervised.
3. Components: Two single-pole, double-throw circuit switches for isolated alarm and auxiliary contacts, 7 A, 125-V ac and 0.25 A, 24-V dc; complete with factory-set, field-adjustable retard element to prevent false signals and tamperproof cover that sends signal if removed.
4. Type: Paddle operated.
5. Pressure Rating: 250 psig.
6. Design Installation: Horizontal or vertical.

E. Pressure Switches:
1. Standard: UL 346.
2. Type: Electrically supervised water-flow switch with retard feature.
3. Components: Single-pole, double-throw switch with normally closed contacts.
4. Design Operation: Rising pressure signals water flow.

F. Valve Supervisory Switches:
1. Standard: UL 346.
2. Type: Electrically supervised.
3. Components: Single-pole, double-throw switch with normally closed contacts.
4. Design: Signals that controlled valve is in other than fully open position.
5. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application

2.6 PRESSURE GAGES

A. Standard: UL 393.

B. Dial Size: 3-1/2- to 4-1/2-inch diameter.

C. Pressure Gage Range: 0- to 250-psig minimum.

D. Label: Include "WATER" label on dial face.

PART 3 - EXECUTION

3.1 PREPARATION

A. Perform fire-hydrant flow test according to NFPA 13 and NFPA 291. Use results for system design calculations required in "Quality Assurance" Article.

B. Report test results promptly and in writing.

3.2 SERVICE-ENTRANCE PIPING

A. Reuse existing water-service piping for service entrance to building.

B. Reuse the existing shutoff valve, check valve, pressure gage, and drain at connection to water service.

3.3 PIPING INSTALLATION

A. Locations and Arrangements: Drawing plans, schematics, and diagrams indicate general location and arrangement of piping. Install piping as indicated on approved working plans.
   1. Deviations from approved working plans for piping require written approval from authorities having jurisdiction. File written approval with Architect before deviating from approved working plans.
   2. Coordinate layout and installation of sprinklers with other construction that penetrates ceilings, including light fixtures, HVAC equipment, and partition assemblies.

B. Piping Standard: Comply with NFPA 13 requirements for installation of sprinkler piping.

C. Use listed fittings to make changes in direction, branch takeoffs from mains, and reductions in pipe sizes.

D. Install unions adjacent to each valve in pipes NPS 2 and smaller.

E. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.

F. Install "Inspector's Test Connections" in sprinkler system piping, complete with shutoff valve, and sized and located according to NFPA 13.

G. Install sprinkler piping with drains for complete system drainage.

H. Install sprinkler control valves, test assemblies, and drain risers adjacent to standpipes when sprinkler piping is connected to standpipes.

I. Install automatic (ball drip) drain valve at each check valve for fire-department connection, to drain piping between fire-department connection and check valve. Install drain piping to and spill over floor drain or to outside building.

J. Install alarm devices in piping systems.

K. Install pressure gages on riser or feed main, at each sprinkler test connection, and at top of each standpipe. Include pressure gages with connection not less than NPS 1/4 and with soft-metal seated globe valve, arranged for draining pipe between gage and valve. Install gages to permit removal, and install where they are not subject to freezing.

L. Fill sprinkler system piping with water.

M. Install electric heating cables and pipe insulation on sprinkler piping in areas subject to freezing.

N. Install sleeves for piping penetrations of walls, ceilings, and floors.

O. Install escutcheons for piping penetrations of walls, ceilings, and floors.

3.4 JOINT CONSTRUCTION

A. Install couplings, flanges, flanged fittings, unions, nipples, and transition and special fittings that have finish and pressure ratings same as or higher than system's pressure rating for aboveground applications unless otherwise indicated.

B. Install unions adjacent to each valve in pipes NPS 2 and smaller.

C. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.

D. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.

E. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.

F. Flanged Joints: Select appropriate gasket material in size, type, and thickness suitable for water service. Join flanges with gasket and bolts according to ASME B31.9.

G. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
   1. Apply appropriate tape or thread compound to external pipe threads.
   2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.

H. Twist-Locked Joints: Insert plain end of steel pipe into plain-end-pipe fitting. Rotate retainer lugs one-quarter turn or tighten retainer pin.

I. Steel-Piping, Pressure-Sealed Joints: Join lightwall steel pipe and steel pressure-seal fittings with tools recommended by fitting manufacturer.

J. Welded Joints: Construct joints according to AWS D10.12M/D10.12, using qualified processes and welding operators according to "Quality Assurance" Article.
   1. Shop weld pipe joints where welded piping is indicated. Do not use welded joints for galvanized-steel pipe.

K. Steel-Piping, Cut-Grooved Joints: Cut square-edge groove in end of pipe according to AWWA C606. Assemble coupling with housing, gasket, lubricant, and bolts. Join steel pipe and grooved-end fittings according to AWWA C606 for steel-pipe joints.

L. Steel-Piping, Roll-Grooved Joints: Roll rounded-edge groove in end of pipe according to AWWA C606. Assemble coupling with housing, gasket, lubricant, and bolts. Join steel pipe and grooved-end fittings according to AWWA C606 for steel-pipe grooved joints.

M. Steel-Piping, Pressure-Sealed Joints: Join Schedule 5 steel pipe and steel pressure-seal fittings with tools recommended by fitting manufacturer.

N. Dissimilar-Material Piping Joints: Make joints using adapters compatible with materials of both piping systems.

3.5 VALVE AND SPECIALTIES INSTALLATION

A. Install listed fire-protection valves, trim and drain valves, specialty valves and trim, controls, and specialties according to NFPA 13 and authorities having jurisdiction.

B. Install listed fire-protection shutoff valves supervised open, located to control sources of water supply except from fire-department connections. Install permanent identification signs indicating portion of system controlled by each valve.

C. Install check valve in each water-supply connection. Install backflow preventers instead of check valves in potable-water-supply sources.

D. Specialty Valves:
   1. Install valves in vertical position for proper direction of flow, in main supply to system.
   2. Install alarm valves with bypass check valve and retarding chamber drain-line connection.

3.6 SPRINKLER INSTALLATION

A. Install sprinklers in suspended ceilings in center of acoustical ceiling panels.

B. Install dry-type sprinklers with water supply from heated space. Do not install pendent or sidewall, wet-type sprinklers in areas subject to freezing.

C. Install sprinklers with stainless steel braided fully welded flexible, sprinkler hose fittings, and install hose into bracket on ceiling grid. Flexible hose shall not use gaskets and shall be true 1” hose sizes.

3.7 IDENTIFICATION

A. Install labeling and pipe markers on equipment and piping according to requirements in NFPA 13.

B. Identify system components, wiring, cabling, and terminals.

3.8 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:
1. Leak Test: After installation, charge systems and test for leaks. Repair leaks and retest until no leaks exist.
2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
3. Flush, test, and inspect sprinkler systems according to NFPA 13, "Systems Acceptance" Chapter.
4. Energize circuits to electrical equipment and devices.
5. Coordinate with fire-alarm tests. Operate as required.
6. Verify that equipment hose threads are same as local fire department equipment. Provide letter to Architect with the approval of the thread type by the local fire department equipment.

B. Sprinkler piping system will be considered defective if it does not pass tests and inspections.

C. Prepare test and inspection reports.

3.9 CLEANING

A. Clean dirt and debris from sprinklers.

B. Only sprinklers with their original factory finish are acceptable. Remove and replace any sprinklers that are painted or have any other finish than their original factory finish.

3.10 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain specialty valves.

3.11 PIPE HANGERS AND SUPPORTS

A. This Contractor shall furnish and install all foundations and supports required for his equipment unless indicated otherwise on the Drawings.

B. This Contractor shall furnish and install all escutcheons, inserts, thimbles, hangers, saddles, etc. required for the proper support and installation of his equipment and piping and he shall cooperate with other trades in locating and placing these items.

3.12 PIPING SCHEDULE

A. Piping between Fire Department Connections and Check Valves: Galvanized, standard-weight steel pipe with threaded ends, cast-iron threaded fittings, and threaded grooved ends, grooved-end fittings, grooved-end-pipe couplings, and grooved joints.

B. Sprinkler specialty fittings may be used, downstream of control valves, instead of specified fittings.

C. Piping within the building 4" and smaller shall be Schedule 40 black steel pipe with threaded fittings. Piping larger than 4” shall be Schedule 40 black steel pipe with welded fittings. At Contractor's option, piping larger than 4" may be Schedule 10. At Contractor's option, roll grooved pipe with mechanical couplings may be used. Schedule 5 piping is not acceptable.

3.13 MECHANICAL GROOVED PIPING

A. At the contractor's option, roll grooved piping and fittings may be used for the Fire Protection and HVAC piping systems inside building in lieu of connections hereinbefore specified. Cut grooved piping is not acceptable.

B. Couplings shall be fabricated in two or more parts of malleable iron castings, in accordance Federal Specification QQ-I-666c, Grade II. Couplings gasket shall be molded synthetic rubber, per ASTM-D-75-61, Grade No. R615BZ. Coupling bolts shall be oval neck track head type with hexagonal heavy nuts, per ASTM A-183-60.

C. All pipe fittings shall be fabricated of malleable iron castings in accordance with Federal Specifications QQ-1-666c, Grade II. Where malleable fitting pattern is not available, fittings fabricated from Schedule 40 steep pipe or standard wall seamless welded fittings with grooved ends may be used.

D. Before assembly of couplings, light coat pipe ends and outside of gaskets with cup grease or graphite paste to facilitate installation.

E. Pipe grooving shall be in accordance with the manufacturer’s specifications contained in latest published literature.

3.14 VICTAULIC COUPLINGS

A. At the contractor's option, Victaulic couplings and fittings may be used for the Fire Protection and HVAC piping systems inside building in lieu of connections hereinbefore specified.

B. Couplings shall be manufactured in two or more parts of ASTM A-395 grade 65-45-15 and A-536 grade 65-45-12 ductile iron castings. Coupling gaskets shall be suited for the intended service as per manufacturer’s guidelines and recommendations. Coupling bolts shall be zinc-plated carbon steel track head type with hexagonal heavy nuts, per ASTM A-183-60.

C. Rigid Couplings shall be Victaulic Style 07, FireLock™ Style 005, or equal with offsetting angle-pattern bolt pads, to provide rigidity and piping system support and hanging requirements in accordance with ANSI B31.1, B31.9, and NFPA 13.

D. Flexible Couplings shall be Victaulic Style 75, or Victaulic Style 77, or equal: Flexible Couplings shall used in locations where stress relief and vibration attenuation are required. Couplings shall be placed in close proximity to the vibration source.

E. Flange Adapters shall be Victaulic Style 741, or equal. Flange adapters shall be Class 150 flange adapters for grooved end pipe shall be manufactured in two or more parts of ASTM A-395 grade 65-45-15 and A-536 grade 65-45-12 ductile iron castings. Flange adapter gaskets shall be suited for the intended service as per manufacturer's guidelines and recommendations.

F. All pipe fittings used with pipe couplings shall be fabricated of ductile iron conforming to ASTM A-395 grade 65-45-15 and A-536 grade 65-45-12 or forged carbon steel conforming to ASTM A234 grade WPB. Where Victaulic ductile iron or forged carbon steel fitting patterns are not available, fittings fabricated from schedule 40 steel pipe conforming to ASTM A-53 with grooved ends may be used. Fittings used in fire protection service shall be UL listed and FM approved, equal to Victaulic FireLock™ fittings.

G. Pipe ends shall be clean and free from indentations, projections, and roll marks. Before assembly of couplings, lightly coat pipe ends and outside of gaskets with lubricant, cup grease or graphite paste to facilitate installation.

H. Pipe grooving shall be in accordance with the manufacturer's specifications contained in latest published literature.

I. All grooved couplings, fittings and flange adapters shall be the products of the same manufacturer. Grooving tools shall be of the same manufacturer as the grooved end components.

3.15 SPRINKLER SCHEDULE

A. Use sprinkler types in subparagraphs below for the following applications:
   1. Rooms without Ceilings: Upright sprinklers with wire guards.
   2. Rooms with Suspended Ceilings: Concealed sprinklers.
   3. Wall Mounting: Sidewall sprinklers.
   4. Spaces Subject to Freezing: Pendent, dry sprinklers.
   5. Special Applications: Extended-coverage, flow-control, and quick-response sprinklers where indicated.

B. Provide sprinkler types in subparagraphs below with finishes indicated.
   1. Concealed Sprinklers: Rough brass, with factory-painted white cover plate.
   2. Upright and Sidewall Sprinklers: Chrome plated in finished spaces exposed to view; rough bronze in unfinished spaces not exposed to view; wax coated where exposed to acids, chemicals, or other corrosive fumes.

END OF SECTION 21 13 13

SECTION 22 00 00 – PLUMBING GENERAL PROVISIONS

PART 1 - GENERAL

1.1 SUMMARY

A. The General Conditions of the Architectural Specifications, along with the supplementary conditions, special conditions, information to bidders, and any other pertinent information and documents shall apply the same as if repeated herein.

1.2 SCOPE OF WORK

A. Furnish all labor and material necessary to provide and install the complete mechanical portion of this Contract, including plumbing systems as called for herein and on accompanying drawings. Parts of the mechanical division may be bid separately or in combination, at the Contractor's option; however, it shall be the responsibility of the General Contractor to assure himself that all items covered in this Division have been included if he chooses to accept separate bids.

B. This Contractor shall refer to the Architectural and Structural drawings and install equipment, piping, etc. to meet building and space requirements. No equipment shall be bid on or submitted for approval if it will not fit in the space provided.

C. It is the intention of these Specifications that all mechanical systems shall be furnished complete with all necessary valves, controls, insulation, piping, devices, equipment, etc. necessary to provide a satisfactory installation in working order.

D. Contractor shall visit the site and acquaint himself thoroughly with all existing facilities and conditions that would affect his portion of the work. Failure to do so shall not relieve the Contractor from the responsibility of installing his work to meet the conditions.

E. This Contractor shall protect the entire system and all parts thereof from injury throughout the project and up to acceptance of the work. Failure to do so shall be sufficient cause for the Architect to reject any piece of equipment.

1.3 DEMOLITION

A. The contractor shall visit the site prior to bid to determine the extent of work required to complete the project.

B. Contractor shall coordinate demolition with owner. The Owner shall have “First Right of Refusal” regarding salvage of all equipment and materials to be removed. Locate equipment as directed by owner. All equipment and materials not salvaged by the owner shall be removed from the site and discarded at the contractor’s expense.

C. Contractor shall coordinate all work with general contractor and phase work as required by project.

D. All equipment piping, etc. required to be removed to accommodate the modifications shall be removed.

E. Contractor shall maintain services to existing facilities which shall remain during and after construction is complete.

F. Contractor shall coordinate any shutdown of services with the owner. It is intended that the building will remain occupied during construction. Contractor shall schedule shut down of services with the owner in order to prevent disruption of building occupancy.

G. Contractor shall be responsible for draining down of existing systems to complete demolition. All work shall be scheduled with the owner. Contractor shall also be responsible for refilling system and removing all air in order to return the systems to proper operating conditions.

H. All shut down of services shall be done at night or during a time period approved by the owner. The systems shall be required to be back up and running each morning unless otherwise approved by the owner.

1.4 GROUNDS AND CHASES

A. This Contractor shall see that all required chases, grounds, holes and accessories necessary for the installation of his work are properly built in as the work progresses; otherwise, he shall bear the cost of providing them.

1.5 CUTTING AND PATCHING

A. Initial cutting and patching shall be the responsibility of the General Contractor, with the Mechanical Contractor being responsible for laying out and marking any and all holes required for the reception of his work. No structural beams or joists shall be cut or thimbled without first receiving the approval of the Architect. After initial surfacing has been done, any further cutting, patching and painting shall be done at this Contractor's expense.

1.6 FILL AND CHARGES FOR EQUIPMENT

A. Fill and charge with materials or chemicals all those devices or equipment as required to comply with the manufacturer's guarantee or as required for proper operation of the equipment.

1.7 MACHINERY GUARDS

A. This Contractor shall provide v-belt guards for each v-belt drive or other hazardous drive. The guard shall enclose the drive entirely and shall have a hole for taking a tachometer reading.

B. Provide protective guard for belts, pulleys, gears, couplings, projecting set screws, keys and other rotating parts which are located such that a person might come in close proximity.

Construct protective guard around angle iron frame, securely bolted to apparatus; comply with safety requirements. Install guard to completely enclose drives and pulleys and not interfere with lubrication of equipment. Provide 2 inch minimum diameter opening in fan belt guards housing for tachometer.

1.8 REPAIRING ROADWAYS AND WALKS

A. Where this Contractor cuts or breaks roadways or walks, in order to lay piping, he shall repair or replace these sections to meet the Architect's approval.

1.9 EXCAVATION AND BACKFILL

A. Contractor shall perform all excavating necessary to lay the specified services. Perform excavation of every description and of whatever substance encountered to depths indicated or specified. Pile materials suitable for backfilling a sufficient distance from banks of trenches to prevent slides or cave-ins. Comply with OSHA requirements for excavation, trenching and shoring. Waste excavation materials, rubbish, etc. shall be carted away from the premises, as indicated. Remove water from trenches by pumping or other approved method, discharge at a safe distance from the excavation.

B. Provide trenches of necessary width for proper laying of pipe and comply with latest publication of OSHA 2226 Excavating and Trenching Operations. Coordinate trench excavation with pipe installation to avoid open trenches for prolonged periods. Accurately grade bottoms of trenches to provide uniform bearing and support for each section of pipe on undisturbed soil or the required thickness of bedding material at every point along its entire length.

C. Provide minimum 12 inches between outer surfaces and embankment or shoring, which may be used, when excavating for manholes and similar structures. Remove unstable soil that is incapable of supporting the structure in the bottom of the excavation to the depth necessary to obtain design bearing.

D. Material to be excavated is “unclassified”. No adjustment in the contract price will be made on account of the presence or absence of rock, shale, masonry, or other materials.

E. Protect existing utility lines that are indicated or the locations of which are made known prior to excavating and trenching and that are to be retained. Protect utility lines encountered during excavating and trenching operations, from damage during excavating, trenching and backfilling; if damaged, repair lines as directed by utilities, owner and A/E. Issue notices when utility lines that are to be removed are encountered within the area of operations in ample time for the necessary measures to be taken to prevent interruption of the service.

F. Provide trenches for utilities of a depth that will provide the following minimum depths of cover from existing grade or from indicated finished grades, or depths of cover in accordance with the manufacturer’s recommendations, whichever is lower:
   1. 1-Foot Minimum Cover: Sanitary sewer, storm drainage, industrial waste, acid waste.
   2. 3-Feet Minimum Cover: Domestic water, fire line.

G. Underground domestic water piping and fire line piping shall have a 6" bed of sand below the piping and backfilled with sand to 6" above the top of piping. Select fill may be used above the sand layer.

H. Backfill trenches after piping, fittings and joints have been tested and approved. Backfill trenches with sand to provide 6 inches of sand below piping and 12 inches of sand cover above piping.

I. Backfill remainder of trenches with satisfactory material consisting of earth, loam, sandy clay, sand and gravel or soft shale, free from large clods of earth and stones not over 1-1/2 inches in size. Deposit backfill material in 9 inch maximum layers, loose depth as indicated or as specified. Take care not to damage utility lines.

J. Deposit the remainder of backfill materials in the trench in 1 foot maximum layers and compact by mechanical means. Refer to architectural for minimum density for compaction (Minimum 85 percent of maximum soil density as determined by ASTM D 698). Re-open trenches and excavation pits improperly backfilled or where settlement occurs to the depth required to obtain the specified compaction, the refill and compact with the surface restored to the required grade and compaction.

K. Backfill utility line trench with backfill material, in 6 inch layers, where trenches cross streets, driveways, building slabs, or other pavement. Moisten each layer and compact to 95 percent of the maximum soil density as determined by ASTM D 698. Accomplish backfilling in such a manner as to permit the rolling and compaction of the filled trench with the adjoining material to provide the required bearing value so that paving of the area can proceed immediately after backfilling is complete.

1.10 NOISE AND VIBRATION

A. Provide the plumbing system and its associated components, items, piping, and equipment free of objectionable vibration or noise. Statically and dynamically balance rotating equipment and mount or fasten so that no vibration is transmitted to or through the building structure by equipment, piping, ducts or other parts of work, rectify such conditions at no additional compensation.

1.11 PAINTING

A. All painting shall be by the General Contractor's Painting Sub-Contractor. All pipe, pipe covering, equipment, supports, hangers, etc. exposed in the building or equipment room shall be painted. This Contractor shall prepare the surface of the material to receive the first coat of paint.

B. All subsequent coatings shall be prepared by the Painting Sub-Contractor. Requirements covering paints, workmanship and preparation of surfaces as stated in the Architectural Specifications shall govern. Colors shall be approved by the Architect. All piping shall be color-coded. All subsequent coatings shall be prepared by the Painting Sub-Contractor. Requirements covering paints, workmanship and preparation of surfaces as stated in the Architectural Specifications shall govern. Colors shall be approved by the Architect. All piping shall be color-coded.

C. All piping shall be color coded per the following:

1.	Natural Gas Piping (Exposed in Mechanical Room)	Yellow
2.	Natural Gas Piping (Outdoor, Roof, Exterior of Building)	Yellow
3.	Natural Gas Piping (Exposed in Building)	Black
4.	Sanitary Sewer Waste & Vent (Exposed in Building)	Black

   a. Thermoplastic pipe and fittings shall be painted using latex(water base) paint .
   b. Pipe should be cleaning to remove moisture, dirt and oil; then wiped with a clean, dry cloth.
   c. Do not use petroleum based paints.

1.12 CLEANING AND ADJUSTING

A. Upon completion of his work, the Contractor shall clean and adjust all equipment, controls, valves, etc.; clean all piping, ductwork, etc.; and leave the entire installation in good working order.

1.13 OPERATING AND MAINTENANCE INSTRUCTIONS

A. Provide the Owner with three (3) copies of printed instructions indicating various pieces of equipment by name and model number, complete with parts lists, maintenance and repair instructions and test and balance report.

B. COPIES OF SHOP DRAWINGS WILL NOT BE ACCEPTABLE AS OPERATION AND MAINTENANCE INSTRUCTIONS BUT MUST BE INCLUDED IN SUBMITTAL PACKAGE.

C. This information shall be bound in plastic hardbound notebooks with the job name permanently embossed on the cover. Rigid board dividers with labeled tabs shall be provided for different pieces of equipment. Submit manuals to the Architect for approval.

D. In addition to the operation and maintenance brochure, the Contractor shall provide a separate brochure which shall include registered warranty certificates on all equipment, especially any pieces of equipment which carry warranties exceeding one (1) year.

E. The operation and maintenance brochure shall be furnished with a detailed list of <u>all</u> equipment furnished to the project, including the serial number and all pertinent nameplate data such as voltage, amperage draw, recommended fuse size, rpm, etc. The Contractor shall include this data on <u>each</u> piece of equipment furnished under this contract.

1.14 GUARANTEE

A. The Contractor shall guarantee all materials, equipment and workmanship for a period of one (1) year from the date of final acceptance of the project. This guarantee shall include furnishing of all labor and material necessary to make any repairs, adjustments or replacement of any equipment, parts, etc. necessary to restore the project to first class condition. This guarantee shall exclude only the changing or cleaning of filters. Warranties exceeding one (1) year are hereinafter specified with individual pieces of equipment.

1.15 LOCAL CONDITIONS

A. The location and elevation of all utility services is based on available surveys and utility maps and are reasonably accurate; however, these shall serve as a general guide only, and the Contractor shall visit the site and verify the location and elevation of all services to his satisfaction in order to determine the amount of work required for the execution of the Contract.

B. The Contractor shall contact the various utility companies, determine the extent of their requirements and he shall include in his bid all lawful fees and payments required by these companies for complete connection and services to the building, including meters, connection charges, street patching, extensions from meters to main, etc.

C. In case major changes are required, this fact, together with the reasons therefor, shall be submitted to the Architect, in writing, not less than seven (7) days before the date of bidding. Failure to comply with this requirement will make the Contractor liable for any changes, additions and expenses necessary for the successful completion of the project.

1.16 PERMITS, INSPECTIONS AND TESTS

A. All permits, fees, etc. for the installation, inspections, plan review, service connections locations, and/or construction of the work which are required by any authority and/or agencies having jurisdiction, shall be obtained and paid for by the Contractor. This shall be verified during the bidding process.

B. The Contractor shall make all tests required by the Architect, Engineer or other governing authorities at no additional cost to the Owner.

C. The Contractor shall notify the Architect and local governing authorities before any tests are made, and the tests are not to be drawn off a line covered or insulated until examined and approved by the authorities. In event defects are found, these shall be corrected and the work shall be retested.

D. Prior to requesting final inspection by the Architect, the Contractor shall have a complete coordination and adjustment meeting of all of his sub-contractors directly responsible for the operation of any portion of the system. At the time of this meeting, each and every sequence of operation shall be checked to assure proper operation. Notify the Architect in writing ten (10) days prior to this meeting, instructing him of the time, date and whom you are requesting to be present.

E. This project shall not be accepted until the above provisions are met to the satisfaction of the Architect.

1.17 CODES AND STANDARDS

A. The entire mechanical work shall comply with the rules and regulations of the City, Parish, County and the State in which this project is being constructed, including the State Fire Marshal and the State Department of Health. Modifications required by these authorities shall be made without additional charge to the Owners. The Contractor shall report these modifications to the Architect and secure his approval before work is started.

B. In addition to the codes heretofore mentioned, mechanical work and equipment shall conform to the applicable portions of the following specifications, codes and/or regulations:
   1. American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
   2. National Electrical Code (NEC)
   3. National Fire Protection Association (NFPA)
   4. American Society of Mechanical Engineers (ASME)
   5. American Gas Association (AGA)
   6. International Building Code (IBC)
   7. International Mechanical Code (IMC)
   8. International Plumbing Code (IPC)
   9. International Fuel Gas Code (IFGC)
   10. Underwriters Laboratories (UL)
   11. Life Safety Code (NFPA 101)
   12. State Sanitary Code
   13. Louisiana State Uniform Construction Code Council (LSUCCC)

C. All materials, equipment and accessories installed under this Contract shall conform to all rules, codes, etc. as recommended by National Associations governing the manufacturer, rating and testing of such materials, equipment and accessories. All materials shall be new and of the best quality and first class in every respect. Whenever directed by the Architect, the Contractor shall submit a sample for approval before proceeding.

D. Where laws or local regulations provide that certain accessories such as gauges, thermometers, relief valves and parts be installed on equipment, it shall be understood that such equipment be furnished complete with the necessary accessories, whether or not called for in these Specifications.

E. All unfired pressure vessels shall be built in accordance with the A.S.M.E. Code and so stamped. Furnish shop certificates for each vessel.

1.18 REVIEW OF MATERIALS

A. Whenever manufacturers or trade names are mentioned in these Plans or Specifications, the words "or approved equivalent" shall be assumed to follow whether or not so stated. Manufacturers or trade names are used to establish a standard of quality only, and should not be construed to infer a preference. Equivalent products which meet the Architect's approval will be accepted; however, these products must be submitted to the Architect a minimum of seven (7) days prior to the Bid Date.

B. Submission shall include the manufacturer's name, model number, rating table and construction features.

C. Upon receipt and checking of this submittal, the Architect will issue an addendum listing items which are approved as equivalent to those specified. THE CONTRACTOR SHALL BASE HIS BID SOLELY ON THOSE ITEMS SPECIFIED OR INCLUDED IN THE "PRIOR APPROVAL ADDENDUM", AS NO OTHER ITEM WILL BE ACCEPTABLE.

D. Prior approval of a particular piece of equipment does not mean automatic final acceptance and will not relieve the Contractor of the responsibility of assuring himself that this equipment is in

complete accord with the Plans and Specifications and that it will fit into the space provided. Shop drawings must be submitted on all items of equipment for approval as hereinafter specified.

E. Before proceeding with work and/or within thirty (30) days after the award of the General Contract for this work, the Mechanical Contractor shall furnish to the Architect complete shop and working drawings of such apparatus, equipment, controls, insulation, etc. to be provided in this project. These drawings shall give dimensions, weights, mounting data, performance curves and other pertinent information.

F. The Architect's approval of shop drawings shall not relieve the Contractor from the responsibility of incorrectly figured dimensions or any other errors which may be contained in these drawings. Any omission from the shop drawings or specifications, even though approved by the Architect, shall not relieve the Contractor from furnishing and erecting same.

G. Six (6) sets of shop drawings shall be submitted to the Architect for approval. These submittals shall be supplied as part of this Contractor's contract. Any drawings not approved shall be resubmitted until they are approved.

H. This information shall be bound in plastic hardbound notebooks with the job name permanently embossed on the cover. Rigid board dividers with labeled tabs shall be provided for different pieces of materials and equipment. Submit shop drawings to the Architect for approval. Faxed copies submissions will not be accepted.

1.19 MINOR DEVIATIONS

A. Plans and detail sketches are submitted to limit, explain and define conditions, specified requirements, pipe sizes and manner of erecting work. Structural or other conditions may require certain modifications from the manner of installation shown, and such deviations are permissible and shall be made as required. However, specified sizes and requirements necessary for satisfactory operation shall remain unchanged. It may be necessary to shift ducts or pipes, or to change the shape of ducts, and these changes shall be made as required. All such changes shall be referred to the Architect and Engineer for approval before proceeding. Extra charges shall not be allowed for these changes. The contractor shall obtain a full set of plans and specifications for the coordination of his work prior to bidding this project. Items which are unclear to the bidding contractor shall be brought to the Architect and Engineers attention prior to bidding the project. An interpretation shall be clarified by the Architect and/or the Engineer prior to bidding.

B. The Contractor shall realize that the drawings could delve into every step, sequence or operation necessary for the completion of the project, without drawing on the Contractor's experience or ingenuity. However, only typical details are shown on the Plans. In cases where the Contractor is not certain about the method of installation of his work, he shall ask for details. Lack of details will not be an excuse for improper installation.

C. In general, the drawings are diagrammatic and the Contractor shall install his work in a manner so that interferences between the various trades are avoided. In cases where interferences do occur, the Architect is to state which item was first installed.

1.20 AS-BUILT RECORD DRAWINGS

A. The Contractor shall obtain at his cost, two sets of blue line prints of the original bid documents by the Architect. One set shall be kept on the site with all information as referenced below, and shall update same as the work progresses. The other set will be utilized to record all field changes to a permanent record copy for the Owner.

B. If the Contractor elects to vary from the Contract Documents and secures prior approval from the Architect for any phase of the work, he shall record in a neat and readable manner, ALL such variances on the blackline print in red. The original blackline prints shall be returned to the Architect for documentation.

C. All deviations from sizes, locations, and from all other features of the installations shown in the Contract Documents shall be recorded.

D. In addition, it shall be possible using these drawings to correctly and easily locate, identify and establish sizes of all piping, directions and the like, as well as other features of the work which will be concealed underground and/or in the finished building.

E. Locations of underground work shall be established by dimensions to columns, lines or walls, locating all turns, etc., and by properly referenced centerline or invert elevations and rates of fall.

F. For work concealed in the building, sufficient information shall be given so it can be located with reasonable accuracy and ease. In some cases this may be by dimension. In others, it may be sufficient to illustrate the work on the drawings in relation to the spaces in the building near which it was actually installed. The Architect's/Engineer's decision in this matter will be final.

G. The following requirements apply to all "As-Built" drawings:
1. They shall be maintained at the Contractor’s expense.
2. All such drawings shall be done carefully and neatly, and in a form approved by the Architect/Engineer.
3. Additional drawings shall be provided as necessary for clarifications.
4. These drawings shall be kept up-to-date during the entire course of the work and shall be available upon request for examination by the Architect/Engineer; and when necessary, to establish clearances for other parts of the work.
5. “As-built” drawings shall be returned to the Architect upon completion of the work and are subject to approval of the Architect/Engineer.

1.21 REQUIRED SHOP DRAWING SUBMITTALS

A. Provide the following shop drawing submittals:
1. Pipe insulation.
2. All Valves.
3. Plumbing fixtures and trim.
4. Pipe and pipe fittings.
5. PVC jacket color samples.
6. Water Heaters.
7. Mixing Valves.
8. Pumps.

9. Sewer Lift Stations.
10. Sewer Treatment Plants.
11. Grease Traps and Interceptors.

PART 2 - PRODUCTS

2.1 PLUMBING PRODUCTS

A. Refer to individual Division 22 sections for plumbing products, pipe, tube and fitting materials and joining methods.

PART 3 - EXECUTION

3.1 MANUFACTURER'S DIRECTION

A. The contractor shall install and operate equipment and material in accordance with the manufacturer's installation and operating instructions. The manufacturer's instructions of installation and operation shall become part of the Contract Documents and shall supplement the Drawings and Specifications.

B. Store equipment in a clean, dry place protected from other construction. While stored, maintain factory wrapping or tightly cover and protect equipment against dirt, water, construction debris, chemical, physical or weather damage, traffic and theft.

3.2 EQUIPMENT LABELS

A. Provide equipment labels for water heaters and mixing valves. Labels shall have permanent laminated construction secured to equipment.

3.3 PIPE LABELS

A. Provide pipe markers and directional arrows on all piping in mechanical equipment rooms, or which is exposed in building, and on both sides of all valves located above ceiling. Markers shall be as manufactured by W.H. Bradley Co., Marking Services Inc. or the equivalent. All letters shall be color-coded and sized as recommended by OSHA. Samples of the type of letters to be used shall be submitted with shop drawings. Piping shall be color-coded.

B. Pipe markers with arrows shall indicate lines content and shall be located 20 feet on center and at each change of direction of line. Identification bands shall be color coded to match pipe markers and shall be provided 10 feet on center. Pipe identification markers shall be taped at each end and shall be taped around the entire circumference of pipe.

C. The following Piping shall be identified:
1. Domestic Cold Water
2. Domestic Hot Water

3. Domestic Hot Water Return
4. Natural Gas
5. Sanitary Sewer
6. Sanitary Vent
7. Condensate Drain
8. Condensate Return

3.4 VALVE TAGS

A. Secure metal tags to all valves. Labeling on all valve tags shall include type of system the valve controls and the area of building, zone, or equipment number affected by valve operation. Tag shall be 2"minimum diameter brass, engraved with code number, service and size. A framed list of the valves, giving manufacturer's name, model number, type and location shall be mounted in the main equipment room.

3.5 ACCESS DOORS:

A. Provide access doors in walls, floors and ceilings to permit access to equipment and piping requiring service or adjustment.
   1. Valves.
   2. Plumbing drainage cleanouts.
   3. Other Plumbing equipment indicated in schedules or specifications which are requiring maintenance, adjustment or operation.

B. Provide hinged access doors and frames as follows:
   1. Drywall Construction:
      a. Provide with concealed spring hinges and flush screwdriver operated cam locks in sufficient number of the size of the panel.
      b. Provide prime paintable surface (not galvanized).
      c. Product: Milcor “Style M” (Karp DSC-214M).
   2. Visible Masonry and Ceramic Tile:
      a. Milcor “Style M” (Karp DSC-214M).
   3. Cement Plaster:
      a. Milcor “Style K” (KarpDSC-214 PL).
   4. Acoustical Plaster:
      a. Reinforced panel as required to prevent sagging. Provide continuous steel piano type hinge for the length of the panel, and sufficient number for the size of the panel. Provide factory prime paint surface (not galvanized).
      b. Product: Milcor “Style AP” (Karp 214 PL).
   5. Acoustical Tile:
      a. Milcor “Style AT” (Larsen L-CPA).

C. Provide continuous concealed hinges and cam locks.

D. Provide UL listed 1-1/2 hour label “B” access doors with automatic self-closing latching mechanism where required.

E. Provide removable ceiling access tile section immediately adjacent to each mechanical or electrical device located in the ceiling plenum above removable tile ceiling.

F. Coordinate approval of type, color and location of access doors & frames with Architect.

3.6 CLEANING AND SERVICE

A. Upon Completion of this work, the contractor shall clean and adjust equipment, controls, valves, etc.;

B. Clean piping, fixtures, cleanout covers, floor drain covers, etc. and leave the entire installation in good working order.

C. Adjust flush valves and faucets to allow for proper operation.

END OF SECTION 23 00 00

SECTION 22 05 23 – GENERAL DUTY VALVES FOR PLUMBING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes the furnishing and installation of general duty valves for plumbing:

1.3 DEFINITIONS

A. CWP: Cold working pressure.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of valve.
   1. Certification that products comply with NSF 61 Annex G and NSF 372 (lead free).

1.5 DELIVERY, STORAGE, AND HANDLING

A. Prepare valves for shipping as follows:
   1. Protect internal parts against rust and corrosion.
   2. Protect threads, flange faces, and soldered ends.
   3. Set ball valves open to minimize exposure of functional surfaces.

B. Use the following precautions during storage:
   1. Maintain valve end protection.
   2. Store valves indoors and maintain at higher-than-ambient-dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS FOR VALVES

A. Source Limitations for Valves: Obtain each type of valve from single source from single manufacturer.

B. ASME Compliance:
   1. ASME B1.20.1 for threads for threaded end valves.

2. ASME B16.1 for flanges on iron valves.
3. ASME B16.5 for flanges on steel valves.
4. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
5. ASME B16.18 for solder-joint connections.
6. ASME B31.9 for building services piping valves.

C. NSF Compliance: NSF 61 Annex G and NSF 372 for valve materials for potable-water service.

D. Bronze valves shall be made with dezincification-resistant materials. Bronze valves made with copper alloy (brass) containing more than 15 percent zinc are not permitted.

E. Valve Pressure-Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.

F. Valve Sizes: Same as upstream piping unless otherwise indicated.

G. Valve Actuator Types:
1. Gear Actuator: For quarter-turn valves NPS 4 and larger.
2. Hand lever: For quarter-turn valves smaller than NPS 4.

H. Valves in Insulated Piping:
1. Include 2-inch stem extensions.
2. Extended operating handles of nonthermal-conductive material and protective sleeves that allow operation of valves without breaking vapor seals or disturbing insulation.
3. Memory stops that are fully adjustable after insulation is applied.

2.2 MANUFACTURERS

A. Valves shall be manufactured by one of the following:
1. Kitz.
2. Red & White.
3. Nibco.
4. Kennedy.
5. Crane.
6. Milwaukee.
7. Keystone.
8. Stockham.
9. Grinnell.
10. Mueller.
11. Jamesbury.
12. DeZurik.
13. Hammond.
14. Apollo.

2.3 BRONZE BALL VALVES

A. Two-Piece, Bronze Ball Valves with Full Port and Brass Trim:
1. Kitz 59/69, Apollo 77C, NIBCO Design S-580-70, Milwaukee BA-150-S, Red & White 5049F or equal, threaded ends of heating hot water and low pressure steam of Kitz 58/68,

Apollo 77CLF, NIBCO Design T-580-70, Milwaukee BA-100-S, Red & White 5044F or equal. For insulated piping systems, provide ball valves with extended stem, insulated handle with protective thermal barrier sleeve to prevent condensate moisture drip and pipe insulation deterioration.

2. Description:
   a. Standard: MSS SP-110.
   b. CWP Rating: 600 psig.
   c. SSP Rating: 150 psi.
   d. Body Design: Two piece.
   e. Body Material: Bronze.
   f. Ends: Threaded and soldered.
   g. Seats: PTFE.
   h. Stem: Brass. Blow-out proof.
   i. Ball: Chrome-plated brass.
   j. Port: Full.
   k. Vinyl covered steel handle.
   l. Lead Free.
   m. Conforms to ASTM B-62.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.

B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.

C. Examine threads on valve and mating pipe for form and cleanliness.

D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.

E. Do not attempt to repair defective valves; replace with new valves.

3.2 VALVE INSTALLATION

A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown. Unions are not required on flanged devices.

B. Locate valves for easy access and provide separate support where necessary.

C. Install valves in horizontal piping with stem at or above center of pipe.

D. Install valves in position to allow full stem movement.

E. Install valve tags.

F. All valves, unions, etc. where pipe is chrome plated shall have similar finish. All exposed supplies to plumbing fixtures shall be chrome plated.

3.3 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

A. If valves with specified CWP ratings are unavailable, the same types of valves with higher CWP ratings may be substituted.

B. All gas cocks, valves, etc. on gas lines shall have local utility company and AGA approval.

C. Select valves with the following end connections:
   1. For Copper Tubing, NPS 2 and Smaller: Solder ends, except provide threaded ends for heating hot water.
   2. For Copper Tubing, NPS 2-1/2 to NPS 4: Flanged ends except where threaded valve-end option is indicated in valve schedules below.
   3. For Copper Tubing, NPS 5 and Larger: Flanged ends.
   4. For Steel Piping, NPS 2 and Smaller: Threaded ends or grooved ends.
   5. For Steel Piping, NPS 2-1/2 to NPS 4: Grooved end or Flanged ends except where threaded valve-end option is indicated in valve schedules below.
   6. For Steel Piping, NPS 5 and Larger: Grooved end or Flanged ends.

3.4 DOMESTIC HOT- AND COLD-WATER VALVE SCHEDULE

A. Pipe NPS 3 and Smaller (above grade):
   1. Two-piece, bronze ball valves with full port and brass trim.

B. Domestic water valves (below grade):
   1. M & H AWWA Series C-509, NIBCO T113 (3/4" to 2"), NIBCO T619 (2-1/2" and above) resilient gate valve with low torque operation, positive shut-off, O- Ring seals, full epoxy coating and square valve stem end.
   2. Provide two (2) adjustable "TEE" handle valve wrenches to be turned over to the owner after construction is complete.

END OF SECTION 22 05 23

SECTION 22 05 29 – HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Metal pipe hangers and supports.
2. Trapeze pipe hangers.
3. Fiberglass pipe hangers.
4. Metal framing systems.
5. Fiberglass strut systems.
6. Thermal-hanger shield inserts.
7. Fastener systems.
8. Pipe stands.
9. Pipe positioning systems.
10. Equipment supports.

1.3 DEFINITIONS

A. MSS: Manufacturers Standardization Society of The Valve and Fittings Industry Inc.

1.4 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design trapeze pipe hangers and equipment supports, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

B. Structural Performance: Hangers and supports for plumbing piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.

1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: Show fabrication and installation details and include calculations for the following; include Product Data for components:

1. Trapeze pipe hangers.
2. Metal framing systems.
3. Fiberglass strut systems.
4. Pipe stands.
5. Equipment supports.

C. Delegated-Design Submittal: For trapeze hangers indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1. Detail fabrication and assembly of trapeze hangers.
2. Design Calculations: Calculate requirements for designing trapeze hangers.

1.6 INFORMATIONAL SUBMITTALS

A. Welding certificates.

1.7 QUALITY ASSURANCE

A. Structural Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

B. Pipe Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code.

PART 2 - PRODUCTS

2.1 METAL PIPE HANGERS AND SUPPORTS

A. Carbon-Steel Pipe Hangers and Supports:

1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
2. Galvanized Metallic Coatings: Pregalvanized or hot dipped.
3. Nonmetallic Coatings: Plastic coating, jacket, or liner.
4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

B. Stainless-Steel Pipe Hangers and Supports:

1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
2. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
3. Hanger Rods: Continuous-thread rod, nuts, and washer made of stainless steel.

C. Copper Pipe Hangers:

1. Description: MSS SP-58, Types 1 through 58, copper-coated-steel, factory-fabricated components.
2. Hanger Rods: Continuous-thread rod, nuts, and washer made of copper-coated steel.

2.2 TRAPEZE PIPE HANGERS

A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural carbon-steel shapes with MSS SP-58 carbon-steel hanger rods, nuts, saddles, and U-bolts.

2.3 METAL FRAMING SYSTEMS

A. MFMA Manufacturer Metal Framing Systems:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

   a. B-line, an Eaton business.
   b. Flex-Strut Inc.

2. Description: Shop- or field-fabricated pipe-support assembly for supporting multiple parallel pipes.
3. Standard: MFMA-4.
4. Channels: Continuous slotted steel channel with inturned lips.
5. Channel Nuts: Formed or stamped steel nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
7. Metallic Coating: Electroplated zinc.

2.4 THERMAL-HANGER SHIELD INSERTS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Buckaroos, Inc.
2. Carpenter & Paterson, Inc.
3. Clement Support Services.
4. National Pipe Hanger Corporation.

B. Insulation-Insert Material for Cold Piping: ASTM C 552, Type II cellular glass with 100-psig minimum compressive strength and vapor barrier.

C. Insulation-Insert Material for Hot Piping: Water-repellent treated, ASTM C 533, Type I calcium silicate with 100-psig minimum compressive strength.

D. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.

E. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.

F. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.5 FASTENER SYSTEMS

A. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

B. Mechanical-Expansion Anchors: Insert-wedge-type, stainless- steel anchors, for use in hardened portland cement concrete; with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

2.6 PIPE STANDS

A. General Requirements for Pipe Stands: Shop- or field-fabricated assemblies made of manufactured corrosion-resistant components to support roof-mounted piping.

B. Compact Pipe Stand: One-piece plastic unit with integral-rod roller, pipe clamps, or V-shaped cradle to support pipe, for roof installation without membrane penetration.

C. Low-Type, Single-Pipe Stand: One-piece [**plastic**] [**stainless-steel**] base unit with plastic roller, for roof installation without membrane penetration.

D. High-Type, Single-Pipe Stand:

1. Description: Assembly of base, vertical and horizontal members, and pipe support, for roof installation without membrane penetration.
2. Base: [**Plastic**] [**Stainless steel**].
3. Vertical Members: Two or more cadmium-plated-steel or stainless-steel, continuous-thread rods.
4. Horizontal Member: Cadmium-plated-steel or stainless-steel rod with plastic or stainless-steel, roller-type pipe support.

E. High-Type, Multiple-Pipe Stand:

1. Description: Assembly of bases, vertical and horizontal members, and pipe supports, for roof installation without membrane penetration.
2. Bases: One or more; plastic.

3. Vertical Members: Two or more protective-coated-steel channels.
4. Horizontal Member: Protective-coated-steel channel.
5. Pipe Supports: Galvanized-steel, clevis-type pipe hangers.

F. Curb-Mounting-Type Pipe Stands: Shop- or field-fabricated pipe supports made from structural-steel shapes, continuous-thread rods, and rollers, for mounting on permanent stationary roof curb.

2.7 PIPE POSITIONING SYSTEMS

A. Description: IAPMO PS 42, positioning system of metal brackets, clips, and straps for positioning piping in pipe spaces; for plumbing fixtures in commercial applications.

2.8 EQUIPMENT SUPPORTS

A. Description: Welded, shop- or field-fabricated equipment support made from structural carbon-steel shapes.

2.9 MISCELLANEOUS MATERIALS

A. Structural Steel: ASTM A 36/A 36M, carbon-steel plates, shapes, and bars; black and galvanized.

B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.

1. Properties: Nonstaining, noncorrosive, and nongaseous.
2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT INSTALLATION

A. Metal Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from the building structure.

B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.

1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified for individual pipe hangers.
2. Field fabricate from ASTM A 36/A 36M, carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1/D1.1M.

C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal framing systems.

D. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.

E. Fastener System Installation:

1. Install powder-actuated fasteners for use in lightweight concrete or concrete slabs less than 4 inches thick in concrete after concrete is placed and completely cured. Use operators that are licensed by powder-actuated tool manufacturer. Install fasteners according to powder-actuated tool manufacturer's operating manual.
2. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.

F. Pipe Stand Installation:

1. Pipe Stand Types except Curb-Mounted Type: Assemble components and mount on smooth roof surface. Do not penetrate roof membrane.
2. Curb-Mounted-Type Pipe Stands: Assemble components or fabricate pipe stand and mount on permanent, stationary roof curb. See Section 077200 "Roof Accessories" for curbs.

G. Pipe Positioning-System Installation: Install support devices to make rigid supply and waste piping connections to each plumbing fixture.

H. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.

I. Equipment Support Installation: Fabricate from welded-structural-steel shapes.

J. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.

K. Install lateral bracing with pipe hangers and supports to prevent swaying.

L. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.

M. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.

N. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.

O. Insulated Piping:

1. Attach clamps and spacers to piping.

a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.

2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.

a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.

3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.

a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.

4. Shield Dimensions for Pipe: Not less than the following:

a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
b. NPS 4: 12 inches long and 0.06 inch thick.
c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.

5. Pipes NPS 8 and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
6. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

3.2 EQUIPMENT SUPPORTS

A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.

B. Grouting: Place grout under supports for equipment and make bearing surface smooth.

C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.3 METAL FABRICATIONS

A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.

B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.

C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. Finish welds at exposed connections so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

3.4 ADJUSTING

A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.

B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.5 PAINTING

A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.

1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.

B. Touchup: Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal are specified in Section 099113 "Exterior Painting." Section 099123 "Interior Painting." Section 099600 "High-Performance Coatings."

C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

3.6 HANGER AND SUPPORT SCHEDULE

A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.

B. Comply with MSS SP-69 for pipe-hanger selections and applications that are not specified in piping system Sections.

C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finish.

D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.

E. Use carbon-steel pipe hangers and supports metal trapeze pipe hangers and metal framing systems and attachments for general service applications.

F. Use stainless-steel pipe hangers and stainless-steel or corrosion-resistant attachments for hostile environment applications.

G. Use copper-plated pipe hangers and copper attachments for copper piping and tubing.

H. Use padded hangers for piping that is subject to scratching.

I. Use thermal-hanger shield inserts for insulated piping and tubing.

J. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F, pipes NPS 4 to NPS 24, requiring up to 4 inches of insulation.
3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes NPS 3/4 to NPS 36, requiring clamp flexibility and up to 4 inches of insulation.
4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes NPS 1/2 to NPS 24 if little or no insulation is required.
5. Pipe Hangers (MSS Type 5): For suspension of pipes NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes NPS 3/4 to NPS 8.
7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8.
11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3.
12. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.
13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
14. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction might occur.

18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes NPS 2-1/2 to NPS 24, from single rod if horizontal movement caused by expansion and contraction might occur.
19. Complete Pipe Rolls (MSS Type 44): For support of pipes NPS 2 to NPS 42 if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is not necessary.
20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes NPS 2 to NPS 24 if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is not necessary.
21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes NPS 2 to NPS 30 if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.

K. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.

L. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.

M. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction, to attach to top flange of structural shape.
3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
6. C-Clamps (MSS Type 23): For structural shapes.
7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.

11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:

    a. Light (MSS Type 31): 750 lb.
    b. Medium (MSS Type 32): 1500 lb.
    c. Heavy (MSS Type 33): 3000 lb.

13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.

N. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.

O. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41, roll hanger with springs.
4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from hanger.
6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from base support.
7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from trapeze support.
8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:

    a. Horizontal (MSS Type 54): Mounted horizontally.
    b. Vertical (MSS Type 55): Mounted vertically.
    c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.

P. Comply with MSS SP-69 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.

Q. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.

R. Use mechanical-expansion anchors instead of building attachments where required in concrete construction.

S. Use pipe positioning systems in pipe spaces behind plumbing fixtures to support supply and waste piping for plumbing fixtures.

END OF SECTION 22 05 29

SECTION 22 07 19 – PLUMBING PIPING INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes insulating the following plumbing piping services:
   1. Domestic cold-water piping.
   2. Domestic hot-water piping.
   3. Sanitary drain piping receiving condensate.
   4. Supplies and drains for handicap-accessible lavatories and sinks.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated and for each application. Include thermal conductivity, water-vapor permeance, thickness, and jackets (both factory- and field-applied, if any).

1.4 QUALITY ASSURANCE

A. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84 by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
   1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
   2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

B. Comply with the following applicable standards and other requirements specified for miscellaneous components:
   1. Supply and Drain Protective Shielding Guards: ICC A117.1.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

B. Reject damaged, deteriorated, wet, or contaminated material and immediately remove from the site. Replace removed materials at no additional cost to Owner.

1.6 COORDINATION

A. Coordinate sizes and locations of supports, hangers, and insulation shields.

B. Coordinate clearance requirements with piping Installer for piping insulation application. Before preparing piping Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.

1.7 SCHEDULING

A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.

B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Insulation:
1. Pittsburgh-Corning.
2. Owens- Corning.
3. Certainteed.
4. Armacell.
5. Rubatex.
6. Knauf.
7. Johns Manville.

B. Jacketing:
1. Ceel-Co.
2. O’Brien.
3. Zeston.
4. Childers.
5. Pabco.

C. Adhesives:
1. Benjamin Foster.
2. Childers.
3. Vimasco.
4. B.E.H.

2.2 INSULATION MATERIALS

A. Comply with requirements in "Piping Insulation Schedule, General," "Indoor Piping Insulation Schedule," "Outdoor, Aboveground Piping Insulation Schedule," and "Outdoor, Underground Piping Insulation Schedule" articles for where insulating materials shall be applied.

B. Products shall not contain asbestos, lead, mercury, or mercury compounds.

C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.

D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.

E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.

F. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials.
1. Density of 5.0 lbs/cubic foot.
2. K factor of 0.27 at 75 degrees F mean.
3. Maximum water vapor transmission of 0.17 per inch.
4. Must be listed for 25/50 flame/smoke spread of thickness used.

G. Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 553, Type II and ASTM C 1290, Type I. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

H. Mineral-Fiber, Preformed Pipe Insulation: Type I, 850 Deg F Materials: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 547, Type I, Grade A, with factory-applied ASJ-SSL. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
1. All-service jacket ASJ-SSL type factory applied jacketing.
2. 6 lbs/cu ft minimum density.
3. k-factor of 0.31 maximum at 200 degrees F mean.
4. 850 degree F service temperature.
5. 0.02 perm maximum Jacket permeance.

2.3 PIPE AND FITTING COVERS

A. Polyvinyl Chloride (PVC) Covers:
1. Ultraviolet resistant.
2. 0.020 inch minimum thickness.
3. Preformed to match outer diameter of insulation.
4. Preformed fitting covers, minimum 10 mil.

B. Aluminum (A) Covers:
1. ASTM B209, Alloy 3003 minimum.
2. 0.016-inch thickness.
3. Bright anodized or acrylic-coated smooth finish on exposed side.
4. 2-piece tee and ribless elbow covers in minimum 0.016-inch, preformed.

5. Provide moisture barrier backing and butt-joint with mastic seal for joining of adjacent sections.

2.4 ADHESIVES

A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated, unless otherwise indicated.

B. Flexible Elastomeric Adhesive: Comply with MIL-A-24179A, Type II, Class I.

C. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.

D. ASJ Adhesive, and FSK Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.

E. PVC Jacket Adhesive: Compatible with PVC jacket.

2.5 MASTICS

A. Vapor-Barrier Mastic: Solvent based; suitable for indoor use on below-ambient services.
1. Water-Vapor Permeance: ASTM F 1249, 0.05 perm at 35-mil dry film thickness.
2. Service Temperature Range: 0 to 180 deg F.
3. Solids Content: ASTM D 1644, 44 percent by volume and 62 percent by weight.
4. Color: White.

2.6 LAGGING ADHESIVES

A. Description: Comply with MIL-A-3316C, Class I, Grade A, and shall be compatible with insulation materials, jackets, and substrates.
1. For indoor applications, use lagging adhesives that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
2. Fire-resistant, water-based lagging adhesive and coating for use indoors to adhere fire-resistant lagging cloths over pipe insulation.
3. Service Temperature Range: 0 to plus 180 deg F.
4. Color: White.

2.7 SEALANTS

A. Joint Sealants:
1. Materials shall be compatible with insulation materials, jackets, and substrates.
2. Permanently flexible, elastomeric sealant.
3. Service Temperature Range: Minus 100 to plus 300 deg F.
4. Color: White or gray.

B. ASJ Flashing Sealants, and Vinyl, PVDC, and PVC Jacket Flashing Sealants:
1. Materials shall be compatible with insulation materials, jackets, and substrates.
2. Fire- and water-resistant, flexible, elastomeric sealant.
3. Service Temperature Range: Minus 40 to plus 250 deg F.

4. Color: White.

2.8 FACTORY-APPLIED JACKETS

A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:

1. ASJ-SSL: ASJ with self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip; complying with ASTM C 1136, Type I.

2.9 TAPES

A. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive, complying with ASTM C 1136.
1. Width: 3 inches.
2. Thickness: 11.5 mils.
3. Adhesion: 90 ounces force/inch in width.
4. Elongation: 2 percent.
5. Tensile Strength: 40 lbf/inch in width.
6. ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape.

2.10 SECUREMENTS

A. Bands:
1. Aluminum: ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, 3/4 inch wide with closed seal.

B. Staples: Outward-clinching insulation staples, nominal 3/4-inch- wide, stainless steel or Monel.

C. Wire: 0.080-inch nickel-copper alloy.

2.11 PROTECTIVE SHIELDING GUARDS

1. Description: Manufactured plastic wraps for covering plumbing fixture hot- and cold-water supplies and trap and drain piping. Comply with Americans with Disabilities Act (ADA) requirements.
2. Description: Manufactured plastic enclosure for covering plumbing fixture hot- and cold-water supplies and trap and drain piping. Comply with ADA requirements.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
1. Verify that systems to be insulated have been tested and are free of defects.
2. Verify that surfaces to be insulated are clean and dry.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

3.3 GENERAL INSTALLATION REQUIREMENTS

A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping including fittings, valves, and specialties.

B. Install insulation materials, forms, vapor barriers or retarders, jackets, and thicknesses required for each item of pipe system as specified in insulation system schedules.

C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.

D. Install insulation with longitudinal seams at top and bottom of horizontal runs.

E. Install multiple layers of insulation with longitudinal and end seams staggered.

F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.

G. Keep insulation materials dry during application and finishing.

H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.

I. Install insulation with least number of joints practical.

J. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
   1. Install insulation continuously through hangers and around anchor attachments.
   2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
   3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
   4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.

K. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.

L. Install insulation with factory-applied jackets as follows:
   1. Draw jacket tight and smooth.

2. Cover circumferential joints with 3-inch- wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
3. Overlap jacket longitudinal seams at least 1-1/2 inches. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 4 inches o.c.
   a. For below-ambient services, apply vapor-barrier mastic over staples.
4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to pipe flanges and fittings.

M. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.

N. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.

O. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.

P. For above-ambient services, do not install insulation to the following:
1. Vibration-control devices.
2. Testing agency labels and stamps.
3. Nameplates and data plates.
4. Cleanouts.

3.4 PENETRATIONS

A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
1. Seal penetrations with flashing sealant.
2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
4. Seal jacket to roof flashing with flashing sealant.

B. Insulation Installation at Underground Exterior Wall Penetrations: Terminate insulation flush with sleeve seal. Seal terminations with flashing sealant.

C. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
1. Seal penetrations with flashing sealant.
2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.

3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
4. Seal jacket to wall flashing with flashing sealant.

D. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.

E. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions.
1. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping and fire-resistive joint sealers.

F. Insulation Installation at Floor Penetrations:
1. Pipe: Install insulation continuously through floor penetrations.
2. Seal penetrations through fire-rated assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

3.5 GENERAL PIPE INSULATION INSTALLATION

A. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.

B. Insulation Installation on Fittings, Valves, Strainers, Flanges, and Unions:
1. Install insulation over fittings, valves, strainers, flanges, unions, and other specialties with continuous thermal and vapor-retarder integrity unless otherwise indicated.
2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts. Fill joints, seams, and irregular surfaces with insulating cement.
5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below-ambient services, provide a design that maintains vapor barrier.
6. Insulate flanges and unions using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker.

7. Cover segmented insulated surfaces with a layer of finishing cement and coat with a mastic. Install vapor-barrier mastic for below-ambient services and a breather mastic for above-ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.
8. For services not specified to receive a field-applied jacket except for flexible elastomeric and polyolefin, install fitted PVC cover over elbows, tees, strainers, valves, flanges, and unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing using PVC tape.
9. Stencil or label the outside insulation jacket of each union with the word "union." Match size and color of pipe labels.

C. Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, test connections, flow meters, sensors, switches, and transmitters on insulated pipes. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.

D. Install removable insulation covers at locations indicated. Installation shall conform to the following:
1. Make removable flange and union insulation from sectional pipe insulation of same thickness as that on adjoining pipe. Install same insulation jacket as adjoining pipe insulation.
2. When flange and union covers are made from sectional pipe insulation, extend insulation from flanges or union long at least two times the insulation thickness over adjacent pipe insulation on each side of flange or union. Secure flange cover in place with stainless-steel or aluminum bands. Select band material compatible with insulation and jacket.
3. Construct removable valve insulation covers in same manner as for flanges, except divide the two-part section on the vertical center line of valve body.
4. When covers are made from block insulation, make two halves, each consisting of mitered blocks wired to stainless-steel fabric. Secure this wire frame, with its attached insulation, to flanges with tie wire. Extend insulation at least 2 inches over adjacent pipe insulation on each side of valve. Fill space between flange or union cover and pipe insulation with insulating cement. Finish cover assembly with insulating cement applied in two coats. After first coat is dry, apply and trowel second coat to a smooth finish.
5. Unless a PVC jacket is indicated in field-applied jacket schedules, finish exposed surfaces with a metal jacket.

3.6 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

B. Insulation Installation on Pipe Flanges:
1. Install pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of sheet insulation of same thickness as pipe insulation.
4. Secure insulation to flanges and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

C. Insulation Installation on Pipe Fittings and Elbows:
1. Install mitered sections of pipe insulation.
2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

D. Insulation Installation on Valves and Pipe Specialties:
1. Install preformed valve covers manufactured of same material as pipe insulation when available.
2. When preformed valve covers are not available, install cut sections of pipe and sheet insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
3. Install insulation to flanges as specified for flange insulation application.
4. Secure insulation to valves and specialties and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

3.7 INSTALLATION OF MINERAL-FIBER INSULATION

A. Insulation Installation on Straight Pipes and Tubes:
1. Secure each layer of preformed pipe insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
3. For insulation with factory-applied jackets on above-ambient surfaces, secure laps with outward clinched staples at 6 inches o.c.
4. For insulation with factory-applied jackets on below-ambient surfaces, do not staple longitudinal tabs. Instead, secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.

B. Insulation Installation on Pipe Flanges:
1. Install preformed pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch, and seal joints with flashing sealant.

C. Insulation Installation on Pipe Fittings and Elbows:
1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

D. Insulation Installation on Valves and Pipe Specialties:
1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.

3. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
4. Install insulation to flanges as specified for flange insulation application.

3.8 FIELD-APPLIED JACKET INSTALLATION

A. Where glass-cloth jackets are indicated, install directly over bare insulation or insulation with factory-applied jackets.
   1. Draw jacket smooth and tight to surface with 2-inch overlap at seams and joints.
   2. Embed glass cloth between two 0.062-inch- thick coats of lagging adhesive.
   3. Completely encapsulate insulation with coating, leaving no exposed insulation.

B. Where FSK jackets are indicated, install as follows:
   1. Draw jacket material smooth and tight.
   2. Install lap or joint strips with same material as jacket.
   3. Secure jacket to insulation with manufacturer's recommended adhesive.
   4. Install jacket with 1-1/2-inch laps at longitudinal seams and 3-inch- wide joint strips at end joints.
   5. Seal openings, punctures, and breaks in vapor-retarder jackets and exposed insulation with vapor-barrier mastic.

C. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints. Seal with manufacturer's recommended adhesive.
   1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

D. Where metal jackets are indicated, install with 2-inch overlap at longitudinal seams and end joints. Overlap longitudinal seams arranged to shed water. Seal end joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless-steel bands 12 inches o.c. and at end joints.

3.9 FINISHES

A. Insulation with ASJ, Glass-Cloth, or Other Paintable Jacket Material: Paint jacket with paint system identified below and as specified in Section 099113 "Exterior Painting" and Section 099123 "Interior Painting."
   1. Flat Acrylic Finish: Two finish coats over a primer that is compatible with jacket material and finish coat paint. Add fungicidal agent to render fabric mildew proof.
      a. Finish Coat Material: Interior, flat, latex-emulsion size.

B. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.

C. Color: Final color as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.

D. Do not field paint aluminum or stainless-steel jackets.

3.10 PIPING INSULATION SCHEDULE, GENERAL

A. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.

B. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:
1. Chrome-plated pipes and fittings unless there is a potential for personnel injury.

3.11 INDOOR PIPING INSULATION SCHEDULE

A. Domestic Cold Water:
1. Insulation shall be the following:
a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1/2 inch thick.

B. Domestic Hot and Recirculated Hot Water Mains:
1. NPS 2 and Smaller: Insulation shall be the following:
a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.
2. NPS 2-1/2 and Larger: Insulation shall be the following:
a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1-1/2 inch thick.

C. Domestic Hot Water Supply and Return runouts (up to NPS 2 and not exceeding 12 feet in length from fixture shutoff valve back toward main line):
1. NPS 2 and Smaller: Insulation shall be the following:
a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1/2 inch thick.

D. Domestic Water, Domestic Hot Water, and Stops for Plumbing Fixtures for People with Disabilities (Handicapped Lavatory & Sinks P-Trap & Supply Lines):
1. All Pipe Sizes: Insulation shall be the following:
a. Insulate p-trap, tailpiece and water supplies on handicapped lavatories with white, Truebro Model 102, Zurn 8947 handi lav-guard, or approved equivalent insulating system to meet A.D.A. Requirements. Provide accessories for offset tailpiece as required.

E. Floor Drains, Traps, and aboveground Sanitary Drain Piping receiving HVAC condensate:
1. All Pipe Sizes: Insulation shall be one of the following:
a. Flexible Elastomeric: 1/2 inch thick.
b. Mineral-Fiber, ¾ lb density, ductwrap insulation with aluminum foil vapor barrier, Type I: 2 inch thick.

F. Exposed Domestic Cold and Hot Water Piping.
1. All exposed domestic cold and hot water piping shall also have field install PVC jacket.

G. Sewer Waste and Vent Piping:
1. Where Contractor elects to use schedule 40 PVC waste and vent piping (in lieu of cast iron piping) (exposed, in walls, in furrings, or above ceilings) (vertical and horizontal lines) shall be insulated with 2" thick 3/4 # density fiberglass ductwrap insulation with aluminum foil vapor barrier. Insulation shall be sealed at all seams and joints. Insulation shall be installed with a foil backed adhesive tape around the diameter of the pipe with insulation at 24" on center intervals.

3.12 INDOOR, PIPING WITHIN CMU BLOCK WALLS PIPING INSULATION SCHEDULE

A. Domestic cold water, hot water and condensate drain lines shall be insulated with 1/2" thick flexible closed cell elastomeric thermal tube insulation as manufactured by Armaflex AP, Rubatex or prior approved equal. All joints are to be firmly butted together. All lap and butt joint strips are to be sealed in place with vapor barrier adhesive. Fittings are to be mitered segments of insulation held in place with vapor barrier sealant. Engineered Polymer Foam Insulation (EPFI) will not be accepted.

3.13 INDOOR, UNDERGROUND PIPING INSULATION SCHEDULE

A. Domestic cold and hot water lines run below slab within building shall be insulated with 1/2" thick flexible closed cell elastomeric thermal tube insulation as manufactured by Armaflex AP, Rubatex or prior approved equal.

B. All joints are to be firmly butted together. All lap and butt joint strips are to be sealed in place with vapor barrier adhesive. Fittings are to be mitered segments of insulation held in place with vapor barrier sealant.

C. Engineered Polymer Foam Insulation (EPFI) will not be accepted.

D. Apply two (2) coats of mastic on insulation.

3.14 OUTDOOR, ABOVE GROUND PIPING INSULATION SCHEDULE

A. All water lines on the outside of the building exposed to the weather shall be insulated with 1/2" thick flexible closed cell elastomeric thermal tube insulation as manufactured by Armaflex AP, Rubatex or prior approved equal.

B. All joints are to be firmly butted together. All lap and butt joint strips are to be sealed in place with vapor barrier adhesive. Fittings are to be mitered segments of insulation held in place with vapor barrier sealant.

C. Engineered Polymer Foam Insulation (EPFI) will not be accepted.

D. Apply two (2) coats of mastic on insulation.

E. Lines shall be covered with 0.016 smooth aluminum jacket and elbows. At contractor’s option, in lieu of 0.016 aluminum jacket, the contractor may use Venture Clad 1577CW multi-layered laminate coated, acrylic pressure sensitive adhesive jacket system.

3.15 UNDERGROUND, FIELD-INSTALLED INSULATION JACKET

A. For underground direct-buried piping applications, install underground direct-buried jacket over insulation material.

END OF SECTION 22 07 19

SECTION 22 11 16 – DOMESTIC WATER PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Under-building-slab and aboveground domestic water pipes, tubes, and fittings inside buildings.
2. Encasement for piping.

1.3 ACTION SUBMITTALS

A. Product Data: For piping, transition fittings and dielectric fittings.

1.4 INFORMATIONAL SUBMITTALS

A. System purging and disinfecting activities report.

B. Field quality-control reports.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

B. Potable-water piping and components shall comply with NSF 14 and NSF 61 Annex G. Plastic piping components shall be marked with "NSF-pw."

2.2 COPPER TUBE AND FITTINGS

A. Hard Copper Tube: ASTM B 88, Type L water tube, drawn temper.

B. Bronze Flanges: ASME B16.24, Class 150, with solder-joint ends.

C. Copper Unions:

1. MSS SP-123.
2. Cast-copper-alloy, hexagonal-stock body.
3. Ball-and-socket, metal-to-metal seating surfaces.
4. Lead free Solder-joint.

2.3 PIPING JOINING MATERIALS

A. Pipe-Flange Gasket Materials:

1. AWWA C110/A21.10, rubber, flat face, 1/8 inch thick or ASME B16.21, nonmetallic and asbestos free unless otherwise indicated.
2. Full-face or ring type unless otherwise indicated.

B. Metal, Pipe-Flange Bolts and Nuts: ASME B18.2.1, carbon steel unless otherwise indicated.

C. Solder Filler Metals: ASTM B 32, lead-free alloys.

D. Flux: ASTM B 813, water flushable.

E. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys for general-duty brazing unless otherwise indicated.

2.4 TRANSITION FITTINGS

A. General Requirements:

1. Same size as pipes to be joined.
2. Pressure rating at least equal to pipes to be joined.
3. End connections compatible with pipes to be joined.

B. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.

2.5 AT CONTRACTOR'S OPTION, PEX TUBE AND FITTINGS

A. PEX Distribution System: ASTM F 877, SDR 9 tubing.

B. Fittings for PEX-a Tube:
   1. Metal insert Crimp ASTM F 1807: metal-insert type with copper or stainless-steel crimp rings and matching PEX-a tube dimensions.
   2. Cold Expansion ASTM F 1960: Lead-free brass or engineered polymer (EP) fittings manufactured by the pipe manufacturer, utilizing cold-expansion PEX-a reinforcing rings made of same material as the pipe. Fittings shall be third party certified to NSF-14, and ASTM-F1960 and shall comply to ASTM-F876 & ASTM-F877.

      a. Flanges: ASME B16.5, Class 150, with ASTM F1960 cold-expansion end.
      b. Groove Adapter: One CSA B242-05 groove end and one ASTM F1960 cold-expansion end.
      c. Press: PEX-a to Press One-piece lead free (LF) brass fitting with one ASME B16.51 copper press end and one ASTM F1960 cold-expansion end, with PEX-a reinforcing cold-expansion ring.

C. Manifold: Multiple-outlet, plastic or corrosion-resistant-metal assembly complying with ASTM F 877; with plastic or corrosion-resistant-metal valve for each outlet.

2.6 DIELECTRIC FITTINGS

A. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.

B. Dielectric Unions:
   1. Standard: ASSE 1079.
   2. Pressure Rating: 150 psig.
   3. End Connections: Solder-joint copper alloy and threaded ferrous.

PART 3 - EXECUTION

3.1 EARTHWORK

A. Comply with requirements in Section 220000 "Plumbing General Provisions" for excavating, trenching, and backfilling.

3.2 PIPING INSTALLATION

A. Drawing plans, schematics, and diagrams indicate general location and arrangement of domestic water piping. Indicated locations and arrangements are used to size pipe and calculate friction

loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.

B. Install copper tubing under building slab according to CDA's "Copper Tube Handbook."

C. Install shutoff valve, hose-end drain valve, strainer, pressure gage, and test tee with valve inside the building at each domestic water-service entrance.

D. Install shutoff valve immediately upstream of each dielectric fitting.

E. Install domestic water piping level and plumb.

F. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.

G. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

H. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal, and coordinate with other services occupying that space.

I. Install piping to permit valve servicing.

J. Install nipples, unions, special fittings, and valves with pressure ratings the same as or higher than the system pressure rating used in applications below unless otherwise indicated.

K. Install piping free of sags and bends.

L. Install fittings for changes in direction and branch connections.

M. Install sleeves for piping penetrations of walls, ceilings, and floors.

N. Install sleeve seals for piping penetrations of concrete walls and slabs.

O. Install escutcheons for piping penetrations of walls, ceilings, and floors.

P. Domestic cold water lines penetrating concrete slabs shall be wrapped with “Protect-O-Sleeve” vinyl flexible tube as manufactured by Robert H. Harris Co., Jones Stephen or equivalent.

Q. PEX-a piping shall be installed per ASTM E84 requirements for plenum applications. Install all PEX-a pipe support and provide all required hangers and supporting strapping as required by manufacturer to provide a code compliant installation.

R. Install PEX-a piping in straight runs free of kinks, provide bend supports at all pipe drops. All PEX-a piping penetrations through wall plates shall be protected or shielded as required to prevent damage to piping.

S. Install PEX-a piping from the manifold to each fixture as a home run, not taps, tees or branches shall be permitted between the manifold and the fixture.

T. Install PEX-a Pipe Support, fixed anchor points and hangers in compliance with the Uponor Commercial Piping Pocket Guide (2017).

U. PEX-a shall not be installed in areas within five feet of UV light unless protected.

V. Install piping in compliance with manufacturer's Commercial Piping Pocket Guide (2017).

W. Install PEX-a piping at each fixture with out of the wall support bracket to secure piping and prevent excess movement when water stops or shut valves are operated.

X. Install all PEX Manifolds centered in access panels to permit servicing.

3.3 JOINT CONSTRUCTION

A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.

B. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.

C. Brazed Joints for Copper Tubing: Comply with CDA's "Copper Tube Handbook," "Brazed Joints" chapter.

D. Soldered Joints for Copper Tubing: Apply ASTM B 813, water-flushable flux to end of tube. Join copper tube and fittings according to ASTM B 828 or CDA's "Copper Tube Handbook."

E. Joints for PEX Piping: Join according to ASTM F 1807 or ASTM F1960

3.4 TRANSITION FITTING INSTALLATION

A. Install transition couplings at joints of dissimilar piping.

B. Transition Fittings in Underground Domestic Water Piping:

1. Fittings for NPS 1-1/2 and Smaller: Fitting-type coupling.
2. Fittings for NPS 2 and Larger: Sleeve-type coupling.

C. Transition Fittings in Aboveground Domestic Water Piping NPS 2 and Smaller: Plastic-to-metal transition unions.

3.5 HANGER AND SUPPORT INSTALLATION

A. Provide pipe hangers and support products. Install as per the following:

1. Vertical Piping: MSS Type 8 or 42, clamps.
2. Individual, Straight, Horizontal Piping Runs:
    a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
    b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
    c. Longer Than 100 Feet if Indicated: MSS Type 49, spring cushion rolls.
3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
4. Base of Vertical Piping: MSS Type 52, spring hangers.

B. Support vertical piping and tubing at base and at each floor.

C. Rod diameter may be reduced one size for double-rod hangers, to a minimum of 3/8 inch.

D. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:

1. NPS 3/4 and Smaller: 60 inches with 3/8-inch rod.
2. NPS 1 and NPS 1-1/4: 72 inches with 3/8-inch rod.
3. NPS 1-1/2 and NPS 2: 96 inches with 3/8-inch rod.
4. NPS 2-1/2: 108 inches with 1/2-inch rod.
5. NPS 3 to NPS 5: 10 feet with 1/2-inch rod.
6. NPS 6: 10 feet with 5/8-inch rod.
7. NPS 8: 10 feet with 3/4-inch rod.

E. Install supports for vertical copper tubing every 10 feet.

F. Support piping and tubing not listed in this article according to MSS SP-69 and manufacturer's written instructions.

G. Install vinyl-coated hangers for PEX-a piping with the following maximum horizontal spacing and minimum rod diameters:

1. Crosslinked Polyethylene PEX-a Pipe: Install hangers for PEX tubing in strict accordance with manufactures instructions.
    a. Horizontal PEX-a Piping Hangers: Install CTS hangers suitable for PEX-a piping in compliance with the Uponor Commercial Piping Pocket Guide (2017) and local codes, with the following maximum spacing:
    b. For IPC Jurisdictions: 3 inch and below: Maximum span, 32 inches.
    c. For UPC Jurisdictions:1 inch and below: Maximum span, 32 inches.

d. For UPC Jurisdictions: 1-1/4 inch and above: Maximum span, 48 inches.
e. Note: The above maximum hanger spacing requirements may be extended with the use of a continuous support channel such as Uponor PEX-a Pipe Support.

2. Horizontal PEX-a Piping with PEX-a Pipe Channel: Install hangers for PEX-a piping with horizontal support channel in accordance with local jurisdiction and manufacturer's recommendations, with the following maximum spacing:
   a. 3/4 inch and below: Maximum span, 6 feet.
   b. 1 inch and above: Maximum span, 8 feet.

H. Install hangers for vertical PEX piping every 48 inches.
1. Vertical PEX-a Piping: Support PEX-a piping with maximum spacing of 5 feet.

I. PEX-a Riser Supports: Install CTS riser clamps at the base of each floor and at the top of every other floor for domestic hot-water systems. Install mid-story guides between each floor. Install CTS riser clamps at the base of each floor and at the top of every fourth floor for domestic cold-water systems. Install mid-story guides.

3.6 CONNECTIONS

A. Drawings indicate general arrangement of piping, fittings, and specialties.

B. When installing piping adjacent to equipment and machines, allow space for service and maintenance.

C. Connect domestic water piping to exterior water-service piping. Use transition fitting to join dissimilar piping materials.

D. Connect domestic water piping to water-service piping with shutoff valve; extend and connect to the following:

1. Water Heaters: Cold-water inlet and hot-water outlet piping in sizes indicated, but not smaller than sizes of water heater connections.
2. Plumbing Fixtures: Cold- and hot-water-supply piping in sizes indicated, but not smaller than that required by plumbing code.
3. Equipment: Cold- and hot-water-supply piping as indicated, but not smaller than equipment connections. Provide shutoff valve and union for each connection. Use flanges instead of unions for NPS 2-1/2 and larger.

3.7 IDENTIFICATION

A. Identify system components.

3.8 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Piping Inspections:

a. Do not enclose, cover, or put piping into operation until it has been inspected and approved by authorities having jurisdiction.

b. During installation, notify authorities having jurisdiction at least one day before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction:

1) Roughing-in Inspection: Arrange for inspection of piping before concealing or closing in after roughing in and before setting fixtures.

2) Final Inspection: Arrange for authorities having jurisdiction to observe tests specified in "Piping Tests" Subparagraph below and to ensure compliance with requirements.

c. Reinspection: If authorities having jurisdiction find that piping will not pass tests or inspections, make required corrections and arrange for reinspection.

d. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.

2. Piping Tests:

a. Fill domestic water piping. Check components to determine that they are not air bound and that piping is full of water.

b. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit a separate report for each test, complete with diagram of portion of piping tested.

c. Leave new, altered, extended, or replaced domestic water piping uncovered and unconcealed until it has been tested and approved. Expose work that was covered or concealed before it was tested.

d. Cap and subject piping to static water pressure of 50 psig above operating pressure, without exceeding pressure rating of piping system materials. Isolate test source and allow it to stand for four hours. Leaks and loss in test pressure constitute defects that must be repaired.

e. Repair leaks and defects with new materials, and retest piping or portion thereof until satisfactory results are obtained.

f. Prepare reports for tests and for corrective action required.

B. Domestic water piping will be considered defective if it does not pass tests and inspections.

C. Prepare test and inspection reports.

3.9 ADJUSTING

A. Perform the following adjustments before operation:

1. Close drain valves, hydrants, and hose bibs.
2. Open shutoff valves to fully open position.
3. Open throttling valves to proper setting.
4. Adjust balancing valves in hot-water-circulation return piping to provide adequate flow.
    a. Manually adjust ball-type balancing valves in hot-water-circulation return piping to provide hot-water flow in each branch.
    b. Adjust calibrated balancing valves to flows indicated.
5. Remove plugs used during testing of piping and for temporary sealing of piping during installation.
6. Remove and clean strainer screens. Close drain valves and replace drain plugs.
7. Remove filter cartridges from housings and verify that cartridges are as specified for application where used and are clean and ready for use.
8. Check plumbing specialties and verify proper settings, adjustments, and operation.

3.10 CLEANING

A. Clean and disinfect potable domestic water piping as follows:

1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
2. Use purging and disinfecting procedures prescribed by authorities having jurisdiction; if methods are not prescribed, use procedures described in either AWWA C651 or AWWA C652 or follow procedures described below:
    a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
    b. Fill and isolate system according to either of the following:
        1) Fill system or part thereof with water/chlorine solution with at least 50 ppm of available chlorine. Isolate with valves and allow to stand for 24 hours (minimum time shall be 6 hours). A chlorine residual of at least 5 ppm should remain before the lines are put in use.
3. Flush system with clean, potable water until no chlorine is in water coming from system after the standing time.
    a. Repeat procedures if biological examination shows contamination.
    b. Submit water samples in sterile bottles to authorities having jurisdiction.

B. Prepare and submit reports of purging and disinfecting activities. Include copies of water-sample approvals from authorities having jurisdiction.

C. Clean interior of domestic water piping system. Remove dirt and debris as work progresses.

3.11 PIPING SCHEDULE

A. Transition and special fittings with pressure ratings at least equal to piping rating may be used in applications below unless otherwise indicated.

B. Flanges and unions may be used for aboveground piping joints unless otherwise indicated.

C. Fitting Option: Extruded-tee connections and brazed joints may be used on aboveground copper tubing.

D. Underground piping up to 5’-0” from building, domestic cold water, building-service piping, NPS 4 and smaller, shall be the following:

1. PVC, Schedule 40; socket fittings; and solvent-cemented joints.

E. Aboveground domestic water piping, NPS 4 and smaller, shall be the following:

1. Hard copper tube, ASTM B 88, Type L; copper, solder-joint fittings; and soldered joints.

F. Under-building-slab, domestic water piping, 3” and smaller, shall be the following:

1. PEX-a tube, 3” and smaller; fittings for PEX-a tube with cold expansion ASTM F1960 connection.

G. Aboveground domestic water piping, 2” and samller, shall be the following:

1. PEX-a tube, 2” and smaller; fittings for PEX-a tube with cold expansion ASTM F1960 connection.

H. Aboveground domestic water piping, 2-1/2” to 4”, shall be the following:

1. PEX-a tube, 3” and smaller; fittings for PEX-a tube with cold expansion ASTM F1960 connection.

3.12 VALVE SCHEDULE

A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:

1. Shutoff Duty: Use ball valves for piping NPS 3 and smaller. Use butterfly or ball valves with flanged ends for piping NPS 4 and larger.

2. Throttling Duty: Use ball or globe valves for piping NPS 2 and smaller. Use butterfly or ball valves with flanged ends for piping NPS 2-1/2 and larger.
3. Drain Duty: Hose-end drain valves.

B. Use check valves to maintain correct direction of domestic water flow to and from equipment.

END OF SECTION 22 11 16

SECTION 22 11 19 – DOMESTIC WATER PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
   1. Vacuum breakers.
   2. Water-hammer arresters.
   3. Escutcheons
   4. Trap-seal primer valves.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.4 INFORMATIONAL SUBMITTALS

A. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For domestic water piping specialties to include in emergency, operation, and maintenance manuals.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS FOR PIPING SPECIALTIES

A. Potable-water piping and components shall comply with NSF 61 Annex G.

2.2 PERFORMANCE REQUIREMENTS

A. Minimum Working Pressure for Domestic Water Piping Specialties: 125 psig unless otherwise indicated.

2.3 VACUUM BREAKERS

A. Pipe-Applied, Atmospheric-Type Vacuum Breakers:
1. Standard: ASSE 1001.
2. Size: NPS 1/4 to NPS 3, as required to match connected piping.
3. Body: Bronze.
4. Inlet and Outlet Connections: Threaded.
5. Finish: Rough bronze.

B. Hose-Connection Vacuum Breakers:
1. Standard: ASSE 1011.
2. Body: Bronze, non-removable, with manual drain.
3. Outlet Connection: Garden-hose threaded complying with ASME B1.20.7.
4. Finish: Chrome or nickel plated.

2.4 WATER-HAMMER ARRESTERS

A. Water-Hammer Arresters:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. AMTROL, Inc.
b. Precision Plumbing Products.
c. Sioux Chief Manufacturing Company, Inc.
2. Standard: ASSE 1010 or PDI-WH 201.
3. Type: Copper tube with piston.
4. Size: ASSE 1010, Sizes AA and A through F, or PDI-WH 201, Sizes A through F.
5. Plumbing fixtures with quick closing valves (i.e.: Dishwashers, Ice Maker, Tub/Shower Valve, Washing Machines, etc.) install "Shock Trol", "Precision Plumbing Products", Sioux Chief “Hydra-Rester”, or equal water Hammer arrester properly sized for each unit.

2.5 ESCUTCHEONS

A. Provide escutcheons for all exposed lines passing through floors, walls, and ceilings. They shall be chrome plated brass and shall be of such flange size as to cover necessary penetrating openings.

2.6 TRAP-SEAL PRIMER DEVICE

A. Supply-Type, Trap-Seal Primer Device:
1. Standard: ASSE 1018.
2. Pressure Rating: 125 psig minimum.
3. Body: Bronze.
4. Inlet and Outlet Connections: NPS 1/2 threaded, union, or solder joint.
5. Gravity Drain Outlet Connection: NPS 1/2 threaded or solder joint.

6. Finish: Chrome plated, or rough bronze for units used with pipe or tube that is not chrome finished.

B. Drainage-Type, Trap-Seal Primer Device:
1. Standard: ASSE 1044, lavatory P-trap with NPS 3/8 minimum, trap makeup connection.
2. Size: NPS 1-1/4 minimum.
3. Material: Chrome-plated, cast brass.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install water-hammer arresters in water piping according to PDI-WH 201.

B. Install supply-type, trap-seal primer valves with outlet piping pitched down toward drain trap a minimum of 1 percent, and connect to floor-drain body, trap, or inlet fitting. Adjust valve for proper flow.

C. Install drainage-type, trap-seal primer valves as lavatory trap with outlet piping pitched down toward drain trap a minimum of 1 percent, and connect to floor-drain body, trap, or inlet fitting.

END OF SECTION 22 11 19

SECTION 22 12 19 – NATURAL GAS DISTRIBUTION AND PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SERVICE

A. Contractor shall contact local utility company, determine the extent of their requirements and include in his price all costs required for the complete installation of gas service, meter and regulator.

B. Contractor shall include routing gas main from local utility main to the building and throughout project as indicated on Drawings.

C. Contractor shall provide gas pressure regulator downstream of the meter to provide adequate gas pressure to equipment furnished in project. Coordinate gas supply pressure and equipment supply pressure requirements with utility company and equipment manufacturers.

1.3 SUMMARY

A. Section Includes:

1. Natural gas pipes, tubes, and fittings in the buildings.

B. Product Data: For piping, transition fittings and dielectric fittings.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

PART 3 - EXECUTION

3.1 PIPING INSTALLATION

A. Drawing plans, schematics, and diagrams indicate general location and arrangement of natural gas distribution piping. Indicated locations and arrangements are used to size pipe and calculate

friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.

3.2 HANGER AND SUPPORT INSTALLATION

A. Provide pipe hangers and support products. Install as per the following:

1. Vertical Piping: MSS Type 8 or 42, clamps.

2. Individual, Straight, Horizontal Piping Runs:

a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.

b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.

c. Longer Than 100 Feet if Indicated: MSS Type 49, spring cushion rolls.

3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.

4. Base of Vertical Piping: MSS Type 52, spring hangers.

B. Support vertical piping and tubing at base and at each floor.

C. Rod diameter may be reduced one size for double-rod hangers, to a minimum of 3/8 inch.

3.3 IDENTIFICATION

A. Identify system components.

B. All piping below grade shall be installed with a 14 Gauge tracer wire on complete system below grade. Tracer wire shall stub up at each pipe penetration from below grade and be secured to the pipe.

3.4 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Piping Inspections:

a. Do not enclose, cover, or put piping into operation until it has been inspected and approved by authorities having jurisdiction.

b. During installation, notify authorities having jurisdiction at least one day before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction:

1) Roughing-in Inspection: Arrange for inspection of piping before concealing or closing in after roughing in and before setting fixtures.

2) Final Inspection: Arrange for authorities having jurisdiction to observe tests specified in "Piping Tests" Subparagraph below and to ensure compliance with requirements.

c. Reinspection: If authorities having jurisdiction find that piping will not pass tests or inspections, make required corrections and arrange for reinspection.

d. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.

2. Piping Tests:

a. All low pressure gas piping shall be tested with a 10" mercury column for thirty (30) minutes.

b. Isolate test source and allow it to stand for four hours. Leaks and loss in test pressure constitute defects that must be repaired.

c. Repair leaks and defects with new materials, and retest piping or portion thereof until satisfactory results are obtained.

d. Prepare reports for tests and for corrective action required.

B. Natural gas water piping will be considered defective if it does not pass tests and inspections.

C. Prepare test and inspection reports.

3.5 PIPING SCHEDULE

A. Transition and special fittings with pressure ratings at least equal to piping rating may be used in applications below unless otherwise indicated.

B. Natural gas piping, NPS 4 and smaller, shall be the following:

1. Gas piping on the building interior of the building shall be standard black steel, Schedule 40, National Tube Co., or equal. Fittings which are 2 inches and below shall be malleable screw fittings. Piping above 2 inches shall be electrically welded utilizing weld fittings.

2. Gas piping on the exterior of the building and on the roof shall be the same as specified above, except to be coated with Scotch-Kote polyethylene coating (20 mil) and all joints weatherproofed with two coats of field applied Scotch-Kote wrapping tape.

3. Gas piping below grade shall be orange polyethylene pipe ASTM D-3350, PE 23533E with polyethylene butt fusion weld fittings.

END OF SECTION 22 12 19

SECTION 22 13 16 – SANITARY WASTE, GREASE AND VENT PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
   1. Stainless-steel drainage pipe and fittings.
   2. PVC pipe and fittings.

B. Related Requirements:

   1. Section 221313 "Facility Sanitary Sewers" for sanitary sewerage piping and structures outside the building.
   2. Section 221329 "Sanitary Sewerage Pumps" for effluent and sewage pumps.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: Include plans, elevations, sections, and details.

1.4 INFORMATIONAL SUBMITTALS

A. Seismic Qualification Certificates: For waste and vent piping, accessories, and components, from manufacturer.

   1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
   2. Detailed description of piping anchorage devices on which the certification is based and their installation requirements.

B. Field quality-control reports.

1.5 FIELD CONDITIONS

A. Interruption of Existing Sanitary Waste Service: Do not interrupt service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service according to requirements indicated:

1. Notify Architect no fewer than two days in advance of proposed interruption of sanitary waste service.
2. Do not proceed with interruption of sanitary waste service without Architect's written permission.

1.6 WARRANTY

A. Listed manufacturers to provide labeling and warranty of their respective products.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Components and installation shall be capable of withstanding the following minimum working pressure unless otherwise indicated:

1. Soil, Waste, and Vent Piping: 10-foot head of water.
2. Waste, Force-Main Piping: 50 psig.

B. Seismic Performance: Soil, waste, and vent piping and support and installation shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

2.2 PIPING MATERIALS

A. All cast iron soil pipe and fittings shall be marked with the collective trademark of the Cast Iron Soil Pipe Institute (CISPI) ® and listed by NSF International.

B. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

2.3 STAINLESS-STEEL DRAINAGE PIPE AND FITTINGS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Anvil International/Smith-Cooper International; Tailwind Capital, LLC.
2. BLÜCHER; A Watts Water Technologies Company.
3. Josam Company.

B. Description: Comply with requirements of ASME A112.3.1, drainage pattern.

C. Material: Type 316L stainless steel

D. Pipe Construction: Seamless.

E. Internal Sealing Rings: EPDM

F. Joints: Single or double, socket and spigot ends.

2.4 PVC PIPE AND FITTINGS

A. Comply with NSF 14, "Plastics Piping Systems Components and Related Materials," for plastic piping components. Include marking with "NSF-dwv" for plastic drain, waste, and vent piping and "NSF-sewer" for plastic sewer piping.

B. Solid-Wall PVC Pipe: ASTM D 2665, drain, waste, and vent.

C. Cellular-Core PVC Pipe: ASTM F 891, Schedule 40 **will not be accepted**.

D. PVC Socket Fittings: ASTM D 2665, made to ASTM D 3311, drain, waste, and vent patterns.

E. PVC Pressure Fittings: ASTM D 2466, Socket Type

F. Primer: ASTM F 656.

1. Primer shall have a VOC content of 550g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24)
2. Adhesive primer shall comply with the testing and product requirements of the California Department of Health Services “Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers”

G. Solvent Cement: ASTM D 2564.
1. PVC solvent cement shall have a VOC content of 510 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24)
2. Solvent cement shall comply with the testing and product requirements of the California Department of Health Services “Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers”

2.9 SPECIALTY PIPE FITTINGS

A. Transition Couplings:

1. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.
2. Unshielded, Nonpressure Transition Couplings:

a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1) Dallas Specialty & Mfg. Co.
2) Fernco Inc.
3) Mission Rubber Company, LLC; a division of MCP Industries.

b. Standard: ASTM C 1173.
c. Description: Elastomeric, sleeve-type, reducing or transition pattern. Include shear ring and corrosion-resistant-metal tension band and tightening mechanism on each end.

d. End Connections: Same size as and compatible with pipes to be joined.
e. Sleeve Materials:

1) For Cast-Iron Soil Pipes: ASTM C 564, rubber.
2) For Plastic Pipes: ASTM F 477, elastomeric seal or ASTM D 5926, PVC.
3) For Dissimilar Pipes: ASTM D 5926, PVC or other material compatible with pipe materials being joined.

3. Shielded, Nonpressure Transition Couplings:

a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1) Cascade Waterworks Mfg. Co.
2) Mission Rubber Company, LLC; a division of MCP Industries.

b. Standard: ASTM C 1460.
c. Description: Elastomeric or rubber sleeve with full-length, corrosion-resistant outer shield and corrosion-resistant-metal tension band and tightening mechanism on each end.
d. End Connections: Same size as and compatible with pipes to be joined.

4. Pressure Transition Couplings:

a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1) Apollo Valves; a part of Aalberts Integrated Piping Systems.
2) EBAA Iron Sales, Inc.
3) Romac Industries, Inc.

b. Standard: AWWA C219.
c. Description: Metal, sleeve-type same size as, with pressure rating at least equal to, and ends compatible with, pipes to be joined.
d. Center-Sleeve Material: Manufacturer's standard.
e. Gasket Material: Natural or synthetic rubber.
f. Metal Component Finish: Corrosion-resistant coating or material.

B. Dielectric Fittings:

1. Dielectric Unions:

a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1) A.Y. McDonald Mfg. Co.
2) WATTS; A Watts Water Technologies Company.
3) Wilkins.

b. Description:

1) Standard: ASSE 1079.

2) Pressure Rating: 150 psig (1035 kPa).
3) End Connections: Solder-joint copper alloy and threaded ferrous.

2. Dielectric Flanges:

a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1) Capitol Manufacturing Company.
2) WATTS; A Watts Water Technologies Company.
3) Zurn Industries, LLC.

b. Description:

1) Standard: ASSE 1079.
2) Factory-fabricated, bolted, companion-flange assembly.
3) Pressure Rating: 150 psig (1035 kPa).
4) End Connections: Solder-joint copper alloy and threaded ferrous; threaded solder-joint copper alloy and threaded ferrous.

3. Dielectric-Flange Insulating Kits:

a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1) Advance Products & Systems, LLC.
2) CALPICO, Inc.
3) GF Piping Systems: Georg Fischer LLC.
4) GPT; a division of EnPRO Industries.

b. Description:

1) Nonconducting materials for field assembly of companion flanges.
2) Pressure Rating: 150 psig (1035 kPa).
3) Gasket: Neoprene or phenolic.
4) Bolt Sleeves: Phenolic or polyethylene.
5) Washers: Phenolic with steel backing washers.

4. Dielectric Nipples:

a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1) Anvil International/Smith-Cooper International; Tailwind Capital, LLC.
2) Precision Plumbing Products.
3) Victaulic Company.

b. Description:

1) Standard: IAPMO PS 66.
2) Electroplated steel nipple.
3) Pressure Rating: 300 psig (2070 kPa) at 225 deg F (107 deg C).

4) End Connections: Male threaded or grooved.
5) Lining: Inert and noncorrosive, propylene.

2.13 ENCASEMENT FOR UNDERGROUND METAL PIPING

A. Standard: ASTM A 674 or AWWA C105/A 21.5.

B. Material: Linear low-density polyethylene film manufactured of virgin polyethylene material conforming to the requirements of ASTM D 1248, and a minimum thickness of 0.008-inch thickness or, high-density, cross-laminated polyethylene film manufactured of virgin polyethylene material conforming to the requirements of ASTM D 1248, and a minimum thickness of 0.004-inch.

C. Form: Sheet or, Tube

D. Color: Black or, Natural

E. Install polyethylene encasement for Hubless, Service, and Extra Heavy DWV cast iron pipe and fitting systems in accordance with ASTM A74, X3, and CISPI Handbook.

PART 3 - EXECUTION

3.1 EARTH MOVING

A. Comply with requirements for excavating, trenching, and backfilling specified in Section 312000 "Earth Moving."

3.2 PIPING INSTALLATION

A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems.

1. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations.
2. Install piping as indicated unless deviations to layout are approved on coordination drawings.

B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.

C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.

E. Install piping to permit valve servicing.

F. Install piping at indicated slopes.

G. Install piping free of sags and bends.

H. Install fittings for changes in direction and branch connections.

I. Install piping to allow application of insulation.

J. Make changes in direction for soil and waste drainage and vent piping using appropriate branches, bends, and long-sweep bends.

1. Sanitary tees and short-sweep 1/4 bends may be used on vertical stacks if change in direction of flow is from horizontal to vertical.
2. Use long-turn, double Y-branch and 1/8-bend fittings if two fixtures are installed back to back or side by side with common drain pipe.

    a. Straight tees, elbows, and crosses may be used on vent lines.

3. Do not change direction of flow more than 90 degrees.
4. Use proper size of standard increasers and reducers if pipes of different sizes are connected.

    a. Reducing size of waste piping in direction of flow is prohibited.

K. Lay buried building waste piping beginning at low point of each system.

1. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream.
2. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements.
3. Maintain swab in piping and pull past each joint as completed.

L. Install soil and waste and vent piping at the following minimum slopes unless otherwise indicated:

1. Building Sanitary Waste: 2 percent downward in direction of flow for piping NPS 3 (DN 80) and smaller; 1 percent downward in direction of flow for piping NPS 4 (DN 100) and larger.
2. Horizontal Sanitary Waste Piping: 2 percent downward in direction of flow.
3. Vent Piping: 1 percent down toward vertical fixture vent or toward vent stack.

M. Install steel piping according to applicable plumbing code.

N. Install stainless-steel piping according to ASME A112.3.1 and applicable plumbing code.

O. Install aboveground copper tubing according to CDA's "Copper Tube Handbook."

P. Install aboveground PVC piping according to ASTM D 2665.

Q. Install underground PVC piping according to ASTM D 2321.

R. Install engineered soil and waste and vent piping systems as follows:

1. Combination Waste and Vent: Comply with standards of authorities having jurisdiction.
2. Reduced-Size Venting: Comply with standards of authorities having jurisdiction.

S. Install underground, ductile-iron, force-main piping according to AWWA C600.

1. Install buried piping inside building between wall and floor penetrations and connection to sanitary sewer piping outside building with restrained joints.
2. Anchor pipe to wall or floor. Install thrust-block supports at vertical and horizontal offsets.
3. Install encasement on piping according to ASTM A 674 or AWWA C105/A 21.5.

T. Install underground, copper, force-main tubing according to CDA's "Copper Tube Handbook."

1. Install encasement on piping according to ASTM A 674 or AWWA C105/A 21.5.

U. Install force mains at elevations indicated.

V. Plumbing Specialties:

1. Install backwater valves in sanitary waster gravity-flow piping.

a. Comply with requirements for backwater valves specified in Section 221319 "Sanitary Waste Piping Specialties."

2. Install cleanouts at grade and extend to where building sanitary drains connect to building sanitary sewers in sanitary waste gravity-flow piping.

a. Install cleanout fitting with closure plug inside the building in sanitary drainage force-main piping.
b. Comply with requirements for cleanouts specified in Section 221319 "Sanitary Waste Piping Specialties."

3. Install drains in sanitary waste gravity-flow piping.

a. Comply with requirements for drains specified in Section 221319 "Sanitary Waste Piping Specialties."

W. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.

X. Install sleeves for piping penetrations of walls, ceilings, and floors.

1. Comply with requirements for sleeves specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."

Y. Install sleeve seals for piping penetrations of concrete walls and slabs.

1. Comply with requirements for sleeve seals specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."

Z. Install escutcheons for piping penetrations of walls, ceilings, and floors.

1. Comply with requirements for escutcheons specified in Section 220518 "Escutcheons for Plumbing Piping."

3.3 JOINT CONSTRUCTION

A. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1.

1. Cut threads full and clean using sharp dies.
2. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:

    a. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
    b. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
    c. Do not use pipe sections that have cracked or open welds.

B. Join stainless-steel pipe and fittings with gaskets according to ASME A112.3.1.

C. Join copper tube and fittings with soldered joints according to ASTM B 828. Use ASTM B 813, water-flushable, lead-free flux and ASTM B 32, lead-free-alloy solder.

D. Grooved Joints: Cut groove ends of pipe according to AWWA C606. Lubricate and install gasket over ends of pipes or pipe and fitting. Install coupling housing sections, over gasket, with keys seated in piping grooves. Install and tighten housing bolts.

E. Flanged Joints: Align bolt holes. Select appropriate gasket material, size, type, and thickness. Install gasket concentrically positioned. Use suitable lubricants on bolt threads. Torque bolts in cross pattern.

F. Plastic, Nonpressure-Piping, Solvent-Cement Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:

1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
2. PVC Piping: Join according to ASTM D 2855 and ASTM D 2665 appendixes.

3.4 SPECIALTY PIPE FITTING INSTALLATION

A. Transition Couplings:

1. Install transition couplings at joints of piping with small differences in ODs.
2. In Waste Drainage Piping: Shielded, nonpressure transition couplings.
3. In Aboveground Force Main Piping: Fitting-type transition couplings.
4. In Underground Force Main Piping:

    a. NPS 1-1/2 (DN 40) and Smaller: Fitting-type transition couplings.
    b. NPS 2 (DN 50) and Larger: Pressure transition couplings.

B. Dielectric Fittings:

1. Install dielectric fittings in piping at connections of dissimilar metal piping and tubing.
2. Dielectric Fittings for NPS 2 (DN 50) and Smaller: Use dielectric unions.
3. Dielectric Fittings for NPS 2-1/2 to NPS 4 (DN 65 to DN 100): Use dielectric flanges.
4. Dielectric Fittings for NPS 5 (DN 125) and Larger: Use dielectric flange kits.

3.5 VALVE INSTALLATION

A. Comply with requirements in Section 220523.12 "Ball Valves for Plumbing Piping," Section 220523.13 "Butterfly Valves for Plumbing Piping," Section 220523.14 "Check Valves for Plumbing Piping," and Section 220523.15 "Gate Valves for Plumbing Piping" for general-duty valve installation requirements.

B. Shutoff Valves:

1. Install shutoff valve on each sewage pump discharge.
2. Install gate or full-port ball valve for piping NPS 2 (DN 50) and smaller.
3. Install gate valve for piping NPS 2-1/2 (DN 65) and larger.

C. Check Valves: Install swing check valve, between pump and shutoff valve, on each sewage pump discharge.

D. Backwater Valves: Install backwater valves in piping subject to backflow.

1. Horizontal Piping: Horizontal backwater valves. Use normally closed type unless otherwise indicated.
2. Floor Drains: Drain outlet backwater valves unless drain has integral backwater valve.
3. Install backwater valves in accessible locations.
4. Comply with requirements for backwater valve specified in Section 221319 "Sanitary Waste Piping Specialties."

3.6 INSTALLATION OF HANGERS AND SUPPORTS

A. Comply with requirements for seismic-restraint devices specified in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."

B. Comply with requirements for pipe hanger and support devices and installation specified in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment." Section 220548.13 "Vibration Controls for Plumbing Piping and Equipment."

1. Install carbon-steel pipe hangers for horizontal piping in noncorrosive environments.
2. Install stainless-steel pipe hangers for horizontal piping in corrosive environments.
3. Install carbon-steel pipe support clamps for vertical piping in noncorrosive environments.
4. Install stainless-steel pipe support clamps for vertical piping in corrosive environments.
5. Vertical Piping: MSS Type 8 or Type 42, clamps.
6. Install individual, straight, horizontal piping runs:

   a. 100 Feet (30 m) and Less: MSS Type 1, adjustable, steel clevis hangers.
   b. Longer Than 100 Feet (30 m): MSS Type 43, adjustable roller hangers.
   c. Longer Than 100 Feet (30 m) if Indicated: MSS Type 49, spring cushion rolls.

7. Multiple, Straight, Horizontal Piping Runs 100 Feet (30 m) or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
8. Base of Vertical Piping: MSS Type 52, spring hangers.

C. Install hangers for PVC piping, with maximum horizontal spacing and minimum rod diameters, to comply with manufacturer's written instructions, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

D. Support horizontal piping and tubing within 12 inches (300 mm) of each fitting, valve, and coupling.

E. All horizontal piping 5" and larger branch openings, or changes in direction shall be suitably restrained to prevent movement of joints and possible separation. Restraints can be field fabricated, or pre-engineered and manufactured.

F. Support vertical runs of PVC piping to comply with manufacturer's written instructions, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

3.7 CONNECTIONS

A. Drawings indicate general arrangement of piping, fittings, and specialties.

B. Connect soil and waste piping to exterior sanitary sewerage piping. Use transition fitting to join dissimilar piping materials.

C. Connect waste and vent piping to the following:

1. Plumbing Fixtures: Connect waste piping in sizes indicated, but not smaller than required by plumbing code.
2. Plumbing Fixtures and Equipment: Connect atmospheric vent piping in sizes indicated, but not smaller than required by authorities having jurisdiction.
3. Plumbing Specialties: Connect waste and vent piping in sizes indicated, but not smaller than required by plumbing code.
4. Install test tees (wall cleanouts) in conductors near floor and floor cleanouts with cover flush with floor.
5. Install horizontal backwater valves with cleanout cover flush with floor.
6. Comply with requirements for backwater valves cleanouts and drains specified in Section 221319 "Sanitary Waste Piping Specialties."
7. Equipment: Connect waste piping as indicated.

    a. Provide shutoff valve if indicated and union for each connection.
    b. Use flanges instead of unions for connections NPS 2-1/2 (DN 65) and larger.

D. Connect force-main piping to the following:

1. Sanitary Sewer: To exterior force main.
2. Sewage Pump: To sewage pump discharge.

E. Where installing piping adjacent to equipment, allow space for service and maintenance of equipment.

F. Make connections according to the following unless otherwise indicated:

1. Install unions, in piping NPS 2 (DN 50) and smaller, adjacent to each valve and at final connection to each piece of equipment.
2. Install flanges, in piping NPS 2-1/2 (DN 65) and larger, adjacent to flanged valves and at final connection to each piece of equipment.

3.8 IDENTIFICATION

A. Identify exposed sanitary waste and vent piping.

B. Comply with requirements for identification specified in Section 220553 "Identification for Plumbing Piping and Equipment."

3.9 FIELD QUALITY CONTROL

A. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.

1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.

B. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.

C. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.

D. Test sanitary waste and vent piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:

1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired.

    a. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.

2. Leave uncovered and unconcealed new, altered, extended, or replaced waste and vent piping until it has been tested and approved.

    a. Expose work that was covered or concealed before it was tested.

3. Roughing-in Plumbing Test Procedure: Test waste and vent piping except outside leaders on completion of roughing-in.

    a. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water (30 kPa).
    b. From 15 minutes before inspection starts to completion of inspection, water level must not drop.

c. Inspect joints for leaks.

4. Finished Plumbing Test Procedure: After plumbing fixtures have been set and traps filled with water, test connections and prove they are gastight and watertight.

a. Plug vent-stack openings on roof and building drains where they leave building. Introduce air into piping system equal to pressure of 1-inch wg (250 Pa).
b. Use U-tube or manometer inserted in trap of water closet to measure this pressure.
c. Air pressure must remain constant without introducing additional air throughout period of inspection.
d. Inspect plumbing fixture connections for gas and water leaks.

5. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
6. Prepare reports for tests and required corrective action.

E. Test force-main piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:

1. Leave uncovered and unconcealed new, altered, extended, or replaced force-main piping until it has been tested and approved.

a. Expose work that was covered or concealed before it was tested.

2. Cap and subject piping to static-water pressure of 50 psig (345 kPa) above operating pressure, without exceeding pressure rating of piping system materials.

a. Isolate test source and allow to stand for four hours.
b. Leaks and loss in test pressure constitute defects that must be repaired.

3. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
4. Prepare reports for tests and required corrective action.

3.10 CLEANING AND PROTECTION

A. Clean interior of piping. Remove dirt and debris as work progresses.

B. Protect sanitary waste and vent piping during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.

C. Place plugs in ends of uncompleted piping at end of day and when work stops.

D. Exposed PVC Piping: Protect plumbing vents exposed to sunlight with two coats of water-based latex paint.

E. Repair damage to adjacent materials caused by waste and vent piping installation.

3.11 PREVENTIVE MAINTENANCE

A. All piping coming from parking deck drains shall be flushed with clean water for not less than 10 minutes in each drain after winter season, and every 120 days. If chemicals are used to clean garage walls, this chemical shall be washed off the exterior of the pipe.

B. All piping from dedicated soda station floor sinks shall be flushed by dumping a basin of 5 gallons of warm clean water every 3rd day into the floor sink.

C. All piping connected to "low flow" fixtures shall be flushed with clean water by filling, and releasing a utility wash basin sink from the furthest point possible not less than once every 7 days.

3.12 PIPING SCHEDULE

A. Flanges and unions may be used on aboveground pressure piping unless otherwise indicated.

B. Aboveground, sanitary waste piping NPS 4 (DN 100) and smaller shall be the following:
1. Solid Wall PVC pipe, PVC socket fittings, and solvent-cemented joints.

C. Aboveground, vent piping NPS 4 (DN 100) and smaller shall be the following:

1. Solid Wall PVC pipe, PVC socket fittings, and solvent-cemented joints.

D. Aboveground, grease waste piping NPS 4 (DN 100) and smaller shall be the following:

1. Type 316L austenitic stainless steel Push-Fit piping and fittings. Sealing rings Push-Fit gaskets shall be of Ethylene Propylene Diene Monomer rubber known as EPDM.

E. Underground, sanitary waste, grease waste, and vent piping NPS 4 (DN 100) and smaller shall be the following:
1. Solid Wall PVC pipe, PVC socket fittings, and solvent-cemented joints.

F. Underground, sanitary waste and grease waste piping NPS 5 (DN 125) and larger shall be the following:
1. Solid Wall PVC pipe; PVC socket fittings; and solvent-cemented joints.

END OF SECTION 22 13 16

SECTION 22 13 19 – SANITARY WASTE PIPING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
1. Cleanouts.
2. Floor drains.
3. Roof flashing assemblies.
4. Through-penetration firestop assemblies.
5. Miscellaneous sanitary drainage piping specialties.
6. Flashing materials.

1.3 DEFINITIONS

A. PVC: Polyvinyl chloride plastic.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For drainage piping specialties to include in emergency, operation, and maintenance manuals.

PART 2 - PRODUCTS

2.1 HUB DRAIN (MARKED "HD"):

A. Provide SureSeal Model SS2009V for 2" diameter condensate hub drains.

2.2 TRAP PRIMER VALVE:

A. Precision Plumbing Products Model P-1/P-2 (Mifab M-500), with air gap supply Precision Plumbing Products AG-500 (Mifab MI-GAP). Provide Precision Plumbing Products

Distribution Unit (DU) (Mifab MI-DU) with proper number of branch lines as indicated on plans.

2.3 CLEANOUTS:

A. Cleanouts other than type listed below as manufactured by J.R. Smith, Josam, Zurn and Wade, will not be acceptable.

B. Cleanouts shall be provided where shown on plans, at each change of direction of the building drain greater than 45 degrees and at or near the foot of each vertical waste or soil stack. Location of all cleanouts shall be the same size as the piping. Every cleanout shall be installed so that the cleanout opens in the direction of the flow of the drainage line or at right angle thereto.

C. Floor cleanouts shall be an adjustable type with anchor flange for clamp device, clamping collar and nickel bronze cover. Contractor shall install 2# lead flashing a minimum of 18" all around cleanout and flash into flange and anchor with clamping collar.

D. Top of cleanout shall be level with top of finished floor so there is a continuous surface.

E. Floor cleanouts shall be Zurn 1400, Wade W-6000, or J.R. Smith 4031 (NB) with adjustable scoriated secured nickel bronze top.

F. Wall cleanouts shall be nickel bronze access frame and cover, Josam 58770, Wade W-8560-E with W-8303-1, J. R. Smith 4735 access cover.

G. Outside cleanouts shall be as detailed on the Plans.

2.4 ROOF FLASHING ASSEMBLIES

A. Roof Flashing Assemblies:
   1. Description: Manufactured assembly made of 4.0-lb/sq. ft., 0.0625-inch- thick, lead flashing collar and skirt extending at least 8 inches from pipe, with galvanized-steel boot reinforcement and counterflashing fitting.
      a. Open-Top Vent Cap: Without cap.

2.5 THROUGH-PENETRATION FIRESTOP ASSEMBLIES

A. Through-Penetration Firestop Assemblies:
   1. Standard: UL 1479 assembly of sleeve and stack fitting with firestopping plug.
   2. Size: Same as connected soil, waste, or vent stack.
   3. Sleeve: Molded PVC plastic, of length to match slab thickness and with integral nailing flange on one end for installation in cast-in-place concrete slabs.
   4. Stack Fitting: ASTM A 48/A 48M, gray-iron, hubless-pattern, wye branch with neoprene O-ring at base and gray-iron plug in thermal-release harness. Include PVC protective cap for plug.
   5. Special Coating: Corrosion resistant on interior of fittings.

2.6 FLASHING MATERIALS

A. Lead Sheet: ASTM B 749, Type L51121, copper bearing, with the following minimum weights and thicknesses, unless otherwise indicated:
   1. General Use: 4.0-lb/sq. ft., 0.0625-inch thickness.
   2. Vent Pipe Flashing: 3.0-lb/sq. ft., 0.0469-inch thickness.
   3. Burning: 6-lb/sq. ft., 0.0938-inch thickness.

B. Zinc-Coated Steel Sheet: ASTM A 653/A 653M, with 0.20 percent copper content and 0.04-inch minimum thickness, unless otherwise indicated. Include G90 hot-dip galvanized, mill-phosphatized finish for painting if indicated.

C. Elastic Membrane Sheet: ASTM D 4068, flexible, chlorinated polyethylene, 40-mil minimum thickness.

D. Fasteners: Metal compatible with material and substrate being fastened.

E. Metal Accessories: Sheet metal strips, clamps, anchoring devices, and similar accessory units required for installation; matching or compatible with material being installed.

F. Solder: ASTM B 32, lead-free alloy.

G. Bituminous Coating: SSPC-Paint 12, solvent-type, bituminous mastic.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install cleanouts in aboveground piping and building drain piping according to the following, unless otherwise indicated:
   1. Size same as drainage piping up to NPS 4. Use NPS 4 for larger drainage piping unless larger cleanout is indicated.
   2. Locate at each change in direction of piping greater than 45 degrees.

B. For floor cleanouts for piping below floors, install cleanout deck plates with top flush with finished floor.

C. For cleanouts located in concealed piping, install cleanout wall access covers, of types indicated, with frame and cover flush with finished wall.

D. Install roof flashing assemblies on sanitary stack vents and vent stacks that extend through roof.

E. Install flashing fittings on sanitary stack vents and vent stacks that extend through roof.

F. Install deep-seal traps on floor drains and other waste outlets, if indicated.

G. Install floor-drain, trap-seal primer fittings on inlet to floor drains that require trap-seal primer connection.
   1. Exception: Fitting may be omitted if trap has trap-seal primer connection.
   2. Size: Same as floor drain inlet.

3.2 FLASHING INSTALLATION

A. Fabricate flashing from single piece unless large pans, sumps, or other drainage shapes are required. Join flashing according to the following if required:
   1. Lead Sheets: Burn joints of lead sheets 6.0-lb/sq. ft., 0.0938-inch thickness or thicker. Solder joints of lead sheets 4.0-lb/sq. ft., 0.0625-inch thickness or thinner.
   2. Copper Sheets: Solder joints of copper sheets.

B. Install sheet flashing on pipes, sleeves, and specialties passing through or embedded in floors and roofs with waterproof membrane.
   1. Pipe Flashing: Sleeve type, matching pipe size, with minimum length of 10 inches, and skirt or flange extending at least 8 inches around pipe.
   2. Sleeve Flashing: Flat sheet, with skirt or flange extending at least 8 inches around sleeve.
   3. Embedded Specialty Flashing: Flat sheet, with skirt or flange extending at least 8 inches around specialty.

C. Set flashing on floors and roofs in solid coating of bituminous cement.

D. Secure flashing into sleeve and specialty clamping ring or device.

E. Install flashing for piping passing through roofs with counterflashing or commercially made flashing fittings, according to Section 076200 "Sheet Metal Flashing and Trim."

F. Extend flashing up vent pipe passing through roofs and turn down into pipe, or secure flashing into cast-iron sleeve having calking recess.

G. Fabricate and install flashing and pans, sumps, and other drainage shapes.

3.3 PROTECTION

A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.

B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION 22 13 19

SECTION 22 13 23 – SANITARY WASTE INTERCEPTORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Grease interceptors.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of interceptor indicated. Include materials of fabrication, dimensions, rated capacities, retention capacities, operating characteristics, size and location of each pipe connection, furnished specialties, and accessories.

B. Shop Drawings: For each type and size of precast-concrete interceptor indicated.

1. Include materials of construction, dimensions, rated capacities, retention capacities, location and size of each pipe connection, furnished specialties, and accessories.

1.4 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Interceptors, drawn to scale, on which the following items are shown and coordinated with each other, based on input from Installers of the items involved:

1. Interceptors.

2. Piping connections. Include size, location, and elevation of each.

3. Interface with underground structures and utility services.

PART 2 - PRODUCTS

2.1 GREASE TRAP (GT):

A. Contractor shall furnish and install Schier Great Basin model GB-1000 with pump out port kit or approved equal grease interceptor.

B. The unit shall be constructed as follows:

1. Lifetime guaranteed and made in USA of seamless, rotationally-molded polyethylene with minimum 3/8” uniform wall thickness.

2. Interceptor shall be furnished for below-grade installation with adjustable cover adapter, safety star access restrictor built into each cover adapter, and three outlet options.

3. Interceptor shall be certified to ASME A112.14.3 (Type D) and CSA B481.1.

4. Interceptor flow rate shall be 100 GPM.

5. Interceptor grease capacity shall be 5,495 lbs.

6. Cast iron cover, pickable 24” gas/water-tight seal and have a minimum 16,000 lbs. load capacity.

C. Certified Performance: Great Basin hydromechanical grease interceptors are third party performance-tested and listed by IAPMO to ASME #A112.14.3 and CSA B481.1 grease interceptor standards and greatly exceed requirements for grease separation and storage. They are compliant to the Uniform Plumbing Code and the International Plumbing Code.

D. Pump Out Port Kit: Shall consist of internal PVC 3" piping, injection molded PVC internal fitting adapter, injection mounded polypropylene retaining nut, injection molded polypropylene 4" MPT x 3" plain end fitting and standard 3" cam and groove fitting for pumper hook-up.

PART 3 - EXECUTION

3.1 EARTHWORK

A. Excavating, trenching, and backfilling are specified in Section 312000 "Earth Moving."

3.2 INSTALLATION

A. Install manhole risers from top of underground interceptors to manholes and gratings at finished grade.

B. Set tops of manhole frames and covers flush with finished surface in pavements. Set tops 3 inches above finish surface elsewhere, unless otherwise indicated.

3.3 CONNECTIONS

A. Make piping connections between interceptors and piping systems.

3.4 IDENTIFICATION

A. Identification materials and installation are specified in Section 312000 "Earth Moving." Arrange for installation of green warning tapes directly over piping and at outside edges of underground interceptors.

1. Use warning tapes or detectable warning tape over ferrous piping.

2. Use detectable warning tape over nonferrous piping and over edges of underground structures.

END OF SECTION 22 13 23

SECTION 22 34 00 – FUEL-FIRED DOMESTIC WATER HEATERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
1. Commercial, power-burner, gas-fired, storage, domestic-water heaters.
2. Commercial, power-vent, gas-fired, storage, domestic-water heaters.
3. Commercial, gas-fired, high-efficiency, storage, domestic-water heaters.
4. Domestic-water heater accessories.

1.3 ACTION SUBMITTALS

A. Product Data: For each type and size of domestic-water heater indicated. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

B. Shop Drawings:

1. Wiring Diagrams: For power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

A. Product Certificates: For each type of commercial, gas-fired domestic-water heater, from manufacturer.

B. Domestic-Water Heater Labeling: Certified and labeled by testing agency acceptable to authorities having jurisdiction.

C. Source quality-control reports.

D. Field quality-control reports.

E. Warranty: Sample of special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For fuel-fired, domestic-water heaters to include in emergency, operation, and maintenance manuals.

1.6 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. ASHRAE/IESNA Compliance: Fabricate and label fuel-fired, domestic-water heaters to comply with ASHRAE/IESNA 90.1.

C. ASME Compliance:

1. Where ASME-code construction is indicated, fabricate and label commercial, domestic-water heater storage tanks to comply with ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.
2. Where ASME-code construction is indicated, fabricate and label commercial, finned-tube, domestic-water heaters to comply with ASME Boiler and Pressure Vessel Code: Section IV.

D. NSF Compliance: Fabricate and label equipment components that will be in contact with potable water to comply with NSF 61 Annex G, "Drinking Water System Components - Health Effects."

1.7 COORDINATION

A. Coordinate sizes and locations of concrete bases with actual equipment provided.

1.8 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of fuel-fired, domestic-water heaters that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Structural failures including storage tank and supports.
b. Faulty operation of controls.
c. Deterioration of metals, metal finishes, and other materials beyond normal use.

2. Warranty Periods: From date of Substantial Completion.

a. Commercial, Gas-Fired, Storage, Domestic-Water Heaters:

1) Storage Tank: Three years.
2) Controls and Other Components: One year(s).

b. Compression Tanks: Five years.

PART 2 - PRODUCTS

2.1 COMMERCIAL, GAS-FIRED, STORAGE, DOMESTIC-WATER HEATERS

A. Commercial, Atmospheric, Gas-Fired, Storage, Domestic-Water Heaters:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
   a. Rheem Manufacturing Company.
   b. State Industries.
2. Standard: ANSI Z21.10.3/CSA 4.3.
3. Storage-Tank Construction: Non-ASME-code steel with 150 psig working-pressure rating.

   a. Tappings: Factory fabricated of materials compatible with tank. Attach tappings to tank before testing.

      1) NPS 2 and Smaller: Threaded ends according to ASME B1.20.1.
      2) NPS 2-1/2 and Larger: Flanged ends according to ASME B16.5 for steel and stainless-steel flanges, and according to ASME B16.24 for copper and copper-alloy flanges.

   b. Interior Finish: Comply with NSF 61 Annex G barrier materials for potable-water tank linings, including extending finish into and through tank fittings and outlets.
   c. Lining: Glass complying with NSF 61 Annex G barrier materials for potable-water tank linings, including extending lining into and through tank fittings and outlets.

4. Factory-Installed Storage-Tank Appurtenances:

   a. Anode Rod: Replaceable magnesium.
   b. Dip Tube: Required unless cold-water inlet is near bottom of tank.
   c. Drain Valve: Corrosion-resistant metal complying with ASSE 1005.
   d. Insulation: Comply with ASHRAE/IESNA 90.1. Surround entire storage tank except connections and controls.
   e. Jacket: Steel with enameled finish.
   f. Burner: For use with atmospheric, gas-fired, domestic-water heaters and natural-gas fuel.
   g. Automatic Ignition: ANSI Z21.20/CSA C22.2 No. 199, electric, automatic, gas-ignition system.
   h. Temperature Control: Adjustable thermostat.
   i. Safety Controls: Automatic, high-temperature-limit and low-water cutoff devices or systems.
   j. Combination Temperature-and-Pressure Relief Valves: ANSI Z21.22/CSA 4.4-M. Include one or more relief valves with total relieving capacity at least as great as heat input, and include pressure setting less than domestic-water heater working-pressure rating. Select one relief valve with sensing element that extends into storage tank.

5. Special Requirements: NSF 5 construction.
6. Draft Hood: Draft diverter, complying with ANSI Z21.12.
7. Power-Vent System: Exhaust fan, interlocked with burner.

B. Capacity and Characteristics:
   a. REFER TO WATER HEATER SCHEDULE FOR ADDITIONAL INFORMATION.

2. Electrical Characteristics:
   a. REFER TO WATER HEATER SCHEDULE FOR ADDITIONAL INFORMATION.

3. Minimum Vent Diameter: 3 inches

2.2 DOMESTIC-WATER HEATER ACCESSORIES

A. Domestic-Water Compression Tanks:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
   a. Watts
   b. Zurn
   c. Wessels
2. Description: Steel, pressure-rated tank constructed with welded joints and factory-installed butyl-rubber diaphragm. Include air precharge to minimum system-operating pressure at tank.
3. Construction:

   a. Tappings: Factory-fabricated steel, welded to tank before testing and labeling. Include ASME B1.20.1 pipe thread.
   b. Interior Finish: Comply with NSF 61 Annex G barrier materials for potable-water tank linings, including extending finish into and through tank fittings and outlets.
   c. Air-Charging Valve: Factory installed.

4. Capacity and Characteristics:

   a. Working-Pressure Rating: 150 psig
   b. Capacity Acceptable: 4.5 gal. minimum.
   c. Air Precharge Pressure: 20 psi

B. Drain Pans: Corrosion-resistant metal with raised edge. Comply with ANSI/CSA LC 3. Include dimensions not less than base of domestic-water heater, and include drain outlet not less than NPS 3/4 with ASME B1.20.1 pipe threads or with ASME B1.20.7 garden-hose threads.

C. Piping-Type Heat Traps: Field-fabricated piping arrangement according to ASHRAE/IESNA 90.1.

D. Heat-Trap Fittings: ASHRAE 90.2.

E. Manifold Kits: Domestic-water heater manufacturer's factory-fabricated inlet and outlet piping for field installation, for multiple domestic-water heater installation. Include ball-, butterfly-, or gate-type shutoff valves to isolate each domestic-water heater and [**calibrated**] [**memory-stop**] balancing valves to provide balanced flow through each domestic-water heater.

F. Comply with requirements for ball-, butterfly-, or gate-type shutoff valves specified in Section 220523.12 "Ball Valves for Plumbing Piping," Section 220523.13 "Butterfly Valves for Plumbing Piping," and Section 220523.15 "Gate Valves for Plumbing Piping."

1. Comply with requirements for balancing valves specified in Section 221119 "Domestic Water Piping Specialties."

G. Gas Shutoff Valves: ANSI Z21.15/CSA 9.1-M, manually operated. Furnish for installation in piping.

H. Gas Pressure Regulators: ANSI Z21.18/CSA 6.3, appliance type. Include pressure rating as required to match gas supply.

I. Automatic Gas Valves: ANSI Z21.21/CSA 6.5, appliance, electrically operated, on-off automatic valve.

J. Combination Temperature-and-Pressure Relief Valves: Include relieving capacity at least as great as heat input, and include pressure setting less than domestic-water heater working-pressure rating. Select relief valves with sensing element that extends into storage tank.

1. Gas-Fired, Domestic-Water Heaters: ANSI Z21.22/CSA 4.4-M.

K. Pressure Relief Valves: Include pressure setting less than domestic-water heater working-pressure rating.

1. Gas-Fired, Domestic-Water Heaters: ANSI Z21.22/CSA 4.4-M.

L. Vacuum Relief Valves: ANSI Z21.22/CSA 4.4-M.

M. Domestic-Water Heater Stands: Manufacturer's factory-fabricated steel stand for floor mounting, capable of supporting domestic-water heater and water. Provide dimension that will support bottom of domestic-water heater a minimum of 18 inches above the floor.

N. Domestic-Water Heater Mounting Brackets: Manufacturer's factory-fabricated steel bracket for wall mounting, capable of supporting domestic-water heater and water.

2.3 SOURCE QUALITY CONTROL

A. Factory Tests: Test and inspect assembled domestic-water heaters and storage tanks specified to be ASME-code construction, according to ASME Boiler and Pressure Vessel Code.

B. Hydrostatically test commercial domestic-water heaters and storage tanks to minimum of one and one-half times pressure rating before shipment.

C. Domestic-water heaters will be considered defective if they do not pass tests and inspections. Comply with requirements in Section 014000 "Quality Requirements" for retesting and reinspecting requirements and Section 017300 "Execution" for requirements for correcting the Work.

D. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 DOMESTIC-WATER HEATER INSTALLATION

A. Commercial, Domestic-Water Heater Mounting: Install commercial domestic-water heaters on concrete base. Comply with requirements for concrete base specified.

1. Exception: Omit concrete bases for commercial domestic-water heaters if installation on stand, bracket, suspended platform, or directly on floor is indicated.
2. Maintain manufacturer's recommended clearances.
3. Arrange units so controls and devices that require servicing are accessible.
4. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around the full perimeter of concrete base.
5. For supported equipment, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete floor.
6. Place and secure anchorage devices. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
7. Install anchor bolts to elevations required for proper attachment to supported equipment.
8. Anchor domestic-water heaters to substrate.

B. Install domestic-water heaters level and plumb, according to layout drawings, original design, and referenced standards. Maintain manufacturer's recommended clearances. Arrange units so controls and devices needing service are accessible.

1. Install shutoff valves on domestic-water-supply piping to domestic-water heaters and on domestic-hot-water outlet piping. Comply with requirements for shutoff valves specified in Section 220523.12 "Ball Valves for Plumbing Piping," Section 220523.13 "Butterfly Valves for Plumbing Piping," and Section 220523.15 "Gate Valves for Plumbing Piping."

C. Install gas-fired, domestic-water heaters according to NFPA 54.

1. Install gas shutoff valves on gas supply piping to gas-fired, domestic-water heaters without shutoff valves.
2. Install gas pressure regulators on gas supplies to gas-fired, domestic-water heaters without gas pressure regulators if gas pressure regulators are required to reduce gas pressure at burner.
3. Install automatic gas valves on gas supplies to gas-fired, domestic-water heaters if required for operation of safety control.
4. Comply with requirements for gas shutoff valves, gas pressure regulators, and automatic gas valves specified in [**Section 231123 "Facility Natural-Gas Piping."**] [**Section 231126 "Facility Liquefied-Petroleum Gas Piping."**]

D. Install combination temperature-and-pressure relief valves in top portion of storage tanks. Use relief valves with sensing elements that extend into tanks. Extend commercial-water-heater relief-valve outlet, with drain piping same as domestic-water piping in continuous downward pitch, and discharge by positive air gap onto closest floor drain.

E. Install water-heater drain piping as indirect waste to spill by positive air gap into open drains or over floor drains. Install hose-end drain valves at low points in water piping for domestic-water

heaters that do not have tank drains. Comply with requirements for hose-end drain valves specified in Section 221119 "Domestic Water Piping Specialties."

F. Assemble and install inlet and outlet piping manifold kits for multiple domestic-water heaters. Fabricate, modify, or arrange manifolds for balanced water flow through each domestic-water heater. Include shutoff valve and thermometer in each domestic-water heater inlet and outlet, and throttling valve in each domestic-water heater outlet. Comply with requirements for valves specified in Section 220523.12 "Ball Valves for Plumbing Piping," Section 220523.13 "Butterfly Valves for Plumbing Piping," and Section 220523.15 "Gate Valves for Plumbing Piping,"and comply with requirements for thermometers specified in Section 220519 "Meters and Gages for Plumbing Piping."

G. Install piping-type heat traps on inlet and outlet piping of domestic-water heater storage tanks without integral or fitting-type heat traps.

H. Fill domestic-water heaters with water.

I. Charge domestic-water compression tanks with air.

3.2 CONNECTIONS

A. Comply with requirements for domestic-water piping specified in Section 221116 "Domestic Water Piping."

B. Comply with requirements for gas piping specified in Section 231123 "Facility Natural-Gas Piping."

C. Drawings indicate general arrangement of piping, fittings, and specialties.

D. Where installing piping adjacent to fuel-fired, domestic-water heaters, allow space for service and maintenance of water heaters. Arrange piping for easy removal of domestic-water heaters.

3.3 IDENTIFICATION

A. Identify system components. Comply with requirements for identification specified in Section 220553 "Identification for Plumbing Piping and Equipment."

3.4 FIELD QUALITY CONTROL

A. Perform tests and inspections.

1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.
2. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
3. Operational Test: After electrical circuitry has been energized, start units to confirm proper operation.

4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

B. Domestic-water heaters will be considered defective if they do not pass tests and inspections. Comply with requirements in Section 014000 "Quality Requirements" for retesting and reinspecting requirements and Section 017300 "Execution" for requirements for correcting the Work.

C. Prepare test and inspection reports.

3.5 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain commercial, gas-fired, storage, domestic-water heaters.

END OF SECTION 22 34 00

SECTION 22 42 00 – PLUMBING FIXTURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
1. Floor drains.
2. Water closets.
3. Flush valves.
4. Toilet seats.
5. Urinals.
6. Lavatories.
7. Sinks.
8. Hose bibs.
9. Electric Water Cooler.
10. Ice Machine Connection.
11. Refrigerator water connection box.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.
1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each of the plumbing fixtures.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

1.4 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For flush valves to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 REFER TO PLUMBING FIXTURE SCHEDULE IN DRAWINGS FOR ADDITIONAL INFORMATION.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine roughing-in of water supply and sanitary drainage and vent piping systems to verify actual locations of piping connections before plumbing fixture installation.

B. Examine walls and floors for suitable conditions where plumbing fixtures will be installed.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Refer to Architectural Drawings for mounting height and exact location of all plumbing fixtures. Handicapped fixtures shall be installed to meet the latest A.D.A. requirements.

3.3 QUALITY

A. Plumbing Contractor shall furnish and install all plumbing fixtures shown on accompanying Drawings. Refer to both Plumbing and Architectural, and provide all fixtures shown on either. Fixtures shall be complete with all necessary brass and accessories required for a complete installation, including traps, escutcheons, angle supplies, basin cocks, etc. All fixtures shall be new and must be delivered to the building properly crated in perfect condition.

B. All brass must be of the best quality. Lightweight goods will not be accepted.

C. All brass pipe shall be seamless brass tubing and nipples shall be extra heavy.

D. All fittings and trim shall be chromium plated heavy brass unless otherwise specified.

E. "P" traps on lavatories and sinks shall be cast brass with cleanouts.

F. All exposed piping shall be chromium plated.

G. Provide cut-off valves at each fixture in both hot and cold water piping.

H. For the purpose of establishing type and class of fixtures required, the following plate numbers have been taken from the Manufacturer’s Catalog as indicated: Other fixture manufacturer's and model numbers, with prior approval, will be acceptable, however fixtures and accessories shall meet standards and features indicated below.

I. Contractor shall install silicon caulk around the base of a plumbing fixture or around the perimeter of a plumbing fixture where it attaches to a wall. The color of the caulk shall match the color of the plumbing fixture or shall be a color selected by the architect. Verify final color prior to installation. Caulked joint shall be properly smoothed out and shall completely seal the joint between the plumbing fixture and the surface the fixture is attached to. Unacceptable applications shall be completely removed and re-applied in accordance with directions from the architect.

J. Water-Closet Installation:
1. Install level and plumb according to roughing-in drawings.
2. Install floor-mounted water closets on bowl-to-drain connecting fitting attachments to piping or building substrate.
3. Install accessible, wall-mounted water closets at mounting height for handicapped/elderly, according to ICC/ANSI A117.1.

K. Support Installation:
1. Install supports, affixed to building substrate, for floor-mounted, back-outlet water closets.
2. Use carrier supports with waste-fitting assembly and seal.
3. Install floor-mounted, back-outlet water closets attached to building floor substrate, onto waste-fitting seals; and attach to support.
4. Install wall-mounted, back-outlet water-closet supports with waste-fitting assembly and waste-fitting seals; and affix to building substrate.

L. Flushometer-Valve Installation:
1. Install flushometer-valve, water-supply fitting on each supply to each water closet.
2. Attach supply piping to supports or substrate within pipe spaces behind fixtures.
3. Install lever-handle flushometer valves for accessible water closets with handle mounted on open side of water closet.
4. Install actuators in locations that are easy for people with disabilities to reach.
5. Install fresh batteries in battery-powered, electronic-sensor mechanisms.

M. Install toilet seats on water closets.

N. Wall Flange and Escutcheon Installation:
1. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations and within cabinets and millwork.
2. Install deep-pattern escutcheons if required to conceal protruding fittings.
3. Comply with escutcheon requirements specified in Section 220518 "Escutcheons for Plumbing Piping."

O. Joint Sealing:
1. Seal joints between water closets and walls and floors using sanitary-type, one-part, mildew-resistant silicone sealant.
2. Match sealant color to water-closet color.
3. Comply with sealant requirements specified in Section 079200 "Joint Sealants."

3.4 CONNECTIONS

A. Connect water closets with water supplies and soil, waste, and vent piping. Use size fittings required to match water closets.

B. Comply with water piping requirements specified in Section 221116 "Domestic Water Piping."

C. Comply with soil and waste piping requirements specified in Section 221316 "Sanitary Waste and Vent Piping."

D. Where installing piping adjacent to water closets, allow space for service and maintenance.

3.5 ADJUSTING

A. Operate and adjust water closets and controls. Replace damaged and malfunctioning water closets, fittings, and controls.

B. Adjust water pressure at flushometer valves to produce proper flow.

3.6 CLEANING AND PROTECTION

A. Clean plumbing fixtures and fittings with manufacturers' recommended cleaning methods and materials.

B. Install protective covering for installed plumbing fixtures and fittings.

C. Do not allow use of plumbing fixtures for temporary facilities unless approved in writing by Owner.

END OF SECTION 22 42 00

SECTION 23 31 13 – METAL DUCTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
1. Single-wall rectangular ducts and fittings.
2. Single-wall round ducts and fittings.
3. Sheet metal materials.
4. Sealants and gaskets.
5. Hangers and supports.

1.3 PERFORMANCE REQUIREMENTS

A. Delegated Duct Design: Duct construction, including sheet metal thicknesses, seam and joint construction, reinforcements, and hangers and supports, shall comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" and performance requirements and design criteria indicated in "Duct Schedule" Article.

B. Structural Performance: Duct hangers and supports shall withstand the effects of gravity loads and stresses within limits and under conditions described in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"

C. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of the following products:
1. Adhesives.
2. Sealants and gaskets.

PART 2 - PRODUCTS

2.1 SINGLE-WALL RECTANGULAR DUCTS AND FITTINGS

A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" based on indicated static-pressure class unless otherwise indicated.

B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-1, "Rectangular Duct/Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-2, "Rectangular Duct/Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

D. Elbows, Transitions, Offsets, Branch Connections, and Other Duct Construction: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 4, "Fittings and Other Construction," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

2.2 SINGLE-WALL ROUND DUCTS AND FITTINGS

A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 3, "Round, Oval, and Flexible Duct," based on indicated static-pressure class unless otherwise indicated.

B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-1, "Round Duct Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
   1. Transverse Joints in Ducts Larger Than 60 Inches in Diameter: Flanged.

C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-2, "Round Duct Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
   1. Fabricate round ducts larger than 90 inches in diameter with butt-welded longitudinal seams.
   2. Fabricate flat-oval ducts larger than 72 inches in width (major dimension) with butt-welded longitudinal seams.

D. Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

2.3 SHEET METAL MATERIALS

A. General Material Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

B. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.
   1. Duct Galvanized Coating Designation: G90.
   2. Finishes for Surfaces Exposed to View: Mill phosphatized.

C. Galvanized sheet metal for rectangular and round ductwork shall have a minimum gauge of 26.

2.4 DUCT LINER

A. Fibrous-Glass Duct Liner: Comply with ASTM C 1071, NFPA 90A, or NFPA 90B; and with NAIMA AH124, "Fibrous Glass Duct Liner Standard."

   1. Manufacturers shall be as follows:
      a. Certainteed
      b. Owens Corning
      c. Johns Manville
      d. Knauf

   2. Maximum Thermal Conductivity:

      a. Type I, Flexible: 0.27 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.

   3. Antimicrobial Erosion-Resistant Coating: Apply to the surface of the liner that will form the interior surface of the duct to act as a moisture repellent and erosion-resistant coating. Antimicrobial compound shall be tested for efficacy by an NRTL and registered by the EPA for use in HVAC systems.

   4. Water-Based Liner Adhesive: Comply with NFPA 90A or NFPA 90B and with ASTM C 916.

      a. For indoor applications, adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

B. Insulation Pins and Washers:

   1. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
   2. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick galvanized steel; with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.

C. Shop Application of Duct Liner: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 7-11, "Flexible Duct Liner Installation."

1. Adhere a single layer of indicated thickness of duct liner with at least 90 percent adhesive coverage at liner contact surface area. Attaining indicated thickness with multiple layers of duct liner is prohibited.
2. Apply adhesive to transverse edges of liner facing upstream that do not receive metal nosing.
3. Butt transverse joints without gaps, and coat joint with adhesive.
4. Fold and compress liner in corners of rectangular ducts or cut and fit to ensure butted-edge overlapping.
5. Do not apply liner in rectangular ducts with longitudinal joints, except at corners of ducts, unless duct size and dimensions of standard liner make longitudinal joints necessary.
6. Apply adhesive coating on longitudinal seams in ducts with air velocity of 2500 fpm.
7. Secure liner with mechanical fasteners 4 inches from corners and at intervals not exceeding 12 inches transversely; at 3 inches from transverse joints and at intervals not exceeding 18 inches longitudinally.
8. Secure transversely oriented liner edges facing the airstream with metal nosings that have either channel or "Z" profiles or are integrally formed from duct wall. Fabricate edge facings at the following locations:

    a. Fan discharges.
    b. Intervals of lined duct preceding unlined duct.
    c. Upstream edges of transverse joints in ducts where air velocities are higher than 2500 fpm or where indicated.

9. Secure insulation between perforated sheet metal inner duct of same thickness as specified for outer shell. Use mechanical fasteners that maintain inner duct at uniform distance from outer shell without compressing insulation.

    a. Sheet Metal Inner Duct Perforations: 3/32-inch diameter, with an overall open area of 23 percent.

10. Terminate inner ducts with buildouts attached to fire-damper sleeves, dampers, turning vane assemblies, or other devices. Fabricated buildouts (metal hat sections) or other buildout means are optional; when used, secure buildouts to duct walls with bolts, screws, rivets, or welds.

2.5 SEALANT AND GASKETS

A. General Sealant and Gasket Requirements: Surface-burning characteristics for sealants and gaskets shall be a maximum flame-spread index of 25 and a maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.

B. Two-Part Tape Sealing System:
1. Tape: Woven cotton fiber impregnated with mineral gypsum and modified acrylic/silicone activator to react exothermically with tape to form hard, durable, airtight seal.
2. Tape Width: 4 inches.
3. Sealant: Modified styrene acrylic.
4. Water resistant.
5. Mold and mildew resistant.
6. Maximum Static-Pressure Class: 10-inch wg, positive and negative.

7. Service: Indoor and outdoor.
8. Service Temperature: Minus 40 to plus 200 deg F.
9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum.
10. For indoor applications, sealant shall have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
11. Sealant shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

C. Water-Based Joint and Seam Sealant:
1. Application Method: Brush on.
2. Solids Content: Minimum 65 percent.
3. Shore A Hardness: Minimum 20.
4. Water resistant.
5. Mold and mildew resistant.
6. VOC: Maximum 75 g/L (less water).
7. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
8. Service: Indoor or outdoor.
9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.

D. Solvent-Based Joint and Seam Sealant:
1. Application Method: Brush on.
2. Base: Synthetic rubber resin.
3. Solvent: Toluene and heptane.
4. Solids Content: Minimum 60 percent.
5. Shore A Hardness: Minimum 60.
6. Water resistant.
7. Mold and mildew resistant.
8. Service: Indoor or outdoor.
9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.

E. Flanged Joint Sealant: Comply with ASTM C 920.
1. General: Single-component, acid-curing, silicone, elastomeric.
2. Type: S.
3. Grade: NS.
4. Class: 25.
5. Use: O.

F. Flange Gaskets: Butyl rubber, neoprene, or EPDM polymer with polyisobutylene plasticizer.

G. Round Duct Joint O-Ring Seals:
1. Seal shall provide maximum 3 cfm/100 sq. ft. at 1-inch wg and shall be rated for10-inch wg static-pressure class, positive or negative.
2. EPDM O-ring to seal in concave bead in coupling or fitting spigot.
3. Double-lipped, EPDM O-ring seal, mechanically fastened to factory-fabricated couplings and fitting spigots.

2.6 HANGERS AND SUPPORTS

A. Hanger Rods for Noncorrosive Environments: Cadmium-plated steel rods and nuts.

B. Hanger Rods for Corrosive Environments: Electrogalvanized, all-thread rods or galvanized rods with threads painted with zinc-chromate primer after installation.

C. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct."

D. Steel Cables for Galvanized-Steel Ducts: Galvanized steel complying with ASTM A 603.

E. Steel Cables for Stainless-Steel Ducts: Stainless steel complying with ASTM A 492.

F. Steel Cable End Connections: Cadmium-plated steel assemblies with brackets, swivel, and bolts designed for duct hanger service; with an automatic-locking and clamping device.

G. Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.

H. Trapeze and Riser Supports:
1. Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates.
2. Supports for Stainless-Steel Ducts: Stainless-steel shapes and plates.
3. Supports for Aluminum Ducts: Aluminum or galvanized steel coated with zinc chromate.

PART 3 - EXECUTION

3.1 DUCT INSTALLATION

A. Drawing plans, schematics, and diagrams indicate general location and arrangement of duct system. Indicated duct locations, configurations, and arrangements were used to size ducts and calculate friction loss for air-handling equipment sizing and for other design considerations. Install duct systems as indicated unless deviations to layout are approved on Shop Drawings and Coordination Drawings.

B. Install ducts according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" unless otherwise indicated.

C. Install round ducts in maximum practical lengths.

D. Install ducts with fewest possible joints.

E. Install factory- or shop-fabricated fittings for changes in direction, size, and shape and for branch connections.

F. Unless otherwise indicated, install ducts vertically and horizontally, and parallel and perpendicular to building lines.

G. Install ducts close to walls, overhead construction, columns, and other structural and permanent enclosure elements of building.

H. Install ducts with a clearance of 1 inch, plus allowance for insulation thickness.

I. Route ducts to avoid passing through transformer vaults and electrical equipment rooms and enclosures.

J. Where ducts pass through non-fire-rated interior partitions and exterior walls and are exposed to view, cover the opening between the partition and duct or duct insulation with sheet metal flanges of same metal thickness as the duct. Overlap openings on four sides by at least 1-1/2 inches.

K. Where ducts pass through fire-rated interior partitions and exterior walls, install fire dampers. Comply with requirements as specified for fire and smoke dampers.

L. Protect duct interiors from moisture, construction debris and dust, and other foreign materials.

3.2 DUCT SEALING

A. Seal ducts for duct static-pressure, seal classes, and leakage classes specified in "Duct Schedule" Article."

B. If ducts are not listed in the “Duct Schedule” Article then seal unlisted ducts to the following seal classes according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible":
   1. Ducts:
      a. Pressure Class: Positive 2-inch wg.
      b. Minimum SMACNA Seal Class: A.
      c. SMACNA Leakage Class for Rectangular: 6.
      d. SMACNA Leakage Class for Round and Flat Oval: 3.

3.3 HANGER AND SUPPORT INSTALLATION

A. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 5, "Hangers and Supports."

B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
   1. Where practical, install concrete inserts before placing concrete.
   2. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
   3. Use powder-actuated concrete fasteners for standard-weight aggregate concretes or for slabs more than 4 inches thick.
   4. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes or for slabs less than 4 inches thick.

C. Hanger Spacing: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum

Hanger Sizes for Round Duct," for maximum hanger spacing; install hangers and supports within 24 inches of each elbow and within 48 inches of each branch intersection.

D. Hangers Exposed to View: Threaded rod and angle or channel supports.

E. Support vertical ducts with steel angles or channel secured to the sides of the duct with welds, bolts, sheet metal screws, or blind rivets; support at each floor and at a maximum intervals of 16 feet.

F. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

3.4 CONNECTIONS

A. Make connections to equipment with flexible connectors.

B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for branch, outlet and inlet, and terminal unit connections.

3.5 PAINTING

A. Paint interior of metal ducts that are visible through registers and grilles and that do not have duct liner. Apply one coat of flat, black, latex paint over a compatible galvanized-steel primer.

3.6 FIELD QUALITY CONTROL

A. Perform tests and inspections.

B. Leakage Tests:

1. Comply with SMACNA's "HVAC Air Duct Leakage Test Manual." Submit a test report for each test.
2. Test the following systems:

    a. Ducts with a Pressure Class Higher Than **3-Inch wg**:
        1) Test representative duct sections totaling no less than **25 percent** of total installed duct area for each designated pressure class.
    b. Exhaust Ducts with a Pressure Class of **2-Inch wg or Higher**:
        1) Test representative duct sections totaling no less than **50 percent** of total installed duct area for each designated pressure class.
    c. Outdoor Air Ducts with a Pressure Class of **2-Inch wg or Higher**:
        1) Test representative duct sections totaling no less than **50 percent** of total installed duct area for each designated pressure class.

3. Disassemble, reassemble, and seal segments of systems to accommodate leakage testing and for compliance with test requirements.
4. Test for leaks before applying external insulation.

5. Conduct tests at static pressures equal to maximum design pressure of system or section being tested. If static-pressure classes are not indicated, test system at maximum system design pressure. Do not pressurize systems above maximum design operating pressure.
6. Give seven days' advance notice for testing.

C. Duct System Cleanliness Tests:

1. Visually inspect duct system to ensure that no visible contaminants are present.
2. Test sections of metal duct system, chosen randomly by Owner, for cleanliness according to "Vacuum Test" in NADCA ACR, "Assessment, Cleaning and Restoration of HVAC Systems."

    a. Acceptable Cleanliness Level: Net weight of debris collected on the filter media shall not exceed 0.75 mg/100 sq. cm.

D. Duct system will be considered defective if it does not pass tests and inspections.

E. Prepare test and inspection reports.

3.7 DUCT CLEANING

A. Clean new and existing duct system(s) before testing, adjusting, and balancing.

B. Use service openings for entry and inspection.

1. Create new openings and install access panels appropriate for duct static-pressure class if required for cleaning access. Provide insulated panels for insulated or lined duct. Patch insulation and liner as recommended by duct liner manufacturer.
2. Disconnect and reconnect flexible ducts as needed for cleaning and inspection.
3. Remove and reinstall ceiling to gain access during the cleaning process.

C. Particulate Collection and Odor Control:

1. When venting vacuuming system inside the building, use HEPA filtration with 99.97 percent collection efficiency for 0.3-micron-size (or larger) particles.
2. When venting vacuuming system to outdoors, use filter to collect debris removed from HVAC system, and locate exhaust downwind and away from air intakes and other points of entry into building.

D. Clean the following components by removing surface contaminants and deposits:

1. Air outlets and inlets (registers, grilles, and diffusers).
2. Supply, return, and exhaust fans including fan housings, plenums (except ceiling supply and return plenums), scrolls, blades or vanes, shafts, baffles, dampers, and drive assemblies.
3. Air-handling unit internal surfaces and components including mixing box, coil section, air wash systems, spray eliminators, condensate drain pans, humidifiers and dehumidifiers, filters and filter sections, and condensate collectors and drains.
4. Coils and related components.

5. Return-air ducts, dampers, actuators, and turning vanes except in ceiling plenums and mechanical equipment rooms.
6. Supply-air ducts, dampers, actuators, and turning vanes.
7. Dedicated exhaust and ventilation components and makeup air systems.

E. Mechanical Cleaning Methodology:

1. Clean metal duct systems using mechanical cleaning methods that extract contaminants from within duct systems and remove contaminants from building.
2. Use vacuum-collection devices that are operated continuously during cleaning. Connect vacuum device to downstream end of duct sections so areas being cleaned are under negative pressure.
3. Use mechanical agitation to dislodge debris adhered to interior duct surfaces without damaging integrity of metal ducts, duct liner, or duct accessories.
4. Clean fibrous-glass duct liner with HEPA vacuuming equipment; do not permit duct liner to get wet. Replace fibrous-glass duct liner that is damaged, deteriorated, or delaminated or that has friable material, mold, or fungus growth.
5. Clean coils and coil drain pans according to NADCA 1992. Keep drain pan operational. Rinse coils with clean water to remove latent residues and cleaning materials; comb and straighten fins.
6. Provide drainage and cleanup for wash-down procedures.
7. Antimicrobial Agents and Coatings: Apply EPA-registered antimicrobial agents if fungus is present. Apply antimicrobial agents according to manufacturer's written instructions after removal of surface deposits and debris.

3.8 START UP

A. Air Balance: Comply with requirements as specified.

3.9 DUCT SCHEDULE

A. Supply Ducts:
1. Ducts Connected to Constant-Volume Units, and RTUs:
a. Pressure Class: Positive 2-inch wg.
b. Minimum SMACNA Seal Class: A.
c. SMACNA Leakage Class for Rectangular: 6.
d. SMACNA Leakage Class for Round and Flat Oval: 3.

B. Return Ducts:
1. Ducts Connected to Constant-Volume Units, and RTUs:
a. Pressure Class: Positive or negative 2-inch wg.
b. Minimum SMACNA Seal Class: A.
c. SMACNA Leakage Class for Rectangular: 6.
d. SMACNA Leakage Class for Round and Flat Oval: 3.

C. Exhaust Ducts:
1. Ducts Connected to Fans Exhausting (ASHRAE 62.1, Class 1 and 2) Air:
a. Pressure Class: Negative 2-inch wg.

b. Minimum SMACNA Seal Class: A if negative pressure, and A if positive pressure.
c. SMACNA Leakage Class for Rectangular: 12.
d. SMACNA Leakage Class for Round and Flat Oval: 6.

D. Outdoor-Air (Not Filtered, Heated, or Cooled) Ducts:
1. Ducts Connected to Constant-Volume Units, VRF Outside Air Units:
a. Pressure Class: Positive or negative 2-inch wg.
b. Minimum SMACNA Seal Class: A.
c. SMACNA Leakage Class for Rectangular: 6.
d. SMACNA Leakage Class for Round and Flat Oval: 3.

E. Duct Liner (Thickness):
1. Transfer Ducts: Fibrous glass, Type I, 1inch thick.

END OF SECTION 23 31 13

SECTION 23 33 00 – AIR DUCT ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
1. Manual volume dampers.
2. Motorized dampers.
3. Spin Collars.
4. Fire dampers.
5. Ceiling Radiation Dampers.
6. Turning vanes.
7. Duct-mounted access doors.
8. Duct Access Panel Assemblies.
9. Flexible connectors.
10. Flexible ducts.
11. Duct accessory hardware.

1.3 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For air duct accessories to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 ASSEMBLY DESCRIPTION

A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."

B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

2.2 MATERIALS

A. Galvanized Sheet Steel: Comply with ASTM A 653/A 653M.
1. Galvanized Coating Designation: G90.
2. Exposed-Surface Finish: Mill phosphatized.

B. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless-steel ducts.

C. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

2.3 MANUAL VOLUME DAMPERS

A. Low-Leakage, Steel, Manual Volume Dampers:
1. Manufacturers:
   a. Greenheck.
   b. Dace Mfg.
   c. Nailor Industries Inc.
   d. Pottorff.
   e. Ruskin Company.
2. Comply with AMCA 500-D testing for damper rating.
3. Low-leakage rating, with linkage outside airstream, and bearing AMCA's Certified Ratings Seal for both air performance and air leakage.
4. Suitable for horizontal or vertical applications.
5. Frames:
   a. Hat Channel shaped.
   b. 0.031-inch- thick, galvanized sheet steel.
   c. Mitered and welded corners.
   d. Flanges for attaching to walls and flangeless frames for installing in ducts.
6. Blades:
   a. Multiple blade.
   b. Opposed-blade design.
   c. Stiffen damper blades for stability.
   d. Galvanized, roll-formed steel, 0.031 inch thick.
7. Blade Axles: Galvanized steel.
8. Bearings:
   a. Molded synthetic.
   b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
9. Blade Seals: Neoprene.
10. Jamb Seals: Stainless Steel.
11. Tie Bars and Brackets: Galvanized steel.
12. Accessories:
    a. Include locking device to hold single-blade dampers in a fixed position without vibration.

B. Jackshaft:
1. Size: 0.5-inch diameter.
2. Material: Galvanized-steel pipe rotating within pipe-bearing assembly mounted on supports at each mullion and at each end of multiple-damper assemblies.
3. Length and Number of Mountings: As required to connect linkage of each damper in multiple-damper assembly.

C. Damper Hardware:
1. Zinc-plated, die-cast core with dial and handle made of 3/32-inch- thick zinc-plated steel, and a 3/4-inch hexagon locking nut.

2. Include center hole to suit damper operating-rod size.
3. Include elevated platform for insulated duct mounting.

2.4 MOTORIZED DAMPERS

A. Low-leakage rating, with linkage outside airstream, and bearing AMCA's Certified Ratings Seal for both air performance and air leakage.

B. Manufacturers:
1. Greenheck.
2. Flex-Tek Group.
3. Nailor Industries Inc.
4. Pottorff.
5. Ruskin Company.

C. For Round Duct Type, Mechanical Contractor shall furnish and install motorized dampers at outdoor intakes as indicated on mechanical and architectural drawings. Damper shall be parallel blade motorized type equivalent to Ruskin CDRS25, Greenheck Model VCDR-53, Arrow Series 250SRD or equal. Motorized dampers shall be operated by 120/1/60 or 24 V electric actuator as indicated on plans. Provide Interlock with respective air handling unit. Interlock with respective air handling unit shall be low voltage. Damper shall be complete with outboard support bearing, blade and jamb seals. Dampers shall be low - leakage type.

D. For Rectangular Duct Type, Mechanical Contractor shall furnish and install motorized dampers at outdoor intakes as indicated on mechanical and architectural drawings. Damper shall be parallel blade motorized type equivalent to Ruskin CD36/PB, Arrow Series 1770, Greenheck Model VCD-23 or equal. Motorized dampers shall be operated by 120/1/60 or 24 V electric actuator as indicated on plans. Provide Interlock with respective air handling unit. Interlock with respective air handling unit shall be low voltage. Damper shall be complete with outboard support bearing, blade and jamb seals. Dampers shall be low - leakage type.

E. Frames:
1. Hat shaped.
2. 0.064-inch- thick, galvanized sheet steel.
3. Mitered and welded corners.

F. Blades:
1. Multiple blade with maximum blade width of 6 inches.
2. Opposed-blade design.
3. Galvanized-steel.
4. 0.064 inch thick single skin.
5. Blade Edging: Closed-cell neoprene.
6. Blade Edging: Inflatable seal blade edging, or replaceable rubber seals.

G. Blade Axles: 1/2-inch- diameter; galvanized steel; blade-linkage hardware of zinc-plated steel and brass; ends sealed against blade bearings.
1. Operating Temperature Range: From minus 40 to plus 200 deg F.

H. Bearings:
1. Molded synthetic.

2. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
3. Thrust bearings at each end of every blade.

2.5 SPIN COLLARS

A. All round take-offs to round branch duct shall be made with factory fabricated spin-type collar fittings with balancing damper and constructed of minimum 26 ga galvanized steel. The damper shall have a raised 2" handle with a high quality locking quadrant. A 3/8" continuous rod with “U” bolts connects the damper to the rod. Nylon end bearing are required where the rod penetrates the spin collar barrel. These spin-collars shall be as manufactured by Flexmaster Model FLD-B03, Dace #26ga MSD-C03 or approved equal.

2.6 FIRE DAMPERS

A. The contractor shall furnish and install UL555 rated 1-1/2 hour fire dampers at the locations indicated on the drawings in new ducts and sound attenuators. The contractor shall provide dampers with sleeves and angle frames necessary to comply with the manufacturer's UL installation requirements. Dampers for vertical or horizontal air flow shall be provided as required.

B. Manufacturers:
1. Greenheck.
2. Flex-Tek Group.
3. Nailor Industries Inc.
4. Pottorff.
5. Ruskin Company.

C. Fire damper shall be 100% free area and installed in wall and floor openings utilizing steel sleeves, angles, other materials and practice required to provide an installation equivalent to that utilized by the manufacturer when dampers are tested by UL555. Installation shall be in accordance with the damper manufacturer's instructions.

D. Fire damper for rectangular ductwork and transfer openings shall be Ruskin type DIBD-B, Greenheck Model DFD-150-B (Basis of Design).

E. Fire dampers for round ductwork shall be Ruskin Model DIBD-CR, Greenheck DFD-150-CR (Basis of Design).

F. All fire dampers shall be installed per N.F.P.A. and U.L. requirements. Install U.L. approved sealant around the perimeter of the angle iron support at the sleeve and the wall in accordance with U. L. recommendations.

G. All fire dampers shall meet the latest Class 1 leakage requirements.

2.7 CEILING RADIATION DAMPERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Nailor Industries Inc.
2. Pottorff.
3. Ruskin Company.

B. General Requirements:
1. Labeled according to UL 555C by an NRTL.
2. Comply with construction details for tested floor- and roof-ceiling assemblies as indicated in UL's "Fire Resistance Directory."

C. Frame: Galvanized sheet steel, round or rectangular, style to suit ceiling construction.

D. Blades: Galvanized sheet steel with refractory insulation.

E. Heat-Responsive Device: Replaceable, 165 deg F (74 deg C) rated, fusible links.

F. Fire Rating: 1 hours.

2.8 SMOKE DAMPERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Greenheck Fan Corporation.
2. Pottorff.
3. Ruskin Company.

B. Manufacturers offer additional features for engineered smoke control system dampers.

C. http://www.specagent.com/Lookup?ulid=3450General Requirements: Label according to UL 555S by an NRTL.

D. Smoke Detector: Integral, factory wired for single-point connection.

E. Frame: Hat-shaped, 0.094-inch- (2.4-mm-) thick, galvanized sheet steel, with welded corners.

F. Blades: Roll-formed, horizontal, interlocking, 0.063-inch- (1.6-mm) thick, galvanized sheet steel.

G. Leakage: Class I.

H. Rated pressure and velocity to exceed design airflow conditions.

I. Mounting Sleeve: Factory-installed, 0.05-inch- (1.3-mm-) thick, galvanized sheet steel; length to suit wall or floor application with factory-furnished silicone calking.

J. Damper Motors: two-position action.

K. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."
1. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.

2. Controllers, Electrical Devices, and Wiring: Comply with requirements for electrical devices and connections specified in Section 230923 "Direct Digital Control (DDC) System for HVAC."
3. Permanent-Split-Capacitor or Shaded-Pole Motors: With oil-immersed and sealed gear trains.
4. Spring-Return Motors: Equip with an integral spiral-spring mechanism where indicated. Enclose entire spring mechanism in a removable housing designed for service or adjustments. Size for running torque rating of 150 in. x lbf (17 N x m) and breakaway torque rating of 150 in. x lbf (17 N x m).
5. Outdoor Motors and Motors in Outdoor-Air Intakes: Equip with O-ring gaskets designed to make motors weatherproof. Equip motors with internal heaters to permit normal operation at minus 40 deg F (minus 40 deg C).
6. Nonspring-Return Motors: For dampers larger than 25 sq. ft. (2.3 sq. m), size motor for running torque rating of 150 in. x lbf (17 N x m) and breakaway torque rating of 300 in. x lbf (34 N x m).
7. Electrical Connection: 115 V, single phase, 60 Hz.

L. Accessories:
1. Auxiliary switches for signaling fan control or position indication.
2. Test and reset switches, damper mounted.

2.9 COMBINATION FIRE AND SMOKE DAMPERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Greenheck Fan Corporation.
2. Pottorff.
3. Ruskin Company.

B. Type: Dynamic; rated and labeled according to UL 555 and UL 555S by an NRTL.

C. Closing rating in ducts up to 4-inch wg (1-kPa) static pressure class and minimum 2000-fpm (10-m/s) velocity.

D. Fire Rating: 1-1/2 and 3 hours.

E. Frame: Hat-shaped, 0.094-inch- (2.4-mm-) thick, galvanized sheet steel, with welded interlocking, gusseted corners.

F. Heat-Responsive Device: Resettable, 165 deg F (74 deg C) rated, fire-closure device.

G. Heat-Responsive Device: Electric resettable device and switch package, factory installed, rated.

H. Smoke Detector: Integral, factory wired for single-point connection.

I. Blades: Roll-formed, horizontal, interlocking, 0.034-inch- (0.85-mm-) thick, galvanized sheet steel.

J. Leakage: Class I.

K. Rated pressure and velocity to exceed design airflow conditions.

L. Mounting Sleeve: Factory-installed, 0.05-inch- (1.3-mm-) thick, galvanized sheet steel; length to suit wall or floor application with factory-furnished silicone calking.

M. Master control panel for use in dynamic smoke-management systems.

N. Damper Motors: two-position action.

O. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."
1. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.
2. Controllers, Electrical Devices, and Wiring: Comply with requirements for electrical devices and connections specified in Section 230923 "Direct Digital Control (DDC) System for HVAC."
3. Permanent-Split-Capacitor or Shaded-Pole Motors: With oil-immersed and sealed gear trains.
4. Spring-Return Motors: Equip with an integral spiral-spring mechanism where indicated. Enclose entire spring mechanism in a removable housing designed for service or adjustments. Size for running torque rating of 150 in. x lbf (17 N x m) and breakaway torque rating of 150 in. x lbf (17 N x m).
5. Outdoor Motors and Motors in Outdoor-Air Intakes: Equip with O-ring gaskets designed to make motors weatherproof. Equip motors with internal heaters to permit normal operation at minus 40 deg F (minus 40 deg C).
6. Nonspring-Return Motors: For dampers larger than 25 sq. ft. (2.3 sq. m), size motor for running torque rating of 150 in. x lbf (17 N x m) and breakaway torque rating of 300 in. x lbf (34 N x m).
7. Electrical Connection: 115 V, single phase, 60 Hz.

P. Accessories:
1. Auxiliary switches for signaling fan control or position indication.
2. Test and reset switches, damper mounted.

2.10 TURNING VANES

A. Manufactured Turning Vanes for Metal Ducts: Curved blades of galvanized sheet steel; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
1. Acoustic Turning Vanes: Fabricate airfoil-shaped aluminum extrusions with perforated faces and fibrous-glass fill.

B. Manufactured Turning Vanes for Nonmetal Ducts: Fabricate curved blades of resin-bonded fiberglass with acrylic polymer coating; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.

C. General Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 4-3, "Vanes and Vane Runners," and 4-4, "Vane Support in Elbows."

D. Vane Construction: Single wall for ducts up to 48 inches wide and double wall for larger dimensions.

2.11 DUCT-MOUNTED ACCESS DOORS

A. Duct-Mounted Access Doors: Fabricate access panels according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 7-2, "Duct Access Doors and Panels," and 7-3, "Access Doors - Round Duct."
   1. Door:
      a. Double wall, rectangular.
      b. Galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class.
      c. Vision panel.
      d. Hinges and Latches: 1-by-1-inchbutt or piano hinge and cam latches.
      e. Fabricate doors airtight and suitable for duct pressure class.
   2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
   3. Number of Hinges and Locks:
      a. Access Doors Less Than 12 Inches Square: No hinges and two sash locks.
      b. Access Doors up to 18 Inches Square: Continuous and two sash locks.
      c. Access Doors up to 24 by 48 Inches: Continuous and two compression latches with outside and inside handles.
      d. Access Doors Larger Than 24 by 48 Inches: Four hinges and two compression latches with outside and inside handles.

2.12 DUCT ACCESS PANEL ASSEMBLIES

A. Labeled according to UL 1978 by an NRTL.

B. Panel and Frame: Minimum thickness 0.0528-inch carbon steel.

C. Fasteners: Carbon steel. Panel fasteners shall not penetrate duct wall.

D. Gasket: Comply with NFPA 96; grease-tight, high-temperature ceramic fiber, rated for minimum 2000 deg F.

E. Minimum Pressure Rating: 10-inch wg, positive or negative.

2.13 FLEXIBLE CONNECTORS

A. Materials: Flame-retardant or noncombustible fabrics.

B. Coatings and Adhesives: Comply with UL 181, Class 1.

C. Metal-Edged Connectors: Factory fabricated with a fabric strip 3-1/2 inches wide attached to two strips of 2-3/4-inch- wide, 0.028-inch- thick, galvanized sheet steel or 0.032-inch- thick aluminum sheets. Provide metal compatible with connected ducts.

D. Indoor System, Flexible Connector Fabric: Glass fabric double coated with neoprene.
   1. Minimum Weight: 26 oz./sq. yd.
   2. Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
   3. Service Temperature: Minus 40 to plus 200 deg F.

E. Outdoor System, Flexible Connector Fabric: Glass fabric double coated with weatherproof, synthetic rubber resistant to UV rays and ozone.
   1. Minimum Weight: 24 oz./sq. yd..
   2. Tensile Strength: 530 lbf/inch in the warp and 440 lbf/inch in the filling.
   3. Service Temperature: Minus 50 to plus 250 deg F.

F. Thrust Limits: Combination coil spring and elastomeric insert with spring and insert in compression, and with a load stop. Include rod and angle-iron brackets for attaching to fan discharge and duct.
   1. Frame: Steel, fabricated for connection to threaded rods and to allow for a maximum of 30 degrees of angular rod misalignment without binding or reducing isolation efficiency.
   2. Outdoor Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
   3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
   4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
   5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
   6. Elastomeric Element: Molded, oil-resistant rubber or neoprene.
   7. Coil Spring: Factory set and field adjustable for a maximum of 1/4-inch movement at start and stop.

2.14 FLEXIBLE DUCTS

A. Manufacturers:
   1. Thermaflex Model M-KE
   2. Flexmaster 1M

B. Insulated, Flexible Duct: UL 181, Class 1, 2-ply vinyl film supported by helically wound, spring-steel wire; fibrous-glass insulation; polyethylene vapor-barrier film.
   1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
   2. Maximum Air Velocity: 4000 fpm.
   3. Temperature Range: Minus 10 to plus 160 deg F.
   4. Insulation R-value: Comply with ASHRAE/IESNA 90.1. (R6)

C. Flexible Duct Connectors:
   1. Clamps: Stainless-steel band with cadmium-plated hex screw to tighten band with a worm-gear action in sizes 3 through 18 inches, to suit duct size.
   2. Non-Clamp Connectors: Liquid adhesive plus tape.

2.15 DUCT ACCESSORY HARDWARE

A. Instrument Test Holes: Cast iron or cast aluminum to suit duct material, including screw cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit duct-insulation thickness.

B. Adhesives: High strength, quick setting, neoprene based, waterproof, and resistant to gasoline and grease.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install duct accessories according to applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.

B. Install duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and fibrous-glass ducts, stainless-steel accessories in stainless-steel ducts, and aluminum accessories in aluminum ducts.

C. Install backdraft dampers at inlet of exhaust fans or exhaust ducts as close as possible to exhaust fan unless otherwise indicated.

D. Install volume dampers at points on supply, return, and exhaust systems where branches extend from larger ducts. Where dampers are installed in ducts having duct liner, install dampers with hat channels of same depth as liner, and terminate liner with nosing at hat channel.
   1. Install steel volume dampers in steel ducts.
   2. Install aluminum volume dampers in aluminum ducts.

E. Set dampers to fully open position before testing, adjusting, and balancing.

F. Install test holes at fan inlets and outlets and elsewhere as indicated.

G. Install fire dampers according to UL listing.

H. Install duct access doors on sides of ducts to allow for inspecting, adjusting, and maintaining accessories and equipment at the following locations:
   1. Upstream from duct filters.
   2. Downstream from manual volume dampers, control dampers, backdraft dampers, and equipment.
   3. Adjacent to and close enough to fire or smoke dampers, to reset or reinstall fusible links. Access doors for access to fire or smoke dampers having fusible links shall be pressure relief access doors and shall be outward operation for access doors installed upstream from dampers and inward operation for access doors installed downstream from dampers.
   4. At each change in direction and at maximum 50-foot spacing.
   5. Control devices requiring inspection.
   6. Elsewhere as indicated.

I. Install access doors with swing against duct static pressure.

J. Access Door Sizes:
   1. One-Hand or Inspection Access: 8 by 5 inches.
   2. Two-Hand Access: 12 by 6 inches.
   3. Head and Hand Access: 18 by 10 inches.
   4. Head and Shoulders Access: 21 by 14 inches.
   5. Body Access: 25 by 14 inches.
   6. Body plus Ladder Access: 25 by 17 inches.

K. Label access doors according to Section 230553 "Identification for HVAC Piping and Equipment" to indicate the purpose of access door.

L. Install flexible connectors to connect ducts to equipment.

M. For fans developing static pressures of 5-inch wg and more, cover flexible connectors with loaded vinyl sheet held in place with metal straps.

N. Connect diffusers or light troffer boots to ducts directly or with maximum 60-inch lengths of flexible duct clamped or strapped in place.

O. Connect flexible ducts to metal ducts with draw bands.

P. Install duct test holes where required for testing and balancing purposes.

Q. Install thrust limits at centerline of thrust, symmetrical on both sides of equipment. Attach thrust limits at centerline of thrust and adjust to a maximum of 1/4-inch movement during start and stop of fans.

3.2 FIELD QUALITY CONTROL

A. Tests and Inspections:
   1. Operate dampers to verify full range of movement.
   2. Inspect locations of access doors and verify that purpose of access door can be performed.
   3. Operate fire, smoke, and combination fire and smoke dampers to verify full range of movement and verify that proper heat-response device is installed.
   4. Inspect turning vanes for proper and secure installation.
   5. Operate remote damper operators to verify full range of movement of operator and damper.

END OF SECTION 23 33 00

SECTION 23 34 23 – HVAC POWER VENTILATORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
   1. Centrifugal roof ventilators.
   2. Centrifugal ceiling fans.

1.3 PERFORMANCE REQUIREMENTS

A. Operating Limits: Classify according to AMCA 99.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product indicated. Include rated capacities, operating characteristics, and furnished specialties and accessories. Also include the following:
   1. Certified fan performance curves with system operating conditions indicated.
   2. Certified fan sound-power ratings.
   3. Motor ratings and electrical characteristics, plus motor and electrical accessories.
   4. Material thickness and finishes, including color charts.
   5. Dampers, including housings, linkages, and operators.
   6. Roof curbs.
   7. Fan speed controllers.

1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For power ventilators to include in emergency, operation, and maintenance manuals.

1.6 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. AMCA Compliance: Fans shall have AMCA-Certified performance ratings and shall bear the AMCA-Certified Ratings Seal.

C. UL Standards: Power ventilators shall comply with UL 705. Power ventilators for use for restaurant kitchen exhaust shall also comply with UL 762.

1.7 COORDINATION

A. Coordinate size and location of structural-steel support members.

B. Coordinate sizes and locations of roof curbs, equipment supports, and roof penetrations with actual equipment provided.

PART 2 - PRODUCTS

2.1 CENTRIFUGAL ROOF VENTILATORS

A. Manufacturers:
1. Cook.
2. Greenheck.
3. ACME
4. Pen-Barry
5. Twin City
6. Captiveaire

B. All exhaust fans shall be equipped with bird screen, automatic back-draft dampers, solid state speed controller (direct drive) and integral disconnect switch unless noted otherwise. Fan motors shall be of the 40 deg C ambient temperature rise type and shall be suitable for continuous duty operation.

C. Direct drive fans shall be complete with solid state speed control switch mounted on unit for balancing. Interlock with remote on/off switch.

D. Housing: Steel, lined with acoustical insulation.

E. Fan Wheel: Centrifugal wheels directly mounted on motor shaft. Fan shrouds, motor, and fan wheel shall be removable for service.

F. Grille: Aluminum, louvered grille with flange on intake and thumbscrew attachment to fan housing.

G. Electrical Requirements: Junction box for electrical connection on housing and receptacle for motor plug-in.

2.2 CEILING MOUNTED FANS

A. Manufacturers:
1. Cook.
2. Greenheck.
3. ACME
4. Pen-Barry
5. Twin City

B. All exhaust fans shall be equipped with bird screen, automatic back-draft dampers, solid state speed controller (direct drive) and integral disconnect switch unless noted otherwise. Fan

motors shall be of the 40 deg C ambient temperature rise type and shall be suitable for continuous duty operation.

C. Direct drive fans shall be complete with solid state speed control switch mounted on unit for balancing. Interlock with remote on/off switch.

D. Housing: Steel, lined with acoustical insulation.

E. Fan Wheel: Centrifugal wheels directly mounted on motor shaft. Fan shrouds, motor, and fan wheel shall be removable for service.

F. Grille: White ceiling mounted metal grille. The grille shall be removable to provide service access to fan, motor, etc.

G. Electrical Requirements: Junction box for electrical connection on housing and receptacle for motor plug-in.

2.3 MOTORS

A. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."
   1. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.

B. Enclosure Type: Totally enclosed, fan cooled.

2.4 SOURCE QUALITY CONTROL

A. Certify sound-power level ratings according to AMCA 301, "Methods for Calculating Fan Sound Ratings from Laboratory Test Data." Factory test fans according to AMCA 300, "Reverberant Room Method for Sound Testing of Fans." Label fans with the AMCA-Certified Ratings Seal.

B. Certify fan performance ratings, including flow rate, pressure, power, air density, speed of rotation, and efficiency by factory tests according to AMCA 210, "Laboratory Methods of Testing Fans for Aerodynamic Performance Rating." Label fans with the AMCA-Certified Ratings Seal.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install power ventilators level and plumb.

B. Install units with clearances for service and maintenance.

C. Label units according to requirements specified.

3.2 CONNECTIONS

A. Drawings indicate general arrangement of ducts and duct accessories. Make final duct connections with flexible connectors.

B. Install ducts adjacent to power ventilators to allow service and maintenance.

C. Ground equipment.

3.3 ADJUSTING

A. Adjust damper linkages for proper damper operation.

B. Adjust belt tension.

C. Replace fan and motor pulleys as required to achieve design airflow.

D. Lubricate bearings.

END OF SECTION 23 34 23

SECTION 23 37 13 – DIFFUSERS, REGISTERS, GRILLES, AND LOUVERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
   1. Rectangular and square ceiling diffusers.
   2. Louvered face diffuser.
   3. Fixed face registers and grilles.

B. Related Sections:
   1. Section 233300 "Air Duct Accessories" for fire and smoke dampers and volume-control dampers not integral to diffusers, registers, and grilles.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated, include the following:
   1. Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static-pressure drop, and noise ratings.
   2. Diffuser, Register, and Grille Schedule: Indicate drawing designation, room location, quantity, model number, size, and accessories furnished.

PART 2 - PRODUCTS

2.1 CEILING DIFFUSERS

A. Louver Face Diffuser:
   1. Manufacturers:
      a. Titus.
      b. Price Industries.
      c. Nailor Industries.
      d. Metalaire, Inc.
   2. Material: Aluminum.
   3. Finish: Baked enamel, white.
   4. Face Size: See schedule on Drawings..
   5. Mounting: Surface with beveled frame.
   6. Pattern: Four-way core style.
   7. Dampers: Radial opposed blade.
   8. Accessories:

a. Square to round neck adaptor.

2.2 REGISTERS AND GRILLES

A. Fixed Face Register:
1. Manufacturers:
   a. Titus.
   b. Price Industries.
   c. Nailor Industries.
   d. Metalaire, Inc.
2. Material: Aluminum.
3. Finish: Baked enamel, white.
4. Core Construction: Integral.
5. Frame: 1 inch wide.
6. Mounting: Lay in.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas where diffusers, registers, and grilles are to be installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Install diffusers, registers, and grilles level and plumb.

B. Ceiling-Mounted Outlets and Inlets: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Make final locations where indicated, as much as practical. For units installed in lay-in ceiling panels, locate units in the center of panel. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.

C. Install diffusers, registers, and grilles with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

3.3 ADJUSTING

A. After installation, adjust diffusers, registers, and grilles to air patterns indicated, or as directed, before starting air balancing.

END OF SECTION 23 37 13

SECTION 23 38 13 – COMMERCIAL- TYPE I KITCHEN HOODS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes the following:

1. Type I Commercial Kitchen Hoods.
2. Wet-Chemical Fire-Suppression System.

1.2 DEFINITIONS

A. Listed Hood: A hood, factory fabricated and tested for compliance with UL 710 by a testing agency acceptable to authorities having jurisdiction.

B. Standard Hood: A hood, usually field fabricated that complies with design, construction, and performance criteria of applicable national and local codes.

C. Type I Hood: A hood designed for grease exhaust applications.

1.3 ACTION SUBMITTALS

A. Product Data: For the following:

1. Filters/baffles.
2. Fire-suppression systems.
3. Lighting fixtures.

B. Shop Drawings: Signed and sealed by a qualified professional engineer.

1. Show plan view, elevation view, sections, roughing-in dimensions, service requirements, duct connection sizes, and attachments to other work.
2. Show cooking equipment plan and elevation to confirm minimum code-required overhang.
3. Indicate performance, exhaust and makeup air airflow, and pressure loss at actual Project-site elevation.
4. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
5. Wiring Diagrams: Include diagrams for power, signal, and control wiring.
6. Piping Diagrams: Detail fire-suppression piping and components and differentiate between manufacturer-installed and field-installed piping. Include roughing-in requirements for drain connections. Show cooking equipment plan and elevation to illustrate fire-suppression nozzle locations.

1.4 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D 1.1M, "Structural Welding Code - Steel," for hangers and supports; and AWS D9.1/D9.1M, "Sheet Metal Welding Code," for joint and seam welding.

PART 2 - PRODUCTS

2.1 ELECTRICAL COMPONENTS, DEVICES AND ACCESSORIES

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 HOOD MATERIALS

A. Stainless-Steel Sheet: ASTM A 666, Type 304.

1. Minimum Thickness: 0.037 inch.
2. Finish: Comply with SSINA's "Finishes for Stainless Steel" for recommendations for applying and designating finishes.

a. Finish shall be free from tool and die marks and stretch lines and shall have uniform, directionally textured, polished finish indicated, free of cross scratches. Grain shall run with long dimension of each piece.

3. Concealed Stainless-Steel Surfaces: ASTM A 480/A 480M, No. 2B finish (bright, cold-rolled, unpolished finish).
4. Exposed Surfaces: ASTM A 480/A 480M, No. 4 finish (directional satin).
5. When polishing is completed, passivate and rinse surfaces. Remove embedded foreign matter and leave surfaces chemically clean.

B. Carbon-Steel Sheets: ASTM A 1008/A 1008M, cold-rolled sheets; commercial quality; with oiled, exposed matte finish.

C. Zinc-Coated Steel Shapes: ASTM A 36/A 36M, zinc coated according to ASTM A 123/A 123M requirements.

D. Sealant: ASTM C 920; Type S, Grade NS, Class 25, Use NT. Elastomeric sealant shall be NSF certified for commercial-kitchen hood application. Sealants, when cured and washed, shall comply with requirements in 21 CFR 177.2600, for use in areas that come in contact with food.

1. Color: As selected by Architect from manufacturer's full range.
2. Backer Rod: Closed-cell polyethylene, in diameter larger than joint width.

E. Sound Dampening: NSF-certified, non-absorbent, hard-drying, sound-deadening compound for permanent adhesion to metal in minimum 1/8-inch thickness that does not chip, flake, or blister.

F. Gaskets: NSF certified for end-use application indicated; of resilient rubber, neoprene, or PVC that is nontoxic, stable, odorless, nonabsorbent, and unaffected by exposure to foods and cleaning compounds, and that passes testing according to UL 710.

2.3 GENERAL HOOD FABRICATION REQUIREMENTS

A. Welding: Use welding rod of same composition as metal being welded. Use methods that minimize distortion and develop strength and corrosion resistance of base metal. Make ductile welds free of mechanical imperfections such as gas holes, pits, or cracks.

1. Welded Butt Joints: Full-penetration welds for full-joint length. Make joints flat, continuous, and homogenous with sheet metal without relying on straps under seams, filling in with solder, or spot welding.
2. Grind exposed welded joints flush with adjoining material and polish to match adjoining surfaces.
3. Where fasteners are welded to underside of equipment, finish reverse side of weld smooth and flush.
4. Coat concealed stainless-steel welded joints with metallic-based paint to prevent corrosion.

B. For metal butt joints, comply with SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines."

C. Where stainless steel is joined to a dissimilar metal, use stainless-steel welding material or fastening devices.

D. Edges: Finish free of burrs, fins, and irregular projections.

E. In food zones, as defined in NSF, fabricate surfaces free from exposed fasteners.

F. Cap exposed fastener threads, including those inside cabinets, with stainless-steel lock washers and stainless-steel cap (acorn) nuts.

G. Fabricate pipe slots on equipment with turned-up edges sized to accommodate service and utility lines and mechanical connections.

H. Fabricate enclosures, including panels, housings, and skirts, to conceal service lines, operating components, and mechanical and electrical devices including those inside cabinets unless otherwise indicated.

I. Fabricate seismic restraints according to SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines," Appendix A, "Seismic Restraint Details."

J. Fabricate equipment edges and backsplashes according to SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines."

K. Fabricate enclosure panels to ceiling and wall as follows:

1. Fabricate panels on all exposed side(s) with same material as hood, and extend from ceiling to top of hood canopy and from canopy to wall.

2. Wall Offset Spacer: Minimum of 3 inches.
3. Wall Shelves and Overshelves: Fabricate according to SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines," with minimum 0.0625-inch-thick, stainless-steel shelf tops.

2.4 TYPE I EXHAUST HOOD FABRICATION

A. Available Manufacturers: Subject to compliance with requirements manufacturers offering products that may be incorporated into the Work included, but are not limited to the following.
1. Duo-Aire Systems
2. Greenheck Systems
3. Accurex

B. Furnish and install a complete commercial ventilation package including hood, exhaust fan, supply fan, fire suppression system, exhaust duct and integral control package.

C. Weld all joints exposed to grease with continuous welds, and make filters/baffles or grease extractors and makeup air diffusers easily accessible for cleaning.

1. Fabricate hoods according to NSF 2, "Food Equipment."
2. Hoods shall be listed and labeled, according to UL 710, by a testing agency acceptable to
3. Include access panels as required for access to fire dampers and fusible links.
4. Duct Collars: Minimum 0.0598-inch-thick steel at least 4 inches long, continuously welded to top of hood and at corners. Fabricate a collar with a 1-inch-wide duct flange.
5. Makeup Air Fire Dampers: Labeled, according to UL 555, by a testing agency acceptable to authorities having jurisdiction.

a. Fire Rating: 1-1/2 hours.
b. Frame: SMACNA [Type A] [Type B], with blades in airstream; fabricated with roll-formed, [galvanized] [stainless] steel; with mitered and interlocking corners.
c. Blades: Roll-formed, interlocking or folded, minimum 0.034-inch-thick, galvanized-steel sheet.
d. Horizontal Dampers: Include a blade lock and stainless-steel closure spring.
e. Fusible Link: Replaceable, [165 deg F] [212 deg F] rated.

D. Hood Configuration: Exhaust and makeup air.

1. Makeup air shall be introduced through laminar-flow-type, perforated metal panels on front of hood canopy.

E. Hood Style: Wall mounted.

F. Filters/Baffles: Removable, stainless steel. Fabricate stainless steel for filter frame and removable collection cup and pitched trough. Exposed surfaces shall be pitched to drain to collection cup. Filters/baffles shall be tested according to UL 1046, "Safety for Grease Filters for Exhaust Ducts," by an NRTL acceptable to authorities having jurisdiction.

G. Lighting Fixtures: Surface-mounted fluorescent fixtures and lamps with lenses sealed vapor tight. Wiring shall be in conduit on hood exterior. Number and location of fixtures shall provide a minimum of 70 fc at 30 inches above finished floor.

1. Light switches shall be mounted on front of hood canopy
2. Lighting Fixtures: Fluorescent] complying with UL 1598.

H. Comply with hood control requirements in Section 230923 "Direct Digital Control (DDC) System for HVAC" and Section 230993.11 "Sequence of Operations for HVAC DDC."

I. Kitchen Hood Controls: Hood mounting control cabinet, factory wired to control groups of adjacent hoods, and fabricated of stainless steel.

J. Smoker Hood Controls: Remote mounted control cabinet.

1. Exhaust Fan: On-off switches shall start and stop the exhaust fan. Interlock exhaust fan with makeup air supply fan to operate simultaneously. Interlock exhaust fan with fire-suppression system to operate fan(s) during fire-suppression-agent release and to remain in operation until manually stopped. Include red pilot light to indicate fan operation. Motor starters shall comply with Section 262913 "Enclosed Controllers."
2. Exhaust Fan Interlock: Factory wire the exhaust fan starters in a multiple control cabinet for adjacent hoods to operate together.

2.5 WET-CHEMICAL FIRE-SUPPRESSION SYSTEM

A. Available Manufacturers: Subject to compliance with requirement, manufacturers offering products that may be incorporated into the Work included, but are not limited to the following:

1. Ansul Incorporated: a Tyco International Ltd. Company
2. Badger Fire Protection.
3. Kidde Fire Systems.
4. Pyro Chem.

B. Description: Engineered distribution piping designed for automatic detection and release or manual release of fire-suppression agent by hood operator. Fire-suppression system shall be listed and labeled for complying with NFPA 17A, "Wet Chemical Extinguishing Systems," by a qualified testing agency acceptable to authorities having jurisdiction.

1. Steel Pipe, NPS 2 and Smaller: ASTM A 53/A 53M, Type S, Grade A, Schedule 40, plain ends.
2. Malleable-Iron Threaded Fittings: ASME B16.3, Classes 150 and 300.
3. Piping, fusible links and release mechanism, tank containing the suppression agent, and controls shall be factory installed. Controls shall be in stainless-steel control cabinet mounted on hood. Furnish manual pull station for wall mounting. Exposed piping shall be covered with chrome-plated aluminum tubing. Exposed fittings shall be chrome plated.
4. Liquid Extinguishing Agent: Noncorrosive, low-pH liquid.
5. Furnish electric-operated gas shutoff valve with clearly marked open and closed indicator for field installation.
6. Fire-suppression system controls shall be integrated with controls for fans, lights, and fuel supply and located in a single cabinet for each group of hoods immediately adjacent.
7. Wiring shall have color-coded, numbered terminal blocks and grounding bar. Spare terminals for fire alarm, optional wiring to start fan with fire alarm, red pilot light to indicate fan operation, and control switches shall all be factory wired in control cabinet

with relays or starters. Include spare terminals for fire alarm, and wiring to start fan with fire alarm.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for piping systems to verify actual locations of piping connections before equipment installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Coordinate equipment layout and installation with adjacent Work, including lighting fixtures, HVAC equipment, plumbing, and fire-suppression system components.

B. Complete field assembly of hoods where required.

1. Make closed butt and contact joints that do not require filler.
2. Grind field welds on stainless-steel equipment smooth, and polish to match adjacent finish. Comply with welding requirements in "General Hood Fabrication Requirements" Article.

C. Install hoods and associated services with clearances and access for maintaining, cleaning, and servicing hoods, filters/baffles, grease extractor, and fire-suppression systems according to manufacturer's written instructions and requirements of authorities having jurisdiction.

D. Make cutouts in hoods where required to run service lines and to make final connections, and seal openings according to UL 1978.

E. Securely anchor and attach items and accessories to walls, floors, or bases with stainless-steel fasteners unless otherwise indicated.

F. Install hoods to operate free from vibration.

G. Install trim strips and similar items requiring fasteners in a bed of sealant. Fasten with stainless-steel fasteners at 48 inches o.c. maximum.

H. Install sealant in joints between equipment and abutting surfaces with continuous joint backing unless otherwise indicated. Provide airtight, watertight, vermin-proof, sanitary joints.

I. Install lamps, with maximum recommended wattage, in equipment with integral lighting.

J. Set initial temperatures, and calibrate sensors.

K. Set field-adjustable switches.

3.3 CONNECTIONS

A. Where installing piping adjacent to hoods, allow space for service and maintenance.

B. Connect ducts according to requirements in Section 233300 "Air Duct Accessories." Install flexible connectors on makeup air supply duct. Weld exhaust-duct connections with continuous liquid tight joint.

C. Install fire-suppression piping for remote-mounted suppression systems according to NFPA 17A, "Wet Chemical Extinguishing Systems."

3.4 FIELD QUALITY CONTROL

A. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections. Report results in writing.

B. Tests and inspections with the assistance of a factory-authorized service representative:

1. Engage a factory-authorized service representative to inspect components, assemblies and equipment installations, including connections and assist in testing.
2. Test each equipment item for proper operation. Repair or replace equipment that is defective, including units that operate below required capacity or that operate with excessive noise or vibration.
3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
4. Perform hood performance tests required by authorities having jurisdiction.
5. Perform fire-suppression system performance tests required by authorities having jurisdiction.

C. Prepare test and inspection reports.

3.5 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain commercial-kitchen hoods.

END OF SECTION 23 38 13

SECTION 23 38 15 - COMMERCIAL-TYPE II KITCHEN HOODS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes Type II commercial kitchen hoods.

1.3 DEFINITIONS

A. Listed Hood: A hood, factory fabricated and tested for compliance with UL 710 by a testing agency acceptable to authorities having jurisdiction.

B. Standard Hood: A hood, usually field fabricated that complies with design, construction, and performance criteria of applicable national and local codes.

C. Type II Hood: A hood designed for heat and steam removal and for other non-grease applications.

1.4 ACTION SUBMITTALS

A. Product Data: For the following:

1. Standard hoods.

2. Lighting fixtures.

1.5 COORDINATION

A. Coordinate equipment layout and installation with adjacent Work, including lighting fixtures, HVAC equipment, plumbing, and fire-suppression system components.

PART 2 - PRODUCTS

2.1 HOOD MATERIALS

A. Stainless-Steel Sheet: ASTM A 666, Type 304.

1. Minimum Thickness: 0.050 inch (18-gage).

2. Finish: Comply with SSINA's "Finishes for Stainless Steel" for recommendations for applying and designating finishes.

a. Finish shall be free from tool and die marks and stretch lines and shall have uniform, directionally textured, polished finish indicated, free of cross scratches. Grain shall run with long dimension of each piece.

3. Concealed Stainless-Steel Surfaces: ASTM A 480/A 480M, No. 2B finish (bright, cold-rolled, unpolished finish).

4. Exposed Surfaces: ASTM A 480/A 480M, No. 3 finish (intermediate polished surface).

5. When polishing is completed, passivate and rinse surfaces. Remove embedded foreign matter and leave surfaces chemically clean.

B. Sealant: ASTM C 920; Type S, Grade NS, Class 25, Use NT. Elastomeric sealant shall be NSF certified for commercial kitchen hood application. Sealants, when cured and washed, shall comply with requirements in 21 CFR, Section 177.2600, for use in areas that come in contact with food.

1. Color: As selected by Architect from manufacturer's full range.

2. Backer Rod: Closed-cell polyethylene, in diameter larger than joint width.

C. Gaskets: NSF certified for end-use application indicated; of resilient rubber, neoprene, or PVC that is nontoxic, stable, odorless, nonabsorbent, and unaffected by exposure to foods and cleaning compounds, and that passes testing according to UL 710.

2.2 GENERAL HOOD FABRICATION REQUIREMENTS

A. Welding: Use welding rod of same composition as metal being welded. Use methods that minimize distortion and develop strength and corrosion resistance of base metal. Make ductile welds free of mechanical imperfections such as gas holes, pits, or cracks.

1. Welded Butt Joints: Full-penetration welds for full-joint length. Make joints flat, continuous, and homogenous with sheet metal without relying on straps under seams, filling in with solder, or spot welding.

2. Grind exposed welded joints flush with adjoining material and polish to match adjoining surfaces.

3. Where fasteners are welded to underside of equipment, finish reverse side of weld smooth and flush.

4. Coat concealed stainless-steel welded joints with metallic-based paint to prevent corrosion.

5. After zinc-coated steel is welded, clean welds and abraded areas and apply SSPC-Paint 20, high-zinc-dust-content, galvanizing repair paint to comply with ASTM A 780/A 780M.

B. For metal butt joints, comply with SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines."

C. Where stainless steel is joined to a dissimilar metal, use stainless-steel welding material or fastening devices.

D. Form metal with break bends that are not flaky, scaly, or cracked in appearance; where breaks mar uniform surface appearance of material, remove marks by grinding, polishing, and finishing.

E. Sheared Metal Edges: Finish free of burrs, fins, and irregular projections.

F. In food zones, as defined in NSF, fabricate surfaces free from exposed fasteners.

G. Cap exposed fastener threads, including those inside cabinets, with stainless-steel lock washers and stainless-steel cap (acorn) nuts.

H. Fabricate pipe slots on equipment with turned-up edges sized to accommodate service and utility lines and mechanical connections.

I. Fabricate enclosures, including panels, housings, and skirts, to conceal service lines, operating components, and mechanical and electrical devices including those inside cabinets, unless otherwise indicated.

J. Fabricate equipment edges and backsplashes according to SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines."

K. Fabricate enclosure panels to ceiling and wall as follows:

1. Fabricate panels on all exposed side(s) with same material as hood, and extend from ceiling to top of hood canopy and from canopy to wall.

2. Wall Offset Spacer: Minimum of 3 inches.

3. Wall Shelves and Overshelves: Fabricate according to SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines," with minimum 0.0625-inch- thick, stainless-steel shelf tops.

2.3 TYPE II EXHAUST HOOD FABRICATION

A. Manufacturer, Basis of design is as follows:

1. DUO-AIRE Model DPO, single shell cap style hood which rests directly above the oven.

2. GREENHECK

B. Fabricate hoods according to NSF 2, "Food Equipment."

C. Fabricate hoods to comply with SMACNA's "HVAC Duct Construction Standards: Metal and Flexible."

D. Hood Configuration: Exhaust only.

E. Hood Type: Heat and vapor removal.

F. Hood Style: Wall-mounted canopy.

G. Condensate Hood Baffles: Removable, stainless-steel baffles to drain into a hood drain trough, and stainless-steel drain piping.

H. Lighting Fixtures: Surface-mounted, incandescent fixtures and lamps with lenses sealed vaportight. Wiring shall be installed in stainless-steel conduit on hood exterior. Number and location of fixtures shall provide a minimum of 70 fc at 30 inches above finished floor.

1. Light switches shall be mounted on front panel of hood canopy.

2. Lighting Fixtures: Incandescent complying with UL 1598.

I. Capacities and Characteristics:

1. Nominal Hood Length: 56 inches.

2. Nominal Hood Width: 39.5 inches.

3. Canopy Height: 18 inches.

4. Exhaust Airflow: 650 - 860 cfm. (Adjust CFM of fan per hood manufacturer's recommendations).

5. Exhaust-Air Pressure Loss: 0.75 inches wg.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance.

B. Examine roughing-in for piping systems to verify actual locations of piping connections before equipment installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Complete field assembly of hoods where required.

1. Make closed butt and contact joints that do not require filler.

2. Grind field welds on stainless-steel equipment smooth, and polish to match adjacent finish. Comply with welding requirements in Part 2 "General Hood Fabrication Requirements" Article.

B. Install hoods and associated services with clearances and access for maintaining, cleaning, and servicing hoods, filters/baffles, grease extractor, and fire-suppression systems according to manufacturer's written instructions and requirements of authorities having jurisdiction.

C. Securely anchor and attach items and accessories to walls, floors, or bases with stainless-steel fasteners, unless otherwise indicated.

D. Install hoods to operate free from vibration.

E. Install trim strips and similar items requiring fasteners in a bed of sealant. Fasten with stainless-steel fasteners at 48 inches o.c. maximum.

F. Install sealant in joints between equipment and abutting surfaces with continuous joint backing, unless otherwise indicated. Provide airtight, watertight, vermin-proof, sanitary joints.

G. Install lamps, with maximum recommended wattage, in equipment with integral lighting.

H. Set initial temperatures, and calibrate sensors.

I. Set field-adjustable switches.

3.3 CONNECTIONS

A. Connect ducts according to requirements in Section 233300 "Air Duct Accessories."

3.4 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections and prepare test reports.

B. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections. Report results in writing.

C. Perform tests and inspections.

1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.

D. Tests and Inspections:

1. Test each equipment item for proper operation. Repair or replace equipment that is defective, including units that operate below required capacity or that operate with excessive noise or vibration.

2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

3. Test water, drain, gas, and liquid-carrying components for leaks. Repair or replace leaking components.

4. Perform hood performance tests required by authorities having jurisdiction.

5. Perform fire-suppression system performance tests required by authorities having jurisdiction.

E. Prepare test and inspection reports.

3.5 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain commercial kitchen hoods. Refer to Section 017900 "Demonstration and Training."

END OF SECTION 23 38 15

SECTION 23 70 30 – AIR PURIFICATION SYSTEM

PART 1 – GENERAL

1.01 DESCRIPTION OF WORK

A. This section describes the design, performance and installation of an air purification system intended for use as part of another manufacturer's air handling unit or mounted on the duct as shown on the plans, details and equipment schedules.

1.02 REFERENCED CODES & STANDARDS

A. The following codes and standards are referenced throughout. The edition to be used is that currently enforced by the authority having jurisdiction (AHJ) or in absence of such direction that referenced by the current enforceable IBC code or as indicated by the contract documents, except where specifically referenced by this section of the specifications.

1. ASHRAE Standards 62 & 52
2. National Electric Code NFPA 70
3. UL 867 including ozone chamber test

1.03 RELATED WORK

A. Testing, Adjusting and Balancing
B. Facility Access and Protection
C. Ductwork
D. Filters
E. Electrical Wiring
F. Control Wiring

1.04 QUALITY ASSURANCE

A. The Air Purification System shall be a product of an established manufacturer in the USA and shall be manufactured and assembled in the USA.

B. A qualified representative from the manufacturer shall be available to inspect the installation of the air purification system to ensure installation in accordance with manufacturer's recommendation.

C. Technologies that do not address gas disassociation such as UV lights, powered particulate filters and/or polarized media filters shall not be considered. Uni-polar ion generators shall not be acceptable. "Plasma" particulate filters shall not be acceptable.

D. Projects designed using ASHRAE Standard 62.1 IAQ Procedure shall require the manufacturer to provide Indoor Air Quality calculations using the formulas within ASHRAE Standard 62.1-2007 to validate acceptable indoor air quality at the quantity of outside air scheduled. The manufacturer shall provide independent test data on a previous installation in a similar application that proves compliance to ASHRAE 62.1 and the accuracy of the calculations.

E. The Air Purification Technology shall have been tested by UL or Intertek/ETL to prove conformance to UL 867-2007 including the ozone chamber testing and peak ozone test for electronic devices. All manufacturers shall submit their independent UL 867 test data with ozone results to the engineer during the submittal process. All manufacturers shall submit a copy with their quotation. Contractors shall not accept any proposal without the proper ozone testing documentation.

F. The maximum allowable ozone concentration per the UL 867-2007 chamber test shall be 0.001 PPM. The maximum peak ozone concentration per the UL 867-2007 peak test as measured 2 inches away from the electronic air cleaner's output shall be no more than 0.0012 PPM. Manufacturers with ozone output exceeding these ozone values shall not be acceptable.

1.05 SUBMITTALS

A. Submit manufacturer's technical product data for ion generators including:

1. Schedule of plasma generators indicating model number and quantity of each type required for each unit/application.
2. Submittal sheet for each type of plasma generator and accessories furnished; indicating construction, dimensions, electrical data, and mounting details.
3. Indoor Air Quality calculations using the formulas within ASHRAE Standard 62.1-2007 to validate acceptable indoor air quality at the quantity of outside air scheduled (when projects are designed with reduced outside air).
4. Product drawings detailing all physical, electrical and control requirements.
5. Copy of UL 867 independent ozone test.

B. Operating & Maintenance Data: Submit O&M data and recommended spare parts list.

1.06 PRODUCT DELIVERY, STORAGE AND HANDLING

A. Delivery of products shall be in factory fabricated shipping cartons. Identify on outside of carton the type of product contained within. Avoid crushing or bending.

B. Store in original cartons and protect from weather and construction work traffic.

C. Store indoors and in accordance with the manufacturers' recommendation for storage.

1.07 WARRANTY

A. Equipment shall be warranted by the manufacturer against defects in material and workmanship for a period of twelve months after shipment or eighteen months from owner acceptance, whichever occurs first. Labor to replace equipment under warranty shall be provided by the owner or installing contractor.

PART 2 – PRODUCTS

2.01 GENERAL

A. The air purification system(s) shall be of the size, type, arrangement and capacity indicated and required by the unit furnished and shall be manufactured by Plasma Air International (www.plasma-air.com). Equal by GPS Air (www.gpsair.com) shall also be acceptable.

B. All other suppliers of comparable products requesting prior approval shall:

1. Submit a request for prior approval at least 15 days prior to bid date. Request received after that time will not be considered.
2. In addition, as part of the prior approval request, Bipolar Ionization manufacturers must submit their IAQ calculations that prove conformance to ASHRAE Standard 62.1-2007 with the reduction of outside air to the scheduled values. A letter on the manufacturer's letterhead requesting prior approval must accompany the request for prior approval stating their calculations are ASHRAE compliant. A third party validation study performed on a previous installation of the same application shall also be included.
3. Submit independent test data from ETL or UL on the ozone chamber test.
4. Submit pathogen testing per section 2.2.
5. Submit at least two other end user references in the same application with contact phone number, email, equipment used and application for the equipment at that facility. Manufacturers not having the above references in similar applications using the same equipment models as proposed on the current project shall not be acceptable.

2.02 BI-POLAR IONIZATION DESIGN & PERFORMANCE CRITERIA

A. Each piece of air handling equipment, so designated on the plans, details, equipment schedules and/or specifications shall contain a plasma ion generator with bipolar ionization output as described here within.

B. The Bi-polar Ionization system shall be capable of:

1. Effectively killing microorganisms downstream of the bipolar ionization equipment (mold, bacteria, virus, etc.).
2. Controlling gas phase contaminants generated from human occupants, building structure, furnishings and outside air contaminants.
3. Reducing space static charges.
4. Reducing space particle counts.
5. When mounted to the air entering side of a cooling coil, keep the cooling coil free from pathogen and mold growth.
6. All manufacturers shall provide documentation by an independent NELEC accredited laboratory that proves the product has minimum kill rates for the following pathogens given the allotted time and in a space condition:
    1. MRSA: 99.5% in 60 minutes or less
    2. E. Coli: 89.0% in 60 minutes or less
    3. H1N1: 86.6% in 60 minutes or less
    4. Aspergillus: 74.8% in 60 minutes or less

Manufacturers not providing the equivalent space kill rates shall not be acceptable.

All manufactures requesting prior approval shall provide to the engineer independent test data from a NELEC accredited independent lab confirming kill rates and time meeting the minimum requirements stated in section 2.2 B, points 6a, 6b and 6c.

C. The bipolar ionization system shall operate in such a manner that equal amounts of positive and negative ions are produced. Single pole ion devices shall not be acceptable.

1. Airflow rates may vary through the full operating range of a VAV system. The quantity of air exchange shall not be increased due to requirements of the air purification system.
2. Velocity Profile: The air purification device shall not have a maximum velocity profile.

D. Humidity: Plasma Generators shall not require preheat protection when the relative humidity of the entering air exceeds 85%. Relative humidity from 0 - 100%, condensing, shall not cause damage, deterioration or dangerous conditions to the air purification system.

E. Ionization Equipment Requirements:

1. Electrode Specifications (Bi-polar Ionization):

   a. Each plasma generator with bipolar ionization output shall include the required number of electrodes and power generators sized to the air handling equipment capacity.
   b. Electrodes shall be energized when the main unit disconnect is turned on and the fan is operating.
   c. Ionization output from each electrode shall be a minimum of 5 million ions/cc when tested at 2” from the ion generator.
   d. Manufacturer shall demonstrate that no voltage potential exists due to exposed electrical components in the duct system or plenum. Exposed needles protruding into the air steam will not be accepted.

2. Air Handler mounted units

   a. Ion generators for air handling unit coils shall be Plasma Air's BAR product furnished in a linear or bar mounted configuration so as to minimize the space required for installation. Ionization "BAR" shall be no more than 3" deep in the direction of airflow.
   b. The mechanical contractor shall mount the plasma ionization bar and wire it to the remote mount power supply panel using only low voltage wiring. Low voltage wiring shall be defined as 12V. The use of high voltage cabling (600V or higher) shall not be acceptable due to safety concerns.
   c. The remote mount power supply panel shall be capable of directly accepting voltage of 12V DC or 24V AC. The panel shall have an on/off switch, ionizer indicator LED, and a set of dry contacts which will indicate ionizer functionality. Dry contacts that indicate power available only shall not be acceptable.
   d. For systems without dry contacts, provide a duct mounted ion sensor powered from 12V DC or 24V AC. Ion sensor to be user adjustable from 500 to 20,000 ions per cm3.

3. Certifications

a. Bipolar ionization units shall be tested and listed by either UL or ETL according to UL Standard 867 – Electrostatic Air Cleaners.
b. The operation of the electrodes or bipolar ionization units shall conform to UL 867 with respect to ozone generation.

F. Electrical Requirements:

1. Ion generators shall contain a built-in power supply and operate on 24V AC and shall connect to the fan and common terminals of the fan coil unit or air handling unit served. Ion generators requiring a loose 24V, 120V or 230V transformer or power supply shall not be accepted.
2. Wiring, conduit and junction boxes shall be furnished and installed by the electrical contractor within housing plenums and shall be UL and NEC NFPA 70 approved.

G. Control Requirements:

1. All plasma ion generators shall include internal short circuit protection, overload protection, and automatic fault reset. Manual fuse replacement shall not be accepted.
2. All plasma ion generators shall include an external BMS interface to indicate ion generator status and alarm.

PART 3 – EXECUTION

3.01 GENERAL

A. The Contractor shall be responsible for maintaining all air systems until the owner accepts the building (Owner Acceptance).

3.02 ASSEMBLY & INSTALLATION: PLASMA GENERATOR WITH BI-POLAR IONIZATION

A. All equipment shall be assembled and installed with a high level of workmanship to the satisfaction of the owner, architect and engineer.

B. Any material damaged by handling, water or moisture shall be replaced by the mechanical contractor at no cost to the owner.

C. All equipment shall be protected from damage on a daily basis throughout construction.

3.03 COMMISSIONING & TRAINING

A. A manufacturer's authorized representative shall provide start-up supervision and training of owner's personnel in the proper operation and maintenance of all equipment.

B. Provide to the owner a portable hand held ion counter with a calibrated range of 0 to 20,000 ions/cm3 and an accuracy of +/- 25% within the specified range. Ion counter shall have automatic zeroing capability on 10 minute intervals.

END OF SECTION 23 70 30

SECTION 23 74 13 – PACKAGED ROOFTOP AC UNITS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes packaged, outdoor, central-station air-handling units (rooftop units) with the following components and accessories:
   1. Direct-expansion cooling.
   2. Modulating Natural Gas Heating section.
   3. Outdoor air intake damper section.
   4. Integral, space temperature controls.
   5. Roof curbs.

1.3 DEFINITIONS

A. ECM: Electrically commutated motor.

B. RTU: Rooftop unit. As used in this Section, this abbreviation means packaged, outdoor, central-station air-handling units. This abbreviation is used regardless of whether the unit is mounted on the roof or on a concrete base on ground.

C. Supply-Air Fan: The fan providing supply air to conditioned space. "Supply air" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.

D. Supply-Air Refrigerant Coil: Refrigerant coil in the supply-air stream to absorb heat (provide cooling) during cooling operations and to reject heat (provide heating) during heating operations. "Supply air" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.

1.4 ACTION SUBMITTALS

A. Product Data: Include manufacturer's technical data for each RTU, including rated capacities, dimensions, required clearances, characteristics, furnished specialties, and accessories.

B. Delegated-Design Submittal: For RTU supports indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
   1. Detail mounting, securing, and flashing of roof curb to roof structure. Indicate coordinating requirements with roof membrane system.

2. Wind-Restraint Details: Detail fabrication and attachment of wind and seismic restraints and snubbers. Show anchorage details and indicate quantity, diameter, and depth of penetration of anchors.

1.5 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Plans and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
1. Structural members to which RTUs will be attached.
2. Roof openings
3. Roof curbs and flashing.

B. Field quality-control test reports.

C. Warranty: Special warranty specified in this Section.

1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For RTUs to include in emergency, operation, and maintenance manuals.

1.7 QUALITY ASSURANCE

A. ARI Compliance:
1. Comply with ARI 203/110 and ARI 303/110 for testing and rating energy efficiencies for RTUs.
2. Comply with ARI 270 for testing and rating sound performance for RTUs.

B. ASHRAE Compliance:
1. Comply with ASHRAE 15 for refrigeration system safety.
2. Comply with ASHRAE 33 for methods of testing cooling and heating coils.
3. Comply with applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Startup."

C. ASHRAE/IESNA 90.1 Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."

D. NFPA Compliance: Comply with NFPA 90A and NFPA 90B.

E. UL Compliance: Comply with UL 1995.

F. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

1.8 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to replace components of RTUs that fail in materials or workmanship within specified warranty period.
   1. Warranty Period for Compressors: Manufacturer's standard, but not less than five years from date of Substantial Completion.
   2. Warranty Period for Gas Furnace Heat Exchangers: Manufacturer's standard, but not less than 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers shall be one of the following:
   1. Johnson Controls
   2. Trane.
   3. Carrier.
   4. York.

2.2 CASING

A. General Fabrication Requirements for Casings: Formed and reinforced single-wall insulated panels, fabricated to allow removal for access to internal parts and components, with joints between sections sealed.

B. Exterior Casing Material: Galvanized steel with factory-painted finish, with pitched roof panels and knockouts with grommet seals for electrical and piping connections and lifting lugs.
   1. Exterior Casing Thickness: 0.0626 inch thick.

C. Casing Insulation and Adhesive: Comply with NFPA 90A or NFPA 90B.
   1. Materials: ASTM C 1071, Type I.
   2. Thickness: 1/2 inch.
   3. Liner materials shall have air-stream surface coated with an erosion- and temperature-resistant coating or faced with a plain or coated fibrous mat or fabric.
   4. Liner Adhesive: Comply with ASTM C 916, Type I.

D. Condensate Drain Pans: Formed sections of stainless-steel sheet, a minimum of 2 inches deep, and complying with ASHRAE 62.1.
   1. Double-Wall Construction: Fill space between walls with foam insulation and seal moisture tight.
   2. Drain Connections: Threaded nipple both sides of drain pan.

2.3 FANS

A. Direct-Driven Supply-Air Fans: Double width, forward curved, centrifugal; with permanently lubricated, motor resiliently mounted in the fan inlet. Aluminum or painted-steel wheels, and galvanized- or painted-steel fan scrolls.

B. Condenser-Coil Fan: Propeller, mounted on shaft of permanently lubricated motor.

C. Fan Motor: Comply with requirements in Section 230513 "Common Motor Requirements for HVAC Equipment."

2.4 COILS

A. Supply-Air Refrigerant Coil:
1. Aluminum-plate fin and seamless internally grooved copper tube in steel casing with equalizing-type vertical distributor.
2. Condensate Drain Pan: Stainless steel formed with pitch and drain connections complying with ASHRAE 62.1.

2.5 REFRIGERANT CIRCUIT COMPONENTS

A. Number of Refrigerant Circuits: Two.

B. Compressor: Hermetic, scroll, mounted on vibration isolators; with internal overcurrent and high-temperature protection, internal pressure relief, and crankcase heater.

C. Refrigeration Specialties:
1. Refrigerant: R-454b or R-30.
2. Expansion valve with replaceable thermostatic element.
3. Refrigerant filter/dryer.
4. Manual-reset high-pressure safety switch.
5. Automatic-reset low-pressure safety switch.
6. Minimum off-time relay.
7. Automatic-reset compressor motor thermal overload.
8. Brass service valves installed in compressor suction and liquid lines.
9. Low-ambient kit high-pressure sensor.

2.6 AIR FILTRATION

A. Minimum arrestance according to ASHRAE 52.1, and a minimum efficiency reporting value (MERV) according to ASHRAE 52.2.
1. Pleated: Minimum 90 percent arrestance, and MERV 7.

2.7 SCR ELECTRIC HEATING COILS

A. Testing Agency Listing and Labeling: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Coil Assembly: Comply with UL 1995.

C. Heating Elements: Coiled resistance wire of 80 percent nickel and 20 percent chromium; surrounded by compacted magnesium-oxide powder in tubular-steel sheath; with spiral-wound, copper-plated, steel fins continuously brazed to sheath.

D. Heating Elements: Open-coil resistance wire of 80 percent nickel and 20 percent chromium, supported and insulated by floating ceramic bushings recessed into casing openings, and fastened to supporting brackets.

E. High-Temperature Coil Protection: Disk-type, automatically reset, thermal-cutout, safety device; serviceable through terminal box without removing heater from duct or casing.

1. Secondary Protection: Load-carrying, manually reset or manually replaceable, thermal cutouts; factory wired in series with each heater stage.

F. Frames: Galvanized-steel channel frame, minimum 0.064 inch (1.6 mm) thick for slip-in mounting.

2.8 INDIRECT NATURAL GAS FIRED HEATER SECTION:

A. Description: Factory assembled, piped, and wired; and complying with ANSI Z21.47, "Gas-Fired Central Furnaces," and with NFPA 54, "National Fuel Gas Code."
1. CSA Approval: Designed and certified by and bearing label of CSA.
2. Burners: Stainless steel.
a. Gas Control Valve: Modulating.
b. Fuel: Natural gas.
c. Minimum Combustion Efficiency: 80 percent.
d. Ignition: Electronically controlled electric spark with flame sensor.

B. Venting: Gravity vented.

C. Heat Exchanger: Stainless steel.

D. Heat-Exchanger Drain Pan: Stainless steel.

E. Safety Controls:
1. Vent Flow Verification: Differential pressure switch to verify open vent.
2. Control Transformer: 24-V ac.
3. High Limit: Thermal switch or fuse to stop burner.
4. Gas Train: Regulated, redundant, 24-V ac gas valve assembly containing pilot solenoid valve, electronic-modulating temperature control valve, pilot filter, pressure regulator, pilot shutoff, and manual shutoff all in one body.
5. Purge-period timer shall automatically delay burner ignition and bypass low-limit control.
6. Gas Manifold: Safety switches and controls complying with ANSI standards.
7. Airflow Proving Switch: Differential pressure switch senses correct airflow before energizing pilot.
8. Automatic-Reset, High-Limit Control Device: Stops burner and closes main gas valve if high-limit temperature is exceeded.
9. Safety Lockout Switch: Locks out ignition sequence if burner fails to light after three tries. Controls are reset manually by turning the unit off and on.

2.9 DAMPERS

A. Outdoor-Air Damper: Linked damper blades, for 0 to 25 percent outdoor air, with motorized damper filter.

2.10 ELECTRICAL POWER CONNECTION

A. Provide for single connection of power to unit with unit-mounted disconnect switch accessible from adjacent to outside unit and control-circuit transformer with built-in overcurrent protection. Do not mount disconnect on outdoor unit.

2.11 CONTROLS

A. Basic Unit Controls:
   1. Control-voltage transformer.
   2. Non programmable - Wall-mounted thermostat or sensor with the following features:
      a. Heat-cool-off switch.
      b. Fan on-auto switch.
      c. Fan-speed switch.
      d. Automatic changeover.
      e. Adjustable deadband.
      f. Concealed set point.
      g. Concealed indication.
      h. Degree F indication.
      i. Unoccupied-period-override push button.

B. Interface Requirements for HVAC Instrumentation and Control System:
   1. Interface relay for scheduled operation.
   2. Interface relay to provide indication of fault at the central workstation and diagnostic code storage.

2.12 ACCESSORIES

A. Low-ambient kit using staged condenser fans for operation down to 35 deg F.

B. Filter differential pressure switch with sensor tubing on either side of filter. Set for final filter pressure loss.

C. Coil guards of painted, galvanized-steel wire.

D. Hail guards of galvanized steel, painted to match casing.

2.13 ROOF CURBS

A. Materials: Galvanized steel with corrosion-protection coating, watertight gaskets, and factory-installed wood nailer; complying with NRCA standards.
   1. Curb Insulation and Adhesive: Comply with NFPA 90A or NFPA 90B.
      a. Materials: ASTM C 1071, Type I or II.

b. Thickness: 2 inches.

2. Application: Factory applied with adhesive and mechanical fasteners to the internal surface of curb.
   a. Liner Adhesive: Comply with ASTM C 916, Type I.
   b. Mechanical Fasteners: Galvanized steel, suitable for adhesive attachment, mechanical attachment, or welding attachment to duct without damaging liner when applied as recommended by manufacturer and without causing leakage in cabinet.
   c. Liner materials applied in this location shall have air-stream surface coated with a temperature-resistant coating or faced with a plain or coated fibrous mat or fabric depending on service air velocity.
   d. Liner Adhesive: Comply with ASTM C 916, Type I.

B. Curb Height: 24 inches.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of RTUs.

B. Examine roughing-in for RTUs to verify actual locations of piping and duct connections before equipment installation.

C. Examine roofs for suitable conditions where RTUs will be installed.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Roof Curb: Install on roof structure or concrete base, level and secure, according to NRCA's "Low-Slope Membrane Roofing Construction Details Manual," Illustration "Raised Curb Detail for Rooftop Air Handling Units and Ducts." ARI Guideline B. Install RTUs on curbs and coordinate roof penetrations and flashing with roof construction specified in Section 077200 "Roof Accessories." Secure RTUs to upper curb rail, and secure curb base to roof framing or concrete base with anchor bolts.

3.3 CONNECTIONS

A. Install condensate drain, minimum connection size, with trap and indirect connection to nearest roof drain or area drain.

B. Install piping adjacent to RTUs to allow service and maintenance.

C. Duct installation requirements are specified in other HVAC Sections. Drawings indicate the general arrangement of ducts. The following are specific connection requirements:
   1. Install ducts to termination at top of roof curb.

2. Remove roof decking only as required for passage of ducts. Do not cut out decking under entire roof curb.

3.4 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain RTUs.

END OF SECTION 23 74 13

SECTION 23 74 20 – PACKAGED 100% OUTSIDE AIR A/C UNITS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes packaged, outdoor, central-station air condition units (pad mount units) with the following components and accessories:
   1. Direct-expansion cooling.
   2. Electric resistance Heating section.
   3. Outdoor air intake damper section.
   4. Integral, space temperature controls.
   5. Staged air volume fan, condenser fan and compressor controls.
   6. Modulating hot gas reheat.

1.3 DEFINITIONS

A. ECM: Electrically commutated motor.

B. RTU: (OAU) Packaged A/C unit. As used in this Section, this abbreviation means packaged, outdoor, dedicated outside air system, central-station air-handling units with electric heat. This abbreviation is used regardless of whether the unit is mounted on the roof or on a concrete base on ground. On this project the unit shall be mounted on a concrete base on ground. Unit shall be provided with duct supply temperature and humidity sensor which shall field installed and wired to unit.

C. Supply-Air Fan: The fan providing supply air to conditioned space. "Supply air" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.

D. Supply-Air Refrigerant Coil: Refrigerant coil in the supply-air stream to absorb heat (provide cooling) during cooling operations and to reject heat (provide heating) during heating operations. "Supply air" is defined as the air entering a space from air-conditioning, heating, or ventilating apparatus.

1.4 ACTION SUBMITTALS

A. Product Data: Include manufacturer's technical data for each RTU, including rated capacities, dimensions, required clearances, characteristics, furnished specialties, and accessories.

B. Delegated-Design Submittal: For RTU supports indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
   1. Detail mounting, securing, and flashing of unit to the concrete slab. Indicate coordinating requirements with roof membrane system.
   2. Wind-Restraint Details: Detail fabrication and attachment of wind and seismic restraints and snubbers. Show anchorage details and indicate quantity, diameter, and depth of penetration of anchors.

1.5 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For RTUs to include in emergency, operation, and maintenance manuals.

1.6 QUALITY ASSURANCE

A. ARI Compliance:
   1. Comply with ARI 203/110 and ARI 303/110 for testing and rating energy efficiencies for RTUs.
   2. Comply with ARI 270 for testing and rating sound performance for RTUs.

B. ASHRAE Compliance:
   1. Comply with ASHRAE 15 for refrigeration system safety.
   2. Comply with ASHRAE 33 for methods of testing cooling and heating coils.
   3. Comply with applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Startup."

C. ASHRAE/IESNA 90.1 Compliance: Applicable requirements in 2007 edition of the ASHRAE/IESNA 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."

D. NFPA Compliance: Comply with NFPA 90A and NFPA 90B.

E. UL Compliance: Comply with UL 1995.

F. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

1.7 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to replace components of RTUs that fail in materials or workmanship within specified warranty period.

B.
   1. Warranty Period for Compressors: Manufacturer's standard, but not less than five years from date of Substantial Completion.
   2. Warranty Period for Gas Furnace Heat Exchangers: Manufacturer's standard, but not less than 10 years from date of Substantial Completion.

3. Warranty Period for Variable Frequency Drives: not less than 24 months from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PACKAGED A/C UNIT

A. Outdoor slab mounted, double wall, electronically controlled heating and cooling unit utilizing hermetic scroll compressors with crankcase heaters for cooling duty, dual refrigerant circuit, staged air volume control, and with electric heat. Units shall have horizontal discharge supply and return air as shown on Drawings.

2.2 MANUFACTURERS

A. Manufacturers shall be one of the following or prior approved equal:
1. Basis of Design:
   a. AAON.
   b. GREENHECK

2.3 RTU CASING

A. General Fabrication Requirements for Casings: Formed and reinforced double-wall insulated panels, fabricated to allow removal for access to internal parts and components, with joints between sections sealed.

B. Exterior Casing Material: Galvanized steel with factory-painted finish, with pitched roof panels and knockouts with grommet seals for electrical and piping connections and lifting lugs.
1. Exterior Casing Thickness: 0.0626 inch thick.
2. Top cover shall be 18 gage sheet metal with 0.75 inch thick, 1.5 lb density, fiberglass insulation.
3. Interior Casing shall be galvanized steel inner panels.

C. Casing Insulation and Adhesive: Comply with NFPA 90A or NFPA 90B.
1. Materials: ASTM C 1071, Type I.
2. Thickness: 1/2 inch, 1.5 lb density.
3. Liner materials shall have air-stream surface coated with an erosion- and temperature-resistant coating or faced with a plain or coated fibrous mat or fabric.
4. Liner Adhesive: Comply with ASTM C 916, Type I.

D. Condensate Drain Pans: Formed sections of stainless-steel sheet, a minimum of 2 inches deep, and complying with ASHRAE 62.1.
1. Double-Wall Construction: Fill space between walls with foam insulation and seal moisture tight.
2. Drain Connections: Threaded nipple both sides of drain pan.

2.4 RTU FANS

A. Direct-Driven Supply-Air Fans: Double width, forward curved, centrifugal; with permanently lubricated, motor resiliently mounted in the fan inlet. Aluminum or painted-steel wheels, and galvanized- or painted-steel fan scrolls.

B. Condenser-Coil Fan: Propeller, mounted on shaft of permanently lubricated motor.

C. Fan Motor: Comply with requirements in Section 230513 "Common Motor Requirements for HVAC Equipment." Fans shall be statically and dynamically balanced.

D. Fan Drive for the staged air volume units shall be equipped with variable frequency drive inverter (VFDs). The VFD shall control motor speed to user configurable speeds. The controls shall allow user configurable speeds for cooling and heating modes. The VFD shall be factory-mounted, wired, and tested.

2.5 RTU COILS

A. Supply-Air Refrigerant Coil:
1. Aluminum fin and seamless internally grooved copper tube in steel casing with equalizing-type vertical distributor.
2. Condensate Drain Pan: Stainless steel formed with pitch and drain connections complying with ASHRAE 62.1.

2.6 RTU CIRCUIT COMPONENTS

A. Number of Refrigerant Circuits: Two.

B. Compressor: Hermetic, scroll, mounted on vibration isolators; with internal overcurrent and high-temperature protection, internal pressure relief, and crankcase heater.

C. Refrigeration Specialties:
1. Refrigerant: R-454b.
2. Expansion valve with replaceable thermostatic element.
3. Refrigerant filter/dryer.
4. Manual-reset high-pressure safety switch.
5. Automatic-reset low-pressure safety switch.
6. Minimum off-time relay.
7. Automatic-reset compressor motor thermal overload.
8. Brass service valves installed in compressor suction and liquid lines.
9. Low-ambient kit high-pressure sensor.

2.7 RTU AIR FILTRATION

A. Minimum arrestance according to ASHRAE 52.1, and a minimum efficiency reporting value (MERV) according to ASHRAE 52.2.
1. Pleated: Minimum 2” thick disposable fiberglass filters with 90 percent arrestance, and MERV 7.

2.8 RTU ELECTRIC HEATER SECTION

A. Provide an electric resistance heater section with capacity as scheduled on Drawings.

2.9 PAC DAMPERS

A. Outdoor-Air Damper: Linked damper blades, for 0 to 25 percent outdoor air, with motorized damper filter. Damper shall open when unit is running and shall close when fan is off.

2.10 PAC ELECTRICAL POWER CONNECTION

A. Provide for single connection of power to unit with unit-mounted disconnect switch accessible from adjacent to outside unit and control-circuit transformer with built-in overcurrent protection. Do not mount disconnect on outdoor unit.

2.11 CONTROLS

A. PAC Basic Unit Controls:
   1. Control-voltage transformer.
   2. Non programmable - Wall-mounted thermostat or sensor with the following features:
      a. Heat-cool-off switch.
      b. Fan on-auto switch.
      c. Fan-speed switch.
      d. Automatic changeover.
      e. Adjustable deadband.
      f. Concealed set point.
      g. Concealed indication.
      h. Degree F indication.
      i. Unoccupied-period-override push button.

B. Supply Air Sensor shall be located in the unit and shall be used for compressor stage control.

C. Variable Capacity Compressor Control:
   1. Variable Compressor control shall be capable of unloading this compressor in an infinite number of steps from 100% of compressor capacity down to 50% of compressor capacity to meet the demand for the staged air volume control.

2.12 PAC ACCESSORIES

A. Low-ambient kit using staged condenser fans for operation down to 35 deg F.

B. Filter differential pressure switch with sensor tubing on either side of filter. Set for final filter pressure loss.

C. Coil guards of painted, galvanized-steel wire.

D. Hail guards of galvanized steel, painted to match casing.

E. Humidity Sensor.

F. Security Grilles.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of RTUs.

B. Examine roughing-in for RTUs to verify actual locations of piping and duct connections before equipment installation.

C. Examine roofs for suitable conditions where RTUs will be installed.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Equipment Curb: Install on concrete base, level and secure. Secure RTUs to upper curb rail, and secure curb base to concrete base with anchor bolts.

3.3 CONNECTIONS

A. Install condensate drain, minimum connection size, with trap and indirect connection to nearest roof drain or area drain.

B. Install piping adjacent to RTUs to allow service and maintenance.

3.4 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain RTUs.

B. Provide factory startup. Submit startup documentation to the Engineer prior to substantial completion and after the TAB work has been completed and the TAB report submitted to the Engineer for review.

C. Provide 8 hours of owner training. Video training session and turn over to owner for their use.

END OF SECTION 23 70 12

SECTION 23 90 20 – TEMPERATURE CONTROLS

PART 1 - GENERAL

1.1 DIRECT-DIGITAL CONTROL (DDC) SYSTEM DESCRIPTION

A. The Controls Contractor shall supply and install components required to extend and modify the existing campus wide Direct Digital Control (DDC) Building Automation System (BAS) as required to accomplish the sequences of control for heating, ventilating, air-conditioning and other building-level equipment and systems as described herein.

B. The temperature control points indicated within this specification for each equipment shall be integrated into existing BAS system shall be visual and have full command functions.

C. Floor plan graphics shall be developed within the BAS system for the new additions, assigned room numbers, unit tag number and all space sensors will be visible on floor plan graphics and system graphic. Dynamic color graphics shall be used to identify actual temperature vs setpoints.
1. Green – Space is at setpoint
2. Orange – Space is 2 degrees (adjustable) above setpoint.
3. Blue – Space is 2 degrees (adjustable) below setpoint.
4. Red – Space is >2 degrees (adjustable) above or below setpoint.

D. Add new equipment to existing system settings graphics page for temperature setpoint at individual campus level. Owner personnel to use this graphics page to change temperature setpoints for all units without having to go to each individual unit.

E. Building maintenance manufacturer shall build graphics for each piece of equipment within this specification that has indicated points. building maintenance manufacturer shall coordinate all integration requirements with the unit's manufacturer's representative.

F. TEMPERATURE SENSORS
1. All temperature sensors to have displays, override buttons, and setpoint adjust. (no override buttons required on VAV boxes).
2. Override times shall be set at a default of 4hrs
   a. Electricians (Div. 26) responsible for all stub-ups
   b. Cooling/Heating ON dead-band: + .5 degrees
   c. Cooling/Heating OFF dead band: +1 degree
   d. Setpoint adjustments of +-3 degrees are to default back to "0" each time the units go into unoccupied mode for all areas except for the Administration and Classrooms

G. HUMIDITY SENSORS
1. Electricians (Div. 26) responsible for all stub-ups
2. Occupied Set-point: 60%: Unoccupied Setpoint: 68%
3. Humidity ON dead-band: + 1%
4. Humidity OFF dead-band: -3%

H. CO2 SENSORS
1. Electricians (Div. 26) responsible for all stub-ups
2. Damper Min Position: 800 PPM
3. Damper Max Position: 1100 PPM

I. DEFAULT SCHEDULES

1. Schedule: Occupied times are 6am – 6 pm
   a. Default Setpoints:
      1) Occupied: 68F Heating, 72 Cooling
      2) Unoccupied 55 heating, 90 Cooling

J. SUPPLY AIR SENSORS
1. All airside equipment shall be designed with Supply Air temperature sensors located at the discharge of the units and each individual DX Coil, and heat strips. This includes all AHU, RTUs, Terminal Units (all types), FCUs, DX Splits, etc.

K. EXHAUST FANS:
1. Provide independent start/stop and status control for all Exhaust fans.

L. STATUS MONITORING
1. Any unit being started and stopped by the controls system shall also monitor the status of the unit using a Current switch, amp reading, or differential pressure switch.

M. GENERAL SPECIFICATION ON BAS CONTROLLERS
1. All output points have independent terminations on the BAS controller. No two points (i.e. OA damper and fan S/S) share the same output.
2. OA dampers to remain closed during unoccupied run times and to have a separate schedule for when they open.

1.2 WARRANTY, MAINTENANCE, NORMAL AND EMERGENCY SERVICE

A. BAS manufacturer shall warranty all DDC controllers and Temperature sensors to be free of defect in material and workmanship under normal operation and expected service as published by the manufacturer in the unit's performance specifications for a period of five (5) years.

B. As a part of this contract, the BAS Contractor shall warranty all other components of the BAS and installation to be free of defects in workmanship and material under normal expected service and use for a period of one (1) year from the date final acceptance of the BAS by the Owner.

C. During the one year (1) installation warranty period the Contractor shall provide all labor and materials required to repair or to replace all items or components that fail due to defects in workmanship or manufacture at no charge or reduction in service to the Owner.

D. Except in the event of property loss or damage, warranty service shall be provided during regular working hours Monday through Friday at no charge unless otherwise explicitly outlined in the Contract Documents.

1.3 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.4 SUMMARY

A. Section Includes:

1. Electric temperature control system by the air conditioning equipment manufacturer, to be installed by the mechanical contractor.
2. Thermostats.
3. Thermostat Covers.
4. Float Switches.
5. Motorized Dampers.
6. Exhaust Fans.
7. Smoke Detectors.
8. Control Wiring.

1.5 ACTION SUBMITTALS

A. Shop Drawings:

1. General Requirements.
2. Operating characteristics, electrical characteristics, and furnished accessories indicating process operating range, accuracy over range, calibration data specific to each unique application, electrical power requirements, and limitations of ambient operating environment, including temperature and humidity.

PART 2 - PRODUCTS

2.1 THERMOSTAT

A. Provide fully automatic programmable (7 day) room type thermostat as indicated on Plans to cycle compressor on cooling cycle, and compressor and/or electric strips in stages on heating cycle as required to maintain space conditions. Unit shall be wired for constant or automatic fan operation and shall be electrically interlocked such that the compressor may not run nor the electric strip heaters be energized unless the evaporator fan is operating. Thermostat shall be complete with fan "Auto-On" switch and system "Auto-Heat-Off-Cool" switch. Thermostats shall be mounted to meet latest A.D.A. requirements.

2.2 THERMOSTAT COVER

A. Provide heavy duty plastic, key-locked thermostat covers on all thermostats. One key shall be capable of opening all covers.

2.3 FLOAT SWITCH

A. Provide float switch to emergency drain pan of each AHU. Switch shall be interlocked with AHU to de-energize the unit when the water level in the pan rises above a set level. Float switch shall meet UL 508 requirements.

2.4 MOTORIZED DAMPERS

A. O.A. motorized dampers shall be interlocked with A/C units in respective mechanical rooms to open when any A/C unit is "on" and closed when all A/C units are "off". Provide all necessary relays, switches, transformers, etc. as required.

B. Motorized dampers shall be furnished and set in place by contractor installing the ductwork.

C. Damper actuators shall be electric actuators specifically selected for damper manufacturer's requirements. Controls contractor shall furnish and install actuators. Coordinate all work with contractor installing dampers.

D. 24V O.A. motorized dampers shall be interlocked with their respective unit to open when the A/C unit’s compressor or heating strip is energized (On), and shall close when the unit’s compressor and heating strip is de-energized (Off). Provide all necessary relays, switches, transformers, etc. as required.

2.5 EXHAUST FAN SEQUENCE OF OPERATION

A. EXHAUST FAN # 1
1. (Restrooms) Provide interlock wiring with lights. Fan shall be on when lights are "on" and off when lights are "off". Solid state speed control switch mounted in fan housing shall be used for balancing air flow.

2.6 SMOKE DETECTOR

A. The Mechanical Contractor shall furnish and install a smoke detector in the supply duct and return duct of all air handlers delivering 2000 C.F.M. or above. Interlock the smoke detector to de-energize fan on actuation of detector.

B. Smoke detectors shall have auxiliary contacts for interlock with the fire alarm system. Coordinate installation and selection of smoke detectors. Entire installation shall meet UL requirements for interlock with building fire alarm and security system.

C. Provide remote audible and visual alarm unit with remote reset (one per AHU with smoke detector) in accordance with latest N.F.P.A. 90A requirements.

D. Dual-chamber, ionization smoke detectors: The combination detector head, and twist-lock base shall be UL listed compatible with a UL listed fire alarm panel.

E. The smoke detector shall have a flashing status indication LED or visual supervision. When the detector is actuated, the flashing LED shall latch on steady and at full brilliance. The detector may be reset by activating the control panel remote reset switch.

F. The sensitivity of the detector shall be monitored without removal of the detector head. Metering set points shall be accessible on the exterior of the detector head. Field adjustment the sensitivity shall be possible when conditions require a change.

G. It shall be possible to perform a functional test of the detector without the need of generating smoke. The test method must simulate effects of products of combustion in the chamber to ensure testing of all detector circuits.

H. Voltage and RF transient suppression techniques shall be employed to minimize false alarm potential. A gated alarm output shall be used for additional detector stability.

I. Auxiliary SPDT relays and/or remote LED alarm indicators shall be installed as required.

J. Duct mounted smoke detectors shall shut down the associated air handling unit fan motor and fire/smoke damper. This contractor shall provide all equipment and labor as required to accomplish same.

K. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.7 CONTROL WIRING

A. All wiring required in the control systems, including electrical connections for the thermostats, firestats, smoke detectors, exhaust fans and all interlocking motor control wiring shall be furnished and installed by Mechanical Contractor.

B. All wiring shall be in conduit and in accordance with the National Electrical Code (N.E.C.).

C. All control wiring located outdoors shall be installed in rigid or intermediate metal conduit.

D. All control wiring located indoors where an accessible ceiling is not available shall be installed in E.M.T. conduit.

E. All control wiring located above accessible ceilings shall be N.E.C. approved cable. All control wiring located above accessible ceilings used as air plenums shall be N.E.C. approved "plenum cable".

F. All conductors shall be copper. Conductors used for power circuits shall be #12 TW minimum. Conductors used for control circuits shall be #18 TW (single strand) minimum. Conductors used for sensor circuits shall be #18 TW (single strand) minimum. Control wiring for DX equipment thermostats shall be 10 conductor cables.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

1. Verify compatibility with and suitability of substrates.

B. Examine roughing-in for products to verify actual locations of connections before installation.

1. Examine roughing-in for instruments installed in piping to verify actual locations of connections before installation.
2. Examine roughing-in for instruments installed in duct systems to verify actual locations of connections before installation.

C. Examine walls, floors, roofs, and ceilings for suitable conditions where product will be installed.

D. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.

END OF SECTION 23 90 20

SECTION 23 00 00 – MECHANICAL GENERAL PROVISIONS

PART 1 - GENERAL

1.1 SUMMARY

A. The General Conditions of the Architectural Specifications, along with the supplementary conditions, special conditions, information to bidders, and any other pertinent information and documents shall apply the same as if repeated herein.

1.2 SCOPE OF WORK

A. Furnish all labor and material necessary to provide and install the complete mechanical portion of this Contract, including HVAC systems as called for herein and on accompanying drawings. Parts of the mechanical division may be bid separately or in combination, at the Contractor's option; however, it shall be the responsibility of the General Contractor to assure himself that all items covered in this Division have been included if he chooses to accept separate bids.

B. This Contractor shall refer to the Architectural and Structural drawings and install equipment, piping, etc. to meet building and space requirements. No equipment shall be bid on or submitted for approval if it will not fit in the space provided.

C. It is the intention of these Specifications that all mechanical systems shall be furnished complete with all necessary valves, controls, insulation, piping, devices, equipment, etc. necessary to provide a satisfactory installation in working order.

D. Contractor shall visit the site and acquaint himself thoroughly with all existing facilities and conditions that would affect his portion of the work. Failure to do so shall not relieve the Contractor from the responsibility of installing his work to meet the conditions.

E. This Contractor shall protect the entire system and all parts thereof from injury throughout the project and up to acceptance of the work. Failure to do so shall be sufficient cause for the Architect to reject any piece of equipment.

1.3 DEMOLITION

A. The contractor shall visit the site prior to bid to determine the extent of work required to complete the project.

B. Contractor shall coordinate demolition with owner. The Owner shall have “First Right of Refusal” regarding salvage of all equipment and materials to be removed. Locate equipment as directed by owner. All equipment and materials not salvaged by the owner shall be removed from the site and discarded at the contractor’s expense.

C. Contractor shall coordinate all work with general contractor and phase work as required by project.

D. All equipment piping, etc. required to be removed to accommodate the modifications shall be removed.

E. Contractor shall maintain services to existing facilities which shall remain during and after construction is complete.

F. Contractor shall coordinate any shutdown of services with the owner. It is intended that the building will remain occupied during construction. Contractor shall schedule shut down of services with the owner in order to prevent disruption of building occupancy.

G. Contractor shall be responsible for draining down of existing systems to complete demolition. All work shall be scheduled with the owner. Contractor shall also be responsible for refilling system and removing all air in order to return the systems to proper operating conditions.

H. All shut down of services shall be done at night or during a time period approved by the owner. The systems shall be required to be back up and running each morning unless otherwise approved by the owner.

1.4 GROUNDS AND CHASES

A. This Contractor shall see that all required chases, grounds, holes and accessories necessary for the installation of his work are properly built in as the work progresses; otherwise, he shall bear the cost of providing them.

1.5 CUTTING AND PATCHING

A. Initial cutting and patching shall be the responsibility of the General Contractor, with the Mechanical Contractor being responsible for laying out and marking any and all holes required for the reception of his work. No structural beams or joists shall be cut or thimbled without first receiving the approval of the Architect. After initial surfacing has been done, any further cutting, patching and painting shall be done at this Contractor's expense.

1.6 FILL AND CHARGES FOR EQUIPMENT

A. Fill and charge with materials or chemicals all those devices or equipment as required to comply with the manufacturer's guarantee or as required for proper operation of the equipment.

1.7 MACHINERY GUARDS

A. This Contractor shall provide v-belt guards for each v-belt drive or other hazardous drive. The guard shall enclose the drive entirely and shall have a hole for taking a tachometer reading.

B. Provide protective guard for belts, pulleys, gears, couplings, projecting set screws, keys and other rotating parts which are located such that a person might come in close proximity.

Construct protective guard around angle iron frame, securely bolted to apparatus; comply with safety requirements. Install guard to completely enclose drives and pulleys and not interfere with lubrication of equipment. Provide 2 inch minimum diameter opening in fan belt guards housing for tachometer.

1.8 REPAIRING ROADWAYS AND WALKS

A. Where this Contractor cuts or breaks roadways or walks, in order to lay piping, he shall repair or replace these sections to meet the Architect's approval.

1.9 EXCAVATION AND BACKFILL

A. Contractor shall perform all excavating necessary to lay the specified services. Perform excavation of every description and of whatever substance encountered to depths indicated or specified. Pile materials suitable for backfilling a sufficient distance from banks of trenches to prevent slides or cave-ins. Comply with OSHA requirements for excavation, trenching and shoring. Waste excavation materials, rubbish, etc. shall be carted away from the premises, as indicated. Remove water from trenches by pumping or other approved method, discharge at a safe distance from the excavation.

B. Provide trenches of necessary width for proper laying of pipe and comply with latest publication of OSHA 2226 Excavating and Trenching Operations. Coordinate trench excavation with pipe installation to avoid open trenches for prolonged periods. Accurately grade bottoms of trenches to provide uniform bearing and support for each section of pipe on undisturbed soil or the required thickness of bedding material at every point along its entire length.

C. Provide minimum 12 inches between outer surfaces and embankment or shoring, which may be used, when excavating for manholes and similar structures. Remove unstable soil that is incapable of supporting the structure in the bottom of the excavation to the depth necessary to obtain design bearing.

D. Material to be excavated is “unclassified”. No adjustment in the contract price will be made on account of the presence or absence of rock, shale, masonry, or other materials.

E. Protect existing utility lines that are indicated or the locations of which are made known prior to excavating and trenching and that are to be retained. Protect utility lines encountered during excavating and trenching operations, from damage during excavating, trenching and backfilling; if damaged, repair lines as directed by utilities, owner and A/E. Issue notices when utility lines that are to be removed are encountered within the area of operations in ample time for the necessary measures to be taken to prevent interruption of the service.

F. Provide trenches for utilities of a depth that will provide the following minimum depths of cover from existing grade or from indicated finished grades, or depths of cover in accordance with the manufacturer’s recommendations, whichever is lower:
   1. 3-Feet Minimum Cover: Chilled Water lines, Heating Hot Water Lines, Condenser Water Lines.

G. Underground piping shall have a 6" bed of sand below the piping and backfilled with sand to 6" above the top of piping. Select fill may be used above the sand layer.

H. Backfill trenches after piping, fittings and joints have been tested and approved. Backfill trenches with sand to provide 6 inches of sand below piping and 12 inches of sand cover above piping.

I. Backfill remainder of trenches with satisfactory material consisting of earth, loam, sandy clay, sand and gravel or soft shale, free from large clods of earth and stones not over 1-1/2 inches in size. Deposit backfill material in 9 inch maximum layers, loose depth as indicated or as specified. Take care not to damage utility lines.

J. Deposit the remainder of backfill materials in the trench in 1 foot maximum layers and compact by mechanical means. Refer to architectural for minimum density for compaction (Minimum 85 percent of maximum soil density as determined by ASTM D 698). Re-open trenches and excavation pits improperly backfilled or where settlement occurs to the depth required to obtain the specified compaction, the refill and compact with the surface restored to the required grade and compaction.

K. Backfill utility line trench with backfill material, in 6 inch layers, where trenches cross streets, driveways, building slabs, or other pavement. Moisten each layer and compact to 95 percent of the maximum soil density as determined by ASTM D 698. Accomplish backfilling in such a manner as to permit the rolling and compaction of the filled trench with the adjoining material to provide the required bearing value so that paving of the area can proceed immediately after backfilling is complete.

1.10 WELDING

A. Weld piping and above grade steel tanks in accordance with qualified procedures using performance qualified welders and welding operators. Qualified procedures and welders in accordance with ASME Section IX. Welding procedures qualified by others and welders and welding operators qualified by another employer may be accepted as permitted by ANSI B31.1. Notify the A/E 24 hours in advance of tests, and perform the tests at the work site if practicable. Furnish A/E with a copy of qualified procedures and a list of names and identification symbols of qualified welders and welding operators. Apply welders or welding operators assigned symbols near each weld they make as permanent record.

1.11 NOISE AND VIBRATION

A. Provide the plumbing system and its associated components, items, piping, and equipment free of objectionable vibration or noise. Statically and dynamically balance rotating equipment and mount or fasten so that no vibration is transmitted to or through the building structure by equipment, piping, ducts or other parts of work, rectify such conditions at no additional compensation.

1.12 PAINTING

A. All painting shall be by the General Contractor's Painting Sub-Contractor. All pipe, pipe covering, equipment, supports, hangers, etc. exposed in the building or equipment room shall be painted. This Contractor shall prepare the surface of the material to receive the first coat of paint.

B. All steel hydronic piping shall have two (2) coats of rust inhibitor primer applied prior to insulating.

C. All subsequent coatings shall be prepared by the Painting Sub-Contractor. Requirements covering paints, workmanship and preparation of surfaces as stated in the Architectural Specifications shall govern. Colors shall be approved by the Architect. All piping shall be color-coded.

D. All piping shall be color coded per the following:
1. Ductwork (Exposed in Building) Black

1.13 CLEANING AND ADJUSTING

A. Upon completion of his work, the Contractor shall clean and adjust all equipment, controls, valves, etc.; clean all piping, ductwork, etc.; and leave the entire installation in good working order.

1.14 OPERATING AND MAINTENANCE INSTRUCTIONS

A. Provide the Owner with three (3) copies of printed instructions indicating various pieces of equipment by name and model number, complete with parts lists, maintenance and repair instructions and test and balance report.

B. COPIES OF SHOP DRAWINGS WILL NOT BE ACCEPTABLE AS OPERATION AND MAINTENANCE INSTRUCTIONS BUT MUST BE INCLUDED IN SUBMITTAL PACKAGE.

C. This information shall be bound in plastic hardbound notebooks with the job name permanently embossed on the cover. Rigid board dividers with labeled tabs shall be provided for different pieces of equipment. Submit manuals to the Architect for approval.

D. In addition to the operation and maintenance brochure, the Contractor shall provide a separate brochure which shall include registered warranty certificates on all equipment, especially any pieces of equipment which carry warranties exceeding one (1) year.

E. The operation and maintenance brochure shall be furnished with a detailed list of all equipment furnished to the project, including the serial number and all pertinent nameplate data such as voltage, amperage draw, recommended fuse size, rpm, etc. The Contractor shall include this data on each piece of equipment furnished under this contract.

1.15 GUARANTEE

A. The Contractor shall guarantee all materials, equipment and workmanship for a period of one (1) year from the date of final acceptance of the project. This guarantee shall include furnishing of all labor and material necessary to make any repairs, adjustments or replacement of any equipment, parts, etc. necessary to restore the project to first class condition. This guarantee shall exclude only the changing or cleaning of filters. Warranties exceeding one (1) year are hereinafter specified with individual pieces of equipment.

1.16 LOCAL CONDITIONS

A. The location and elevation of all utility services is based on available surveys and utility maps and are reasonably accurate; however, these shall serve as a general guide only, and the Contractor shall visit the site and verify the location and elevation of all services to his satisfaction in order to determine the amount of work required for the execution of the Contract.

B. The Contractor shall contact the various utility companies, determine the extent of their requirements and he shall include in his bid all lawful fees and payments required by these companies for complete connection and services to the building, including meters, connection charges, street patching, extensions from meters to main, etc.

C. In case major changes are required, this fact, together with the reasons therefor, shall be submitted to the Architect, in writing, not less than seven (7) days before the date of bidding. Failure to comply with this requirement will make the Contractor liable for any changes, additions and expenses necessary for the successful completion of the project.

1.17 PERMITS, INSPECTIONS AND TESTS

A. All permits, fees, etc. for the installation, inspections, plan review, service connections locations, and/or construction of the work which are required by any authority and/or agencies having jurisdiction, shall be obtained and paid for by the Contractor. This shall be verified during the bidding process.

B. The Contractor shall make all tests required by the Architect, Engineer or other governing authorities at no additional cost to the Owner.

C. The Contractor shall notify the Architect and local governing authorities before any tests are made, and the tests are not to be drawn off a line covered or insulated until examined and approved by the authorities. In event defects are found, these shall be corrected and the work shall be retested.

D. Prior to requesting final inspection by the Architect, the Contractor shall have a complete coordination and adjustment meeting of all of his sub-contractors directly responsible for the operation of any portion of the system. At the time of this meeting, each and every sequence of operation shall be checked to assure proper operation. Notify the Architect in writing ten (10) days prior to this meeting, instructing him of the time, date and whom you are requesting to be present.

E. This project shall not be accepted until the above provisions are met to the satisfaction of the Architect.

1.18 CODES AND STANDARDS

A. The entire mechanical work shall comply with the rules and regulations of the City, Parish, County and State in which this project is being constructed, including the State Fire Marshal and the State Board of Health. All modifications required by these authorities shall be made without additional charge to the Owners. The Mechanical Contractor shall report these changes to the Architect and secure his approval before work is started.

B. In addition to the codes heretofore mentioned, all mechanical work and equipment shall conform to the applicable portions of the following specifications, codes and/or regulations:
   1. American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
   2. National Electrical Code (NEC)
   3. National Fire Protection Association (NFPA)
   4. American Society of Mechanical Engineers (ASME)
   5. American Gas Association (AGA)
   6. International Building Code (IBC)
   7. International Mechanical Code (IMC)
   8. International Plumbing Code (IPC)
   9. International Fuel Gas Code (IFGC)
   10. Underwriters Laboratories (UL)
   11. Life Safety Code (NFPA 101)
   12. State Sanitary Code
   13. Louisiana State Uniform Construction Code Council (LSUCCC)

C. All materials, equipment and accessories installed under this Contract shall conform to all rules, codes, etc. as recommended by National Associations governing the manufacturer, rating and testing of such materials, equipment and accessories. All materials shall be new and of the best quality and first class in every respect. Whenever directed by the Architect, the Contractor shall submit a sample for approval before proceeding.

D. Where laws or local regulations provide that certain accessories such as gauges, thermometers, relief valves and parts be installed on equipment, it shall be understood that such equipment be furnished complete with the necessary accessories, whether or not called for in these Specifications.

E. All unfired pressure vessels shall be built in accordance with the A.S.M.E. Code and so stamped. Furnish shop certificates for each vessel.

1.19 REVIEW OF MATERIALS

A. Whenever manufacturers or trade names are mentioned in these Plans or Specifications, the words "or approved equivalent" shall be assumed to follow whether or not so stated. Manufacturers or trade names are used to establish a standard of quality only, and should not be construed to infer a preference. Equivalent products which meet the Architect's approval will be accepted; however, these products must be submitted to the Architect a minimum of seven (7) days prior to the Bid Date.

B. Submission shall include the manufacturer's name, model number, rating table and construction features.

C. Upon receipt and checking of this submittal, the Architect will issue an addendum listing items which are approved as equivalent to those specified. THE CONTRACTOR SHALL BASE HIS BID SOLELY ON THOSE ITEMS SPECIFIED OR INCLUDED IN THE "PRIOR APPROVAL ADDENDUM", AS NO OTHER ITEM WILL BE ACCEPTABLE.

D. Prior approval of a particular piece of equipment does not mean automatic final acceptance and will not relieve the Contractor of the responsibility of assuring himself that this equipment is in

complete accord with the Plans and Specifications and that it will fit into the space provided. Shop drawings must be submitted on all items of equipment for approval as hereinafter specified.

E. Before proceeding with work and/or within thirty (30) days after the award of the General Contract for this work, the Mechanical Contractor shall furnish to the Architect complete shop and working drawings of such apparatus, equipment, controls, insulation, etc. to be provided in this project. These drawings shall give dimensions, weights, mounting data, performance curves and other pertinent information.

F. The Architect's approval of shop drawings shall not relieve the Contractor from the responsibility of incorrectly figured dimensions or any other errors which may be contained in these drawings. Any omission from the shop drawings or specifications, even though approved by the Architect, shall not relieve the Contractor from furnishing and erecting same.

G. If contractor submits hard copies, Six (6) sets of shop drawings shall be submitted to the Architect for approval. These submittals shall be supplied as part of this Contractor's contract.

H. This information shall be bound in plastic hardbound notebooks with the job name on the cover. Rigid board dividers with labeled tabs shall be provided for different pieces of materials and equipment. Submit shop drawings to the Architect for approval. Faxed copies shall not be acceptable. We prefer electronic submissions sent via E-Mail.

I. Required shop drawing submittals shall include but are not limited to the following:
1. Packaged Air Conditioning Equipment.
2. Grilles, registers, diffusers and louvers.
3. Ductwork and duct sealer.
4. Duct insulation and accessories.
5. Controls/Building Automation System.
6. Exhaust fans.
7. Unit heaters.
8. Double wall spiral pipe and fittings.
9. Relief and intake hoods.
10. Heat and Smoke Vents
11. Fire dampers
12. Smoke dampers.
13. Combination Fire and Smoke Dampers
14. Manual Dampers, Motorized Dampers and Control Dampers.
15. Actuators.
16. Test and Balancing Agency (including forms).

1.20 COORDINATION DRAWINGS

A. Submit three (3) black line prints of all mechanical room layouts showing locations of all equipment, piping, etc. to insure all will fit in space provided. Submit drawings at 1/4" scale. Layouts shall include equipment submitted on project to scale on plans.

B. Submit coordination drawings with the respective equipment shop drawings.

1.21 MINOR DEVIATIONS

A. Plans and detail sketches are submitted to limit, explain and define conditions, specified requirements, pipe sizes and manner of erecting work. Structural or other conditions may require certain modifications from the manner of installation shown, and such deviations are permissible and shall be made as required. However, specified sizes and requirements necessary for satisfactory operation shall remain unchanged. It may be necessary to shift ducts or pipes, or to change the shape of ducts, and these changes shall be made as required. All such changes shall be referred to the Architect and Engineer for approval before proceeding. Extra charges shall not be allowed for these changes. The contractor shall obtain a full set of plans and specifications for the coordination of his work prior to bidding this project. Items which are unclear to the bidding contractor shall be brought to the Architect and Engineers attention prior to bidding the project. An interpretation shall be clarified by the Architect and/or the Engineer prior to bidding.

B. The Contractor shall realize that the drawings could delve into every step, sequence or operation necessary for the completion of the project, without drawing on the Contractor's experience or ingenuity. However, only typical details are shown on the Plans. In cases where the Contractor is not certain about the method of installation of his work, he shall ask for details. Lack of details will not be an excuse for improper installation.

C. In general, the drawings are diagrammatic and the Contractor shall install his work in a manner so that interferences between the various trades are avoided. In cases where interferences do occur, the Architect is to state which item was first installed.

1.22 AS-BUILT RECORD DRAWINGS

A. The Contractor shall obtain at his cost, two sets of blackline prints of the original bid documents by the Architect. One set shall be kept on the site with all information as referenced below, and shall update same as the work progresses. The other set will be utilized to record all field changes to a permanent record copy for the Owner.

B. If the Contractor elects to vary from the Contract Documents and secures prior approval from the Architect for any phase of the work, he shall record in a neat and readable manner, ALL such variances on the blackline print in red. The original blackline prints shall be returned to the Architect for documentation.

C. All deviations from sizes, locations, and from all other features of the installations shown in the Contract Documents shall be recorded.

D. In addition, it shall be possible using these drawings to correctly and easily locate, identify and establish sizes of all piping, directions and the like, as well as other features of the work which will be concealed underground and/or in the finished building.

E. Locations of underground work shall be established by dimensions to columns, lines or walls, locating all turns, etc., and by properly referenced centerline or invert elevations and rates of fall.

F. For work concealed in the building, sufficient information shall be given so it can be located with reasonable accuracy and ease. In some cases this may be by dimension. In others, it may

be sufficient to illustrate the work on the drawings in relation to the spaces in the building near which it was actually installed. The Architect's/Engineer's decision in this matter will be final.

G. The following requirements apply to all "As-Built" drawings:
1. They shall be maintained at the Contractor’s expense.
2. All such drawings shall be done carefully and neatly, and in a form approved by the Architect/Engineer.
3. Additional drawings shall be provided as necessary for clarifications.
4. These drawings shall be kept up-to-date during the entire course of the work and shall be available upon request for examination by the Architect/Engineer; and when necessary, to establish clearances for other parts of the work.
5. “As-built” drawings shall be returned to the Architect upon completion of the work and are subject to approval of the Architect/Engineer.

PART 2 - PRODUCTS

2.1 HVAC SYSTEM PRODUCTS

A. Refer to individual Division 23 sections for mechanical products, controls, fans, pipe, tube and fitting materials and joining methods.

PART 3 - EXECUTION

3.1 MANUFACTURER’S DIRECTION

A. The contractor shall install and operate all equipment and material in accordance with the manufacturer’s installation and operating instructions. The manufacturer’s instructions of installation and operation shall become part of the Contract Documents and shall supplement the Drawings and Specifications.

3.2 EQUIPMENT LABELS

A. Provide equipment labels for HVAC Equipment. Labels shall have permanent laminated construction secured to equipment.

3.3 VALVE TAGS

A. Secure metal tags to all valves. Labeling on all valve tags shall include type of system the valve controls and the area of building, zone, or equipment number affected by valve operation. Tag shall be 2"minimum diameter brass, engraved with code number, service and size. A framed list of the valves, giving manufacturer's name, model number, type and location shall be mounted in the main equipment room.

3.4 ACCESS DOORS:

A. Provide access doors in walls, floors and ceilings to permit access to equipment and piping requiring service or adjustment.
   1. Valves.
   2. Manual balancing dampers and automatic control dampers.
   3. Air terminal units and VRF indoor units.
   4. Duct mounted filters and coils.
   5. Drainage cleanouts.
   6. Kitchen Hood exhaust ductwork in accordance with NFPA requirements.
   7. Equipment shutoff protection devices such as disconnects, motor rated switches, etc.
   8. Other mechanical equipment indicated in schedules or specifications which are requiring maintenance, adjustment or operation.

B. Provide hinged access doors and frames as follows:
   1. Drywall Construction:
      a. Provide with concealed spring hinges and flush screwdriver operated cam locks in sufficient number of the size of the panel.
      b. Provide prime paintable surface (not galvanized).
      c. Product: Milcor “Style M” (Karp DSC-214M).
   2. Visible Masonry and Ceramic Tile:
      a. Milcor “Style M” (Karp DSC-214M).
   3. Cement Plaster:
      a. Milcor “Style K” (KarpDSC-214 PL).
   4. Acoustical Plaster:
      a. Reinforced panel as required to prevent sagging. Provide continuous steel piano type hinge for the length of the panel, and sufficient number for the size of the panel. Provide factory prime paint surface (not galvanized).
      b. Product: Milcor “Style AP” (Karp 214 PL).
   5. Acoustical Tile:
      a. Milcor “Style AT” (Larsen L-CPA).

C. Provide continuous concealed hinges and cam locks.

D. Provide UL listed 1-1/2 hour label “B” access doors with automatic self-closing latching mechanism where required.

E. Provide removable ceiling access tile section immediately adjacent to each mechanical or electrical device located in the ceiling plenum above removable tile ceiling.

F. Coordinate approval of type, color and location of access doors & frames with Architect.

3.5 CLEANING AND SERVICE

A. Upon Completion of this work, the contractor shall clean and adjust equipment, controls, valves, etc.;

B. Inspect, clean and service air filters and strainers immediately prior to final acceptance of project.

C. Provide complete and working charge of proper refrigerant, free of contaminants, into each refrigerant system. After each system has been in operation long enough to ensure completely balanced condition, check the charge and modify it for proper operation as required.

D. Place mechanical systems in complete working order. Clean equipment and piping materials thoroughly returning to "as new" condition prior to request for substantial completion.

E. Remove excess materials and debris from mechanical rooms and drain pans. Broom clean areas. Thoroughly clean ductwork inside and outside before air devices (diffusers, grilles, etc.) are installed.

3.6 TEMPORARY HEATING AND AIR CONDITIONING DURING CONSTRUCTION PHASE

A. Permanent building air conditioning equipment or systems are not designed to control building temperature and humidity levels during construction of the building. The building's HVAC system is not designed nor is it well suited for the proper drying of building/construction materials, and should not be used for such purposes.

B. At all times, during construction phases, provide temporary ventilation both for comfort and protection of workers, for proper drying of wet work, and for proper curing of installed materials. Follow material manufacturer's published instructions with regard to installation of building materials.

C. Provide temporary heat both for the comfort and protection of workers and as necessary to ensure suitable working conditions for construction operations of construction trades, and also as necessary for storage of products and materials. Refer to material manufacturer's literature for environmental operational temperature and humidity requirements.

D. Provide temporary heat by use of self-contained, vented portable heating units, employing tanked gas or other approved heat source.

E. Use only heating apparatus and fuels labeled or listed by a "National Recognized Testing Laboratory" recognized by OSHA. Keep equipment and surroundings in clean, safe conditions.

F. Use flame resistant tarpaulins other material for temporary enclosures of space.

G. Provide temporary humidity control by the use of small incremental de-humidifiers, packaged desiccant type de-humidifiers, and/or packaged DX type air conditioners.

H. Do not permit space temperatures to reach or fall to a level which will cause damage to work. Coordinate the temperature and humidity requirements with the manufacturer of the finishes being provided.

I. Replace interior or exterior surfaces damaged by the use of temporary heaters with new materials or refinish at no additional expense to the owner.

J. As soon as practical after permanent heating, ventilation, and air conditioning systems are in place and operable, the contractor at his option, may provide heat from the permanent building heating system, until such time that the building is complete. It is recommended that the building's permanent heating and air conditioning systems not be utilized to maintain

temperature and humidity conditions within the building during the construction phase. Small space heaters and portable de-humidifiers are suggested as sources of temperature and humidity control. It is the intent that the permanent HVAC systems should not be used to condition or control humidity during construction.

K. The use of permanent HVAC systems will require that the systems be complete and fully controllable by the Building Automation System (BAS) including the ability to remotely alarm proper maintenance personnel in the event of any and all system failure(s) or inability to maintain setpoint temperatures and humidity levels. Should the contractor elect to utilize the building's permanent HVAC system, the contractor shall bring the HVAC systems and ductwork back to an original unused condition or state by thoroughly cleaning and/or repairing both equipment and ductwork including repair and refinishing scrapes, tears, scratches and dents, cleaning ductwork, cleaning AHU coils, etc.

L. All dust, dirt, fungal growth, and debris in duct work shall be cleaned.

M. All disposable or wearable parts such as belts, filters, etc., shall be replaced without option or cause.

N. Contractor's Use of Permanent HVAC Systems:
1. Heating System:
   a. Should the contractor (at his option and at his own risk), utilize the building's permanent heating systems provided under this contract to provide space heating prior to project completion date subject to the restraints stated herein.
   b. The fuel for such space heating and for required tests of heating equipment shall be provided by contractor.
   c. The start up of equipment for use by the contractor shall not commence any warranty period.
   d. The heating system shall be operated only by qualified personnel, and shall be operated with all auxiliaries, safeties, and in accordance with manufacturer's instructions and good operating practice.
   e. If at any time the Owner's Representative determines that the equipment is being improperly operated or maintained, contractor will be directed to disconnect its use.
   f. Heating systems shall be operated and controlled to prevent temperature in any room or space in any building from exceeding 90 deg. F.
   g. Temperature controls shall be functional to the extent that the operating temperatures of equipment, ductwork piping, etc., shall not either fall or be elevated above or below normal operating limits. The contractor shall demonstrate to the owner or his representative the ability of the system to be controlled, including limit alarms installed and the ability to monitor the systems off-site.
   h. Systems shall not be operated unattended such as on holidays, weekends, nights, etc, nor shall personnel unfamiliar with the operation of the HVAC Systems be employed to "monitor or attend to" the systems such as security personnel, or janitorial staff. The heating system, when in operation, shall be continuously monitored by the mechanical contractor's approved personnel.
   i. Systems when activated, may be placed into operation without diffusers and registers in place, but filters capable of filtering gypsum dust or other associated construction dust and debris shall be provided both in air handling equipment and at return air grille locations. Filter all return air entering duct work, to prevent return air ductwork from accumulating dust or otherwise becoming dirty.

j. Prior to final acceptance of the work, the contractor shall place heating systems and related equipment in a condition equal to new in that contractor shall clean all ductwork, coils, equipment, etc.
k. All disposable or wearable parts such as belts, filters, etc., shall be replaced without option or cause.

2. Preliminary Heating Test, Adjusting and Balancing Report:
   a. Provide a TAB report at the time the heating system(s) start-up which shall indicate the following conditions:
      1) Air pressure drop across the unit filters
      2) Air pressure drop across the unit's cooling coil(s)
      3) Air pressure drop across the unit's heating coil(s)
      4) Total static pressure produced by the unit
      5) Discharge air static pressure
      6) Fan RPM
      7) Suction air pressure
      8) Provide a unit pressure graph
      9) Discharge air temperature (each air moving device)
      10) Return air temperature (each air moving device)
3. Air Conditioning System:
   a. Should the contractor (at his option and at his own risk), utilize the building's permanent air conditioning systems provided under this contract to provide space cooling and de-humidification prior to the project completion date. As such, any damages, loss of performance, wear, and other detrimental effects caused by the operational performance characteristics of the A/C system such as condensation, sweating of grilles, registers, diffusers, ducts, equipment, walls, floors, ceilings, and other conditions which may cause damage to building components or which cause mold, mildew, etc., shall be the total responsibility of the contractor.
   b. The fuel, electricity or other energy required for space cooling and for any subsequent operation or testing shall be provided by the Contractor.
   c. The cooling system(s) shall be operated only by fulling qualified personnel and shall be operated with all safety auxiliaries, and in accordance with manufacturer's instructions and good operating practice.
   d. Start-up of equipment for use by the Contractor shall not commence any warranty period.
   e. If at any time the Owner's Representative determines that the equipment is being improperly operated or maintained, the contractor will be directed to discontinue and disconnect its use and the contractor will be required to provide portable units to maintain space temperatures.
   f. Temporary cooling and/or de-humidification systems shall be operated and controlled to prevent temperature and humidity in any room or space in any portion of the building from falling below 75 deg. F or above 65% relative humidity.
   g. Temperature controls shall be functional to the extent that the operating temperatures of equipment, ductwork, piping, etc., shall not fall below the normal stated "design" operating limits. The contractor shall demonstrate to the owner or his representative the ability of the system to be controlled, including limit alarms installed and the ability to monitor the systems off-site.
   h. Insulation systems for all piping, ductwork, etc., shall be completely installed prior to use of the permanent systems.
   i. Systems shall not be operated unattended such as on holidays, weekends, nights, etc., nor shall personnel unfamiliar with the operation of the HVAC Systems be

employed to “monitor or attend to” the systems such as security personnel, or janitorial staff. The air conditioning system when in operation, shall be continuously monitored by the mechanical contractor’s approved personnel.

j. Systems when activated, may be placed into operation without diffusers and registers in place, but filters capable of filtering gypsum dust or other associated construction dust and debris shall be provided both in air handling equipment and at return air grille locations. Filter all return air entering duct work, to prevent return air duct work from accumulating dust or otherwise becoming dirty.

k. Contractor shall, prior to final acceptance of the work, place cooling systems and related equipment in a condition equal to new in that contractor shall clean all ductwork, coils, equipment, etc.

l. All disposable or wearable parts such as belts, filters, etc., shall be replaced without option or cause.

4. Preliminary Air Conditioning Test, Adjusting and Balancing Report:
   a. Provide a TAB report at the time the heating system(s) start-up which shall indicate the following conditions:
      1) Air pressure drop across the unit filters
      2) Air pressure drop across the unit’s cooling coil(s)
      3) Air pressure drop across the unit’s heating coil(s)
      4) Total static pressure produced by the unit
      5) Discharge air static pressure
      6) Fan RPM
      7) Suction air pressure
      8) Provide a unit pressure graph
      9) Discharge air temperature (each air moving device)
      10) Return air temperature (each air moving device)

END OF SECTION 23 00 00

SECTION 23 05 13 – COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes general requirements for single-phase and polyphase, general-purpose, horizontal, small and medium, squirrel-cage induction motors for use on ac power systems up to 600 V and installed at equipment manufacturer's factory or shipped separately by equipment manufacturer for field installation.

1.3 COORDINATION

A. Coordinate features of motors, installed units, and accessory devices to be compatible with the following:
   1. Motor controllers.
   2. Torque, speed, and horsepower requirements of the load.
   3. Ratings and characteristics of supply circuit and required control sequence.
   4. Ambient and environmental conditions of installation location.

PART 2 - PRODUCTS

2.1 GENERAL MOTOR REQUIREMENTS

A. Comply with NEMA MG 1 unless otherwise indicated.

2.2 MOTOR CHARACTERISTICS

A. Duty: Continuous duty at ambient temperature of 40 deg C and at altitude of 3300 feet above sea level.

B. Capacity and Torque Characteristics: Sufficient to start, accelerate, and operate connected loads at designated speeds, at installed altitude and environment, with indicated operating sequence, and without exceeding nameplate ratings or considering service factor.

2.3 POLYPHASE MOTORS

A. Description: NEMA MG 1, Design B, medium induction motor.

B. Efficiency: Energy efficient, as defined in NEMA MG 1.

C. Service Factor: 1.15.

D. Multispeed Motors: Variable torque.
1. For motors with 2:1 speed ratio, consequent pole, single winding.
2. For motors with other than 2:1 speed ratio, separate winding for each speed.

E. Rotor: Random-wound, squirrel cage.

F. Bearings: Regreasable, shielded, antifriction ball bearings suitable for radial and thrust loading.

G. Temperature Rise: Match insulation rating.

H. Insulation: Class F.

I. Code Letter Designation:
1. Motors 15 HP and Larger: NEMA starting Code F or Code G.
2. Motors Smaller than 15 HP: Manufacturer's standard starting characteristic.

J. Enclosure Material: Cast iron for motor frame sizes 324T and larger; rolled steel for motor frame sizes smaller than 324T.

2.4 POLYPHASE MOTORS WITH ADDITIONAL REQUIREMENTS

A. Motors Used with Reduced-Voltage and Multispeed Controllers: Match wiring connection requirements for controller with required motor leads. Provide terminals in motor terminal box, suited to control method.

B. Motors Used with Variable Frequency Controllers: Ratings, characteristics, and features coordinated with and approved by controller manufacturer.
1. Windings: Copper magnet wire with moisture-resistant insulation varnish, designed and tested to resist transient spikes, high frequencies, and short time rise pulses produced by pulse-width modulated inverters.
2. Energy- and Premium-Efficient Motors: Class B temperature rise; Class F insulation.
3. Inverter-Duty Motors: Class F temperature rise; Class H insulation.
4. Thermal Protection: Comply with NEMA MG 1 requirements for thermally protected motors.

2.5 SINGLE-PHASE MOTORS

A. Motors larger than 1/20 hp shall be one of the following, to suit starting torque and requirements of specific motor application:
1. Permanent-split capacitor.
2. Split phase.
3. Capacitor start, inductor run.
4. Capacitor start, capacitor run.

B. Multispeed Motors: Variable-torque, permanent-split-capacitor type.

C. Bearings: Prelubricated, antifriction ball bearings or sleeve bearings suitable for radial and thrust loading.

D. Motors 1/20 HP and Smaller: Shaded-pole type.

E. Thermal Protection: Internal protection to automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature rating of motor insulation. Thermal-protection device shall automatically reset when motor temperature returns to normal range.

PART 3 - EXECUTION

3.1 INSTALLATION

A. All materials and equipment shall be installed in accordance with Manufacturer's recommended installation methods for obtaining conformance with the Contract Documents.

B. Alignment of all motors, factory coupled or mounted, and all motors field coupled and mounted, shall be rechecked after all connections have been made and after 48 hours of operation in designed service.

C. Verify the voltage characteristics of each motor prior to ordering.

D. Verify the correct wire connections and rotation of equipment by "bumping" motor after wiring.

E. Confirm voltage imbalance on 3-phase motors is less than 2%.

3.2 APPLICATION: Except as specifically indicated, motors shall be selected as follows:

A. Phase:
1. Less than 1.0 HP: Single-Phase.
2. 1 HP and Larger: Three-phase.

B. Single Phase Starting:
1. 1/8 HP and Less: Split phase or permanent split capacitor.
2. Greater than 1/8 HP: Capacitor start.

C. Enclosure:
1. Totally enclosed fan-cooled (TEFC) for all motors located outside above roof, in wet areas, in mechanical rooms, or elsewhere as indicated.
2. Open drip-proof (ODP) for motors located elsewhere, in a clean, dry environment.

END OF SECTION 23 05 13

SECTION 23 05 29 – HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
1. Metal pipe hangers and supports.
2. Trapeze pipe hangers.
3. Metal framing systems.
4. Thermal-hanger shield inserts.
5. Fastener systems.
6. Pipe stands.
7. Equipment supports.

1.3 DEFINITIONS

A. MSS: Manufacturers Standardization Society of the Valve and Fittings Industry Inc.

1.4 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design trapeze pipe hangers and equipment supports, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

B. Structural Performance: Hangers and supports for HVAC piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

1.6 INFORMATIONAL SUBMITTALS

A. Welding certificates.

1.7 QUALITY ASSURANCE

A. Structural Steel Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

B. Pipe Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code.

PART 2 - PRODUCTS

2.1 METAL PIPE HANGERS AND SUPPORTS

A. Carbon-Steel Pipe Hangers and Supports:
1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
2. Galvanized Metallic Coatings: Pregalvanized or hot dipped.
3. Nonmetallic Coatings: Plastic coating, jacket, or liner.
4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

2.2 TRAPEZE PIPE HANGERS

A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural carbon-steel shapes with MSS SP-58 carbon-steel hanger rods, nuts, saddles, and U-bolts.

2.3 METAL FRAMING SYSTEMS

A. MFMA Manufacturer Metal Framing Systems:
1.
2. Manufacturers:
a. Cooper B-Line, Inc.; a division of Cooper Industries.
b. Flex-Strut Inc.
c. Thomas & Betts Corporation, A Member of the ABB Group.
d. Unistrut; an Atkore International company.
e. Wesanco, Inc.
3. Standard: MFMA-4.
4. Channels: Continuous slotted steel channel with inturned lips.
5. Channel Nuts: Formed or stamped steel nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
7. Metallic Coating: Electroplated zinc.

2.4 FASTENER SYSTEMS

A. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened Portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

B. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel anchors, for use in hardened Portland cement concrete; with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

2.5 EQUIPMENT SUPPORTS

A. Description: Welded, shop- or field-fabricated equipment support made from structural carbon-steel shapes.

B. Roof Sleepers for VRF outdoor condensing units: Pate Model ES-2 or equal, equipment rail supports, 18 ga. Galvanized steel, unitized construction with integral base plate, continuous welded corner seams, pressure treated wood nailer, counterflashing with screws. Height of support shall be a minimum of 16 inches. Coordinate layout of supports with the equipment manufacturer's representative and equipment point loading requirements. Coordinate flashing and exterior insulation with the roofing installer and Architect.

2.6 MISCELLANEOUS MATERIALS

A. Structural Steel: ASTM A 36/A 36M, carbon-steel plates, shapes, and bars; black and galvanized.

B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
1. Properties: Nonstaining, noncorrosive, and nongaseous.
2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT INSTALLATION

A. Metal Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from the building structure.

B. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.
1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified for individual pipe hangers.

2. Field fabricate from ASTM A 36/A 36M, carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1/D1.1M.

C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal framing systems.

D. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.

E. Fastener System Installation:
1. Install powder-actuated fasteners for use in lightweight concrete or concrete slabs less than 4 inches thick in concrete after concrete is placed and completely cured. Use operators that are licensed by powder-actuated tool manufacturer. Install fasteners according to powder-actuated tool manufacturer's operating manual.
2. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.

F. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.

G. Equipment Support Installation: Fabricate from welded-structural-steel shapes.

H. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.

I. Install lateral bracing with pipe hangers and supports to prevent swaying.

J. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.

K. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.

L. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.

M. Insulated Piping:
1. Attach clamps and spacers to piping.
   a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
   b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
   c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.
2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
   a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.

3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
    a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
4. Shield Dimensions for Pipe: Not less than the following:
    a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
    b. NPS 4: 12 inches long and 0.06 inch thick.
    c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
    d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
    e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
5. Pipes NPS 8 and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
6. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

3.2 EQUIPMENT SUPPORTS

A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.

B. Grouting: Place grout under supports for equipment and make bearing surface smooth.

C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.3 METAL FABRICATIONS

A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.

B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.

C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:
1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. Finish welds at exposed connections so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

3.4 ADJUSTING

A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.

B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

3.5 PAINTING

A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
   1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.

B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

3.6 HANGER AND SUPPORT SCHEDULE

A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.

B. Comply with MSS SP-69 for pipe-hanger selections and applications that are not specified in piping system Sections.

C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finish.

D. Use carbon-steel pipe hangers and supports metal trapeze pipe hangers and metal framing systems and attachments for general service applications.

E. Use thermal-hanger shield inserts for insulated piping and tubing.

F. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
   1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
   2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F, pipes NPS 4 to NPS 24, requiring up to 4 inches of insulation.
   3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes NPS 3/4 to NPS 36, requiring clamp flexibility and up to 4 inches of insulation.
   4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes NPS 1/2 to NPS 24 if little or no insulation is required.
   5. Pipe Hangers (MSS Type 5): For suspension of pipes NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
   6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes NPS 3/4 to NPS 8.
   7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
   8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
   9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
   10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8.
   11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3.

12. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.
13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
14. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction might occur.
18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes NPS 2-1/2 to NPS 24, from single rod if horizontal movement caused by expansion and contraction might occur.
19. Complete Pipe Rolls (MSS Type 44): For support of pipes NPS 2 to NPS 42 if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is not necessary.
20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes NPS 2 to NPS 24 if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is not necessary.
21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes NPS 2 to NPS 30 if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.

G. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.

H. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.

I. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction, to attach to top flange of structural shape.
3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.

5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
6. C-Clamps (MSS Type 23): For structural shapes.
7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:
    a. Light (MSS Type 31): 750 lb.
    b. Medium (MSS Type 32): 1500 lb.
    c. Heavy (MSS Type 33): 3000 lb.
13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.

J. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.

K. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41, roll hanger with springs.
4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from hanger.
6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from base support.
7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from trapeze support.
8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:

a. Horizontal (MSS Type 54): Mounted horizontally.
b. Vertical (MSS Type 55): Mounted vertically.
c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.

L. Comply with MSS SP-69 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.

M. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.

END OF SECTION 23 05 29

SECTION 23 05 53 – IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
   1. Equipment Labels.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Samples: For color, letter style, and graphic representation required for each identification material and device.

C. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.

PART 2 - PRODUCTS

2.1 EQUIPMENT LABELS

A. Plastic Labels for Equipment:
   1. Manufacturer shall be one of the following:
      a. Brady Corporation.
      b. Brimar Industries, Inc.
      c. Carlton Industries, LP.
      d. Champion America.
      e. Craftmark Pipe Markers.
      f. Emedco.
      g. Kolbi Pipe Marker Co.
      h. LEM Products Inc.
      i. Marking Services, Inc.
      j. Seton Identification Products.
   2. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/8 inch thick, and having predrilled holes for attachment hardware.
   3. Letter Color: White.
   4. Background Color: Black.
   5. Maximum Temperature: Able to withstand temperatures up to 160 deg F.

6. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
7. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-quarters the size of principal lettering.
8. Fasteners: Stainless-steel rivets.
9. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

B. Label Content: Include equipment's Drawing designation or unique equipment number, drawing numbers where equipment is indicated (plans, details, and schedules).

C. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number, and identify Drawing numbers where equipment is indicated (plans, details, and schedules) and the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulated.

3.2 GENERAL INSTALLATION REQUIREMENTS

A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.

B. Coordinate installation of identifying devices with locations of access panels and doors.

C. Install identifying devices before installing acoustical ceilings and similar concealment.

3.3 EQUIPMENT LABEL INSTALLATION

A. Install or permanently fasten labels on each major item of mechanical equipment.

B. Locate equipment labels where accessible and visible.

END OF SECTION 23 05 53

SECTION 23 05 93 – TESTING, ADJUSTING, AND BALANCING FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SCOPE OF WORK

A. The Contractor shall obtain the services of an independent Test and Balance (TAB) Company which specializes in the testing and balancing of heating, ventilating and air conditioning (HVAC) systems to test, adjust and balance all HVAC systems in the building(s).

B. The work included in this section consists of furnishing labor, instruments, and tools required in testing, adjusting and balancing the HVAC systems as described in these specifications or shown on accompanying drawings. Services shall include checking equipment performance, taking the specified measurements, and recording and reporting the results. The testing, adjusting and balancing agency shall act as a reporting agency; that is, list and report each piece of equipment as to identification number, manufacturer, model number, serial number, proper location, specified performance, and report actual performance of all equipment as found during testing. The report is intended to be used during the life of the building as a ready reference indicating original conditions, equipment components, etc.

C. Representatives of the Test and Balance Company shall visit the job site during installation of the HVAC equipment, piping and ductwork as required.

D. Upon completion of the HVAC system installation, the Test and Balance Company shall perform all required testing and balancing with the full cooperation of the Contractor and his Sub-contractors. The Contractor shall make changes and/or adjustments to the HVAC system components that are required by the Test and Balance Company to accomplish proper balancing. The TAB agency shall not supply or install any materials or balancing devices such as pulleys, drives, belts, etc. All of this work is by the Contractor and shall be performed at no additional cost to the Owner.

E. The test and balance report complete with a summary page listing all deficiencies shall be submitted to the Architect for review. If the Architect agrees with the report, he shall sign it and return it to the Contractor. The test and balance report must be complete and must be accepted by the Architect prior to acceptance of the project. Any outstanding test and balance items shall be placed on the punch list and a monetary value shall be assigned to them.

F. After all deficiencies have been corrected the Architect shall sign the testing and balancing report, and the Test and Balance Company shall supply four (4) copies of the final and complete report to the Contractor for inclusion in the Operation and Maintenance Manuals.

G. The Test and Balance Company shall obtain a copy of all HVAC related shop drawings from the contractor. The contractor shall provide a set of approved shop drawings to the TAB contractor within 30 days from receiving approved shop drawings.

H. The items requiring testing, adjusting, and balancing include (but are not restricted to) the following:

1. Air Systems:

a. Supply Fan AHU
b. Relief Fans
c. Exhaust Fans
d. Zone Branch and main ducts
e. Diffusers, Registers, Grilles and Dampers
f. Coils (Air Temperatures)
g. Valves
h. Vibration Isolators

2. Duct leakage tests.

1.3 DEFINITIONS

A. AABC: Associated Air Balance Council.

B. BAS: Building automation systems.

C. NEBB: National Environmental Balancing Bureau.

D. TAB: Testing, adjusting, and balancing.

E. TABB: Testing, Adjusting, and Balancing Bureau.

F. TAB Specialist: An independent entity meeting qualifications to perform TAB work.

G. TDH: Total dynamic head.

1.4 INFORMATIONAL SUBMITTALS

A. Certified TAB reports.

B. Sample report forms.

1.5 QUALITY ASSURANCE

A. TAB Specialists Qualifications: Certified by AABC NEBB or TABB.

B. Instrumentation Type, Quantity, Accuracy, and Calibration: Comply with requirements in ASHRAE 111, Section 4, "Instrumentation."

C. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 7.2.2 - "Air Balancing."

D. ASHRAE/IESNA Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6.7.2.3 - "System Balancing."

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems designs that may preclude proper TAB of systems and equipment.

B. Examine installed systems for balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers. Verify that locations of these balancing devices are applicable for intended purpose and are accessible.

C. Examine the approved submittals for HVAC systems and equipment.

D. Examine design data including HVAC system descriptions, statements of design assumptions for environmental conditions and systems output, and statements of philosophies and assumptions about HVAC system and equipment controls.

E. Examine ceiling plenums and underfloor air plenums used for supply, return, or relief air to verify that they are properly separated from adjacent areas. Verify that penetrations in plenum walls are sealed and fire-stopped if required.

F. Examine equipment performance data including fan and pump curves.
   1. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
   2. Calculate system-effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from the conditions used to rate equipment performance. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," or in SMACNA's "HVAC Systems - Duct Design." Compare results with the design data and installed conditions.

G. Examine system and equipment installations and verify that field quality-control testing, cleaning, and adjusting specified in individual Sections have been performed.

H. Examine test reports specified in individual system and equipment Sections.

I. Examine HVAC equipment and verify that bearings are greased, belts are aligned and tight, filters are clean, and equipment with functioning controls is ready for operation.

J. Examine operating safety interlocks and controls on HVAC equipment.

K. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

3.2 PREPARATION

A. Prepare a TAB plan that includes the following:
   1. Equipment and systems to be tested.
   2. Strategies and step-by-step procedures for balancing the systems.
   3. Instrumentation to be used.
   4. Sample forms with specific identification for all equipment.

B. Perform system-readiness checks of HVAC systems and equipment to verify system readiness for TAB work. Include, at a minimum, the following:
   1. Airside:
      a. Verify that leakage and pressure tests on air distribution systems have been satisfactorily completed.
      b. Duct systems are complete with terminals installed.
      c. Volume, smoke, and fire dampers are open and functional.
      d. Clean filters are installed.
      e. Fans are operating, free of vibration, and rotating in correct direction.
      f. Variable-frequency controllers' startup is complete and safeties are verified.
      g. Automatic temperature-control systems are operational.
      h. Ceilings are installed.
      i. Windows and doors are installed.
      j. Suitable access to balancing devices and equipment is provided.

3.3 GENERAL PROCEDURES FOR TESTING AND BALANCING

A. Perform testing and balancing procedures on each system according to the procedures contained in AABC's "National Standards for Total System Balance" NEBB's "Procedural Standards for Testing, Adjusting, and Balancing of Environmental Systems" and in this Section.

B. Cut insulation, ducts, pipes, and equipment cabinets for installation of test probes to the minimum extent necessary for TAB procedures.
   1. After testing and balancing, patch probe holes in ducts with same material and thickness as used to construct ducts.
   2. After testing and balancing, install test ports and duct access doors.
   3. Install and join new insulation that matches removed materials. Restore insulation, coverings, vapor barrier, and finish.

C. Mark equipment and balancing devices, including damper-control positions, valve position indicators, fan-speed-control levers, and similar controls and devices, with paint or other suitable, permanent identification material to show final settings.

D. Take and report testing and balancing measurements in inch-pound (IP) units.

3.4 GENERAL PROCEDURES FOR BALANCING AIR SYSTEMS

A. Prepare test reports for both fans and outlets. Obtain manufacturer's outlet factors and recommended testing procedures. Cross-check the summation of required outlet volumes with required fan volumes.

B. Prepare schematic diagrams of systems' "as-built" duct layouts.

C. Determine the best locations in main and branch ducts for accurate duct-airflow measurements.

D. Check airflow patterns from the outdoor-air louvers and dampers and the return- and exhaust-air dampers through the supply-fan discharge and mixing dampers.

E. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.

F. Verify that motor starters are equipped with properly sized thermal protection.

G. Check dampers for proper position to achieve desired airflow path.

H. Check for airflow blockages.

I. Check condensate drains for proper connections and functioning.

J. Check for proper sealing of air-handling-unit components.

K. Verify that air duct system is sealed as specified.

3.5 PROCEDURES FOR CONSTANT-VOLUME AIR SYSTEMS

A. Adjust fans to deliver total indicated airflows within the maximum allowable fan speed listed by fan manufacturer.
   1. Measure total airflow.
      a. Set outside-air, return-air, and relief-air dampers for proper position that simulates minimum outdoor-air conditions.
      b. Where duct conditions allow, measure airflow by Pitot-tube traverse. If necessary, perform multiple Pitot-tube traverses to obtain total airflow.
      c. Where duct conditions are not suitable for Pitot-tube traverse measurements, a coil traverse may be acceptable.
      d. If a reliable Pitot-tube traverse or coil traverse is not possible, measure airflow at terminals and calculate the total airflow.
   2. Measure fan static pressures as follows:
      a. Measure static pressure directly at the fan outlet or through the flexible connection.
      b. Measure static pressure directly at the fan inlet or through the flexible connection.
      c. Measure static pressure across each component that makes up the air-handling system.
      d. Report artificial loading of filters at the time static pressures are measured.
   3. Review Record Documents to determine variations in design static pressures versus actual static pressures. Calculate actual system-effect factors. Recommend adjustments to accommodate actual conditions.

4. Obtain approval from Construction Manager for adjustment of fan speed higher or lower than indicated speed. Comply with requirements in HVAC Sections for air-handling units for adjustment of fans, belts, and pulley sizes to achieve indicated air-handling-unit performance.
5. Do not make fan-speed adjustments that result in motor overload. Consult equipment manufacturers about fan-speed safety factors. Modulate dampers and measure fan-motor amperage to ensure that no overload occurs. Measure amperage in full-cooling, full-heating, economizer, and any other operating mode to determine the maximum required brake horsepower.

B. Adjust volume dampers for main duct, submain ducts, and major branch ducts to indicated airflows.
1. Measure airflow of submain and branch ducts.
2. Adjust submain and branch duct volume dampers for specified airflow.
3. Re-measure each submain and branch duct after all have been adjusted.

C. Adjust air inlets and outlets for each space to indicated airflows.
1. Set airflow patterns of adjustable outlets for proper distribution without drafts.
2. Measure inlets and outlets airflow.
3. Adjust each inlet and outlet for specified airflow.
4. Re-measure each inlet and outlet after they have been adjusted.

D. Verify final system conditions.
1. Re-measure and confirm that minimum outdoor, return, and relief airflows are within design. Readjust to design if necessary.
2. Re-measure and confirm that total airflow is within design.
3. Re-measure all final fan operating data, rpms, volts, amps, and static profile.
4. Mark all final settings.
5. Test system in economizer mode. Verify proper operation and adjust if necessary.
6. Measure and record all operating data.
7. Record final fan-performance data.

3.6 PROCEDURES FOR MOTORS

A. Motors 1/2 HP and Larger: Test at final balanced conditions and record the following data:
1. Manufacturer's name, model number, and serial number.
2. Motor horsepower rating.
3. Motor rpm.
4. Phase and hertz.
5. Nameplate and measured voltage, each phase.
6. Nameplate and measured amperage, each phase.
7. Starter size and thermal-protection-element rating.
8. Service factor and frame size.

3.7 PROCEDURES FOR CONDENSING UNITS

A. Verify proper rotation of fans.

B. Measure entering- and leaving-air temperatures.

C. Record fan and motor operating data.

3.8 DUCT LEAKAGE TESTS

A. Witness the duct pressure testing performed by Installer.

B. Verify that proper test methods are used and that leakage rates are within specified tolerances.

C. Report deficiencies observed.

D. Ductwork that initially fails these tests shall be replaced, modified, resealed, etc. as required to meet the leakage requirement and then re-test to ensure compliance.

3.9 TOLERANCES

A. Set HVAC system's airflow rates and water flow rates within the following tolerances:
1. Supply, Return, and Equipment with Fans: Plus or minus 10 percent.
2. Exhaust Fans: Plus 10 percent.
3. Outside Airflow: Plus 10 percent.
4. Air Outlets and Inlets: Plus or minus 10 percent.

B. Maintaining pressure relationships as designed shall have priority over the tolerances specified above.

3.10 FINAL REPORT

A. General: Prepare a certified written report; tabulate and divide the report into separate sections for tested systems and balanced systems.
1. Include a certification sheet at the front of the report's binder, signed and sealed by the certified testing and balancing engineer.
2. Include a list of instruments used for procedures, along with proof of calibration.
3. Certify validity and accuracy of field data.

B. Final Report Contents: In addition to certified field-report data, include the following:
1. Fan curves.
2. Manufacturers' test data.
3. Field test reports prepared by system and equipment installers.
4. Other information relative to equipment performance; do not include Shop Drawings and Product Data.

C. General Report Data: In addition to form titles and entries, include the following data:
1. Title page.
2. Name and address of the TAB specialist.
3. Project name.
4. Project location.
5. Architect's name and address.
6. Engineer's name and address.
7. Contractor's name and address.

8. Report date.
9. Signature of TAB supervisor who certifies the report.
10. Table of Contents with the total number of pages defined for each section of the report. Number each page in the report.
11. Summary of contents including the following:
    a. Indicated versus final performance.
    b. Notable characteristics of systems.
    c. Description of system operation sequence if it varies from the Contract Documents.
12. Nomenclature sheets for each item of equipment.
13. Notes to explain why certain final data in the body of reports vary from indicated values.
14. Test conditions for fans performance forms including the following:
    a. Settings for outdoor-, return-, and exhaust-air dampers.
    b. Conditions of filters.
    c. Cooling coil, wet- and dry-bulb conditions.
    d. Fan drive settings including settings and percentage of maximum pitch diameter.
    e. Settings for supply-air, static-pressure controller.
    f. Other system operating conditions that affect performance.

D. Air-Handling-Unit Test Reports: For air-handling units with coils, include the following:
1. Unit Data:
    a. Unit identification.
    b. Location.
    c. Make and type.
    d. Model number and unit size.
    e. Manufacturer's serial number.
    f. Unit arrangement and class.
    g. Discharge arrangement.
    h. Sheave make, size in inches, and bore.
    i. Center-to-center dimensions of sheave and amount of adjustments in inches.
    j. Number, make, and size of belts.
    k. Number, type, and size of filters.
2. Motor Data:
    a. Motor make, and frame type and size.
    b. Horsepower and rpm.
    c. Volts, phase, and hertz.
    d. Full-load amperage and service factor.
    e. Sheave make, size in inches, and bore.
    f. Center-to-center dimensions of sheave and amount of adjustments in inches.
3. Test Data (Indicated and Actual Values):
    a. Total airflow rate in cfm.
    b. Total system static pressure in inches wg.
    c. Fan rpm.
    d. Discharge static pressure in inches wg.
    e. Filter static-pressure differential in inches wg.
    f. Preheat-coil static-pressure differential in inches wg.
    g. Cooling-coil static-pressure differential in inches wg.
    h. Heating-coil static-pressure differential in inches wg.
    i. Outdoor airflow in cfm.
    j. Return airflow in cfm.
    k. Outdoor-air damper position.

l. Return-air damper position.
m. Vortex damper position.

E. Fan Test Reports: For supply, return, and exhaust fans, include the following:
1. Fan Data:
a. System identification.
b. Location.
c. Make and type.
d. Model number and size.
e. Manufacturer's serial number.
f. Arrangement and class.
g. Sheave make, size in inches, and bore.
h. Center-to-center dimensions of sheave and amount of adjustments in inches.
2. Motor Data:
a. Motor make, and frame type and size.
b. Horsepower and rpm.
c. Volts, phase, and hertz.
d. Full-load amperage and service factor.
e. Sheave make, size in inches, and bore.
f. Center-to-center dimensions of sheave, and amount of adjustments in inches.
g. Number, make, and size of belts.
3. Test Data (Indicated and Actual Values):
a. Total airflow rate in cfm.
b. Total system static pressure in inches wg.
c. Fan rpm.
d. Discharge static pressure in inches wg.
e. Suction static pressure in inches wg.

F. Round, Flat-Oval, and Rectangular Duct Traverse Reports: Include a diagram with a grid representing the duct cross-section and record the following:
1. Report Data:
a. System and air-handling-unit number.
b. Location and zone.
c. Traverse air temperature in deg F.
d. Duct static pressure in inches wg.
e. Duct size in inches.
f. Duct area in sq. ft.
g. Indicated airflow rate in cfm.
h. Indicated velocity in fpm.
i. Actual airflow rate in cfm.
j. Actual average velocity in fpm.
k. Barometric pressure in psig.

G. Instrument Calibration Reports:
1. Report Data:
a. Instrument type and make.
b. Serial number.
c. Application.
d. Dates of use.
e. Dates of calibration.

3.11 VERIFICATION OF TAB REPORT

A. The TAB specialist's test and balance engineer shall conduct the inspection in the presence of Architect.

B. Architect may randomly select measurements, documented in the final report, to be rechecked. Rechecking shall be limited to either 10 percent of the total measurements recorded or the extent of measurements that can be accomplished in a normal 8-hour business day.

C. If rechecks yield measurements that differ from the measurements documented in the final report by more than the tolerances allowed, the measurements shall be noted as "FAILED."

D. If the number of "FAILED" measurements is greater than 10 percent of the total measurements checked during the final inspection, the testing and balancing shall be considered incomplete and shall be rejected.

E. If TAB work fails, proceed as follows:
   1. TAB specialists shall recheck all measurements and make adjustments. Revise the final report and balancing device settings to include all changes; resubmit the final report and request a second final inspection.
   2. If the second final inspection also fails, Owner may contract the services of another TAB specialist to complete TAB work according to the Contract Documents and deduct the cost of the services from the original TAB specialist's final payment.
   3. If the second verification also fails, the design professional may contact AABC Headquarters regarding the AABC National Performance Guaranty.

F. Prepare test and inspection reports.

3.12 ADDITIONAL TESTS

A. Within 90 days of completing TAB, perform additional TAB to verify that balanced conditions are being maintained throughout and to correct unusual conditions.

B. Seasonal Periods: If initial TAB procedures were not performed during near-peak summer and winter conditions, perform additional TAB during near-peak summer and winter conditions.

END OF SECTION 23 05 93

SECTION 23 07 13 – DUCT INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes insulating the following duct services:

1. Indoor, concealed supply air.
2. Indoor, concealed return air.
3. Indoor, concealed exhaust air.
4. Indoor, concealed outdoor air.
5. Indoor, return air plenum boxes.
6. Indoor, tops of ceiling diffusers and grilles.
7. Indoor, kitchen hood and kitchen hood exhaust air.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance, thickness, and jackets (both factory- and field-applied if any).

B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.

1. Detail application of protective shields, saddles, and inserts at hangers for each type of insulation and hanger.
2. Detail insulation application at elbows, fittings, dampers, specialties and flanges for each type of insulation.
3. Detail application of field-applied jackets.
4. Detail application at linkages of control devices.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For qualified Installer.

B. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.

C. Field quality-control reports.

1.5 QUALITY ASSURANCE

A. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84, by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.

1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.7 COORDINATION

A. Coordinate sizes and locations of supports, hangers, and insulation shields as specified.

B. Coordinate clearance requirements with duct Installer for duct insulation application. Before preparing ductwork Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.

1.8 SCHEDULING

A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.

B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PART 2 - PRODUCTS

2.1 INSULATION MATERIALS

A. Comply with requirements in "Duct Insulation Schedule, General," "Indoor Duct and Plenum Insulation Schedule," articles for where insulating materials shall be applied.

B. Products shall not contain asbestos, lead, mercury, or mercury compounds.

C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.

D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.

E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.

F. Fire Rated Insulation:
   1. Manufacturer shall be one of the following:
      a. 3M FireMaster Fast Wrap 615+.
      b. Thermal Ceramics FireMaster.

G. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type II for sheet materials.
   1. Manufacturer shall be one of the following:
      a. Aeroflex, USA, Inc.
      b. Armacell LLC.

H. Fiber-Glass Blanket Insulation: Fiber-Glass bonded with a thermosetting resin. Comply with ASTM C 553, Type II and ASTM C 1290, Type III with factory-applied FSK jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
   1. Manufacturer shall be one of the following:
      a. Certainteed Corporation.
      b. Johns Manville; a Berkshire Hathaway company.
      c. Knauf Insulation.
      d. Manson Insulation Inc.
      e. Owens Corning.

2.2 ADHESIVES

A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.

B. Flexible Elastomeric Adhesive: Comply with MIL-A-24179A, Type II, Class I.
   1. Manufacture shall be one of the following:
      a. Aeroflex USA, Inc.
      b. Armacell LLC.
      c. Foster Brand.

C. Fiber-Glass Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.

   1. Manufacturer shall be one of the following:
      a. Childers Brand.
      b. Eagle Bridges – Marathon Industries.
      c. Foster Brand.
      d. Mon-Eco Industries, Inc.

2.3 MASTICS

A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.

1. For indoor applications, use mastics that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

B. Vapor-Barrier Mastic: Water based; suitable for indoor use on below ambient services.

1. Manufacturer:
   a. Foster Brand.
   b. Knauf Insulation.
   c. Vimasco Corporation.
   d. Childers.
2. Water-Vapor Permeance: ASTM E 96/E 96M, Procedure B, 0.013 perm at 43-mil dry film thickness.
3. Service Temperature Range: Minus 20 to plus 180 deg F.
4. Solids Content: ASTM D 1644, 58 percent by volume and 70 percent by weight.
5. Color: White.

2.4 SEALANTS

A. FSK and Metal Jacket Flashing Sealants:
1. Materials shall be compatible with insulation materials, jackets, and substrates.
2. Fire- and water-resistant, flexible, elastomeric sealant.
3. Service Temperature Range: Minus 40 to plus 250 deg F.
4. Color: Aluminum.
5. For indoor applications, sealants shall have a VOC content of 420 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
6. Sealants shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

2.5 FACTORY-APPLIED JACKETS

A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
1. FSK Jacket: Aluminum-foil, fiberglass-reinforced scrim with kraft-paper backing; complying with ASTM C 1136, Type II.

2.6 TAPES

A. FSK Tape: Foil-face, vapor-retarder tape matching factory-applied jacket with acrylic adhesive; complying with ASTM C 1136.
1. Width: 3 inches.
2. Thickness: 6.5 mils.
3. Adhesion: 90 ounces force/inch in width.
4. Elongation: 2 percent.
5. Tensile Strength: 40 lbf/inch in width.
6. FSK Tape Disks and Squares: Precut disks or squares of FSK tape.

2.7 SECUREMENTS

A. Bands:
1. Aluminum: ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, 3/4 inch wide with wing seal or closed seal.

B. Insulation Pins and Hangers:

1. Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.135-inch- diameter shank, length to suit depth of insulation indicated.
2. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.135-inch- diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
3. Metal, Adhesively Attached, Perforated-Base Insulation Hangers: Baseplate welded to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
   a. Baseplate: Perforated, galvanized carbon-steel sheet, 0.030 inch thick by 2 inches square.
   b. Spindle: Copper- or zinc-coated, low-carbon steel, fully annealed, 0.106-inch-diameter shank, length to suit depth of insulation indicated.
   c. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.
   d. Baseplate: Perforated, nylon sheet, 0.030 inch thick by 1-1/2 inches in diameter.
   e. Spindle: Nylon, 0.106-inch- diameter shank, length to suit depth of insulation indicated, up to 2-1/2 inches.
   f. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.

C. Staples: Outward-clinching insulation staples, nominal 3/4-inch- wide, stainless steel or Monel.

2.8 WALL LINER

A. Fibrous-Glass Duct Liner: Comply with ASTM C 1071, NFPA 90A, or NFPA 90B; and with NAIMA AH124, "Fibrous Glass Duct Liner Standard."

1. Manufacturers shall be as follows:
   a. Certainteed
   b. Owens Corning
   c. Johns Manville
   d. Knauf

2. Maximum Thermal Conductivity:

   a. Type I, Flexible: 0.27 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.

3. Antimicrobial Erosion-Resistant Coating: Apply to the surface of the liner that will form the interior surface of the duct to act as a moisture repellent and erosion-resistant coating. Antimicrobial compound shall be tested for efficacy by an NRTL and registered by the EPA for use in HVAC systems.

4. Water-Based Liner Adhesive: Comply with NFPA 90A or NFPA 90B and with ASTM C 916.

   a. For indoor applications, adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

B. Insulation Pins and Washers:

1. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
2. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick galvanized steel; with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.

1. Verify that systems to be insulated have been tested and are free of defects.
2. Verify that surfaces to be insulated are clean and dry.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

3.3 GENERAL INSTALLATION REQUIREMENTS

A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of ducts and fittings.

B. Install insulation materials, vapor barriers or retarders, jackets, and thicknesses required for each item of duct system as specified in insulation system schedules.

C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.

D. Install insulation with longitudinal seams at top and bottom of horizontal runs.

E. Install multiple layers of insulation with longitudinal and end seams staggered.

F. Keep insulation materials dry during application and finishing.

G. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.

H. Install insulation with least number of joints practical.

I. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.

1. Install insulation continuously through hangers and around anchor attachments.
2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.

J. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.

K. Install insulation with factory-applied jackets as follows:

1. Draw jacket tight and smooth.
2. Cover circumferential joints with 3-inch- wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
3. Overlap jacket longitudinal seams at least 1-1/2 inches. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 4 inches o.c.

    a. For below ambient services, apply vapor-barrier mastic over staples.

4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to duct flanges and fittings.

L. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.

M. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.

N. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.

3.4 PENETRATIONS

A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.

1. Seal penetrations with flashing sealant.
2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
4. Seal jacket to roof flashing with flashing sealant.

B. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.

1. Seal penetrations with flashing sealant.
2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
4. Seal jacket to wall flashing with flashing sealant.

C. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.

D. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Terminate insulation at fire damper sleeves for fire-rated wall and partition penetrations. Externally insulate damper sleeves to match adjacent insulation and overlap duct insulation at least 2 inches.

E. Insulation Installation at Floor Penetrations:

1. Duct: For penetrations through fire-rated assemblies, terminate insulation at fire damper sleeves and externally insulate damper sleeve beyond floor to match adjacent duct insulation. Overlap damper sleeve and duct insulation at least 2 inches.
2. Seal penetrations through fire-rated assemblies.

3.5 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

A. Seal longitudinal seams and end joints with manufacturer’s recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

3.6 INSTALLATION OF FIBER-GLASS INSULATION

A. Blanket Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.

1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of duct and plenum surfaces.
2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:

    a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
    b. On duct sides with dimensions larger than 18 inches, place pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
    c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
    d. Do not overcompress insulation during installation.
    e. Impale insulation over pins and attach speed washers.
    f. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.

4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.

    a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
    b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.

5. Overlap unfaced blankets a minimum of 2 inches on longitudinal seams and end joints. At end joints, secure with steel bands spaced a maximum of 18 inches o.c.
6. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
7. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch- wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

3.7 WALL LINER

A. Apply on all mechanical room walls from floor to ceiling / deck.

1. Adhere a single layer of indicated thickness of duct liner with at least 90 percent adhesive coverage at liner contact surface area. Attaining indicated thickness with multiple layers of duct liner is prohibited.
2. Apply adhesive to transverse edges of liner facing upstream that do not receive metal nosing.
3. Butt transverse joints without gaps, and coat joint with adhesive.
4. Fold and compress liner in corners or cut and fit to ensure butted-edge overlapping.
5. Secure liner with mechanical fasteners 4 inches from corners and at intervals not exceeding 12 inches transversely; at 3 inches from transverse joints and at intervals not exceeding 18 inches longitudinally.

3.8 FIELD-APPLIED JACKET INSTALLATION

A. Where FSK jackets are indicated, install as follows:

1. Draw jacket material smooth and tight.
2. Install lap or joint strips with same material as jacket.
3. Secure jacket to insulation with manufacturer's recommended adhesive.
4. Install jacket with 1-1/2-inch laps at longitudinal seams and 3-inch- wide joint strips at end joints.
5. Seal openings, punctures, and breaks in vapor-retarder jackets and exposed insulation with vapor-barrier mastic.

3.9 FIRE-RATED INSULATION SYSTEM INSTALLATION

A. Where fire-rated insulation system is indicated, secure system to ducts and duct hangers and supports to maintain a continuous fire rating.

B. Insulate duct access panels and doors to achieve same fire rating as duct.

C. Install firestopping at penetrations through fire-rated assemblies.

3.10 FINISHES

A. Insulation with ASJ, Glass-Cloth, or Other Paintable Jacket Material: Paint jacket with paint system identified below and as specified.

1. Flat Acrylic Finish: Two finish coats over a primer that is compatible with jacket material and finish coat paint. Add fungicidal agent to render fabric mildew proof.

    a. Finish Coat Material: Interior, flat, latex-emulsion size.

B. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer’s recommended protective coating.

C. Color: Final color as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.

D. Do not field paint aluminum or stainless-steel jackets.

3.11 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

B. Perform tests and inspections.

C. Tests and Inspections:

1. Inspect ductwork, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one location(s) for each duct system defined in the "Duct Insulation Schedule, General" Article.

D. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

3.12 DUCT INSULATION SCHEDULE, GENERAL

A. Plenums and Ducts Requiring Insulation:

1. Indoor, concealed supply air.
2. Indoor, concealed return air.
3. Indoor, concealed exhaust air.
4. Indoor, return air plenum boxes.
5. Indoor, tops of ceiling diffusers and grilles.
6. Indoor, kitchen hood and kitchen hood exhaust air.
7. Indoor, kitchen hood make-Up supply air.

B. Items Not Insulated:
1. Metal ducts with duct liner of sufficient thickness to comply with energy code and ASHRAE/IESNA 90.1.
2. Factory-insulated flexible ducts.
3. Factory-insulated plenums and casings.
4. Flexible connectors.
5. Vibration-control devices.
6. Factory-insulated access panels and doors.

3.13 DUCT AND PLENUM INSULATION SCHEDULE

A. Concealed, round and flat-oval, supply-air duct insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
2. Minimum installed R-value shall be R-6.0.

B. Concealed, round and flat-oval, return-air duct insulation shall be the following:

1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
2. Minimum installed R-value shall be R-6.0.

C. Concealed, round and flat-oval, outdoor-air duct insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
2. Minimum installed R-value shall be R-6.0.

D. Concealed, round and flat-oval, exhaust-air duct insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
2. Minimum installed R-value shall be R-6.0.

E. Concealed, rectangular, supply-air duct insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
2. Minimum installed R-value shall be R-6.0.

F. Concealed, rectangular, return-air duct insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
2. Minimum installed R-value shall be R-6.0.

G. Concealed, rectangular, exhaust-air duct shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
2. Minimum installed R-value shall be R-6.0.

H. Concealed, supply-air plenum insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
2. Minimum installed R-value shall be R-6.0.

I. Concealed, rectangular, outdoor-air duct insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
2. Minimum installed R-value shall be R-6.0.

J. Return air plenum boxes installation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
2. Minimum installed R-value shall be R-6.0.

K. Tops of supply air diffusers and grilles insulation shall be the following:
1. Mineral-Fiber Blanket: 2.125 inches thick and 0.75-lb/cu. ft. nominal density.
2. Minimum installed R-value shall be R-6.0.

L. Indoor, kitchen hood and kitchen hood exhaust air shall be the following:
1. Fire rated blanket: (Minimum) Two layers of 1-1/2” thick fire wrap insulation.
2. Insulate the grease duct with a high temperature, flexible, blanket insulation with FSK jacket that is tested and certified to provide a 2 hour fire rating. Thickness of insulation and the quantity of layers shall be as required to achieve 2-hour fire rating. The fire rated blanket system shall be installed in accordance with the manufacturer’s recommendations to meet the latest NFPA requirements for 0 inch clearance to combustibles.

END OF SECTION 23 07 13

SECTION 23 07 19 – HVAC PIPING INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes insulating the following HVAC piping systems:
   1. Condensate drain piping, indoors and outdoors.
   2. Refrigerant suction and hot-gas piping, indoors and outdoors.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory and field applied if any).

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For qualified Installer.

B. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.

C. Field quality-control reports.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.

B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84, by a testing and inspecting agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
   1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
   2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.7 COORDINATION

A. Coordinate sizes and locations of supports, hangers, and insulation shields specified.

B. Coordinate clearance requirements with piping Installer for piping insulation application. Before preparing piping Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.

1.8 SCHEDULING

A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.

B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PART 2 - PRODUCTS

2.1 INSULATION MATERIALS

A. Comply with requirements in "Piping Insulation Schedule, General," "Indoor Piping Insulation Schedule," and "Outdoor, Aboveground Piping Insulation Schedule" articles for where insulating materials shall be applied.

B. Products shall not contain asbestos, lead, mercury, or mercury compounds.

C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.

D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.

E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.

F. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials.
   1. Manufacturer shall be one of the following:
      a. Armacell AP.
      b. Aeroflex USA.
      c. K-Flex USA.

2.2 ADHESIVES

A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.

B. Flexible Elastomeric and Polyolefin Adhesive: Comply with MIL-A-24179A, Type II, Class I.

2.3 MASTICS

A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.
   1. For indoor applications, use mastics that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

B. Vapor-Barrier Mastic: Solvent based; suitable for outdoor use on below-ambient services.
   1. Manufacturers shall be one of the following:
      a. Childers Brand.
      b. Eagle Bridges – Marathon Industries.
      c. Foster Brand.
   2. Water-Vapor Permeance: ASTM F 1249, 0.05 perm at 30-mil dry film thickness.
   3. Service Temperature Range: Minus 50 to plus 220 deg F.
   4. Solids Content: ASTM D 1644, 33 percent by volume and 46 percent by weight.
   5. Color: White.

2.4 FIELD-APPLIED JACKETS

A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.

B. Metal Jacket:
   1. Aluminum Jacket: Comply with ASTM B 209, Alloy 3003, 3005, 3105, or 5005, Temper H-14.
      a. Finish and thickness are indicated in field-applied jacket schedules.
      b. Moisture Barrier for Outdoor Applications: 3-mil- thick, heat-bonded polyethylene and kraft paper.
      c. Factory-Fabricated Fitting Covers:
         1) Same material, finish, and thickness as jacket.
         2) Preformed 2-piece or gore, 45- and 90-degree, short- and long-radius elbows.
         3) Tee covers.
         4) Flange and union covers.
         5) End caps.
         6) Beveled collars.
         7) Valve covers.
         8) Field fabricate fitting covers only if factory-fabricated fitting covers are not available.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
   1. Verify that systems to be insulated have been tested and are free of defects.
   2. Verify that surfaces to be insulated are clean and dry.
   3. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

3.3 GENERAL INSTALLATION REQUIREMENTS

A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping including fittings, valves, and specialties.

B. Install insulation materials, forms, vapor barriers or retarders, jackets, and thicknesses required for each item of pipe system as specified in insulation system schedules.

C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.

D. Install insulation with longitudinal seams at top and bottom of horizontal runs.

E. Install multiple layers of insulation with longitudinal and end seams staggered.

F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.

G. Keep insulation materials dry during application and finishing.

H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.

I. Install insulation with least number of joints practical.

J. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.

K. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.

L. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.

M. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.

3.4 PENETRATIONS

A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
   1. Seal penetrations with flashing sealant.
   2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
   3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
   4. Seal jacket to roof flashing with flashing sealant.

B. Insulation Installation at Underground Exterior Wall Penetrations: Terminate insulation flush with sleeve seal. Seal terminations with flashing sealant.

C. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
   1. Seal penetrations with flashing sealant.
   2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
   3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
   4. Seal jacket to wall flashing with flashing sealant.

D. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.

E. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions.
   1. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping and fire-resistive joint sealers.

F. Insulation Installation at Floor Penetrations:
   1. Pipe: Install insulation continuously through floor penetrations.
   2. Seal penetrations through fire-rated assemblies.

3.5 GENERAL PIPE INSULATION INSTALLATION

A. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.

B. Insulation Installation on Fittings, Valves, Strainers, Flanges, and Unions:

1. Install insulation over fittings, valves, strainers, flanges, unions, and other specialties with continuous thermal and vapor-retarder integrity unless otherwise indicated.
2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts. Fill joints, seams, and irregular surfaces with insulating cement.
5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below-ambient services, provide a design that maintains vapor barrier.
6. Insulate flanges and unions using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker.
7. Cover segmented insulated surfaces with a layer of finishing cement and coat with a mastic. Install vapor-barrier mastic for below-ambient services and a breather mastic for above-ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.

3.6 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

B. Insulation Installation on Pipe Flanges:
   1. Install pipe insulation to outer diameter of pipe flange.
   2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
   3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of sheet insulation of same thickness as pipe insulation.
   4. Secure insulation to flanges and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

C. Insulation Installation on Pipe Fittings and Elbows:
   1. Install mitered sections of pipe insulation.

2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

D. Insulation Installation on Valves and Pipe Specialties:
1. Install preformed valve covers manufactured of same material as pipe insulation when available.
2. When preformed valve covers are not available, install cut sections of pipe and sheet insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
3. Install insulation to flanges as specified for flange insulation application.
4. Secure insulation to valves and specialties and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

3.7 FIELD-APPLIED JACKET INSTALLATION

A. Where metal jackets are indicated, install with 2-inch overlap at longitudinal seams and end joints. Overlap longitudinal seams arranged to shed water. Seal end joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless-steel bands 12 inches o.c. and at end joints.

3.8 PIPING INSULATION SCHEDULE, GENERAL

A. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.

B. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:
1. Drainage piping located in crawl spaces.
2. Underground piping.
3. Chrome-plated pipes and fittings unless there is a potential for personnel injury.

3.9 INDOOR PIPING INSULATION SCHEDULE

A. Condensate and Equipment Drain Water below 60 Deg F:
1. All Pipe Sizes: Insulation shall be the following:
a. Flexible Elastomeric: 3/4 inch thick.

B. Refrigerant Suction and Hot-Gas Piping:
1. All Pipe Sizes: Insulation shall be the following:
a. Flexible Elastomeric: 3/4 inch thick.

3.10 OUTDOOR, ABOVEGROUND PIPING INSULATION SCHEDULE

A. Refrigerant Suction and Hot-Gas Piping:
1. All Pipe Sizes: Insulation shall be the following:
a. Flexible Elastomeric: 1 inches thick.

3.11 OUTDOOR, FIELD-APPLIED JACKET SCHEDULE

A. Install jacket over insulation material.

B. If more than one material is listed, selection from materials listed is Contractor's option.

C. Refrigerant Piping, Concealed:
1. None.

D. Refrigerant Piping, Exposed:
1. Aluminum, Smooth: 0.016 inch thick.

3.12 OUTDOOR, FIELD-APPLIED MASTIC SCHEDULE

A. Install two layers of mastic **over** insulation material.

B. If more than one material is listed, selection from materials listed is Contractor's option.

C. Condensate and refrigerant Piping, Concealed:
1. None.

D. Condensate and Refrigerant Piping, Exposed:
1. Vapor-Barrier Mastic: Solvent based.

END OF SECTION 23 07 19

SECTION 23 21 14 – HVAC CONDENSATE PIPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes pipe and fitting materials and joining methods for the following:
   1. Condensate-drain piping.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of the following:

   1. Copper Tube.

   2. Plastic pipe and fittings with solvent cement.

B. Delegated-Design Submittal:

   1. Design calculations and detailed fabrication and assembly of pipe anchors and alignment guides, hangers and supports for multiple pipes, expansion joints and loops, and attachments of the same to the building structure.
   2. Locations of pipe anchors and alignment guides and expansion joints and loops.
   3. Locations of and details for penetrations, including sleeves and sleeve seals for exterior walls, floors, basement, and foundation walls.
   4. Locations of and details for penetration and firestopping for fire- and smoke-rated wall and floor and ceiling assemblies.

1.3 INFORMATIONAL SUBMITTALS

A. Field quality-control reports.

1.4 QUALITY ASSURANCE

A. ASME Compliance: Comply with ASME B31.9, "Building Services Piping," for materials, products, and installation.

PART 2 - PRODUCTS

2.1 COPPER TUBE AND FITTINGS

A. DWV Copper Tubing: ASTM B 306, Type DWV.

2.2 PLASTIC PIPE AND FITTINGS

A. PVC Plastic Pipe: ASTM D 1785, with wall thickness as indicated in "Piping Applications" Article.

1. PVC Plastic Pipe Fittings: Socket-type pipe fittings, ASTM D 2466 for Schedule 40 pipe; ASTM D 2467 for Schedule 80 pipe.

2.3 JOINING MATERIALS

A. Plastic, Pipe-Flange Gasket, Bolts, and Nuts: Type and material recommended by piping system manufacturer unless otherwise indicated.

B. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.

C. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys for joining copper with copper; or BAg-1, silver alloy for joining copper with bronze or steel.

D. Solvent Cements for Joining Plastic Piping:

1. PVC Piping: ASTM D 2564. Include primer according to ASTM F 656.

a. PVC solvent cement shall have a VOC content of 510 g/L or less.
b. Adhesive primer shall have a VOC content of 550 g/L or less.
c. Solvent cement and adhesive primer shall comply with the testing and product requirements of the California Department of Public Health's (formerly, the California Health Services') "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

E. Gasket Material: Thickness, material, and type suitable for fluid to be handled and working temperatures and pressures.

2.4 TRANSITION FITTINGS

A. Plastic-to-Metal Transition Fittings:
1. One-piece fitting with one threaded brass or copper insert and one solvent-cement-joint end of material and wall thickness to match plastic pipe material.

B. Plastic-to-Metal Transition Unions:
1. Brass or copper end, solvent-cement-joint end of material and wall thickness to match plastic pipe material, rubber gasket, and threaded union.

2.5 DIELECTRIC FITTINGS

A. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.

PART 3 - EXECUTION

3.1 PIPING APPLICATIONS

A. Condensate-Drain Piping: Type DWV, drawn-temper copper tubing, wrought-copper fittings, and soldered joints or Schedule 40 PVC plastic pipe and fittings and solvent-welded joints.

B. Condensate-Drain Piping: Schedule 40 PVC plastic pipe and fittings and solvent-welded joints.

3.2 PIPING INSTALLATIONS

A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.

B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.

C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.

E. Install piping to permit valve servicing.

F. Install piping at indicated slopes.

G. Install piping free of sags and bends.

H. Install fittings for changes in direction and branch connections.

I. Install piping to allow application of insulation.

J. Select system components with pressure rating equal to or greater than system operating pressure.

K. Install groups of pipes parallel to each other, spaced to permit applying insulation and servicing of valves.

L. Reduce pipe sizes using eccentric reducer fitting installed with level side up.

M. Install shutoff valve immediately upstream of each dielectric fitting.

N. Comply with requirements specified for identifying piping.

3.3 DIELECTRIC FITTING INSTALLATION

A. Install dielectric fittings in piping at connections of dissimilar metal piping and tubing.

B. Dielectric Fittings for NPS 2 and Smaller: Use dielectric nipples.

C. Dielectric Fittings for NPS 2-1/2 to NPS 4: Use dielectric nipples.

3.4 HANGERS AND SUPPORTS

A. Comply with requirements specified for hanger, support, and anchor devices. Comply with the following requirements for maximum spacing of supports.

B. Install the following pipe attachments:

1. Adjustable steel clevis hangers for individual horizontal piping less than 20 feet long.
2. Adjustable roller hangers and spring hangers for individual horizontal piping 20 feet or longer.
3. Pipe Roller: MSS SP-58, Type 44 for multiple horizontal piping 20 feet or longer, supported on a trapeze.
4. Spring hangers to support vertical runs.
5. Provide copper-clad hangers and supports for hangers and supports in direct contact with copper pipe.
6. On plastic pipe, install pads or cushions on bearing surfaces to prevent hanger from scratching pipe.

C. Install hangers for copper piping with the following maximum spacing and minimum rod sizes:

1. NPS 3/4: Maximum span, 5 feet; minimum rod size, 1/4 inch.
2. NPS 1: Maximum span, 6 feet; minimum rod size, 1/4 inch.
3. NPS 1-1/4Maximum span, 7 feet; minimum rod size, 3/8 inch.
4. NPS 1-1/2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
5. NPS 2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
6. NPS 2-1/2: Maximum span, 9 feet; minimum rod size, 3/8 inch.
7. NPS 3 and Larger: Maximum span, 10 feet; minimum rod size, 3/8 inch.

D. Plastic Piping Hanger Spacing: Space hangers shall be according to pipe manufacturer's written instructions for service conditions. Avoid point loading. Space and install hangers with the fewest practical rigid anchor points.

E. Support vertical runs at roof, at each floor, and at 10-foot intervals between floors.

3.5 PIPE JOINT CONSTRUCTION

A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.

B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.

C. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.

D. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8/A5.8M.

E. Plastic Piping Solvent-Cemented Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:

1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
2. PVC Pressure Piping: Join ASTM D 1785 schedule number, PVC pipe and PVC socket fittings according to ASTM D 2672. Join other-than-schedule number PVC pipe and socket fittings according to ASTM D 2855.
3. PVC Nonpressure Piping: Join according to ASTM D 2855.

F. Mechanically Formed, Copper-Tube-Outlet Joints: Use manufacturer-recommended tool and procedure, and brazed joints.

END OF SECTION 23 21 14

SECTION 23 23 00 – REFRIGERANT PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
1. Refrigerant pipes and fittings.
2. Refrigerant piping valves and specialties.
3. Refrigerants.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of valve, refrigerant pipe and refrigerant piping specialty.

B. Shop Drawings:
1. Show layout of refrigerant piping and specialties, including pipe, tube, and fitting sizes; flow capacities; pipe lengths, branch controller locations, valve arrangements and locations; slopes of horizontal runs; oil traps; double risers; wall and floor penetrations; and equipment connection details.
2. Show piping size and piping layout, including oil traps, double risers, specialties, and pipe and tube sizes to accommodate, as a minimum, equipment provided, elevation difference between compressor and evaporator, and length of piping to ensure proper operation and compliance with warranties of connected equipment.
3. Show interface and spatial relationships between piping and equipment.
4. Calculate refrigerant volume based on actual pipe layout for each VRF system.
5. Shop Drawing Scale: 1/8 inch equals 1 foot.

1.4 INFORMATIONAL SUBMITTALS

A. Welding certificates.

B. Field quality-control reports.

1.5 QUALITY ASSURANCE

A. Comply with ASHRAE 15, "Safety Code for Refrigeration Systems."

B. Comply with ASHRAE 34, “Designation and Safety Classification of Refrigerants.”

C. Comply with ASME B31.5, "Refrigeration Piping and Heat Transfer Components."

1.6 PRODUCT STORAGE AND HANDLING

A. Store piping with end caps in place to ensure that piping interior and exterior are clean when installed.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Line Test Pressure for Refrigerant R-454B/R-32:
   1. Suction Lines for Air-Conditioning Applications: 300 psig.
   2. Suction Lines for Heat-Pump Applications: 535 psig.
   3. Hot-Gas and Liquid Lines: 535 psig.

2.2 COPPER TUBE AND FITTINGS

A. Copper Tube: ASTM B 88, Type K or ASTM B 280, Type ACR.

B. Contractor may use pre-insulated refrigerant line sets provided and/or approved by the VRF equipment manufacturer.

2.3 REFRIGERANTS

A. ASHRAE 34, R-454B or R-32

PART 3 - EXECUTION

3.1 PIPING APPLICATIONS FOR REFRIGERANT R-454B/R-32

A. Hot-Gas and Liquid Lines, and Suction Lines for Heat-Pump Applications: Copper, Type ACR Type L, annealed- or drawn-temper tubing and copper fittings with brazed joints.

B. Safety-Relief-Valve Discharge Piping: Copper, Type L, annealed- or drawn-temper tubing and wrought-copper fittings with soldered joints.

3.2 PIPING INSTALLATION

A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems; indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on Shop Drawings.

B. Install refrigerant piping according to ASHRAE 15.

C. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.

D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.

F. Install piping adjacent to machines to allow service and maintenance.

G. Install piping free of sags and bends.

H. Install fittings for changes in direction and branch connections.

I. Select system components with pressure rating equal to or greater than system operating pressure.

J. Install piping as short and direct as possible, with a minimum number of joints, elbows, and fittings.

K. Arrange piping to allow inspection and service of refrigeration equipment. Install valves and specialties in accessible locations to allow for service and inspection. Install access doors or panels as specified if valves or equipment requiring maintenance is concealed behind finished surfaces.

L. When brazing or soldering, remove solenoid-valve coils and sight glasses; also remove valve stems, seats, and packing, and accessible internal parts of refrigerant specialties. Do not apply heat near expansion-valve bulb.

M. Install piping with adequate clearance between pipe and adjacent walls and hangers or between pipes for insulation installation.

3.3 PIPE JOINT CONSTRUCTION

A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.

B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.

C. Fill pipe and fittings with an inert gas (nitrogen or carbon dioxide), during brazing or welding, to prevent scale formation.

D. Soldered Joints: Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook."

E. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," Chapter "Pipe and Tube."
   1. Use Type BCuP (copper-phosphorus) alloy for joining copper socket fittings with copper pipe.
   2. Use Type BAg (cadmium-free silver) alloy for joining copper with bronze or steel.

3.4 HANGERS AND SUPPORTS

A. Comply with requirements for pipe hangers and supports specified.

B. Install the following pipe attachments:
   1. Adjustable steel clevis hangers for individual horizontal runs less than 20 feet long.
   2. Roller hangers and spring hangers for individual horizontal runs 20 feet or longer.
   3. Pipe Roller: MSS SP-58, Type 44 for multiple horizontal piping 20 feet or longer, supported on a trapeze.
   4. Spring hangers to support vertical runs.

C. Install hangers for copper tubing with the following maximum spacing and minimum rod diameters:
   1. NPS 1/2: Maximum span, 60 inches; minimum rod, 1/4 inch.
   2. NPS 5/8: Maximum span, 60 inches; minimum rod, 1/4 inch.
   3. NPS 1: Maximum span, 72 inches; minimum rod, 1/4 inch.
   4. NPS 1-1/4: Maximum span, 96 inches; minimum rod, 3/8 inch.
   5. NPS 1-1/2: Maximum span, 96 inches; minimum rod, 3/8 inch.
   6. NPS 2: Maximum span, 96 inches; minimum rod, 3/8 inch.
   7. NPS 2-1/2: Maximum span, 108 inches; minimum rod, 3/8 inch.
   8. NPS 3: Maximum span, 10 feet; minimum rod, 3/8 inch.
   9. NPS 4: Maximum span, 12 feet; minimum rod, 1/2 inch.

3.5 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:
   1. Comply with ASME B31.5, Chapter VI.
   2. Test refrigerant piping, specialties, and receivers. Isolate compressor, condenser, evaporator, and safety devices from test pressure if they are not rated above the test pressure.
   3. Test high- and low-pressure side piping of each system separately at not less than the pressures indicated in "Performance Requirements" Article.
      a. Fill system with nitrogen to the required test pressure.
      b. System shall maintain test pressure at the manifold gage throughout duration of test.
      c. Test joints and fittings with electronic leak detector or by brushing a small amount of soap and glycerin solution over joints.
      d. Remake leaking joints using new materials, and retest until satisfactory results are achieved.

B. Prepare test and inspection reports.

3.6 SYSTEM CHARGING

A. Charge system using the following procedures:
   1. Install core in filter dryers after leak test but before evacuation.
   2. Evacuate entire refrigerant system with a vacuum pump to 500 micrometers. If vacuum holds for 12 hours, system is ready for charging.
   3. Break vacuum with refrigerant gas, allowing pressure to build up to 2 psig.
   4. Charge system with a new filter-dryer core in charging line.

END OF SECTION 23 23 00

SECTION 26 05 00 – COMMON WORK RESULTS FOR ELECTRICAL

PART 1 - GENERAL

1.1 SUMMARY

A. This Section includes the following:

1. Supporting devices for electrical components.
2. Electricity-metering components.
3. Concrete equipment bases.
4. Touchup painting.

1.2 DEFINITIONS

A. EMT: Electrical metallic tubing.

B. FMC: Flexible metal conduit.

C. IMC: Intermediate metal conduit.

D. LFMC: Liquidtight flexible metal conduit.

E. RNC: Rigid nonmetallic conduit.

1.3 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Comply with NFPA 70.

1.4 COORDINATION

A. Coordinate chases, slots, inserts, sleeves, and openings with general construction work and arrange in building structure during progress of construction to facilitate the electrical installations that follow.

1. Set inserts and sleeves in poured-in-place concrete, masonry work, and other structural components as they are constructed.

B. Sequence, coordinate, and integrate installing electrical materials and equipment for efficient flow of the Work. Coordinate installing large equipment requiring positioning before closing in the building.

C. Coordinate electrical service connections with buildings and grounds.

D. Where electrical identification devices are applied to field-finished surfaces, coordinate installation of identification devices with completion of finished surface.

E. Where electrical identification markings and devices will be concealed by acoustical ceilings and similar finishes, coordinate installation of these items before ceiling installation.

F. Coordinate connecting to all equipment with equipment provider. This includes mechanical, plumbing, owner provided and contractor provided equipment. Contractor to refer to equipment installation documents prior to any rough-in.

G. Contractor to coordinate with door hardware provider, architect and owner prior to installation of any devices associated with doors to verify door operational requirement, placement of proximity readers, motion sensors, door switches, fire alarm control, magnetic locks, hold open devices, etc..

H. Contractor to coordinate with architectural millwork shop drawings prior to rough-in for locations of under counter lighting to be installed in and around millwork. No receptacles shall be installed in an enclosed cabinet unless noted on the drawings. Outlets for refrigerators, microwaves, etc. shall be installed in the space identified on the millwork shop drawings.

I. Contractor shall not penetrate any stair wall assemble with conduit, boxes, cabling and the like, except for items that serve the stairwell.

J. The contractor shall label the main service disconnecting means with the maximum available fault current shall be listed on the device to meet the requirements of NFPA 70:110.24. The labeling shall be engraved plastic. The maximum available fault current shall be obtained from the electrical utility for the secondary side of the utility transformer.

PART 2 - PRODUCTS

2.1 SUPPORTING DEVICES

A. Material: Cold-formed steel, with corrosion-resistant coating acceptable to authorities having jurisdiction.

B. Metal Items for Use Outdoors or in Damp Locations: Hot-dip galvanized steel.

C. Slotted-Steel Channel Supports: Flange edges turned toward web, and 9/16-inch- (14-mm-) diameter slotted holes at a maximum of 2 inches (50 mm) o.c., in webs.

D. Raceway and Cable Supports: Manufactured clevis hangers, riser clamps, straps, threaded C-clamps with retainers, ceiling trapeze hangers, wall brackets, and spring-steel clamps or click-type hangers.

E. Cable Supports for Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug for nonarmored electrical cables in riser conduits. Plugs have

number and size of conductor gripping holes as required to suit individual risers. Body constructed of malleable-iron casting with hot-dip galvanized finish.

F. Expansion Anchors: Carbon-steel wedge or sleeve type.

G. Toggle Bolts: All-steel springhead type.

H. Powder-Driven Threaded Studs: Heat-treated steel.

2.2 EQUIPMENT FOR ELECTRICITY METERING BY CONTRACTOR

A. Meter: Contractor shall provide metering per the local utility. Contractor shall provide all necessary enclosures, meter cans, etc. per the local utility requirements including any fees associated with the service.

2.3 CONCRETE BASES

A. Concrete: 3000-psi (20.7-MPa), 28-day compressive strength as specified

2.4 TOUCH-UP PAINT

A. For Equipment: Equipment manufacturer's paint selected to match installed equipment finish.

B. Galvanized Surfaces: Zinc-rich paint recommended by item manufacturer.

PART 3 - EXECUTION

3.1 ELECTRICAL EQUIPMENT INSTALLATION

A. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide the maximum possible headroom.

B. Materials and Components: Install level, plumb, and parallel and perpendicular to other building systems and components, unless otherwise indicated.

C. Equipment: Install to facilitate service, maintenance, and repair or replacement of components. Connect for ease of disconnecting, with minimum interference with other installations.

D. Right of Way: Give to raceways and piping systems installed at a required slope.

3.2 ELECTRICAL SUPPORTING DEVICE APPLICATION

A. Damp Locations and Outdoors: Hot-dip galvanized materials or nonmetallic, U-channel system components.

B. Dry Locations: Steel materials.

C. Support Clamps for PVC Raceways: Click-type clamp system.

D. Selection of Supports: Comply with manufacturer's written instructions.

E. Strength of Supports: Adequate to carry present and future loads, times a safety factor of at least four; minimum of 200-lb (90-kg) design load.

3.3 SUPPORT INSTALLATION

A. Install support devices to securely and permanently fasten and support electrical components.

B. Install individual and multiple raceway hangers and riser clamps to support raceways. Provide U-bolts, clamps, attachments, and other hardware necessary for hanger assemblies and for securing hanger rods and conduits.

C. Support parallel runs of horizontal raceways together on trapeze- or bracket-type hangers.

D. Size supports for multiple raceway installations so capacity can be increased by a 25 percent minimum in the future.

E. Support individual horizontal raceways with separate, malleable-iron pipe hangers or clamps.

F. Install 1/4-inch- (6-mm-) diameter or larger threaded steel hanger rods, unless otherwise indicated.

G. Spring-steel fasteners specifically designed for supporting single conduits or tubing may be used instead of malleable-iron hangers for 1-1/2-inch (38-mm) and smaller raceways serving lighting and receptacle branch circuits above suspended ceilings and for fastening raceways to slotted channel and angle supports.

H. Arrange supports in vertical runs so the weight of raceways and enclosed conductors is carried entirely by raceway supports, with no weight load on raceway terminals.

I. Simultaneously install vertical conductor supports with conductors.

J. Separately support cast boxes that are threaded to raceways and used for fixture support. Support sheet-metal boxes directly from the building structure or by bar hangers. If bar hangers are used, attach bar to raceways on opposite sides of the box and support the raceway with an approved fastener not more than 24 inches (610 mm) from the box.

K. Install metal channel racks for mounting cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices unless components are mounted directly to structural elements of adequate strength.

L. Install sleeves for cable and raceway penetrations of concrete slabs and walls unless core-drilled holes are used. Install sleeves for cable and raceway penetrations of masonry and fire-rated gypsum walls and of all other fire-rated floor and wall assemblies. Install sleeves during erection of concrete and masonry walls.

M. Securely fasten electrical items and their supports to the building structure, unless otherwise indicated. Perform fastening according to the following unless other fastening methods are indicated:

1. Wood: Fasten with wood screws.
2. Masonry: Toggle bolts on hollow masonry units and expansion bolts on solid masonry units.
3. New Concrete: Concrete inserts with machine screws and bolts.
4. Existing Concrete: Expansion bolts.
5. Instead of expansion bolts, threaded studs driven by a powder charge and provided with lock washers may be used in existing concrete.
6. Steel: Welded threaded studs or spring-tension clamps on steel.
   a. Field Welding: Comply with AWS D1.1.
7. Welding to steel structure may be used only for threaded studs, not for conduits, pipe straps, or other items.
8. Light Steel: Sheet-metal screws.
9. Fasteners: Select so the load applied to each fastener does not exceed 25 percent of its proof-test load.

3.4 FIRESTOPPING AND FIRE RATED WALLS/CEILINGS/FLOORS

A. Apply firestopping to cable and raceway penetrations of fire-rated floor and wall assemblies to achieve fire-resistance rating of the assembly. Firestopping materials and installation requirements are specified.

B. Repair and refinish disturbed finish materials and other surfaces to match adjacent undisturbed surfaces. Install new fireproofing where existing firestopping has been disturbed. Repair and refinish materials and other surfaces by skilled mechanics of trades involved.

3.5 CONCRETE BASES

A. Provide a concrete base for all floor mounted equipment. Construct concrete bases of dimensions indicated, but not less than 4 inches (100 mm) larger, in both directions, than supported unit. Follow supported equipment manufacturer's anchorage recommendations and setting templates for anchor-bolt and tie locations, unless otherwise indicated. Use 3000-psi (20.7-MPa), 28-day compressive-strength concrete and reinforcement as specified in Section "Cast-in-Place Concrete."

3.6 CUTTING AND PATCHING

A. Cut, channel, chase, and drill floors, walls, partitions, ceilings, and other surfaces required to permit electrical installations. Perform cutting by skilled mechanics of trades involved.

B. Repair and refinish disturbed finish materials and other surfaces to match adjacent undisturbed surfaces. Install new fireproofing where existing firestopping has been disturbed. Repair and refinish materials and other surfaces by skilled mechanics of trades involved.

3.7 REFINISHING AND TOUCH-UP PAINTING

A. Refinish and touch up paint.

1. Clean damaged and disturbed areas and apply primer, intermediate, and finish coats to suit the degree of damage at each location.
2. Follow paint manufacturer's written instructions for surface preparation and for timing and application of successive coats.
3. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
4. Repair damage to PVC or paint finishes with matching touchup coating recommended by manufacturer.

3.8 CLEANING AND PROTECTION

A. On completion of installation, including outlets, fittings, and devices, inspect exposed finish. Remove burrs, dirt, paint spots, and construction debris.

B. Protect equipment and installations and maintain conditions to ensure that coatings, finishes, and cabinets are without damage or deterioration at time of Substantial Completion.

END OF SECTION 26 05 00

SECTION 26 05 19 – LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes building wires and cables and associated connectors, splices, and terminations for wiring systems rated 600 V and less.

B. Related Sections include the following:

1. Section "Medium-Voltage Cables" for single-conductor and multiconductor cables, cable splices, and terminations for electrical distribution systems with 2001 to 35,000 V.

1.3 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Comply with NFPA 70- Latest edition or edition enforced by state and local code authority.

PART 2 - PRODUCTS

2.1 CONDUCTORS AND CABLES

A. Refer to Part 3 "Conductor and Insulation Applications" Article for insulation type, cable construction, and ratings.

B. Conductor Material: Copper; stranded conductor or solid conductor for No. 10 AWG and smaller, stranded for No. 8 AWG and larger.

C. Conductor Insulation Types: Type THHN-THWN.

2.2 CONNECTORS AND SPLICES

A. Description: Factory-fabricated connectors and splices of size, ampacity rating, material, type, and class for application and service indicated.

PART 3 - EXECUTION

3.1 CONDUCTOR AND INSULATION APPLICATIONS

A. Service Entrance: Type THHN-THWN, single conductors in raceway.

B. Exposed Feeders: Type THHN-THWN, single conductors in raceway.

C. Feeders Concealed in Ceilings, Walls, and Partitions: Type THHN-THWN, single conductors in raceway.

D. Feeders Concealed in Concrete, below Slabs-on-Grade, and in Crawlspaces: Type THHN-THWN, single conductors in raceway.

E. Exposed Branch Circuits, including in Crawlspaces: Type THHN-THWN, single conductors in raceway.

F. Branch Circuits Concealed in Ceilings, Walls, and Partitions: Type THHN-THWN, single conductors in raceway or MC Cable is allowed for concealed lighting and receptacle branch circuits.

G. Branch Circuits Concealed in Concrete and below Slabs-on-Grade: Type THHN-THWN, single conductors in raceway.

H. Fire Alarm Cabling: Plenum rated in plenum areas, exposed above accessible ceilings and in conduit when concealed in finished walls, unaccessible ceilings. Secured per NFPA 70-760.

I. Low Voltage Cabling: Plenum rated in plenum areas, exposed above accessible ceilings and in conduit when concealed in finished walls, unaccessible ceilings. Secured per NFPA 70-760.

J. Single Phase Circuits: Provide a dedicated neutral. Sharing of neutrals is not allowed.

3.2 INSTALLATION

A. Conceal cables in conduit in finished walls, unaccessible ceilings, and floors.

B. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.

C. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.

D. Support cables according to Section "Basic Electrical Materials and Methods."

E. Identify and color-code conductors and cables according to Section "Electrical Identification."

F. Use #10 AWG conductors for 20 amperage 120 circuits when the circuit conductors are longer than 75 feet. Use #10 AWG conductors for 20 amperage 277 circuits when the circuit conductors are longer than 200 feet.

3.3 CONNECTIONS

A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values.

1. Wiring at Outlets: Install conductor at each outlet, with at least 6 inches (150 mm) of slack.

END OF SECTION 26 05 19

SECTION 26 05 26 – GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes methods and materials for grounding systems and equipment.
   1. Underground grounding.
   2. Common ground bonding with lightning protection system.

1.3 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Comply with UL 467 for grounding and bonding materials and equipment.

PART 2 - PRODUCTS

2.1 CONDUCTORS

A. Insulated Conductors: Copper or tinned-copper wire or cable insulated for 600 V unless otherwise required by applicable Code or authorities having jurisdiction.

B. Bare Copper Conductors:

   1. Solid Conductors: ASTM B 3.
   2. Stranded Conductors: ASTM B 8.
   3. Tinned Conductors: ASTM B 33.
   4. Bonding Cable: 28 kcmil, 14 strands of No. 17 AWG conductor, 1/4 inch (6 mm) in diameter.
   5. Bonding Conductor: No. 4 or No. 6 AWG, stranded conductor.
   6. Bonding Jumper: Copper tape, braided conductors, terminated with copper ferrules; 1-5/8 inches (41 mm) wide and 1/16 inch (1.6 mm) thick.
   7. Tinned Bonding Jumper: Tinned-copper tape, braided conductors, terminated with copper ferrules; 1-5/8 inches (41 mm) wide and 1/16 inch (1.6 mm) thick.

C. Bare Grounding Conductor and Conductor Protector for Wood Poles:
   1. No. 4 AWG minimum, soft-drawn copper.
   2. Conductor Protector: Half-round PVC or wood molding. If wood, use pressure-treated fir or cypress or cedar.

D. Grounding Bus: Rectangular bars of annealed copper, 1/4 by 2 inches by 24" minimum in cross section, unless otherwise indicated; with insulators.

2.2 CONNECTORS

A. Listed and labeled by a nationally recognized testing laboratory acceptable to authorities having jurisdiction for applications in which used, and for specific types, sizes, and combinations of conductors and other items connected.

B. Bolted Connectors for Conductors and Pipes: Copper or copper alloy, bolted pressure-type, with at least two bolts.

   1. Pipe Connectors: Clamp type, sized for pipe.

C. Welded Connectors: Exothermic-welding kits of types recommended by kit manufacturer for materials being joined and installation conditions.

2.3 GROUNDING ELECTRODES

A. Ground Rods: Copper-clad steel, sectional type; 3/4 inch by10 feet (19 mm by 3 m) in diameter.

2.4 GROUND ACCESS WELLS

A. Molded high density polyethylene well with 9" diameter twist-lock cover and locking bolt. Two knock-outs (mouse holes) for routing conductor to inside. Harger #GAW910 or equal.

PART 3 - EXECUTION

3.1 APPLICATIONS

A. Conductors: Install solid conductor for No. 8 AWG and smaller, and stranded conductors for No. 6 AWG and larger, unless otherwise indicated.

B. Underground Grounding Conductors: Install bare tinned-copper conductor, No. 2/0 AWG minimum.

   1. Bury at least 24 inches below grade.
   2. Duct-Bank Grounding Conductor: Bury 12 inches above duct bank when indicated as part of duct-bank installation.

C. Isolated Grounding Conductors: Green-colored insulation with continuous yellow stripe. On feeders with isolated ground, identify grounding conductor where visible to normal inspection, with alternating bands of green and yellow tape, with at least three bands of green and two bands of yellow.

D. Grounding Bus: Install in electrical and telephone equipment rooms, in rooms housing service equipment, and elsewhere as indicated.

1. Install bus on insulated spacers 1 inch, minimum, from wall 6 inches above finished floor, unless otherwise indicated.
2. Where indicated on both sides of doorways, route bus up to top of door frame, across top of doorway, down to specified height above floor, and connect to horizontal bus.

E. Conductor Terminations and Connections:

1. Pipe and Equipment Grounding Conductor Terminations: Bolted connectors.
2. Underground Connections: Welded connectors, except at test wells and as otherwise indicated.
3. Connections to Ground Rods at Test Wells: Bolted connectors.
4. Connections to Structural Steel: Welded connectors.

3.2 GROUNDING UNDERGROUND DISTRIBUTION SYSTEM COMPONENTS

A. Comply with IEEE C2 grounding requirements.

B. Grounding Manholes and Handholes: Install a driven ground rod through manhole or handhole floor, close to wall, and set rod depth so 4 inches (100 mm) will extend above finished floor. If necessary, install ground rod before manhole is placed and provide No. 1/0 AWG bare, tinned-copper conductor from ground rod into manhole through a waterproof sleeve in manhole wall. Protect ground rods passing through concrete floor with a double wrapping of pressure-sensitive insulating tape or heat-shrunk insulating sleeve from 2 inches (50 mm) above to 6 inches (150 mm) below concrete. Seal floor opening with waterproof, nonshrink grout.

C. Grounding Connections to Manhole Components: Bond exposed-metal parts such as inserts, cable racks, pulling irons, ladders, and cable shields within each manhole or handhole, to ground rod or grounding conductor. Make connections with No. 4 AWG minimum, stranded, hard-drawn copper bonding conductor. Train conductors level or plumb around corners and fasten to manhole walls. Connect to cable armor and cable shields as recommended by manufacturer of splicing and termination kits

D. Pad-Mounted Transformers and Switches: The following is a minimum if the utility company does not have requirements, otherwise meet the utility company requirements. Install two ground rods and ground ring around the pad. Ground pad-mounted equipment and noncurrent-carrying metal items associated with substations by connecting them to underground cable and grounding electrodes. Install tinned-copper conductor not less than No. 2 AWG for ground ring and for taps to equipment grounding terminals. Bury ground ring not less than 6 inches (150 mm) from the foundation.

3.3 EQUIPMENT GROUNDING

A. Install insulated equipment grounding conductors with all feeders and branch circuits.

B. Install insulated equipment grounding conductors with the following items, in addition to those required by NFPA 70:
   1. Feeders and branch circuits.
   2. Lighting circuits.
   3. Receptacle circuits.
   4. Single-phase motor and appliance branch circuits.
   5. Three-phase motor and appliance branch circuits.
   6. Flexible raceway runs.
   7. Armored and metal-clad cable runs.
   8. Busway Supply Circuits: Install insulated equipment grounding conductor from grounding bus in the switchgear, switchboard, or distribution panel to equipment grounding bar terminal on busway.
   9. Computer and Rack-Mounted Electronic Equipment Circuits: Install insulated equipment grounding conductor in branch-circuit runs from equipment-area power panels and power-distribution units.
   10. X-ray Equipment Circuits: Install insulated equipment grounding conductor in circuits supplying x-ray equipment.

C. Air-Duct Equipment Circuits: Install insulated equipment grounding conductor to duct-mounted electrical devices operating at 120 V and more, including air cleaners, heaters, dampers, humidifiers, and other duct electrical equipment. Bond conductor to each unit and to air duct and connected metallic piping.

D. Water Heater, Heat-Tracing, and Antifrost Heating Cables: Install a separate insulated equipment grounding conductor to each electric water heater and heat-tracing cable. Bond conductor to heater units, piping, connected equipment, and components.

E. Isolated Grounding Receptacle Circuits: Install an insulated equipment grounding conductor connected to the receptacle grounding terminal. Isolate conductor from raceway and from panelboard grounding terminals. Terminate at equipment grounding conductor terminal of the applicable derived system or service, unless otherwise indicated.

F. Isolated Equipment Enclosure Circuits: For designated equipment supplied by a branch circuit or feeder, isolate equipment enclosure from supply circuit raceway with a nonmetallic raceway fitting listed for the purpose. Install fitting where raceway enters enclosure, and install a separate insulated equipment grounding conductor. Isolate conductor from raceway and from panelboard grounding terminals. Terminate at equipment grounding conductor terminal of the applicable derived system or service, unless otherwise indicated.

G. Signal and Communication Equipment: For telephone, alarm, voice and data, and other communication equipment, provide No. 4 AWG minimum insulated grounding conductor in raceway from grounding electrode system to each service location, terminal cabinet, wiring closet, and central equipment location.

   1. Service and Central Equipment Locations and Wiring Closets: Terminate grounding conductor on a 1/4-by-2-by-12-inch grounding bus.
   2. Terminal Cabinets: Terminate grounding conductor on cabinet grounding terminal.

H. Metal Poles Supporting Outdoor Lighting Fixtures: Install grounding electrode and a separate insulated equipment grounding conductor in addition to grounding conductor installed with branch-circuit conductors.

3.4 INSTALLATION

A. Grounding Conductors: Route along shortest and straightest paths possible, unless otherwise indicated or required by Code. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.

B. Common Ground Bonding with Lightning Protection System: Comply with NFPA 780 and UL 96 when interconnecting with lightning protection system. Bond electrical power system ground directly to lightning protection system grounding conductor at closest point to electrical service grounding electrode. Use bonding conductor sized same as system grounding electrode conductor, and install in conduit.

C. Ground Rods: Drive rods until tops are 2 inches (50 mm) below finished floor or final grade, unless otherwise indicated.

1. Interconnect ground rods with grounding electrode conductor below grade and as otherwise indicated. Make connections without exposing steel or damaging coating, if any.
2. For grounding electrode system, install at least three rods spaced at least one-rod length from each other and located at least the same distance from other grounding electrodes, and connect to the service grounding electrode conductor.
3. Install ground access well with cover for each ground rod (mounted flush with finished grade).

D. Bonding Straps and Jumpers: Install in locations accessible for inspection and maintenance, except where routed through short lengths of conduit.

1. Bonding to Structure: Bond straps directly to basic structure, taking care not to penetrate any adjacent parts.
2. Bonding to Equipment Mounted on Vibration Isolation Hangers and Supports: Install so vibration is not transmitted to rigidly mounted equipment.
3. Use exothermic-welded connectors for outdoor locations, but if a disconnect-type connection is required, use a bolted clamp.

E. Grounding and Bonding for Piping:

1. Metal Water Service Pipe: Install insulated copper grounding conductors, in conduit, from building's main service equipment, or grounding bus, to main metal water service entrances to building. Connect grounding conductors to main metal water service pipes, using a bolted clamp connector or by bolting a lug-type connector to a pipe flange, using one of the lug bolts of the flange. Where a dielectric main water fitting is installed, connect grounding conductor on street side of fitting. Bond metal grounding conductor conduit or sleeve to conductor at each end.
2. Water Meter Piping: Use braided-type bonding jumpers to electrically bypass water meters. Connect to pipe with a bolted connector.

3. Bond each aboveground portion of gas piping system downstream from equipment shutoff valve.

F. Bonding Interior Metal Ducts: Bond metal air ducts to equipment grounding conductors of associated fans, blowers, electric heaters, and air cleaners. Install tinned bonding jumper to bond across flexible duct connections to achieve continuity.

G. Grounding for Steel Building Structure: Install a driven ground rod at base of each corner column and at intermediate exterior columns at distances not more than 60 feet apart.

H. Ground Ring: Install a grounding conductor, electrically connected to each building structure ground rod and to each indicated item, extending around the perimeter of building as indicated on detail or drawings.

1. Install tinned-copper conductor not less than No. 2/0 AWG for ground ring and for taps to building steel.
2. Bury ground ring not less than 24 inches from building foundation.

I. Ufer Ground (Concrete-Encased Grounding Electrode): Fabricate according to NFPA 70, using a minimum of 20 feet of bare copper conductor not smaller than No. 4 AWG.

1. If concrete foundation is less than 20 feet long, coil excess conductor within base of foundation.
2. Bond grounding conductor to reinforcing steel in at least four locations and to anchor bolts. Extend grounding conductor below grade and connect to building grounding grid or to grounding electrode external to concrete.

3.5 FIELD QUALITY CONTROL

A. Perform the following tests and inspections and prepare test reports:

1. After installing grounding system but before permanent electrical circuits have been energized, test for compliance with requirements.
2. Test completed grounding system at each location where a maximum ground-resistance level is specified, at service disconnect enclosure grounding terminal, and at individual ground rods. Make tests at ground rods before any conductors are connected.

    a. Measure ground resistance not less than two full days after last trace of precipitation and without soil being moistened by any means other than natural drainage or seepage and without chemical treatment or other artificial means of reducing natural ground resistance.
    b. Perform tests by fall-of-potential method according to IEEE 81.

3. Prepare dimensioned drawings locating each test well, ground rod and ground rod assembly, and other grounding electrodes. Identify each by letter in alphabetical order, and key to the record of tests and observations. Include the number of rods driven and their depth at each location, and include observations of weather and other phenomena that may affect test results. Describe measures taken to improve test results.

B. Report measured ground resistances that exceed the following values:

1. Power and Lighting Equipment or System with Capacity 500 kVA and less: 10 ohms.
2. Power and Lighting Equipment or System with Capacity 500 to 1000 kVA: 5 ohms.
3. Power and Lighting Equipment or System with Capacity More Than 1000 kVA: 3 ohms.
4. Manhole Grounds: 10 ohms.

C. Excessive Ground Resistance: If resistance to ground exceeds specified values, notify Architect promptly and include recommendations to reduce ground resistance.

END OF SECTION 26 05 26

SECTION 26 05 29 – HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:

1. Hangers and supports for electrical equipment and systems.
2. Construction requirements for concrete bases.

B. Related Sections include the following:

1. Division 26 Section "Vibration and Seismic Controls for Electrical Systems" for products and installation requirements necessary for compliance with seismic criteria.

1.3 DEFINITIONS

A. EMT: Electrical metallic tubing.

B. IMC: Intermediate metal conduit.

C. RMC: Rigid metal conduit.

1.4 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design supports for multiple raceways, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

B. Design supports for multiple raceways capable of supporting combined weight of supported systems and its contents.

C. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

D. Rated Strength: Adequate in tension, shear, and pullout force to resist maximum loads calculated or imposed for this Project, with a minimum structural safety factor of five times the applied force.

1.5 SUBMITTALS

A. Product Data: For the following:

1. Steel slotted support systems.
2. Nonmetallic slotted support systems.

B. Shop Drawings: Show fabrication and installation details and include calculations for the following:

1. Trapeze hangers. Include Product Data for components.
2. Steel slotted channel systems. Include Product Data for components.
3. Equipment supports.

C. Welding certificates.

1.6 QUALITY ASSURANCE

A. Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

B. Comply with NFPA 70.

1.7 COORDINATION

A. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 03.

B. Coordinate installation of roof curbs, equipment supports, and roof penetrations. These items are specified in Division 07 Section "Roof Accessories."

PART 2 - PRODUCTS

2.1 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

A. Steel Slotted Support Systems: Comply with MFMA-4, factory-fabricated components for field assembly.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
   a. Allied Tube & Conduit.
   b. Cooper B-Line, Inc.; a division of Cooper Industries.
   c. ERICO International Corporation.
   d. GS Metals Corp.
   e. Thomas & Betts Corporation.

f. Unistrut; Tyco International, Ltd.
g. Wesanco, Inc.

2. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
3. Nonmetallic Coatings: Manufacturer's standard PVC, polyurethane, or polyester coating applied according to MFMA-4.
4. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.
5. Channel Dimensions: Selected for applicable load criteria.

B. Raceway and Cable Supports: As described in NECA 1 and NECA 101.

C. Conduit and Cable Support Devices: Steel and malleable-iron hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.

D. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for non-armored electrical conductors or cables in riser conduits. Plugs shall have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body shall be malleable iron.

E. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.

F. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:

1. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened Portland cement concrete, steel, or wood, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.

a. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1) Hilti Inc.
2) ITW Ramset/Red Head; a division of Illinois Tool Works, Inc.
3) MKT Fastening, LLC.
4) Simpson Strong-Tie Co., Inc.; Masterset Fastening Systems Unit.

2. Mechanical-Expansion Anchors: Insert-wedge-type, stainless steel, for use in hardened Portland cement concrete with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.

a. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1) Cooper B-Line, Inc.; a division of Cooper Industries.
2) Empire Tool and Manufacturing Co., Inc.
3) Hilti Inc.
4) ITW Ramset/Red Head; a division of Illinois Tool Works, Inc.
5) MKT Fastening, LLC.

3. Concrete Inserts: Steel or malleable-iron, slotted support system units similar to MSS Type 18; complying with MFMA-4 or MSS SP-58.
4. Clamps for Attachment to Steel Structural Elements: MSS SP-58, type suitable for attached structural element.
5. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM A 325.
6. Toggle Bolts: All-steel springhead type.
7. Hanger Rods: Threaded steel.

2.2 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

A. Description: Welded or bolted, structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.

B. Materials: Comply with requirements in Division 05 Section "Metal Fabrications" for steel shapes and plates.

PART 3 - EXECUTION

3.1 APPLICATION

A. Comply with NECA 1 and NECA 101 for application of hangers and supports for electrical equipment and systems except if requirements in this Section are stricter.

B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway: Space supports for EMT, IMC, and RMC as required by scheduled in NECA 1, where its Table 1 lists maximum spacings less than stated in NFPA 70. Minimum rod size shall be 1/4 inch in diameter.

C. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted or other support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.

1. Secure raceways and cables to these supports with two-bolt conduit clamps / single-bolt conduit clamps using spring friction action for retention in support channel.

D. Spring-steel clamps designed for supporting single conduits without bolts may be used for 1-1/2-inch and smaller raceways serving branch circuits and communication systems above suspended ceilings and for fastening raceways to trapeze supports.

3.2 SUPPORT INSTALLATION

A. Comply with NECA 1 and NECA 101 for installation requirements except as specified in this Article.

B. Raceway Support Methods: In addition to methods described in NECA 1, EMT IMC RMC EMT, IMC, and RMC may be supported by openings through structure members, as permitted in NFPA 70.

C. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.

D. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:

1. To Wood: Fasten with lag screws or through bolts.
2. To New Concrete: Bolt to concrete inserts.
3. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
4. To Existing Concrete: Expansion anchor fasteners.
5. Instead of expansion anchors, powder-actuated driven threaded studs provided with lock washers and nuts may be used in existing standard-weight concrete 4 inches thick or greater. Do not use for anchorage to lightweight-aggregate concrete or for slabs less than 4 inches thick.
6. To Steel: Beam clamps (MSS Type 19, 21, 23, 25, or 27) complying with MSS SP-69 or Spring-tension clamps.
7. To Light Steel: Sheet metal screws.
8. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate.

E. Drill holes for expansion anchors in concrete at locations and to depths that avoid reinforcing bars.

3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

A. Comply with installation requirements in Division 05 Section "Metal Fabrications" for site-fabricated metal supports.

B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.

C. Field Welding: Comply with AWS D1.1/D1.1M.

3.4 CONCRETE BASES

A. Construct concrete bases of dimensions indicated but not less than 4 inches larger in both directions than supported unit, and so anchors will be a minimum of 10 bolt diameters from edge of the base.

B. Use 3000-psi, 28-day compressive-strength concrete. Concrete materials, reinforcement, and placement requirements are specified in Division 03 Section "Cast-in-Place Concrete."

C. Anchor equipment to concrete base.

1. Place and secure anchorage devices. Use supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
2. Install anchor bolts to elevations required for proper attachment to supported equipment.

3. Install anchor bolts according to anchor-bolt manufacturer's written instructions.

3.5 PAINTING

A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.

1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils.

B. Touchup: Comply with requirements in Division 09 painting Sections for cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal.

C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 26 05 29

SECTION 26 05 33 – RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes raceways, fittings, boxes, enclosures, and cabinets for electrical wiring.

B. Related Sections include the following:

1. Refer to architectural for firestopping materials and installation at penetrations through walls, ceilings, and other fire-rated elements.
2. "Basic Electrical Materials and Methods" for supports, anchors, and identification products.
3. "Wiring Devices" for devices installed in boxes and for floor-box service fittings.

1.3 DEFINITIONS

A. EMT: Electrical metallic tubing.

B. ENT: Electrical nonmetallic tubing.

C. FMC: Flexible metal conduit.

D. IMC: Intermediate metal conduit.

E. LFMC: Liquidtight flexible metal conduit.

F. LFNC: Liquidtight flexible nonmetallic conduit.

G. RNC: Rigid nonmetallic conduit.

1.4 SUBMITTALS

A. Product Data: For surface raceways, floor boxes, and cabinets.

1.5 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Comply with NFPA 70-Latest edition or edition enforced by state and local code authority.

1.6 COORDINATION

A. Coordinate layout and installation of raceways, boxes, enclosures, cabinets, and suspension system with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, fire-suppression system, and partition assemblies.

PART 2 - PRODUCTS

2.1 METAL WIREWAYS

A. Material and Construction: Sheet metal sized and shaped as indicated, NEMA 1 or 3R.

B. Fittings and Accessories: Include couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.

C. Select features, unless otherwise indicated, as required to complete wiring system and to comply with NFPA 70.

D. Wireway Covers: Hinged type.

E. Finish: Manufacturer's standard enamel finish.

2.2 NONMETALLIC WIREWAYS

A. Description: Fiberglass polyester, extruded and fabricated to size and shape indicated, with no holes or knockouts. Cover is gasketed with oil-resistant gasket material and fastened with captive screws treated for corrosion resistance. Connections are flanged, with stainless-steel screws and oil-resistant gaskets.

B. Description: PVC plastic, extruded and fabricated to size and shape indicated, with snap-on cover and mechanically coupled connections with plastic fasteners.

C. Fittings and Accessories: Include couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.

D. Select features, unless otherwise indicated, as required to complete wiring system and to comply with NFPA 70.

2.3 SURFACE RACEWAYS

A. Surface Metal Raceways: Galvanized steel with snap-on covers. Finish with manufacturer's standard prime coating and two coats of paint. Color by Architect.

B. Types, sizes, and channels as indicated and required for each application, with fittings that match and mate with raceways.

2.4 BOXES, ENCLOSURES, AND CABINETS

A. Floor Boxes: Cast metal, fully adjustable, rectangular with four separate wiring compartments for power outlets, voice and data outlets, and/or AV devices as indicated on the drawing. Wiremold RFB4 Series, T&B 665 Series or approved equal. Covers shall be UL Listed to U.S. and Canadian safety standards for tile, carpet, wood, bare concrete and terrazzo floors. Covers shall be selected by the architect and shall be of Nickel, Brass, Black, Gray or Bronze.

B. Poke Thru Floor Boxes: Two hour rated poke thru floor unit with capabilities of two duplex power receptacles, data and AV devices. Provide power, data and phone outlets indicated on drawing. Wiremold Evolution Series 6AT or prior approved equal. Covers shall be selected by the architect and shall be of Nickel, Brass, Black, Gray or Bronze. Poke thru floor boxes are to be utilized on upper floors unless noted otherwise. There must be accessibility in the space below the poke thru box.

C. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.

D. Cast-Metal Pull and Junction Boxes: NEMA FB 1, cast aluminum with gasketed cover.

E. Hinged-Cover Enclosures: NEMA 250, Type 1, with continuous hinge cover and flush latch.

1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
2. Nonmetallic Enclosures: Plastic, finished inside with radio-frequency-resistant paint.

F. Cabinets: NEMA 250, Type 1, galvanized steel box with removable interior panel and removable front, finished inside and out with manufacturer's standard enamel. Hinged door in front cover with flush latch and concealed hinge. Key latch to match panelboards. Include metal barriers to separate wiring of different systems and voltage and include accessory feet where required for freestanding equipment.

G. Exterior Outlet Lock Box: Cast aluminum with self closing door withlock. All units shlal be keyed alike. 16 gauge steel housing. Unit for Interior and Exterior installation. Cole: TL-310 or equivalent.

H. In grade enclosures, boxes and covers are required to conform to all test provisions of the most current ANSI/SCTE 77 “Specification For Underground Enclosure Integrity” for Tier 22 applications. When multiple “Tiers” are specified the boxes must physically accommodate and

structurally support compatible covers while possessing the highest Tier rating. All covers are required to have the Tier level rating embossed on the surface. In no assembly can the cover design load exceed the design load of the box. All components in an assembly (box & cover) are manufactured using matched surface tooling. Independent third party verification or test reports stamped by a registered Professional Engineer certifying that all test provisions of this specification have been met are required with each submittal. Cover to labeled per use of box, ie “Electrical, Communications, etc”. Communications pull boxes shall be a minimum of 24" w x 36" l x 36 “ d.

2.5 FACTORY FINISHES

A. Finish: For raceway, enclosure, or cabinet components, provide manufacturer's standard prime-coat finish ready for field painting.

2.6 METAL CONDUIT AND TUBING

A. Rigid Steel Conduit: ANSI C80.1.
B. Aluminum Rigid Conduit: ANSI C80.5.
C. IMC: ANSI C80.6.
D. Plastic-Coated Steel Conduit and Fittings: NEMA RN 1.
E. Plastic Coated IMC and Fittings: NEMA RN 1.
F. EMT and Fittings: ANSI C 80.3.
G. EMT and Fittings: ANSI C80.3.
H. FMC: Aluminum
I. LFMC: Flexible steel conduit with PVC jacket.
J. Fittings: NEMA FB 1; compatible with conduit and tubing materials.

PART 3 - EXECUTION

3.1 RACEWAY APPLICATION

A. Outdoors:

1. Exposed: Rigid steel or IMC.
2. Concealed: Rigid steel or IMC.
3. Underground, Single Run: RNC.
4. Underground, Grouped: RNC.
5. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.
6. Boxes and Enclosures: NEMA 250, Type 4.

B. Indoors:

1. Exposed: EMT in non finished areas. Surface metal raceway in existing finished unaccessible areas unless noted otherwise.

2. Concealed: EMT. MC Cable is allowed for concealed lighting and receptacle branch circuits.
3. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): FMC; except use LFMC in damp or wet locations.
4. Damp or Wet Locations above Ground: Rigid steel conduit.
5. Boxes and Enclosures: NEMA 250, Type 1, except as follows:
   a. Damp or Wet Locations: NEMA 250, Type 4, stainless steel.

C. Minimum Raceway Size: 3/4-inch trade size (DN 21) below grade and ½ inch trade size above grade. When combining circuits, min. 3/4-inch trade size required.

D. Raceway Fittings: Compatible with raceways and suitable for use and location.

E. Contractor to provide metal raceway in Patient Care Areas per 517.13. Raceway shall be installed as a redundant ground. Raceway shall be a considered a ground.

3.2 INSTALLATION

A. Keep raceways at least 6 inches (150 mm) away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping.

B. Complete raceway installation before starting conductor installation.

C. Support raceways as specified in "Basic Electrical Materials and Methods."

D. Install temporary closures to prevent foreign matter from entering raceways.

E. Protect stub-ups from damage where conduits rise through floor slabs. Arrange so curved portions of bends are not visible above the finished slab.

F. Make bends and offsets so ID is not reduced. Keep legs of bends in the same plane and keep straight legs of offsets parallel, unless otherwise indicated.

G. Conceal conduit and EMT within finished walls, ceilings, and floors, unless otherwise indicated.

1. Install concealed raceways with a minimum of bends in the shortest practical distance, considering type of building construction and obstructions, unless otherwise indicated.

H. Raceways Embedded in Slabs: Install in middle 1/3 of slab thickness where practical and leave at least 2 inches (50 mm) of concrete cover. Conduits larger than 1” shall not be installed in the slab.

1. Secure raceways to reinforcing rods to prevent sagging or shifting during concrete placement.
2. Space raceways laterally to prevent voids in concrete.

3. Run conduit larger than 1-inch trade size (DN 27) parallel or at right angles to main reinforcement. Where at right angles to reinforcement, place conduit close to slab support.

I. Install exposed raceways parallel or at right angles to nearby surfaces or structural members and follow surface contours as much as possible.

1. Run parallel or banked raceways together on common supports.
2. Make parallel bends in parallel or banked runs. Use factory elbows only where elbows can be installed parallel; otherwise, provide field bends for parallel raceways.

J. Join raceways with fittings designed and approved for that purpose and make joints tight.

1. Use insulating bushings to protect conductors.

K. Tighten set screws of threadless fittings with suitable tools.

L. Terminations:

1. Where raceways are terminated with locknuts and bushings, align raceways to enter squarely and install locknuts with dished part against box. Use two locknuts, one inside and one outside box.
2. Where raceways are terminated with threaded hubs, screw raceways or fittings tightly into hub so end bears against wire protection shoulder. Where chase nipples are used, align raceways so coupling is square to box; tighten chase nipple so no threads are exposed.

M. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb (90-kg) tensile strength. Leave at least 12 inches (300 mm) of slack at each end of pull wire.

N. Stub-up Connections: Extend conduits through concrete floor for connection to freestanding equipment. Install with an adjustable top or coupling threaded inside for plugs set flush with finished floor. Extend conductors to equipment with rigid steel conduit; FMC may be used 6 inches (150 mm) above the floor. Install screwdriver-operated, threaded plugs flush with floor for future equipment connections.

O. Flexible Connections: Use maximum of 72 inches (1830 mm) of flexible conduit for recessed and semirecessed lighting fixtures; for equipment subject to vibration, noise transmission, or movement; and for all motors. Use LFMC in damp or wet locations. Install separate ground conductor across flexible connections.

P. Surface Raceways: Install a separate, green, ground conductor in raceways from junction box supplying raceways to receptacle or fixture ground terminals.

Q. Set floor boxes level and flush with finished floor surface.

R. Install hinged-cover enclosures and cabinets plumb. Support at each corner.

3.3 PROTECTION

A. Provide final protection and maintain conditions that ensure coatings, finishes, and cabinets are without damage or deterioration at time of Substantial Completion.

1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
2. Repair damage to PVC or paint finishes with matching touchup coating recommended by manufacturer.

3.4 CLEANING

A. After completing installation of exposed, factory-finished raceways and boxes, inspect exposed finishes and repair damaged finishes.

END OF SECTION 26 05 33

SECTION 26 05 53 – IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:

1. Identification for conductors and communication and control cable.
2. Warning labels and signs.
3. Instruction signs.
4. Equipment identification labels.
5. Miscellaneous identification products.

1.3 SUBMITTALS

A. Product Data: For each electrical identification product indicated.

B. Identification Schedule: An index of nomenclature of electrical equipment and system components used in identification signs and labels.

C. Samples: For each type of label and sign to illustrate size, colors, lettering style, mounting provisions, and graphic features of identification products.

1.4 QUALITY ASSURANCE

A. Comply with ANSI A13.1 and ANSI C2.

B. Comply with NFPA 70.

1.5 COORDINATION

A. Coordinate identification names, abbreviations, colors, and other features with requirements in the Contract Documents, Shop Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual, and with those required by codes and standards. Use consistent designations throughout Project.

B. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.

C. Coordinate installation of identifying devices with location of access panels and doors.

D. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 CONDUCTOR AND COMMUNICATION- AND CONTROL-CABLE IDENTIFICATION MATERIALS

A. Color-Coding Conductor Tape: Colored, self-adhesive vinyl tape not less than 3 mils thick by 1 to 2 inches wide.

B. Marker Tapes: Vinyl or vinyl-cloth, self-adhesive wraparound type, with circuit identification legend machine printed by thermal transfer or equivalent process.

2.2 WARNING LABELS AND SIGNS

A. Comply with NFPA 70 and 29 CFR 1910.145.

B. Self-Adhesive Warning Labels: Factory printed, multicolor, pressure-sensitive adhesive labels, configured for display on front cover, door, or other access to equipment, unless otherwise indicated.

C. Baked-Enamel Warning Signs: Preprinted aluminum signs, punched or drilled for fasteners, with colors, legend, and size required for application. 1/4-inch grommets in corners for mounting. Nominal size, 7 by 10 inches.

D. Warning label and sign shall include, but are not limited to, the following legends:

1. Multiple Power Source Warning: "DANGER - ELECTRICAL SHOCK HAZARD - EQUIPMENT HAS MULTIPLE POWER SOURCES."
2. Workspace Clearance Warning: "WARNING - OSHA REGULATION - AREA IN FRONT OF ELECTRICAL EQUIPMENT MUST BE KEPT CLEAR FOR 36 INCHES."

2.3 INSTRUCTION SIGNS

A. Engraved, laminated acrylic or melamine plastic, minimum 1/16 inch thick for signs up to 20 sq. in. and 1/8 inch thick for larger sizes.

1. Engraved legend with black letters on white face.
2. Punched or drilled for mechanical fasteners.
3. Framed with mitered acrylic molding and arranged for attachment at applicable equipment.

2.4 EQUIPMENT IDENTIFICATION LABELS

A. Engraved, Laminated Acrylic or Melamine Label: Punched or drilled for screw mounting. White letters on a dark-gray background. Minimum letter height shall be 3/8 inch.

2.5 MISCELLANEOUS IDENTIFICATION PRODUCTS

A. Cable Ties: Fungus-inert, self-extinguishing, 1-piece, self-locking, Type 6/6 nylon cable ties.

1. Minimum Width: 3/16 inch.
2. Tensile Strength: 50 lb, minimum.
3. Temperature Range: Minus 40 to plus 185 deg F.
4. Color: Black, except where used for color-coding.

B. Paint: Paint materials and application requirements are specified in Division 09 painting Sections.

1. Exterior Concrete Unit Masonry:
   a. Semigloss Acrylic-Enamel Finish: Two finish coat(s) over a block filler.
      1) Block Filler: Concrete unit masonry block filler.
      2) Finish Coats: Exterior semigloss acrylic enamel.

2. Exterior Ferrous Metal:
   a. Semigloss Alkyd-Enamel Finish: Two finish coat(s) over a primer.
      1) Primer: Exterior ferrous-metal primer.
      2) Finish Coats: Exterior semigloss alkyd enamel.

3. Exterior Zinc-Coated Metal (except Raceways):
      1) Primer: Exterior zinc-coated metal primer.
      2) Finish Coats: Exterior semigloss alkyd enamel.

4. Interior Ferrous Metal:
   a. Semigloss Acrylic-Enamel Finish: Two finish coat(s) over a primer.
      1) Primer: Interior ferrous-metal primer.
      2) Finish Coats: Interior semigloss acrylic enamel.

5. Interior Zinc-Coated Metal (except Raceways):
   a. Semigloss Acrylic-Enamel Finish: Two finish coat(s) over a primer.
      1) Primer: Interior zinc-coated metal primer.
      2) Finish Coats: Interior semigloss acrylic enamel.

C. Fasteners for Labels and Signs: Self-tapping, stainless-steel screws or stainless-steel machine screws with nuts and flat and lock washers.

PART 3 - EXECUTION

3.1 APPLICATION

A. Branch-Circuit Conductor Identification: Where there are conductors for more than three branch circuits in same junction or pull box, use color-coding conductor tape. Identify each ungrounded conductor according to source and circuit number.

B. Conductors to Be Extended in the Future: Attach write-on tags to conductors and list source and circuit number.

C. Auxiliary Electrical Systems Conductor Identification: Identify field-installed alarm, control, signal, sound, intercommunications, voice, and data connections.

1. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, and pull points. Identify by system and circuit designation.
2. Use system of marker tape designations that is uniform and consistent with system used by manufacturer for factory-installed connections.
3. Coordinate identification with Project Drawings, manufacturer's wiring diagrams, and Operation and Maintenance Manual.

D. Warning Labels for Indoor Cabinets, Boxes, and Enclosures for Power and Lighting: Comply with 29 CFR 1910.145 and apply self-adhesive warning labels. Identify system voltage with black letters on an orange background. Apply to exterior of door, cover, or other access.

1. Equipment with Multiple Power or Control Sources: Apply to door or cover of equipment including, but not limited to, the following:
   a. Power transfer switches.
   b. Controls with external control power connections.

2. Equipment Requiring Workspace Clearance According to NFPA 70: Unless otherwise indicated, apply to door or cover of equipment but not on flush panelboards and similar equipment in finished spaces.

E. Instruction Signs:

1. Operating Instructions: Install instruction signs to facilitate proper operation and maintenance of electrical systems and items to which they connect. Install instruction signs with approved legend where instructions are needed for system or equipment operation.
2. Emergency Operating Instructions: Install instruction signs with white legend on a red background with minimum 3/8-inch- high letters for emergency instructions at equipment used for power transfer.

F. Equipment Identification Labels: On each unit of equipment, install unique designation label that is consistent with wiring diagrams, schedules, and Operation and Maintenance Manual. Apply labels to disconnect switches and protection equipment, central or master units, control panels, control stations, terminal cabinets, and racks of each system. Systems include power, lighting, control,

communication, signal, monitoring, and alarm systems unless equipment is provided with its own identification.

1. Labeling Instructions:
   a. Indoor Equipment: Engraved, laminated acrylic or melamine label. Unless otherwise indicated, provide a single line of text with 1/2-inch- high letters on 1-1/2-inch- high label; where 2 lines of text are required, use labels 2 inches high.
   b. Outdoor Equipment: Engraved, laminated acrylic or melamine label.
   c. Elevated Components: Increase sizes of labels and letters to those appropriate for viewing from the floor.

2. Equipment to Be Labeled:
   a. Panelboards, electrical cabinets, and enclosures.
   b. Access doors and panels for concealed electrical items.
   c. Electrical switchgear and switchboards.
   d. Transformers.
   e. Emergency system boxes and enclosures.
   f. Receptacles with panel and circuit numbers.
   g. Disconnect switches.
   h. Enclosed circuit breakers.
   i. Power transfer equipment.
   j. Contactors.

3.2 INSTALLATION

A. Verify identity of each item before installing identification products.

B. Location: Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment.

C. Apply identification devices to surfaces that require finish after completing finish work.

D. Self-Adhesive Identification Products: Clean surfaces before application, using materials and methods recommended by manufacturer of identification device.

E. Attach nonadhesive signs and plastic labels with screws and auxiliary hardware appropriate to the location and substrate.

F. Color-Coding for Phase and Voltage Level Identification, 600 V and Less: Use the colors listed below for ungrounded service feeder branch-circuit service, feeder, and branch-circuit conductors.

1. Color shall be factory applied factory applied or, for sizes larger than No. 10 AWG if authorities having jurisdiction permit, field applied.
2. Colors for 208/120-V Circuits:
   a. Phase A: Black.
   b. Phase B: Red.
   c. Phase C: Blue.
3. Colors for 480/277-V Circuits:

a. Phase A: Brown.
b. Phase B: Orange.
c. Phase C: Yellow.

4. Field-Applied, Color-Coding Conductor Tape: Apply in half-lapped turns for a minimum distance of 6 inches from terminal points and in boxes where splices or taps are made. Apply last two turns of tape with no tension to prevent possible unwinding. Locate bands to avoid obscuring factory cable markings.

END OF SECTION 26 05 53

SECTION 26 05 73 – OVERCURRENT PROTECTION DEVICE COORDINATION STUDY

1.1 SCOPE

A. The contractor shall provide an engineering analysis and coordination study for the entire electrical distribution system. The analysis shall include a short-circuit analysis with protective device evaluation, emergency power system selective coordination study, a protective device coordination study and an arc fault hazard analysis study.

B. The project shall begin at the point of utility service on the primary side for the facility and continue down through the system, to all downstream distribution and branch panelboards, motor control centers and significant motor locations.

1.2 RELATED DOCUMENTS

A. Single line diagrams

B. Specifications

1.3 SUBMITTALS

A. General. Submit the following according to Conditions of the Contract and Division 1 Specification Sections:

B. Submit for review six copies of the protection coordination study.

C. Shop drawings for equipment effected by the coordination study will not be reviewed until the coordination study has been submitted and approved.

D. Qualification data for firms and persons specified in the “Quality Assurance” Article to demonstrate their capabilities and experience. Include list of completed projects with project names, addresses, names of Engineer and Owner, and other information specified.

E. A one-line diagram of the system shall be included.

F. The final report shall be bound in a three-ring binder.

G. The final report shall contain individual, tabbed sections for each section. Each tabbed section shall contain the information as outlined in Part 2 of this document. Tab 1 shall list the manufacturer’s name, address, general business phone number, after hours service phone number, spare parts phone number, distributor’s name, address, general business phone number, after hours service phone number and spare parts phone number. Tab 2 shall contain Section 2.2’s short-circuit analysis with protective device evaluation. Tab 3 shall contain Section 2.3’s protective device coordination study. Tab 4 contains Section 2.4’s information and so on.

H. Arc flash labels shall be provided in hard copy and in electronic format.

1.4 Emergency Power System Selective Coordination Study

A. Four copies of the Emergency Power System Selective Coordination Study including, but not limited to:

1. Time-current characteristic curve drawings on log-log printouts which illustrate:
   a. Compliance of the provided overcurrent protective devices with the specified selective coordination requirements.
   b. The recommended settings for all adjustable relays, overcurrent protective devices and ground fault protective devices provided for the project.
   c. A tabulation of the recommended settings for all adjustable relays, overcurrent protective devices and ground fault protective devices and type selections for fuse protective devices supplied.
   d. An analysis of the results in which any inadequacies related to the specified selective coordination shall be called to the attention of the Engineer with recommendations for improved coordination.

1.5 RELATED STANDARDS

A. All studies shall be performed in accordance with the latest applicable IEEE and ANSI standards.

1.6 QUALITY ASSURANCE

A. Preparer Qualifications: The study shall be prepared in accordance with the latest edition of NETA Std. ATS, NFPA 70B, the "National Electrical Code", ANSI C2" National Electrical Safety Code", and ANSI/IEEE Guidelines, as well as manufacturer's recommendations.

B. Short-Circuit Analysis and Coordination Study shall be performed by a registered Professional Engineer. Study shall be signed and sealed by the Engineer. The Engineer shall have a minimum of eight years experience in the analysis, evaluation, and coordination of electrical distribution systems. The study must be prepared by a Louisiana licensed professional electrical engineer.

C. The firm conducting the study shall have one million worth of Professional Liability Insurance in addition to standard general insurance.

1.7 DELIVERY, STORAGE AND HANDLING

A. The six sets of submittals shall be submitted for review and approval.

B. The six sets are due no later than 4 weeks after contract award and are required prior to the review of the shop drawings.

PART 2 - PRODUCTS

2.1 SHORT-CIRCUIT ANALYSIS WITH PROTECTIVE DEVICE EVALUATION

A. Systematically calculate fault currents based on the available fault current at the facility service entrance. Study preparer shall obtain the available fault current from the local utility.

B. Short-circuit calculations shall be prepared by means of a digital computer utilizing a commercially available software package. Motor contribution shall be incorporated in

determining fault levels. Results of short-circuit calculations shall be presented in tabular form and shall include momentary and interrupting fault values for three-phase and phase-to-ground faults.

C. Analyze the short-circuit currents by preparing a tabulation comparing the fault levels to the device interrupting ratings. Indicate areas in which integrated/series ratings are utilized. The following information shall be included in the tabulation:
   1. Bus identification number.
   2. Location identification.
   3. Voltage
   4. Manufacturer and type of equipment.
   5. Device rating.
   6. Calculated short-circuit current.

D. Protective Device Evaluation:

   1. Evaluate equipment and protective devices and compare to short-circuit ratings.
   2. Tabulations of circuit breaker, fuse, and other protective device ratings versus calculated short-circuit duties.
   3. For 600-V overcurrent protective devices, ensure that interrupting ratings are equal to or higher than calculated 1/2-cycle symmetrical fault current.
   4. For devices and equipment rated for asymmetrical fault current, apply multiplication factors listed in the standards to 1/2-cycle symmetrical fault current.
   5. Verify adequacy of phase conductors at maximum three-phase bolted fault currents; verify adequacy of equipment grounding conductors and grounding electrode conductors at maximum ground-fault currents. Ensure that short-circuit withstand ratings are equal to or higher than calculated 1/2-cycle symmetrical fault current.

2.2 PROTECTIVE DEVICE COORDINATION STUDY

A. Prepare coordination time-current characteristic curves to determine the required settings/sizes of the protective devices to maximize selectivity. The utility upstream protective device feeding the facility shall be maintained as the upper limit for coordination. These settings shall be obtained by the preparer, along with any other protective device setting requirements. The coordination curves shall be prepared on log-log paper and illustrate adequate clearing times between series devices. The curves shall be created through the use of the study software package, but must reflect actual protective devices to be installed. Adequate time-current curves shall be generated to depict coordination. In addition, protective device characteristics shall be suitably determined to reflect calculated short-circuit levels at the location.

B. A narrative analysis shall accompany each coordination curve sheet and describe the coordination and protection in explicit detail. All curve sheets shall be multi-color for improved clarity. Areas lacking complete coordination shall be highlighted and reasons provided for allowing condition to remain or provide solution to resolve situation. System coordination, recommended ratings, and setting of protective devices shall be accomplished by a registered professional electrical engineer with a minimum of eight years of current experience in the coordination of electrical power systems.

C. The following information shall be provided on all curve sheets.
   1. Device identification and associated settings/size.
   2. Voltage at which curves are plotted.

3. Current multiplier.
4. ANSI frequent fault damage curve.
5. Cable insulation damage curves.
6. Transformer inrush point.
7. Single-line for the portion of the system.
8. Motor starting profiles (where applicable).

2.3 ARC FAULT STUDY AND COORDINATION

A. The arc flash hazard analysis shall be performed according to the IEEE 1584 equations that are presented in NFPA70E, Annex D.

B. The flash protection boundary and the incident energy shall be calculated at all significant locations in the electrical distribution system (switchboards, switchgear, motor-control centers, panelboards, busway and splitters) where work could be performed on energized parts.

C. The Arc-Flash Hazard Analysis shall include all significant locations in 240 volt and 208 volt systems fed from transformers equal to or greater than 125 kVA where work could be performed on energized parts.

D. Safe working distances shall be based upon the calculated arc flash boundary considering an incident energy of 1.2 cal/cm2.

E. When appropriate, the short circuit calculations and the clearing times of the phase overcurrent devices will be retrieved from the short-circuit and coordination study model. Ground overcurrent relays should not be taken into consideration when determining the clearing time when performing incident energy calculations.

F. The short-circuit calculations and the corresponding incident energy calculations for multiple system scenarios must be compared and the greatest incident energy must be uniquely reported for each equipment location. Calculations must be performed to represent the maximum and minimum contributions of fault current magnitude for all normal and emergency operating conditions. The minimum calculation will assume that the utility contribution is at a minimum and will assume a minimum motor contribution (all motors off). Conversely, the maximum calculation will assume a maximum contribution from the utility and will assume the maximum amount of motors to be operating. Calculations shall take into consideration the parallel operation of synchronous generators with the electric utility, where applicable.

G. The incident energy calculations must consider the accumulation of energy over time when performing arc flash calculations on buses with multiple sources. Iterative calculations must take into account the changing current contributions, as the sources are interrupted or decremented with time. Fault contribution from motors and generators should be decremented as follows:

   1. Fault contribution from induction motors should not be considered beyond 3-5 cycles.

   2. Fault contribution from synchronous motors and generators should be decayed to match the actual decrement of each as closely as possible (e.g. contributions from permanent magnet generators will typically decay from 10 per unit to 3 per unit after 10 cycles).

H. For each equipment location with a separately enclosed main device (where there is adequate separation between the line side terminals of the main protective device and the work location), calculations for incident energy and flash protection boundary shall include both the line and load side of the main breaker.

I. When performing incident energy calculations on the line side of a main breaker (as required per above), the line side and load side contributions must be included in the fault calculation.

J. Mis-coordination should be checked amongst all devices within the branch containing the immediate protective device upstream of the calculation location and the calculation should utilize the fastest device to compute the incident energy for the corresponding location.

K. Arc Flash calculations shall be based on actual overcurrent protective device clearing time. Maximum clearing time will be capped at 2 seconds based on IEEE 1584-2002 section B.1.2. Where it is not physically possible to move outside of the flash protection boundary in less than 2 seconds during an arc flash event, a maximum clearing time based on the specific location shall be utilized.

2.4 SINGLE-LINE DIAGRAM

A. The final report shall include a multi-color single-line diagram of the electrical distribution system within the scope of the project. The single-line shall include:
   1. Transformer rating, voltage ratio, impedance, and winding connection.
   2. Feeder cable phase, neutral and ground sizes, length of cable, conductor material, and conduit size and type.
   3. Switchgear, switchboards, panelboards, MCC's, fuses, circuit breakers, ATS's and switches continuous current ratings.
   4. Protective relays with appropriate device numbers and CT's and PT's with associated ratios.
   5. Detailed legend indicating device type identification and other significant details.

2.5 EMERGENCY POWER SYSTEM SELECTIVE COORDINATION STUDY

A. The Emergency Power System Selective Coordination Study shall comply with all applicable NEC requirements and shall start at the electric service and emergency power source(s) and include all electrical distribution equipment protective devices to and including the final branch circuit protective devices serving applicable emergency loads. The curves and settings for the Power Company protective devises shall be included in the scope of this study. The coordination plots shall terminate with the final branch circuit protective devices serving applicable emergency loads. The protective device study shall include a separate analysis for phase and ground protection.

B. The Study shall include the following:
   1. Confirmation of selective coordination of all overcurrent devices associated with supplying utility and generator/UPS to emergency loads in accordance with all applicable requirements of NEC Article 100 and Paragraphs 700.27 and 701.18. Study shall be based on coordination to [0.1] [0.01] seconds. Study shall be based on the actual electrical equipment and overcurrent protective devices being submitted for the project.
   2. Time-current coordination plots shall be made on log-log sheets or equivalent software generated plots and shall graphically indicate the coordination proposed for all of the key systems. The plots shall include complete titles, one-line diagram and legend.
   3. Circuit breakers shall indicate manufacturer and type and have instantaneous, short delay, long-time pick-up and ground fault trip settings and ground fault ampere and time delay settings identified as plotted. Sensor or monitor rating shall be stated for each circuit breaker. All regions of the circuit breaker curve shall be identified. Circuit breaker curves shall include complete operating bands, terminating with the appropriate available short circuit current.

4. Fuses shall have fuse manufacturer and type indicated. Fuse curves shall be identified as either total clearing time or damage time as applicable.
5. High voltage relays shall indicate manufacturer and type and have coil taps, time-dial settings and pick-up settings identified as plotted. Current transformer ratios shall be stated. Relays shall be separated by a 0.45 second time margin to assure proper selectivity where feasible. The relay operating curves shall be suitably terminated to reflect the actual maximum fault current sensed by the device.
6. A summary tabulation shall be provided listing manufacturer and type for all overcurrent protective devices and all recommended settings of each adjustable band included in each device.
7. Confirmation that the proposed overcurrent protection devices, set or selected as recommended, will provide the specified selective coordination. Should the overcurrent devices proposed for the project not be capable of providing the specified selective coordination, the report shall include recommendations for overcurrent protective device changes required to provide the specified coordination and calculations, plots, recommended settings as specified herein for the recommended overcurrent device changes to provide the specified selective coordination.
8. All information shall be presented in a report form, signed and sealed by the Engineer providing the analysis.

2.6 COMPUTER SOFTWARE

B. Comply with IEEE 242, IEEE 1584, NFPA 70E, IEEE 399 and IEEE 551.

C. Retain first paragraph below if the software used for this study should have the capability of protective device coordination and arc-flash studies. See Evaluations for more information.

D. Analytical features of fault-current-study computer software program shall have the capability to calculate "mandatory," "very desirable," and "desirable" features as listed in IEEE 399.

E. Computer software program shall be capable of plotting and diagramming time-current-characteristic curves as part of its output.

PART 3 - EXECUTION

3.1 SUMMARY

A. The results of the system studies shall be summarized in a final report.

B. Where required, copies of the final report shall be submitted to the power company for their review and approval. Approved copies or the report shall be submitted to the Design Engineer.

3.2 SHORT-CIRCUIT STUDY

A Perform study following the general study procedures contained in IEEE 399.

F. Calculate short-circuit currents according to IEEE 551.

G. Base study on the device characteristics supplied by device manufacturer.

H. The extent of the electrical power system to be studied is indicated on Drawings.

I. Begin short-circuit current analysis at the service, extending down to the system overcurrent protective devices as follows:

1. To normal system low-voltage load buses where fault current is 10 kA or less.
2. Exclude equipment rated 240-V ac or less when supplied by a single transformer rated less than 125 kVA.

J. Study electrical distribution system from normal and alternate power sources throughout electrical distribution system for Project. Study all cases of system-switching configurations and alternate operations that could result in maximum fault conditions.

K. The calculations shall include the ac fault-current decay from induction motors, synchronous motors, and asynchronous generators and shall apply to low- and medium-voltage, three-phase ac systems. The calculations shall also account for the fault-current dc decrement, to address the asymmetrical requirements of the interrupting equipment.

1. For grounded systems, provide a bolted line-to-ground fault-current study for areas as defined for the three-phase bolted fault short-circuit study.

L. Calculate short-circuit momentary and interrupting duties for a three-phase bolted fault at each of the following:

1. Electric utility's supply termination point.
2. Incoming switchgear.
3. Low-voltage switchgear.
4. Motor-control centers.
5. Control panels.
6. Standby generators and automatic transfer switches.
7. Branch circuit panelboards.
8. Disconnect switches.

3.3 FIELD SETTINGS

A. The contractor shall engage the gear manufacture's service group to perform field adjustments of the protective devices as required for placing the equipment in final operating condition. The settings shall be in accordance with the approved short circuit study and protective device evaluation / coordination study.

B. Necessary field settings of devices and adjustments and minor modifications to equipment to accomplish conformance with the approved short-circuit and protective device coordination study, shall be carried out by manufacturer’s service group.

3.4 ARC FLASH WARNING LABELS

A. The contractor of the Arc Flash Hazard Analysis shall provide a 3.5 in. x 5 in. thermal transfer type label of high adhesion polyester for each work location analyzed.

B. All labels will be based on recommended overcurrent device settings and will be provided after the results of the analysis have been presented to the owner and after any system changes, upgrades or modifications have been incorporated in the system.

C. The label shall include the following information, at a minimum:

1. Location designation
2. Nominal voltage
3. Flash protection boundary
4. Hazard risk category
5. Incident energy
6. Working distance
7. Engineering report number, revision number and issue date.

D. Labels shall be machine printed, with no field markings.

E. Arc flash labels shall be provided in the following manner and all labels shall be based on recommended overcurrent device settings.

1. For each 600, 480 and applicable 208 volt panelboard, one arc flash label shall be provided.
2. For each motor control center, one arc flash label shall be provided.
3. For each low voltage switchboard, one arc flash label shall be provided.
4. For each switchgear, one flash label shall be provided.
5. For medium voltage switches one arc flash label shall be provided.

F. Labels shall be field installed by the engineering service division of the equipment manufacturer under the Startup and Acceptance Testing contract portion.

3.5 ARC FLASH TRAINING

A. The contractor of the Arc Flash Hazard Analysis shall train the owner’s qualified electrical personnel of the potential arc flash hazards associated with working on energized equipment (minimum of 4 hours). The training shall be certified for continuing education units (CEUs) by the International Association for Continuing Education Training (IACET) or equivalent.

END OF SECTION 260573

SECTION 26 09 23 – LIGHTING CONTROL DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following lighting control devices:

1. Time switches.
2. Outdoor photoelectric switches.
3. Daylight-harvesting controls.
4. Indoor occupancy sensors.
5. Lighting contactors.
6. Emergency shunt relays.

B. Related Sections include the following:
1. Division 26 Section "Wiring Devices" for wall-box dimmers, wall-switch occupancy sensors, and manual light switches.

1.3 DEFINITIONS

A. LED: Light-emitting diode.

B. PIR: Passive infrared.

1.4 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: Show installation details for occupancy and light-level sensors.

1. Interconnection diagrams showing field-installed wiring.

2. Layout of all devices on floor plan. Work to be done in electronic form such as AutoCAD. Manufacture shall provide a design to accommodate proper coverage throughout.

C. Field quality-control test reports.

D. Operation and Maintenance Data: For each type of product to include in emergency, operation, and maintenance manuals.

1.5 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Color of all wall mounted devices of this section shall match color of devices and plates of the wiring device section.

1.6 COORDINATION

A. Coordinate layout and installation of ceiling-mounted devices with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, smoke detectors, fire-suppression system, and partition assemblies.

PART 2 - PRODUCTS

2.1 TIME SWITCHES

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Grasslin Controls Corporation; a GE Industrial Systems Company.
2. Intermatic, Inc.
3. Leviton Mfg. Company Inc.
4. Lightolier Controls; a Genlyte Company.
5. Lithonia Lighting; Acuity Lighting Group, Inc.
6. Paragon Electric Co.; Invensys Climate Controls.
7. Square D; Schneider Electric.
8. TORK.
9. Touch-Plate, Inc.
10. Watt Stopper (The).

B. Electronic Time Switches: Electronic, solid-state programmable units with alphanumeric display; complying with UL 917.

1. Contact Configuration: DPDT.
2. Contact Rating: 30-A inductive or resistive, 240-V ac.
3. Program: 8 on-off set points on a 24-hour schedule and an annual holiday schedule that overrides the weekly operation on holidays.
4. Programs: 2 channels; each channel shall be individually programmable with 8 on-off set points on a 24-hour schedule.
5. Circuitry: Allow connection of a photoelectric relay as substitute for on-off function of a program on selected channels.
6. Astronomic Time: All channels.
7. Battery Backup: For schedules and time clock.

C. Electromechanical-Dial Time Switches: Type complying with UL 917.

1. Contact Configuration: DPDT.
2. Contact Rating: 30-A inductive or resistive, 240-V ac.
3. Circuitry: Allow connection of a photoelectric relay as substitute for on-off function of a program.
4. Astronomic time dial.
5. Eight-Day Program: Uniquely programmable for each weekday and holidays.
6. Skip-a-day mode.
7. Wound-spring reserve carryover mechanism to keep time during power failures, minimum of 16 hours.

2.2 OUTDOOR PHOTOELECTRIC SWITCHES

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Area Lighting Research, Inc.; Tyco Electronics.
2. Grasslin Controls Corporation; a GE Industrial Systems Company.
3. Intermatic, Inc.
4. Lithonia Lighting; Acuity Lighting Group, Inc.
5. GreenGate.
6. Paragon Electric Co.; Invensys Climate Controls.
7. Square D; Schneider Electric.
8. TORK.
9. Touch-Plate, Inc.
10. Watt Stopper (The).

B. Description: Solid state, with DPST dry contacts rated for 1800-VA tungsten or 1000-VA inductive, to operate connected relay, contactor coils, or microprocessor input; complying with UL 773A.

1. Light-Level Monitoring Range: 1.5 to 10 fc (16.14 to 108 lx), with an adjustment for turn-on and turn-off levels within that range, and a directional lens in front of photocell to prevent fixed light sources from causing turn-off.
2. Time Delay: 15-second minimum, to prevent false operation.
3. Surge Protection: Metal-oxide varistor, complying with IEEE C62.41.1, IEEE C62.41.2, and IEEE 62.45 for Category A1 locations.
4. Mounting: Twist lock complying with IEEE C136.10, with base-and-stem mounting or stem-and-swivel mounting accessories as required to direct sensor to the north sky exposure.

C. Description: Solid state, with DPST dry contacts rated for 1800 VA to operate connected load, relay, or contactor coils; complying with UL 773.

1. Light-Level Monitoring Range: 1.5 to 10 fc (16.14 to 108 lx), with an adjustment for turn-on and turn-off levels within that range.
2. Time Delay: 30-second minimum, to prevent false operation.
3. Lightning Arrester: Air-gap type.
4. Mounting: Twist lock complying with IEEE C136.10, with base.

2.3 DAYLIGHT-HARVESTING DIMMING CONTROLS

A. Available Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Hubbell Lighting.
2. Leviton Mfg. Company Inc.
3. Lithonia Lighting; Acuity Lighting Group, Inc.
4. GreenGate.
5. Sensor Switch, Inc.
6. Watt Stopper (The).

B. Description: Sensing daylight and electrical lighting levels, the system adjusts the indoor electrical lighting levels. As daylight increases, the lights are dimmed.

1. Lighting control set point is based on two lighting conditions:

a. When no daylight is present (target level).
b. When significant daylight is present.

2. System programming is done with two hand-held, remote-control tools.

a. Initial setup tool.
b. Tool for occupants to adjust the target levels by increasing the set point up to 25 percent, or by minimizing the electric lighting level.

C. Ceiling-Mounted Dimming Controls: Solid-state, light-level sensor unit, with power pack, to detect changes in indoor lighting levels that are perceived by the eye.

D. Electrical Components, Devices, and Accessories:

1. Listed and labeled in accordance with NFPA 70, by a qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
2. Sensor Output: zero to 10 V dc to operate luminaires. Sensor is powered by switch/controller.
3. Light-Level Sensor Set-Point Adjustment Range: 20 to 60 fc (120 to 640 lx).

E. Relay Unit:
1. Analog System: Dry contacts rated for 20 A LED load at 120 and 277 V ac, for 13 A tungsten at 120 V(ac), and for 1 hp at 120 V ac. Sensor has 24 V dc, 150 mA, Class 2 power source.
   a. Plenum rated.
2. Digital System: Digital controller capable of accepting three or four 8PSJ inputs with two outputs rated for 20 A incandescent or LED load at 120 and 277 V ac , for 16 A LED at 120 and 277 V ac, and for 1 hp at 120 Vac. Sensor has 24 V(dc) Class 2 power source.
   a. With integral current monitoring.
   b. Compatible with digital addressable lighting interface.
   c. Plenum rated.

2.4 INDOOR OCCUPANCY AND VACANCY SENSORS

A. Available Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Hubbell Lighting.
2. Leviton Mfg. Company Inc.
3. Lithonia Lighting; Acuity Lighting Group, Inc.
4. GreenGate.
5. Sensor Switch, Inc.
6. Watt Stopper (The).

B. General Requirements for Sensors:

1. Wall- or Ceiling-mounted, solid-state indoor occupancy and vacancy sensors.
2. Separate relay unit.
3. Listed and labeled in accordance with NFPA 70, by a qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
4. Operation:

    a. Occupancy Sensor: Unless otherwise indicated, turn lights on when coverage area is occupied, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
    b. Vacancy Sensor: Unless otherwise indicated, lights are manually turned on and sensor turns lights off when the room is unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
    c. Combination Sensor: Unless otherwise indicated, sensor must be programmed to turn lights on when coverage area is occupied and turn them off when unoccupied, or to turn off lights that have been manually turned on; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
5. Sensor Output: Contacts rated to operate the connected relay, complying with UL 773A. Sensor shall be powered from the relay unit.
6. Relay Unit: Dry contacts rated for 20-A ballast or LED load at 120- and 277-V ac, for 13-A tungsten at 120-V ac, and for 1 hp at 120-V ac. Power supply to sensor shall be 24-V dc, 150-mA, Class 2 power source as defined by NFPA 70.
7. Mounting:

    a. Sensor: Suitable for mounting in any position on a standard outlet box.
    b. Relay: Externally mounted through a 1/2-inch (13-mm) knockout in a standard electrical enclosure.
    c. Time-Delay and Sensitivity Adjustments: Recessed and concealed behind hinged door.

8. Indicator: LED, to show when motion is being detected during testing and normal operation of the sensor.
9. Bypass Switch: Override the “on” function in case of sensor failure.
10. Automatic Light-Level Sensor: Adjustable from 2 to 200 fc (21.5 to 2152 lx); turn lights off when selected lighting level is present.
11. Wall mounted devices color shall match color selected for switches and receptacles. Refer to other sections in specifications.

12. Meet Nema WD 7-2011 requirements.

C. PIR Type: Ceiling-mounting; detect occupancy by sensing a combination of heat and movement in area of coverage.

1. Detector Sensitivity: Detect occurrences of 6-inch- (150-mm-) minimum movement of any portion of a human body that presents a target of not less than 36 sq. in. (232 sq. cm).
2. Detection Coverage (Room): Detect occupancy anywhere in a circular area of 1000 sq. ft. (93 sq. m) when mounted on a 96-inch- (2440-mm-) high ceiling.
3. Detection Coverage (Corridor): Detect occupancy within 90 feet (27.4 m) when mounted on a 10-foot- (3-m-) high ceiling.

D. Ultrasonic Type: Ceiling mounting; detect occupancy by sensing a change in pattern of reflected ultrasonic energy in area of coverage.

1. Detector Sensitivity: Detect a person of average size and weight moving not less than 12 inches (305 mm) in either a horizontal or a vertical manner at an approximate speed of 12 inches/s (305 mm/s).
2. Detection Coverage (Small Room): Detect occupancy anywhere within a circular area of 600 sq. ft. (56 sq. m) when mounted on a 96-inch- (2440-mm-) high ceiling.
3. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. (93 sq. m) when mounted on a 96-inch- (2440-mm-) high ceiling.
4. Detection Coverage (Large Room): Detect occupancy anywhere within a circular area of 2000 sq. ft. (186 sq. m) when mounted on a 96-inch- (2440-mm-) high ceiling.
5. Detection Coverage (Corridor): Detect occupancy anywhere within 90 feet (27.4 m) when mounted on a 10-foot- (3-m-) high ceiling in a corridor not wider than 14 feet (4.3 m).

E. Dual-Technology Type: Ceiling-mounting; detect occupancy by using a combination of PIR and ultrasonic detection methods in area of coverage. The particular technology or combination of technologies that controls on-off functions shall be selectable in the field by operating controls on unit.

1. Sensitivity Adjustment: Separate for each sensing technology.
2. Detector Sensitivity: Detect occurrences of 6-inch- (150-mm-) minimum movement of any portion of a human body that presents a target of not less than 36 sq. in. (232 sq. cm), and detect a person of average size and weight moving not less than 12 inches (305 mm) in either a horizontal or a vertical manner at an approximate speed of 12 inches/s (305 mm/s).
3. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. (93 sq. m) when mounted on a 96-inch- (2440-mm-) high ceiling.

F. System and Design Requirements:
1. Products supplied shall be from a single manufacturer that has been continuously involved in manufacturing of occupancy sensors for a minimum of five (5) years. Mixing of manufacturers shall not be allowed.
2. All components shall be U.L. listed, offer a five (5) year warranty and meet all state and local applicable code requirements.
3. Products shall be manufactured by an ISO 9002 certified manufacturing facility and shall have a defect rate of less than 1/3 of 1%.

4. The objective of this section is to ensure the proper installation of the occupancy sensor based lighting control system so that lighting is turned off automatically after reasonable time delay when a room or area is vacated by the last person to occupy said room or area.
5. The occupancy sensor based lighting control shall accommodate all conditions of space utilization and all irregular work hours and habits
6. Where specified, sensor shall have an internal additional isolated relay with Normally Open, Normally Closed and Common outputs for use with HVAC control, Data Logging and other control options. Sensors utilizing separate components or specially modified units to achieve this function are not acceptable.
7. Meet Nema WD 7-2011 requirements.

2.5 LIGHTING CONTACTORS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Allen-Bradley/Rockwell Automation.
2. ASCO Power Technologies, LP; a division of Emerson Electric Co.
3. Eaton Electrical Inc.; Cutler-Hammer Products.
4. GE Industrial Systems; Total Lighting Control.
5. Grasslin Controls Corporation; a GE Industrial Systems Company.
6. Hubbell Lighting.
7. Lithonia Lighting; Acuity Lighting Group, Inc.
8. MicroLite Lighting Control Systems.
9. Square D; Schneider Electric.
10. TORK.
11. Touch-Plate, Inc.
12. Watt Stopper (The).
13. Siemens

B. Description: Electrically operated and mechanically held, combination type with nonfused disconnect, complying with NEMA ICS 2 and UL 508.

1. Current Rating for Switching: Listing or rating consistent with type of load served, including tungsten filament, inductive, and high-inrush ballast (ballast with 15 percent or less total harmonic distortion of normal load current).
2. Fault Current Withstand Rating: Equal to or exceeding the available fault current at the point of installation.
3. Enclosure: Comply with NEMA 250.
4. Provide with control and pilot devices as indicated on Drawings, matching the NEMA type specified for the enclosure.

2.6 CONDUCTORS AND CABLES

A. Power Wiring to Supply Side of Remote-Control Power Sources: Not smaller than No. 12 AWG. Comply with requirements in Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

B. Classes 2 and 3 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 18 AWG. Comply with requirements in Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

C. Class 1 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 18 AWG. Comply with requirements in Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

PART 3 - EXECUTION

3.1 SENSOR INSTALLATION

A. It shall be the contractor's responsibility to locate and aim sensors in the correct location required for complete and proper volumetric coverage within the range of coverage(s) of controlled areas per the manufacturer's recommendations. Rooms shall have ninety (90) to one hundred (100) percent coverage to completely cover the controlled area to accommodate all occupancy habits of single or multiple occupants at any location within the room(s). The drawings indicate only the rooms which are to be provided with sensors. The contractor shall provide sensors as required to properly and completely cover the respective room.

B. It is the contractor’s responsibility to arrange a pre-installation meeting with manufacturer's factory authorized representative, at owner's facility, to verify placement of sensors and installation criteria.

C. It is the contractor’s responsibility to arrange a pre-installation meeting with manufacturer's factory authorized representative, at owner's facility, to verify placement of sensors and installation criteria.

D. Contractor's work to include all labor, materials, tools, appliances, control hardware, sensor, wire, junction boxes and equipment necessary for and incidental to the delivery, installation and furnishing of a completely operational occupancy sensor lighting control system, as described herein. Drawings may indicate the room in which occupancy sensor control is required. The contractor and manufacture shall provide a device to provide proper coverage of the area.

3.2 CONTACTOR INSTALLATION

A. Mount electrically held lighting contactors with elastomeric isolator pads, to eliminate structure-borne vibration, unless contactors are installed in an enclosure with factory-installed vibration isolators.

3.3 WIRING INSTALLATION

A. Wiring Method: Comply with Division 26 Section "Low-Voltage Electrical Power Conductors and Cables." Minimum conduit size shall be 1/2 inch (13 mm).

B. Wiring within Enclosures: Comply with NECA 1. Separate power-limited and nonpower-limited conductors according to conductor manufacturer's written instructions.

C. Size conductors according to lighting control device manufacturer's written instructions, unless otherwise indicated.

D. Splices, Taps, and Terminations: Make connections only on numbered terminal strips in junction, pull, and outlet boxes; terminal cabinets; and equipment enclosures.

3.4 IDENTIFICATION

A. Identify components and power and control wiring according to Division 26 Section "Identification for Electrical Systems."

1. Identify controlled circuits in lighting contactors.
2. Identify circuits or luminaries controlled by photoelectric and occupancy sensors at each sensor.

B. Label time switches and contactors with a unique designation.

3.5 FIELD QUALITY CONTROL

A. Perform the following field tests and inspections and prepare test reports:

1. After installing time switches and sensors, and after electrical circuitry has been energized, adjust and test for compliance with requirements.
2. Operational Test: Verify operation of each lighting control device, and adjust time delays.

B. Lighting control devices that fail tests and inspections are defective work.

C. Upon completion of the installation, the system shall be completely commissioned by the manufacturer's factory authorized technician who will verify all adjustments and sensor placement to ensure a trouble-free occupancy-based lighting control system.

3.6 ADJUSTING

A. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting sensors to suit occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.7 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain lighting control devices. Refer to Division 01 Section "Demonstration and Training."

END OF SECTION 26 09 23

SECTION 26 24 16 – PANELBOARDS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Distribution panelboards.
2. Lighting and appliance branch-circuit panelboards.
3. Load centers.

1.3 DEFINITIONS

A. ATS: Acceptance testing specification.

B. GFCI: Ground-fault circuit interrupter.

C. GFEP: Ground-fault equipment protection.

D. HID: High-intensity discharge.

E. MCCB: Molded-case circuit breaker.

F. VPR: Voltage protection rating.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of panelboard.

1. Include materials, switching and overcurrent protective devices, accessories, and components indicated.
2. Include dimensions and manufacturers' technical data on features, performance, electrical characteristics, ratings, and finishes.

B. Shop Drawings: For each panelboard and related equipment.

1. Include dimensioned plans, elevations, sections, and details.
2. Show tabulations of installed devices with nameplates, conductor termination sizes, equipment features, and ratings.

3. Detail enclosure types including mounting and anchorage, environmental protection, knockouts, corner treatments, covers and doors, gaskets, hinges, and locks.
4. Detail bus configuration, current, and voltage ratings.
5. Short-circuit current rating of panelboards and overcurrent protective devices.
6. Include evidence of NRTL listing for series rating of installed devices.
7. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices and auxiliary components.
8. Include wiring diagrams for power, signal, and control wiring.
9. Key interlock scheme drawing and sequence of operations.
10. Include time-current coordination curves for each type and rating of overcurrent protective device included in panelboards. Submit on translucent log-log graft paper; include selectable ranges for each type of overcurrent protective device. Include an Internet link for electronic access to downloadable PDF of the coordination curves.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For testing agency.

B. Panelboard Schedules: For installation in panelboards. Submit final versions after load balancing.

1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For panelboards and components to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 01 78 23 "Operation and Maintenance Data," include the following:

1. Manufacturer's written instructions for testing and adjusting overcurrent protective devices.
2. Time-current curves, including selectable ranges for each type of overcurrent protective device that allows adjustments.

1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Keys: Two spares for each type of panelboard cabinet lock.
2. Fuses for Fused Switches: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.
3. Fuses for Fused Power-Circuit Devices: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.

1.8 QUALITY ASSURANCE

A. Manufacturer Qualifications: ISO 9001 or 9002 certified.

1.9 DELIVERY, STORAGE, AND HANDLING

A. Remove loose packing and flammable materials from inside panelboards; install temporary electric heating (250 W per panelboard) to prevent condensation.

B. Handle and prepare panelboards for installation according to NECA 407.

1.10 FIELD CONDITIONS

A. Environmental Limitations:

1. Do not deliver or install panelboards until spaces are enclosed and weathertight, wet work in spaces is complete and dry, work above panelboards is complete, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.
2. Rate equipment for continuous operation under the following conditions unless otherwise indicated:

a. Ambient Temperature: Not exceeding 23 deg F to plus 104 deg F.
b. Altitude: Not exceeding 6600 feet.

B. Service Conditions: NEMA PB 1, usual service conditions, as follows:

1. Ambient temperatures within limits specified.
2. Altitude not exceeding 6600 feet.

C. Interruption of Existing Electric Service: Do not interrupt electric service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary electric service according to requirements indicated:

1. Notify Architect no fewer than two days in advance of proposed interruption of electric service.
2. Do not proceed with interruption of electric service without Architect's written permission.
3. Comply with NFPA 70E.

1.11 WARRANTY

A. Manufacturer's Warranty: Manufacturer agrees to repair or replace panelboards that fail in materials or workmanship within specified warranty period.

1. Panelboard Warranty Period: 18 months from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PANELBOARDS AND LOAD CENTERS COMMON REQUIREMENTS

A. Fabricate and test panelboards according to IEEE 344 to withstand seismic forces defined in Section 26 05 48.16 "Seismic Controls for Electrical Systems."

B. Product Selection for Restricted Space: Drawings indicate maximum dimensions for panelboards including clearances between panelboards and adjacent surfaces and other items. Comply with indicated maximum dimensions.

C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

D. Comply with NEMA PB 1.

E. Comply with NFPA 70.

F. Enclosures: Flush and Surface-mounted, dead-front cabinets.

1. Rated for environmental conditions at installed location.

    a. Indoor Dry and Clean Locations: NEMA 250, Type 1.
    b. Outdoor Locations: NEMA 250, Type 3R.
    c. Kitchen and Wash-Down Areas: NEMA 250, Type 4X, stainless steel.
    d. Other Wet or Damp Indoor Locations: NEMA 250, Type 4.
    e. Indoor Locations Subject to Dust, Falling Dirt, and Dripping Noncorrosive Liquids: NEMA 250, Type 5.

2. Height: 84 inches maximum.
3. Front: Secured to box with concealed trim clamps. For surface-mounted fronts, match box dimensions; for flush-mounted fronts, overlap box. Trims shall cover all live parts and shall have no exposed hardware.
4. Hinged Front Cover: Entire front trim hinged to box and with standard door within hinged trim cover. Trims shall cover all live parts and shall have no exposed hardware.
5. Gutter Extension and Barrier: Same gage and finish as panelboard enclosure; integral with enclosure body. Arrange to isolate individual panel sections.
6. Finishes:

    a. Panels and Trim: Steel and galvanized steel, factory finished immediately after cleaning and pretreating with manufacturer's standard two-coat, baked-on finish consisting of prime coat and thermosetting topcoat.
    b. Back Boxes: Galvanized steel.

G. Incoming Mains:

1. Location: Convertible between top and bottom.
2. Main Breaker: Main lug interiors up to 400 amperes shall be field convertible to main breaker.

H. Phase, Neutral, and Ground Buses:

1. Material: Hard-drawn copper, 98 percent conductivity.

   a. Plating shall run entire length of bus.
   b. Bus shall be fully rated the entire length.

2. Interiors shall be factory assembled into a unit. Replacing switching and protective devices shall not disturb adjacent units or require removing the main bus connectors.
3. Equipment Ground Bus: Adequate for feeder and branch-circuit equipment grounding conductors; bonded to box.
4. Isolated Ground Bus: Adequate for branch-circuit isolated ground conductors; insulated from box.
5. Full-Sized Neutral: Equipped with full-capacity bonding strap for service entrance applications. Mount electrically isolated from enclosure. Do not mount neutral bus in gutter.
6. Split Bus: Vertical buses divided into individual vertical sections.

I. Conductor Connectors: Suitable for use with conductor material and sizes.

1. Material: Hard-drawn copper, 98 percent conductivity.
2. Terminations shall allow use of 75 deg C rated conductors without derating.
3. Size: Lugs suitable for indicated conductor sizes, with additional gutter space, if required, for larger conductors.
4. Main and Neutral Lugs: Mechanical type, with a lug on the neutral bar for each pole in the panelboard.
5. Ground Lugs and Bus-Configured Terminators: Mechanical type, with a lug on the bar for each pole in the panelboard.
6. Feed-Through Lugs: Mechanical type, suitable for use with conductor material. Locate at opposite end of bus from incoming lugs or main device.
7. Subfeed (Double) Lugs: Mechanical type suitable for use with conductor material. Locate at same end of bus as incoming lugs or main device.
8. Gutter-Tap Lugs: Mechanical type suitable for use with conductor material and with matching insulating covers. Locate at same end of bus as incoming lugs or main device.

J. NRTL Label: Panelboards or load centers shall be labeled by an NRTL acceptable to authority having jurisdiction for use as service equipment with one or more main service disconnecting and overcurrent protective devices. Panelboards or load centers shall have meter enclosures, wiring, connections, and other provisions for utility metering. Coordinate with utility company for exact requirements.

K. Future Devices: Panelboards or load centers shall have mounting brackets, bus connections, filler plates, and necessary appurtenances required for future installation of devices.

1. Percentage of Future Space Capacity: 20 percent.

L. Panelboard Short-Circuit Current Rating: Fully rated to interrupt symmetrical short-circuit current available at terminals. Assembly listed by an NRTL for 100 percent interrupting capacity.

1. Panelboards and overcurrent protective devices rated 240 V or less shall have short-circuit ratings as shown on Drawings, but not less than 10,000 A rms symmetrical.
2. Panelboards and overcurrent protective devices rated above 240 V and less than 600 V shall have short-circuit ratings as shown on Drawings, but not less than 14,000 A rms symmetrical.

2.2 POWER PANELBOARDS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Eaton.
2. General Electric Company; GE Energy Management - Electrical Distribution.
3. Siemens Industry, Inc., Energy Management Division.
4. Square D; by Schneider Electric.

B. Panelboards: NEMA PB 1, distribution type.

C. Doors: Secured with vault-type latch with tumbler lock; keyed alike.

1. For doors more than 36 inches high, provide two latches, keyed alike.

D. Mains: As per schedule

E. Branch Overcurrent Protective Devices for Circuit-Breaker Frame Sizes 125 A and Smaller: Bolt-on circuit breakers.

F. Branch Overcurrent Protective Devices for Circuit-Breaker Frame Sizes Larger Than 125 A: Bolt-on electronic circuit breakers.

2.3 LIGHTING AND APPLIANCE BRANCH-CIRCUIT PANELBOARDS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Eaton.
2. General Electric Company; GE Energy Management - Electrical Distribution.
3. Siemens Industry, Inc., Energy Management Division.
4. Square D; by Schneider Electric.

B. Panelboards: NEMA PB 1, lighting and appliance branch-circuit type.

C. Mains: As indicated on the schedules.

D. Branch Overcurrent Protective Devices: Bolt-on circuit breakers, replaceable without disturbing adjacent units.

E. Doors: Door-in-door construction with concealed hinges; secured with multipoint latch with tumbler lock; keyed alike. Outer door shall permit full access to the panel interior. Inner door

shall permit access to breaker operating handles and labeling, but current carrying terminals and bus shall remain concealed.

F. Column-Type Panelboards: Single row of overcurrent devices with narrow gutter extension and overhead junction box equipped with ground and neutral terminal buses.

1. Doors: Concealed hinges secured with multipoint latch with tumbler lock; keyed alike.

2.4 DISCONNECTING AND OVERCURRENT PROTECTIVE DEVICES

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Eaton.
2. General Electric Company; GE Energy Management - Electrical Distribution.
3. Siemens Industry, Inc., Energy Management Division.
4. Square D; by Schneider Electric.

B. MCCB: Comply with UL 489, with interrupting capacity to meet available fault currents.

1. Thermal-Magnetic Circuit Breakers:

a. Inverse time-current element for low-level overloads.
b. Instantaneous magnetic trip element for short circuits.
c. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.

2. Adjustable Instantaneous-Trip Circuit Breakers: Magnetic trip element with front-mounted, field-adjustable trip setting.
3. Electronic Trip Circuit Breakers:

a. RMS sensing.
b. Field-replaceable rating plug or electronic trip.
c. Digital display of settings, trip targets, and indicated metering displays.
d. Multi-button keypad to access programmable functions and monitored data.
e. Ten-event, trip-history log. Each trip event shall be recorded with type, phase, and magnitude of fault that caused the trip.
f. Integral test jack for connection to portable test set or laptop computer.
g. Field-Adjustable Settings:

1) Instantaneous trip.
2) Long- and short-time pickup levels.
3) Long and short time adjustments.
4) Ground-fault pickup level, time delay, and I squared T response.

4. Current-Limiting Circuit Breakers: Frame sizes 400 A and smaller; let-through ratings less than NEMA FU 1, RK-5.
5. GFCI Circuit Breakers: Single- and double-pole configurations with Class A ground-fault protection (6-mA trip).
6. GFEP Circuit Breakers: Class B ground-fault protection (30-mA trip).

7. Arc-Fault Circuit Interrupter Circuit Breakers: Comply with UL 1699; 120/240-V, single-pole configuration.
8. Subfeed Circuit Breakers: Vertically mounted.
9. MCCB Features and Accessories:

    a. Standard frame sizes, trip ratings, and number of poles.
    b. Breaker handle indicates tripped status.
    c. UL listed for reverse connection without restrictive line or load ratings.
    d. Lugs: Mechanical style, suitable for number, size, trip ratings, and conductor materials.
    e. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HID for feeding fluorescent and HID lighting circuits.
    f. Ground-Fault Protection: Integrally mounted relay and trip unit with adjustable pickup and time-delay settings, push-to-test feature, and ground-fault indicator.
    g. Communication Capability: Circuit-breaker-mounted communication module with functions and features compatible with power monitoring and control system specified in Section 26 09 13 "Electrical Power Monitoring and Control."
    h. Shunt Trip: 120-V trip coil energized from separate circuit, set to trip at 55 percent of rated voltage.
    i. Auxiliary Contacts: Two, SPDT switches with "a" and "b" contacts; "a" contacts mimic circuit-breaker contacts and "b" contacts operate in reverse of circuit-breaker contacts.
    j. Alarm Switch: Single-pole, normally open contact that actuates only when circuit breaker trips.
    k. Key Interlock Kit: Externally mounted to prohibit circuit-breaker operation; key shall be removable only when circuit breaker is in off position.
    l. Zone-Selective Interlocking: Integral with electronic trip unit; for interlocking ground-fault protection function with other upstream or downstream devices.
    m. Handle Padlocking Device: Fixed attachment, for locking circuit-breaker handle in on or off position.

C. Fused Switch: NEMA KS 1, Type HD; clips to accommodate specified fuses; lockable handle.

1. Fuses and Spare-Fuse Cabinet: Comply with requirements specified in Section 26 28 13 "Fuses."
2. Fused Switch Features and Accessories:

    a. Standard ampere ratings and number of poles.
    b. Mechanical cover interlock with a manual interlock override, to prevent the opening of the cover when the switch is in the on position. The interlock shall prevent the switch from being turned on with the cover open. The operating handle shall have lock-off means with provisions for three padlocks.

2.5 IDENTIFICATION

A. Panelboard Label: Manufacturer's name and trademark, voltage, amperage, number of phases, and number of poles shall be located on the interior of the panelboard door.

B. Breaker Labels: Faceplate shall list current rating, UL and IEC certification standards, and AIC rating.

C. Circuit Directory: Directory card inside panelboard door, mounted in metal frame with transparent protective cover. Typed written.

1. Circuit directory shall identify specific purpose with detail sufficient to distinguish it from all other circuits.

D. Circuit Directory: Computer-generated circuit directory mounted inside panelboard door with transparent plastic protective cover.

1. Circuit directory shall identify specific purpose with detail sufficient to distinguish it from all other circuits.

2.6 ACCESSORY COMPONENTS AND FEATURES

A. Accessory Set: Include tools and miscellaneous items required for overcurrent protective device test, inspection, maintenance, and operation.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify actual conditions with field measurements prior to ordering panelboards to verify that equipment fits in allocated space in, and comply with, minimum required clearances specified in NFPA 70.

B. Receive, inspect, handle, and store panelboards according to NECA 407.

C. Examine panelboards before installation. Reject panelboards that are damaged, rusted, or have been subjected to water saturation.

D. Examine elements and surfaces to receive panelboards for compliance with installation tolerances and other conditions affecting performance of the Work.

E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Coordinate layout and installation of panelboards and components with other construction that penetrates walls or is supported by them, including electrical and other types of equipment, raceways, piping, encumbrances to workspace clearance requirements, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

B. Comply with NECA 1.

C. Install panelboards and accessories according to NECA 407.

D. Equipment Mounting:

1. Install panelboards on cast-in-place concrete equipment base(s). Comply with requirements for equipment bases and foundations specified in Section 03 30 00 "Cast-in-Place Concrete."
2. Attach panelboard to the vertical finished or structural surface behind the panelboard.
3. Comply with requirements for seismic control devices specified in Section 26 05 48.16 "Seismic Controls for Electrical Systems."

E. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, and brackets and temporary blocking of moving parts from panelboards.

F. Comply with mounting and anchoring requirements specified in Section 26 05 48.16 "Seismic Controls for Electrical Systems."

G. Mount panelboard cabinet plumb and rigid without distortion of box.

H. Mount recessed panelboards with fronts uniformly flush with wall finish and mating with back box.

I. Install overcurrent protective devices and controllers not already factory installed.

1. Set field-adjustable, circuit-breaker trip ranges.
2. Tighten bolted connections and circuit breaker connections using calibrated torque wrench or torque screwdriver per manufacturer's written instructions.

J. Make grounding connections and bond neutral for services and separately derived systems to ground. Make connections to grounding electrodes, separate grounds for isolated ground bars, and connections to separate ground bars.

K. Install filler plates in unused spaces.

L. Stub four 1-inch empty conduits from panelboard into accessible ceiling space or space designated to be ceiling space in the future. Stub four 1-inch empty conduits into raised floor space or below slab not on grade.

M. Arrange conductors in gutters into groups and bundle and wrap with wire ties after completing load balancing.

N. Mount spare fuse cabinet in accessible location.

3.3 IDENTIFICATION

A. Identify field-installed conductors, interconnecting wiring, and components; install warning signs complying with requirements in Section 26 05 53 "Identification for Electrical Systems."

B. Create a directory to indicate installed circuit loads after balancing panelboard loads; incorporate Owner's final room designations. Obtain approval before installing. Handwritten directories are not acceptable. Install directory inside panelboard door.

C. Panelboard Nameplates: Label each panelboard with a nameplate complying with requirements for identification specified in Section 26 05 53 "Identification for Electrical Systems."

D. Device Nameplates: Label each branch circuit device in power panelboards with a nameplate complying with requirements for identification specified in Section 26 05 53 "Identification for Electrical Systems."

E. Install warning signs complying with requirements in Section 26 05 53 "Identification for Electrical Systems" identifying source of remote circuit.

3.4 FIELD QUALITY CONTROL

A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections.

B. Perform tests and inspections.

1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.

C. Acceptance Testing Preparation:

1. Test insulation resistance for each panelboard bus, component, connecting supply, feeder, and control circuit.
2. Test continuity of each circuit.

D. Tests and Inspections:

1. Perform each visual and mechanical inspection and electrical test for low-voltage air circuit breakers stated in NETA ATS, Paragraph 7.6 Circuit Breakers. Certify compliance with test parameters.
2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
3. Perform the following infrared scan tests and inspections and prepare reports:

a. Initial Infrared Scanning: After Substantial Completion, but not more than 60 days after Final Acceptance, perform an infrared scan of each panelboard. Remove front panels so joints and connections are accessible to portable scanner.
b. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each panelboard 11 months after date of Substantial Completion.
c. Instruments and Equipment:

1) Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.

E. Panelboards will be considered defective if they do not pass tests and inspections.

F. Prepare test and inspection reports, including a certified report that identifies panelboards included and that describes scanning results, with comparisons of the two scans. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3.5 ADJUSTING

A. Adjust moving parts and operable components to function smoothly, and lubricate as recommended by manufacturer.

B. Set field-adjustable circuit-breaker trip ranges as specified in Section 26 05 73.16 "Coordination Studies."

C. Load Balancing: After Substantial Completion, but not more than 60 days after Final Acceptance, measure load balancing and make circuit changes. Prior to making circuit changes to achieve load balancing, inform Architect of effect on phase color coding.

1. Measure loads during period of normal facility operations.
2. Perform circuit changes to achieve load balancing outside normal facility operation schedule or at times directed by the Architect. Avoid disrupting services such as fax machines and on-line data processing, computing, transmitting, and receiving equipment.
3. After changing circuits to achieve load balancing, recheck loads during normal facility operations. Record load readings before and after changing circuits to achieve load balancing.
4. Tolerance: Maximum difference between phase loads, within a panelboard, shall not exceed 20 percent.

3.6 PROTECTION

A. Temporary Heating: Prior to energizing panelboards, apply temporary heat to maintain temperature according to manufacturer's written instructions.

END OF SECTION 26 24 16

SECTION 26 27 26 – WIRING DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:

1. Single and duplex receptacles, ground-fault circuit interrupters and isolated-ground receptacles.
2. Single- and double-pole snap switches.
3. Device wall plates.
4. Pin and sleeve connectors and receptacles.
5. Floor service outlets, poke-through assemblies, service poles, and multioutlet assemblies.

1.3 DEFINITIONS

A. EMI: Electromagnetic interference.

B. GFCI: Ground-fault circuit interrupter.

C. PVC: Polyvinyl chloride.

D. RFI: Radio-frequency interference.

E. TVSS: Transient voltage surge suppressor.

F. UTP: Unshielded twisted pair.

1.4 SUBMITTALS

A. Product Data: For each type of product indicated.

1. Receptacles, switches, plates, floor outlets, poke through assemblies, service poles and multioutlet assemblies.

1.5 QUALITY ASSURANCE

A. Source Limitations: Obtain each type of wiring device through one source from a single manufacturer.

B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

C. Comply with NFPA 70 latest edition or edition enforced by state or local code authority.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Outlets - Duplex:
   a. Hubbell Incorporated- HBL 5362.
   b. Leviton Mfg. Company Inc.-5362.
   c. Pass & Seymour-CRB5362.
   d. Pass & Seymour -PT5362A (Plug Tail Device).

2. Switches-Single Pole:
   a. Hubbell Incorporated - HBL 1221.
   b. Pass & Seymour - PS20AC1.
   c. Leviton Mfg. Company, Inc.- 1221-1

3. Switches-Three Pole:
   a. Hubbell Incorporated - HBL1223
   b. Leviton Mfg. Company, Inc.-1223-2.
   c. Pass & Seymour-PS20AC3.

4. Dimmer Switches Line Voltage:
   a. Lutron Nova T
   b. Pass & Seymour CD2000

* Dimmer must be compatible with Ballast or LED Driver.

5. Dimmer Switches 0-10V:
   a. Synergy ISD
   b. Cooper SF10P

* Dimmer must be compatible with Ballast or LED Driver.

6. GFI Receptacles: Weather Resistant:
   a. Hubbell Incorporated - GFWRST20
   b. Leviton Mfg. Company Inc.-GFWR2
   c. Pass & Seymour- 2097TRWR

7. GFI Receptacles: Weather Resistant and Tamper Resistant:
   a. Hubbell Incorporated - GFTWRST20
   b. Leviton Mfg. Company Inc.-GFWT2
   c. Pass & Seymour- 2097TRWR

8. Receptacles: Tamper Resistant:
   a. Hubbell Incorporated - BR20TR.
   b. Leviton Mfg. Company Inc.-TBR20
   c. Pass & Seymour- TR5362.

9. USB Charger Duplex Receptacles:
   a. Hubbell Incorporated – USB20AC
   b. Leviton – T5833

2.2 RECEPTACLES

A. Straight-Blade-Type Receptacles: Comply with UL 498, 20 amp.

B. Straight-Blade and Locking Receptacles: Heavy-Duty grade 20 amp.

C. GFCI Receptacles: Straight blade, feed-through type, Heavy-Duty grade, with integral NEMA WD 6, Configuration 5-20R duplex receptacle; complying with UL 498 and UL 943. Design units for installation in a 2-3/4-inch- (70-mm-) deep outlet box without an adapter.

2.3 CORD AND PLUG SETS

A. Description: Match voltage and current ratings and number of conductors to requirements of equipment being connected.

1. Cord: Rubber-insulated, stranded-copper conductors, with Type SOW-A jacket; with green-insulated grounding conductor and equipment-rating ampacity plus a minimum of 30 percent.
2. Plug: Nylon body and integral cable-clamping jaws. Match cord and receptacle type for connection.

2.4 SWITCHES

A. Single- and Double-Pole Switches: Comply with UL 20, 20 amp.

B. Snap Switches: Heavy-Duty grade, quiet type 20 amp, 120/277 volt.

C. Line Voltage Dimmer: 120V, 2000 watt, slide to-off. Dimmer must be compatible with ballast or driver.

D. 0-10V Dimmer: 120/277VAC, capable of three way, max wattage 1200 w 120VAC, 150000 277 VAC, Dimmer must be compatible with ballast or driver. 100% to 1% continuous.

2.5 WALL PLATES

A. Single and combination types to match corresponding wiring devices.

1. Plate-Securing Screws: Metal with head color to match plate finish.
2. Material for Finished Spaces: **As selected by Architect**.
3. Material for Unfinished Spaces: Galvanized steel.
4. Material for Wet Locations: Heavy duty die-cast metal, gasketed with powdercoat finish and lockable tab. Listed and labeled “extra duty”, “in-use”, for use in "wet locations”.

2.6 POKE-THROUGH ASSEMBLIES

A. Description: Factory-fabricated and -wired assembly of below-floor junction box with multi-channeled, through-floor raceway/firestop unit and detachable matching floor service outlet assembly.

1. Service Outlet Assembly: Recessed type with three (3) compartments that allow for up to three (3) duplex receptacles and/or 12 communication ports and/or 10 AV devices.
2. Size: Selected to fit nominal 6-inch (100-mm) cored holes in floor and matched to floor thickness.
3. Fire Rating: Unit is listed and labeled for fire rating of floor-ceiling assembly.
4. Wiring Raceways and Compartments: For a minimum of four No. 12 AWG conductors; and a minimum of four, 4-pair, Category 6 voice and data communication cables.

2.7 FINISHES

A. Color:

1. Wiring Devices Connected to Normal Power System: As selected by Architect, unless otherwise indicated or required by NFPA 70.2.
2. Wiring Devices Connected to Emergency Power System: Red.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install devices and assemblies level, plumb, and square with building lines.

B. Arrangement of Devices: Unless otherwise indicated, mount flush, with long dimension vertical, and with grounding terminal of receptacles on top. Group adjacent switches under single, multigang wall plates.

C. Remove wall plates and protect devices and assemblies during painting.

D. Adjust locations of floor service outlets and service poles to suit arrangement of partitions and furnishings.

E. Install weather resistant receptacles in damp and wet locations per N.E.C. requirements.

F. Install tamper resistant receptacles in homes, apartments, hotel rooms and daycares per N.E.C. requirements.

3.2 CONNECTIONS

A. Ground equipment according to Division 16 Section "Grounding and Bonding."

B. Connect wiring according to Division 16 Section "Conductors and Cables."

C. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values.

3.3 FIELD QUALITY CONTROL

A. Perform the following field tests and inspections and prepare test reports:

1. After installing wiring devices and after electrical circuitry has been energized, test for proper polarity, ground continuity, and compliance with requirements.
2. Test GFCI operation with both local and remote fault simulations according to manufacturer's written instructions.

B. Remove malfunctioning units, replace with new units, and retest as specified above.

END OF SECTION 26 27 26

SECTION 26 28 13 – FUSES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes the following:

1. Cartridge fuses rated 600 V and less for use in switches.

1.3 SUBMITTALS

A. Product Data: Include the following for each fuse type indicated:

1. Dimensions and manufacturer's technical data on features, performance, electrical characteristics, and ratings.
2. Fuse size for elevator feeders and elevator disconnect switches.

1.4 QUALITY ASSURANCE

A. Source Limitations: Obtain fuses from a single manufacturer.

B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

C. Comply with NFPA 70.

1.5 PROJECT CONDITIONS

A. Where ambient temperature to which fuses are directly exposed is less than 40 deg F (5 deg C) or more than 100 deg F (38 deg C), apply manufacturer's ambient temperature adjustment factors to fuse ratings.

1.6 COORDINATION

A. Coordinate fuse ratings with utilization equipment nameplate limitations of maximum fuse size.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Ferraz Shawmut, Inc.
2. Little Fuse.

2.2 CARTRIDGE FUSES

A. Characteristics: NEMA FU 1, nonrenewable cartridge fuse; class and current rating indicated; voltage rating consistent with circuit voltage.

B. End Caps: End caps shall be capable of being tested if fuse is blown.

C. Indicating Feature: Fuse shall have an indicating feature which clearly indicates when fuse is blown.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine utilization equipment nameplates and installation instructions. Install fuses of sizes and with characteristics appropriate for each piece of equipment.

B. Evaluate ambient temperatures to determine if fuse rating adjustment factors must be applied to fuse ratings.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 FUSE APPLICATIONS

A. Motor Branch Circuits: Class RK1, time delay.

3.3 INSTALLATION

A. Install fuses in fusible devices. Arrange fuses so rating information is readable without removing fuse.

3.4 IDENTIFICATION

A. Install labels indicating fuse replacement information on inside door of each fused switch.

END OF SECTION 26 28 13

SECTION 26 28 16 – ENCLOSED SWITCHES AND CIRCUIT BREAKERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions Specification Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes individually mounted enclosed switches and circuit breakers used for the following:

1. Feeder and branch-circuit protection.
2. Motor and equipment disconnecting means.

1.3 DEFINITIONS

A. GFCI: Ground-fault circuit interrupter.

B. RMS: Root mean square.

C. SPDT: Single pole, double throw.

1.4 SUBMITTALS

A. Product Data: For each type of switch, circuit breaker, accessory, and component indicated. Include dimensions and manufacturers' technical data on features, performance, electrical characteristics, ratings,
and finishes.

B. Shop Drawings: For each switch and circuit breaker.

1. Dimensioned plans, elevations, sections, and details, including required clearances and service space around equipment. Show tabulations of installed devices, equipment features, and ratings. Include the following:

a. Enclosure types and details for types other than NEMA 250, Type 1.
b. Current and voltage ratings.
c. Short-circuit current rating.
d. UL listing for series rating of installed devices.
e. Features, characteristics, ratings, and factory settings of individual overcurrent protective devices and auxiliary components.

2. Wiring Diagrams: Power, signal, and control wiring. Differentiate between manufacturer-installed and field-installed wiring.

3. Qualification Data: Submit data for testing agencies indicating that they comply with qualifications specified in "Quality Assurance" Article.

1.5 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Comply with NFPA 70- Latest edition or edition enforced by state and local code authority.

C. Product Selection for Restricted Space: Drawings indicate maximum dimensions for enclosed switches and circuit breakers, including clearances between enclosures, and adjacent surfaces and other items. Comply with indicated maximum dimensions.

1.6 COORDINATION

A. Coordinate layout and installation of switches, circuit breakers, and components with other construction, including conduit, piping, equipment, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Fusible Switches:

a. Eaton Corp.; Cutler-Hammer Products, K-Series.
b. General Electric Co.; Electrical Distribution & Control Division, TH.
c. Siemens Energy & Automation, Inc., VBII.
d. Square D Co, 3110.

2.2 ENCLOSED SWITCHES

A. Enclosed, Nonfusible Switch: NEMA KS 1, Type HD, with lockable handle.

B. Enclosed, Fusible Switch, 800 A and Smaller: NEMA KS 1, Type HD, with clips to accommodate specified fuses, lockable handle with two padlocks, and interlocked with cover in closed position.

2.3 ENCLOSURES

A. NEMA AB 1 and NEMA KS 1 to meet environmental conditions of installed location.

1. Outdoor Locations: NEMA 250, Type 3R.
2. Other Wet or Damp Indoor Locations: NEMA 250, Type 4.

2.4 FACTORY FINISHES

A. Manufacturer's standard prime-coat finish ready for field painting.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine elements and surfaces to receive enclosed switches and circuit breakers for compliance with installation tolerances and other conditions affecting performance.

1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 IDENTIFICATION

A. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs as specified in "Basic Electrical Materials and Methods."

B. Enclosure Nameplates: Label each enclosure with engraved metal or laminated-plastic nameplate mounted with corrosion-resistant screws.

C. If the disconnect or enclosed circuit breaker is used as a Main Service Disconnect then the maximum available fault current shall be listed on the device to meet the requirements of NFPA 70:110.24. The labeling shall be engraved plastic. The maxiumum available fault current shall be obtained from the electrical utility for the secondary side of the utility transformer.

3.3 CONNECTIONS

A. Install equipment grounding connections for switches and circuit breakers with ground continuity to main electrical ground bus.

B. Install power wiring. Install wiring between switches and circuit breakers, and control and indication devices.

C. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values.

D. Maintain all necessary clearances per NFPA-70.

3.4 FIELD QUALITY CONTROL

A. Prepare for acceptance tests as follows:

1. Test insulation resistance for each enclosed switch, circuit breaker, component, and control circuit.
2. Test continuity of each line- and load-side circuit.

3.5 ADJUSTING

A. Set field-adjustable switches and circuit-breaker trip ranges.

3.6 CLEANING

A. On completion of installation, inspect interior and exterior of enclosures. Remove paint splatters and other spots. Vacuum dirt and debris; do not use compressed air to assist in cleaning. Repair exposed surfaces to match original finish.

END OF SECTION 26 28 16

SECTION 26 43 13 – SURGE PROTECTION DEVICES FOR SERVICE ENTRANCE AND BRANCH PANELS

PART 1 - GENERAL

1.1 DESCRIPTION/SCOPE

A. The Surge Protection Device (SPD) covered under this section includes all service entrance type surge protection devices suitable for use as Type 1 or Type 2 devices per UL1449 4th Edition, applied to the line or load side of the utility feed inside the facility.

B. A SPD located at Service Entrance and Distribution and Branch Panels, Switchgear, Motor Control Centers, and Switchboard assemblies as indicated on the drawings.

C. Contractor shall provide all labor, materials, equipment and incidentals as shown, specified and required to finish and install surge protection devises.

1.2 QUALITY ASSURANCE

A. Reference Standard: Comply with the latest edition of the applicable provisions and recommendations of the following, except as otherwise stated in this document:

1. UL 1449 4th Edition.
2. UL 1283.
3. ANSI/IEEE C62.41, Recommended Practice for Surge Voltages in Low-Voltage AC Power Circuits.
4. ANSI/IEEE C62.45, Guide for Surge Testing for equipment connected to Low-Voltage AC Power Circuits.
5. UL96A
6. IEEE 1100 Emerald Book.
7. National Fire Protection Association (NFPA 70: National Electrical Code).

1.3 SUBMITTALS/QUALITY ASSURANCE – SUBMIT THE FOLLOWING:

A. Package must include shop drawings complete with all technical information, unit dimensions, detailed installation instructions, maintenance manual, recommended replacement parts list and wiring configuration.

B. Copies of Manufacturer’s catalog data, technical information and specifications on equipment proposed for use.

C. Copies of documentation stating that the Surge Protection Device is listed by UL to UL1449 4th Edition, category code VZCA.

D. Copies of actual let through voltage data in the form of oscillograph results for both ANSI/IEEE C62.41 Category C3 (combination wave) and B3 (Ring wave) tested in accordance with ANSI/IEEE C6245.

E. Copies of Noise Rejection testing as outlined in NEMA LS1-1992 (R2000) Section 3.11. Noise rejection is to be measured between 50 kHz and 100 MHz verifying the devices noise attenuation. Must show multiple attenuation levels over a range of frequencies.

F. Copies of test reports from a recognized independent testing laboratory, capable of producing 200kA surge current waveforms, verifying the suppressor components can survive published surge current rating on a per mode basis using the ANSI/IEEE C62.41 impulse waveform C3 (8 x 20 microsecond, 20kV/10kA). Test data on an individual module is not acceptable.

G. Copy of warranty statement clearly establishing the terms and conditions to the building/facility owner/operator.

PART 2 - PRODUCTS

2.1 APPROVED MANUFACTURER FOR ***TYPE C SPD's for Service Entrance Application:***

A. Current Technology – Transguard3 or TG3 Series **150kA** per mode surge rating or ASCO 560 series.

B. Approved equivalent. Submission package must be received by engineer 2 weeks prior to bid date shall fully comply with all performance characteristics included in this specification.

2.2 MANUFACTURED UNITS/ ELECTRICAL REQUIREMENTS

A. Refer to drawing for operating voltage, configuration and surge current capacity per mode for each location, or you may list locations and information here.

B. Declared Maximum Continuous Operating Voltage (MCOV) shall be greater than 115 percent of the nominal system operating voltage and in compliance with test and evaluation procedures outlined in the nominal discharge surge current test of UL1449 4th Edition, section 37.7.3. MCOV values claimed based on the component's value or on the 30-minute 115% operational voltage test, section 38 in UL1449 will not be accepted.

C. Unit shall have no more than 10% deterioration or degradation of the UL1449 4th Edition Voltage Protection Rating (VPR) when exposed to a minimum of 5,000 repeated category C3 (20kV/10kA) surges. The SPD manufacturer must provide a test report validating the repetitive surge test was performed.

D. Protection Modes UL1449 4th Edition VPR(6kV, 3kA) for grounded WYE/delta and High Leg Delta circuits with voltages of (480Y/277), (208Y/120), (600Y/347). 3-Phase, 4 wire circuits, (120/240) split phase shall be as follows and comply with test procedures outlined in UL1449 4th Edition section 37.6:

System Voltage	Mode	MCOV	B3 Ringwave 6kV, 500A	C3 Comb. Wave 20kV, 10kA	UL 1449 Third Edition VPR Rating
120/240, 120/208	L-N	150	490	980	700
	L-G	150	570	980	700
	N-G	150	640	1170	700
	L-L	300	500	1600	1200
277/480	L-N	320	450	1420	1200
	L-G	320	540	1540	1200
	N-G	320	570	1600	1000
	L-L	552	530	2600	2000

E. Electrical Noise Filter- each unit shall include a high performance EMI/RFI noise rejection filter with a maximum attenuation of 54dB per MIL-STD-220B.

1. SPD shall include an EMI/RFI noise rejection filter for all L-N modes as well as a removable filter in the N-G mode.

F. Integral Disconnect Switch (IF REQUIRED)

1. The device shall have an optional NEMA compliant safety interlocked integral disconnect switch with an externally mounted metal manual operator.
2. The switch shall disconnect all ungrounded circuit conductors from the distribution system to enable testing and maintenance without interruption to the facility's distribution system.
3. The switch shall be rated for 600Vac.
4. The SPD device shall be tested to UL1449 4th Edition listed with the integral disconnect switch and the UL1449 VPR ratings shall be provided.
5. The integral disconnect switch shall be capable of withstanding, without failure, the published maximum surge current magnitude without failure or damage to the switch.
6. The line side of the integral disconnect shall be blocked off so that when the SPD is opened there is no direct access to the voltage present on the line side of the disconnect.

G. The UL1449 Voltage Protective Rating (VPR) shall be permanently affixed to the SPD unit.

H. The UL1449 Nominal Discharge Surge Current Rating shall be 20Ka

I. The SCCR rating of the SPD shall be 200kAIC without the need for upstream over current protection.

J. The SPD shall be listed as Type1 SPD, suitable for use in Type1 or Type2 applications.

K. The SPD shall have the following monitoring options.

1. Time Date stamp, duration and magnitude for the following power quality events (sags, swells, surges, dropouts, outages, THD, frequency, Volts RMS per phase)
2. SPD monitoring shall track surge protection and display it as a percentage
3. SPD shall provide a surge counter with three categories to be defined as

Low Level surge (100A-500A) Medium Level surge (500A-3,000A) High Level surge (>3,000A)

2.3 APPROVED MANUFACTURER FOR ***TYPE B SPD's for Branch Panel Application:***

A. Current Technology – Transguard3 or TG3 Series 50 **kA** per mode surge rating or ASCO 560 series.

B. Approved equivalent. Submission package must be received by engineer 2 weeks prior to bid date shall fully comply with all performance characteristics included in this specification.

2.4 MANUFACTURED UNITS/ ELECTRICAL REQUIREMENTS

A. Refer to drawing for operating voltage, configuration and surge current capacity per mode for each location, or you may list locations and information here.

B. Declared Maximum Continuous Operating Voltage (MCOV) shall be greater than 115 percent of the nominal system operating voltage and in compliance with test and evaluation procedures outlined in the nominal discharge surge current test of UL1449 4th Edition, section 37.7.3. MCOV values claimed based on the component's value or on the 30-minute 115% operational voltage test, section 38 in UL1449 will not be accepted.

C. Unit shall have no more than 10% deterioration or degradation of the UL1449 4th Edition Voltage Protection Rating (VPR) when exposed to a minimum of 5,000 repeated category C3 (20kV/10kA) surges. The SPD manufacturer must provide a test report validating the repetitive surge test was performed.

D. Protection Modes UL1449 4th Edition VPR(6kV, 3kA) for grounded WYE/delta and High Leg Delta circuits with voltages of (480Y/277), (208Y/120), (600Y/347). 3-Phase, 4 wire circuits, (120/240) split phase shall be as follows and comply with test procedures outlined in UL1449 4th Edition section 37.6:

System Voltage	Mode	MCOV	B3 Ringwave 6kV, 500A	C3 Comb. Wave 20kV, 10kA	UL 1449 Third Edition VPR Rating
120/240, 120/208	L-N	150	490	980	700
	L-G	150	570	980	700
	N-G	150	640	1170	700
	L-L	300	500	1600	1200
277/480	L-N	320	450	1420	1200
	L-G	320	540	1540	1200
	N-G	320	570	1600	1000
	L-L	552	530	2600	2000

E. Electrical Noise Filter- each unit shall include a high performance EMI/RFI noise rejection filter with a maximum attenuation of 54dB per MIL-STD-220B.

1. SPD shall include an EMI/RFI noise rejection filter for all L-N modes as well as a removable filter in the N-G mode.

F. Integral Disconnect Switch (IF REQUIRED)

1. The device shall have an optional NEMA compliant safety interlocked integral disconnect switch with an externally mounted metal manual operator.
2. The switch shall disconnect all ungrounded circuit conductors from the distribution system to enable testing and maintenance without interruption to the facility's distribution system.
3. The switch shall be rated for 600Vac.
4. The SPD device shall be tested to UL1449 4th Edition listed with the integral disconnect switch and the UL1449 VPR ratings shall be provided.
5. The integral disconnect switch shall be capable of withstanding, without failure, the published maximum surge current magnitude without failure or damage to the switch.
6. The line side of the integral disconnect shall be blocked off so that when the SPD is opened there is no direct access to the voltage present on the line side of the disconnect.

G. The UL1449 Voltage Protective Rating (VPR) shall be permanently affixed to the SPD unit.

H. The UL1449 Nominal Discharge Surge Current Rating shall be 20kA

I. The SCCR rating of the SPD shall be 200kAIC without the need for upstream over current protection.

J. The SPD shall be listed as Type1 SPD, suitable for use in Type1 or Type2 applications.

K. The SPD shall have the following monitoring options available.

1. Time Date stamp, duration and magnitude for the following power quality events (sags, swells, surges, dropouts, outages, THD, frequency, Volts RMS per phase)
2. SPD monitoring shall track surge protection and display it as a percentage
3. SPD shall provide a surge counter with three categories to be defined as Low Level surge (100A-500A) Medium Level surge (500A-3,000A) High Level surge (>3,000A)

PART 3 - EXECUTION/INSTALLATION

3.1 STARTUP - The SPD manufacturer's technician shall perform a system checkout and start-up in the field to assure proper installation, operation and to initiate the warranty of the system. The technician will be required to do the following:

A. Verify voltage clamping levels utilizing a diagnostic test kit, comparing factory readings to installed readings.

B. Verify N-G connection.

C. Record information to a product signature card for each product installed.

3.2 Unit may be installed on either the line or load side of the main service disconnect. If installed on the line side unit shall be installed with an integral disconnect. If installed on the load side the unit shall be installed on the largest breaker size available. If installed lead length exceeds 5' installer shall use a low impedance (HPI) cable to reduce the lead lengths effect on the installed performance of the SPD.

PART 4 - PRODUCT WARRANTY

4.1 Warranty on defective material and workmanship shall be for 15 years.

4.2 Copy of Warranty to be sent with submittal.

END OF SECTION 26 43 13

SECTION 26 51 00 – INTERIOR LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions, apply to this Section.

1.2 REFERENCES

A. ANSI/NFPA 70, National Electrical Code

B. IEEE C62.41, Guide on the Surge Environment in Low-Voltage (1000 V and Less) AC Power Circuits

C. FCC 47 CFR Part 15, Federal Code of Regulation (CFR) testing standard for electronic equipment

D. IESNA LM-79, Electrical and Photometric Measurements of Solid-State Lighting Products

E. IESNA LM-80, Approved Method for Measuring Lumen Maintenance of LED Light Sources

F. UL1598, Standard for Safety of Luminaires

G. NEMA SSL 3-2010, High-Power White LED Binning for General Illumination

1.3 SUMMARY

A. This Section includes interior lighting fixtures, lighting fixtures mounted on exterior building surfaces, lamps, ballasts, emergency lighting units, and accessories.

1.4 SUBMITTALS

A. Product Data: For each type of lighting fixture indicated, arranged in order of fixture designation. Include data on features, accessories, and the following:

1. Dimensions of fixtures.
2. Certified results of independent laboratory tests for fixtures and lamps for electrical ratings and photometric data.
3. Certified results of laboratory tests for fixtures and lamps for photometric performance.
4. Emergency lighting unit battery and charger.
5. Fluorescent and high-intensity-discharge ballasts.
6. Types of lamps.

B. Shop Drawings: Show details of nonstandard or custom fixtures. Indicate dimensions, weights, method of field assembly, components, features, and accessories.

1. Wiring Diagrams: Detail wiring for fixtures and differentiate between manufacturer-installed and field-installed wiring.

C. Submit product data on luminaires. Product data to include, but not limited to materials, finishes, approvals, photometric performance, and dimensional information.

D. Maintenance Data: For lighting fixtures to include in maintenance manuals specified in the front-end documents.

1.5 DRAWINGS

A. The drawings, which constitute a part of these specifications, indicate the general location of the luminaires. Data presented on these drawings is as accurate as preliminary surveys and planning can determine until final equipment selection is made. Accuracy is not guaranteed and field verification of all dimensions, routing, etc., is required.

B. Photometric layout shall meet or exceed the criteria of the fixtures indicated on drawings.

1.6 QUALITY ASSURANCE

A. Fixtures, Emergency Lighting Units, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction.

B. Comply with NFPA 70- Latest edition or edition enforced by state and local code authority.

C. NFPA 101 Compliance: Comply with visibility and luminance requirements for exit signs.

D. LED Luminaires

1. Manufactures of LED luminaires shall demonstrate a suitable testing program incorporating high heat, high humidity, and thermal shock test regimens to ensure system reliability and to substantiate lifetime claims.
2. The use of IESNA LM-80 data to predict luminaire lifetime is not acceptable.
3. At time of manufacture, electrical and light technical properties shall be recorded for each luminaire. At a minimum, this should include lumen output, CCT, and CRI. Each luminaire shall utilize a unique serial numbering scheme. Technical properties must be made available for a minimum of 5 years after the date of manufacture.
4. Luminaires shall be provided with a 5-year warranty covering LEDs, drivers, paint, and mechanical components.

1.7 COORDINATION

A. Fixtures, Mounting Hardware, and Trim: Coordinate layout and installation of lighting fixtures with ceiling system and other construction.

1.8 WARRANTY

A. General Warranty: The contractor shall warranty all work for one year after acceptance of project.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the products indicated in the Fixture schedule on the drawings. Manufacture shall submit for prior approval where required at least (10) days prior to bid.

B. Subject to compliance with these specifications, luminaires shall be manufactured by the manufacturer indicated on the drawings or prior approved equivalent.

2.2 FIXTURES AND FIXTURE COMPONENTS, GENERAL

A. Metal Parts: Free from burrs, sharp corners, and edges.

B. Sheet Metal Components: Steel, unless otherwise indicated. Form and support to prevent warping and sagging.

C. Doors, Frames, and Other Internal Access: Smooth operating, free from light leakage under operating conditions, and arranged to permit relamping without use of tools. Arrange doors, frames, lenses, diffusers, and other pieces to prevent accidental falling during relamping and when secured in operating position.

2.3 EXIT SIGNS

A. Internally Lighted Signs: As follows:

1. Lamps for AC Operation: Light-emitting diodes, 70,000 hours minimum rated lamp life.

2.4 LAMPS

A. Fluorescent Color Temperature and Minimum Color-Rendering Index: Refer to drawings.

B. 4-foot lamps shall be 28-watt, 68,000 rated life 12 hour on with instant start ballast and 90,000 12 hours on with programmable start. Initial lumens 2650, minimum CRI of 82 and 96% lumen maintenance. The approved lamp is Philips Energy Advantage.

C. All fluorescent lamps shall be low on mercury.

2.5 LED LUMINAIRES

A. General: Except as otherwise indicated, provide LED luminaires, of types and sizes indicated on fixture schedules.

B. Material and specifications for each luminaire are as follows:
1. Each luminaire shall consist of an assembly that utilizes LEDs as the light source. In addition, a complete luminaire shall consist of a housing, LED array, and electronic driver (power supply)
2. Each luminaire shall be rated for a minimum operational life of 50,000 hours and to LM-70 lumen depreciation standards. This life rating must be conducted at 40C ambient temperature.
3. The rated operating temperature range shall be -30°C to +40°C.
4. Each luminaire can operate above 100°F [37°C], but not expected to comply with photometric requirements at elevated temperatures.
5. Photometry must be compliant with IESNA LM-79 and shall be conducted at 25°C ambient temperature.
6. The individual LEDs shall be constructed such that a catastrophic loss or the failure of one LED will not result in the loss of the entire luminaire.
7. Luminaire shall be constructed such that LED modules may be replaced or repaired without replacement of whole luminaire.
8. Each luminaire shall be listed with Underwriters Laboratory, Inc. under UL1598 for luminaires, or an equivalent standard from a nationally recognized testing laboratory.

C. Technical Requirements
1. Electrical
   a. Power Consumption: Maximum power consumption allowed for the luminaire shall be determined by application. The luminaire shall not consume power in the off state.
   b. Operation Voltage: The luminaire shall operate from a 60 HZ ±3 HZ AC line over a voltage ranging from 108 VAC to 305 VAC. The fluctuations of line voltage shall have no visible effect on the luminous output.
   c. Power Factor: The luminaire shall have a power factor of 0.90 or greater.
   d. THD: Total harmonic distortion (current and voltage) induced into an AC power line by a luminaire shall not exceed 20 percent.
   e. Each Luminaire shall have UL Listed Class II power supplies. Class I power supplies will not be acceptable.
   f. Operational Performance: The LED circuitry shall prevent visible flicker to the unaided eye over the voltage range specified above.
   g. RF Interference: LED Drivers must meet Class A emission limits referred to in Federal Communications Commission (FCC) Title 47, Subpart B, Section 15 regulations concerning the emission of electronic noise.
   h. Drivers shall have a Class A sound rating.

2. Thermal Management
   a. The thermal management (of the heat generated by the LEDs) shall be of sufficient capacity to assure proper operation of the luminaire over the expected useful life.
   b. The LED manufacturer’s maximum thermal pad temperature for the expected life shall not be exceeded.

c. Thermal management shall be passive by design. The use of fans or other mechanical devices shall not be allowed.
d. The luminaire shall have a minimum heat sink surface such that LED manufacturer's maximum junction temperature is not exceeded at maximum rated ambient temperature.
e. The heat sink material shall be aluminum.

2.6 FIXTURE SUPPORT COMPONENTS

A. Comply with "Basic Electrical Materials and Methods," for channel- and angle-iron supports, and nonmetallic channel and angle supports.

B. Rod Hangers: 3/16-inch- (5-mm-) minimum diameter, cadmium-plated, threaded steel rod.

C. Hook Hangers: Integrated assembly matched to fixture and line voltage and equipped with threaded attachment, cord, and locking-type plug.

D. Aircraft Cable Support: Use cable, anchorages, and intermediate support recommended by fixture manufacturer.

2.7 FINISHES

A. Fixtures: Manufacturer's standard, unless otherwise indicated.

1. Paint Finish: Applied over corrosion-resistant treatment or primer, free of defects.
2. Metallic Finish: Corrosion resistant.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Fixtures: Set level, plumb, and square with ceiling and walls, and secure according to manufacturer's written instructions and approved submittal materials. Install lamps in each fixture.

B. Support for Fixtures in or on Grid-Type Suspended Ceilings: Use grid for support.

1. Install a minimum of four ceiling support system rods or wires for each fixture. Locate not more than 6 inches (150 mm) from fixture corners.
2. Fixtures of Sizes Less Than Ceiling Grid: Arrange as indicated on reflected ceiling plans or center in acoustical panel, and support fixtures independently with at least two 3/4-inch (20-mm) metal channels spanning and secured to ceiling tees.

C. Suspended Fixture Support: As follows:

1. Pendants and Rods: Where longer than 48 inches (1200 mm), brace to limit swinging.
2. Stem-Mounted, Single-Unit Fixtures: Suspend with twin-stem hangers.

3.2 CONNECTIONS

A. Ground equipment.

1. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values.

3.3 FIELD QUALITY CONTROL

A. Inspect each installed fixture for damage. Replace damaged fixtures and components.

B. Provide instruments to make and record test results.

C. Tests: As follows:

1. Verify normal operation of each fixture after installation.
2. Emergency Lighting: Interrupt electrical supply to demonstrate proper operation.
3. Verify normal transfer to emergency source and retransfer to normal.
4. Report results in writing.

D. Malfunctioning Fixtures and Components: Replace or repair, then retest. Repeat procedure until units operate properly.

E. Corrosive Fixtures: Replace during warranty period.

3.4 CLEANING AND ADJUSTING

A. Clean fixtures internally and externally after installation. Use methods and materials recommended by manufacturer.

END OF SECTION 26 51 00

SECTION 28 31 11 – FIRE ALARM SYSTEM WITH VOICE EVACUATION

PART 1 - GENERAL

1.1 SUMMARY

A. This Section includes fire alarm systems.

B. Definitions:

1. FACP: Fire alarm control panel.
2. LED: Light-emitting diode.
3. Definitions in NFPA 72 apply to fire alarm terms used in this Section.

C. System Description:

1. Noncoded, Analog addressable system; multiplexed signal transmission dedicated to fire alarm service only.

D. Performance Requirements:

1. Comply with NFPA 72 latest edition or edition enforced by state or local code authority.
2. Fire alarm signal initiation shall be by one or more of the following devices:

    a. Manual stations.
    b. Heat detectors.
    c. Smoke detectors.
    d. Automatic sprinkler system water flow.

3. Fire alarm signal shall initiate the following actions:

    a. Alarm notification appliances shall operate continuously and be synchronized as required per code.
    b. Identify alarm at the FACP and remote annunciators.
    c. Transmit an alarm signal to the remote alarm receiving station.
    d. Shut down heating, ventilating, and air-conditioning equipment over 2000 cfm.
    e. Record events in the system memory.

4. Supervisory signal initiation shall be by one or more of the following devices or actions:

    a. Operation of a fire-protection system valve tamper.

5. System trouble signal initiation shall be by one or more of the following devices or actions:

    a. Open circuits, shorts and grounds of wiring for initiating device, signaling line, and notification-appliance circuits.
    b. Opening, tampering, or removal of alarm-initiating and supervisory signal-initiating devices.
    c. Loss of primary power at the FACP.

d. Ground or a single break in FACP internal circuits.
e. Abnormal ac voltage at the FACP.
f. A break in standby battery circuitry.
g. Failure of battery charging.
h. Abnormal position of any switch at the FACP or annunciator.

6. Resetting of other systems:

a. Resetting of duct detectors shall be from the panel.

1.2 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings:

1. System Operation Description: Detailed description for this Project, including method of operation and supervision of each type of circuit and sequence of operations for manually and automatically initiated system inputs and outputs. Manufacturer's standard descriptions for generic systems are not acceptable.
2. Device Address List: Coordinate with final system programming.
3. System riser diagram with device addresses, conduit sizes, and cable and wire types and sizes.
4. Wiring Diagrams: Power, signal, and control wiring. Include diagrams for equipment and for system with all terminals and interconnections identified. Show wiring color code.
5. Batteries: Size calculations.
6. CAD drawings with device locations, device ratings, cable routing, cable size/type, etc. indicated on floor plans.
7. All shop drawings are to be electronic in nature and submitted in PDF form. Paper shop drawings will not be reviewed.

C. Field quality-control test reports per NFPA 72.

D. Operation and maintenance data.

E. Submittals to Authorities Having Jurisdiction: In addition to distribution requirements for submittals specified in "Submittals," make an identical submittal to authorities having jurisdiction. To facilitate review, include copies of annotated Contract Drawings as needed to depict component locations. Complete all required form. Contractor is responsible for all required fees. Resubmit if required to make clarifications or revisions to obtain approval. On receipt of comments from authorities having jurisdiction, submit them to Architect for review. All drawings shall be done in AutoCAD R14 format or newer.

F. All fire alarm drawings are to be submitted digitally. Fire alarm devices with any notation are to clearly stand out from the floor plan by using a bolder line width contrasting a screened floorplan. Devices and notation are to be proportionally sized to the scale of the drawing. Fire alarm devices only are to be indicated on drawings, drawings are not to be shared with electrical devices or any other discipline.

G. Documentation:

1. Approval and Acceptance: Provide the "Record of Completion" form according to NFPA 72 to Owner, Architect, and authorities having jurisdiction.
2. Record of Completion Documents: Provide the "Permanent Records" according to NFPA 72 to Owner, Architect, and authorities having jurisdiction. Format of the written sequence of operation shall be the optional input/output matrix.

a. Electronic media shall be provided to Architect and authorities having jurisdiction.

1.3 QUALITY ASSURANCE

A. Installer Qualifications: Personnel shall be trained and certified by manufacturer for installation of units required for this Project and shall be supervised by a Nicet Level III Supervisor.

B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

Manufacturers: Subject to compliance with existing system Silent Knight model 6820 control communicator, Silent Knight Voice Evacuation System Control SKE Series

1. FACP and Equipment:

2. Wire and Cable:

a. Comtran Corporation.
b. Helix/HiTemp Cables, Inc.; a Draka USA Company.
c. Rockbestos-Suprenant Cable Corporation; a Marmon Group Company.
d. West Penn Wire/CDT; a division of Cable Design Technologies.
e. Coleman Cable.

2.2 MANUAL FIRE ALARM PULL STATION

A. Description: UL 38 listed; finished in red with molded, raised-letter operating instructions in contrasting color. Station shall show visible indication of operation. Mounted on recessed outlet box; if indicated as surface mounted, provide manufacturer's surface back box.

1. Double-action mechanism requiring two actions to initiate an alarm, pull-lever type. With integral addressable module, arranged to communicate manual-station status (normal, alarm, or trouble) to the FACP.
2. Station Reset: Key- or wrench-operated switch.

2.3 SYSTEM SMOKE DETECTORS

A. General Description:

1. UL 268 listed, operating at 24-V dc, nominal.
2. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to the FACP.
3. Integral Visual-Indicating Light: LED type. Indicating detector has operated and power-on status.

B. Multi Criteria Detectors:

1. Minimum of photoelectric and heat.
2. Sensor: LED or infrared light source with matching silicon-cell receiver.
3. Photoelectric Detector Sensitivity: Between 2.5 and 3.5 percent/foot (0.008 and 0.011 percent/mm) smoke obscuration when tested according to UL 268A.
4. Thermal detection.

C. Photoelectric Smoke Detectors:

1. Sensor: LED or infrared light source with matching silicon-cell receiver.
2. Detector Sensitivity: Between 2.5 and 3.5 percent/foot (0.008 and 0.011 percent/mm) smoke obscuration when tested according to UL 268A.

D. Duct Smoke Detectors:
PRODUCT DATA SHEET 0 -

1. Photoelectric Smoke Detectors:

    a. Sensor: LED or infrared light source with matching silicon-cell receiver.
    b. Detector Sensitivity: Between 2.5 and 3.5 percent/foot (0.008 and 0.011 percent/mm) smoke obscuration when tested according to UL 268A.

2. UL 268A listed, operating at 24-V dc, nominal.
3. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to the FACP.
4. Plug-in Arrangement: Detector and associated electronic components shall be mounted in a plug-in module that connects to a fixed base. The fixed base shall be designed for mounting directly to the air duct. Provide terminals in the fixed base for connection to building wiring.
5. Self-Restoring: Detectors shall not require resetting or readjustment after actuation to restore them to normal operation.
6. Integral Visual-Indicating Light: LED type. Indicating detector has operated and power-on status.
7. Sampling Tubes: Design and dimensions as recommended by manufacturer for the specific duct size, air velocity, and installation conditions where applied.
8. Relay Fan Shutdown: Rated to interrupt fan motor-control circuit.

2.4 HEAT DETECTORS

A. General: UL 521 listed.

B. Heat Detector, Combination Type: Actuated by either a fixed temperature of 135 deg F (57 deg C) or rate-of-rise of temperature that exceeds 15 deg F (8 deg C) per minute, unless otherwise indicated.

1. Mounting: Plug-in base, interchangeable with smoke-detector bases.
2. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to the FACP.

C. Heat Detector, Fixed-Temperature Type: Actuated by temperature that exceeds a fixed temperature of 190 deg F (88 deg C).

1. Mounting: Plug-in base, interchangeable with smoke-detector bases.
2. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to the FACP.

2.5 NOTIFICATION APPLIANCES

A. Description: Equipped for mounting as indicated and with screw terminals for system connections.

1. Combination Devices: Factory-integrated audible and visible devices in a single-mounting assembly. Factory standard color by Architect (Red or Beige).

B. Voice/Tone Speakers:

1. UL 1480 listed.
2. High-Range Units: Rated 2 to 15 W.
3. Low-Range Units: Rated 1 to 2 W.
4. Mounting: Flush, semi-recessed, or surface mounted; bidirectional as indicated.
5. Matching Transformers: Tap range matched to the acoustical environment of the speaker location.

C. Visible Alarm Devices: Xenon strobe lights listed under UL 1971, with clear or nominal white polycarbonate lens mounted on an aluminum faceplate. The word "FIRE" is engraved in minimum 1-inch- (25-mm-) high letters on the lens.

1. Rated Light Output: Candela indicated on drawings.
2. Strobe Leads: Factory connected to screw terminals.
3. Where multiple visual notification appliances can be seen from any location, circuitry shall be incorporated for the synchronization of flash rate.
4. Adjustable Strobes-Field selectable from 15cd, 30cd, 75cd, 110cd.

2.6 SPRINKLER SYSTEM REMOTE INDICATORS

A. Remote status and alarm indicator and test stations, with LED indicating lights. Light is connected to flash when the associated device is in an alarm or trouble mode. Lamp is flush mounted in a single-gang wall plate. A red, laminated, phenolic-resin identification plate at the indicating light identifies, in engraved white letters, device initiating the signal and room where

the smoke detector or valve is located. For water-flow switches, the identification plate also designates protected spaces downstream from the water-flow switch.

2.7 REMOTE ANNUNCIATOR

A. Description: Duplicate annunciator functions of the FACP for alarm, supervisory, and trouble indications. Also duplicate manual switching functions of the FACP, including acknowledging, silencing, resetting, and testing.

1. Mounting: Flush cabinet, NEMA 250, Class 1.

B. Display Type and Functional Performance: Alphanumeric display same as the FACP. Controls with associated LEDs permit acknowledging, silencing, resetting, and testing functions for alarm, supervisory, and trouble signals identical to those in the FACP.

2.8 ADDRESSABLE INTERFACE DEVICE

A. Description: Microelectronic monitor module listed for use in providing a system address for listed alarm-initiating devices for wired applications with normally open contacts.

B. Integral Relay: Capable of providing a direct signal to the elevator controller to initiate elevator recall and to a circuit-breaker shunt trip for power shutdown.

2.9 DIGITAL ALARM COMMUNICATOR TRANSMITTER

A. Listed and labeled according to UL 632.

B. Functional Performance: Unit receives an alarm, supervisory, or trouble signal from the FACP, and automatically captures one or two telephone lines and dials a preset number for a remote central station. When contact is made with the central station(s), the signal is transmitted. The unit supervises up to two telephone lines. Where supervising 2 lines, if service on either line is interrupted for longer than 45 seconds, the unit initiates a local trouble signal and transmits a signal indicating loss of telephone line to the remote alarm receiving station over the remaining line. When telephone service is restored, unit automatically reports that event to the central station. If service is lost on both telephone lines, the local trouble signal is initiated. The contractor shall provide conduit and cable to telephone backboard and make final connections to telephone service.

C. Secondary Power: Integral rechargeable battery and automatic charger. Battery capacity is adequate to comply with NFPA 72 requirements.

D. Self-Test: Conducted automatically every 24 hours with report transmitted to central station.

2.10 CELLULAR COMMUNICATOR TRANSMITTER

A. Napco Starlink Fire LTE Commercial or approved equal.

B. UL Listed.

C. Functional Performance: Unit receives an alarm, supervisory, or trouble signal from the FACP, and automatically communicates to the central station. When contact is made with the central station(s), the signal is transmitted.

D. If needed remote antennas shall be installed to allow for communications to monitoring company.

E. Communicator shall be compatible with the owner's monitoring company.

F. Communicator shall be powered by the FACP.

G. Self-Test: Conducted automatically every 24 hours with report transmitted to central station.
1.1

2.11 NETWORK COMMUNICATIONS

A. Provide network communications for fire-alarm system according to fire-alarm manufacturer's written requirements.

B. Provide network communications pathway per manufacturer's written requirements and requirements in NFPA 72 and NFPA 70.

C. Provide integration gateway using BACnet and Modbus protocol for connection to building automation system.

2.12 WIRE AND CABLE

A. Wire and cable for fire alarm systems shall be UL listed and labeled as complying with NFPA 70, Article 760.

B. Signaling Line Circuits: Twisted, shielded pair, size as recommended by system manufacturer.

1. Twisted shielded pair, NFPA 70 Article 760, UL listed as Type FPLP, plenum rated and complying with requirements in UL 1424.

C. Non-Power-Limited Circuits: Solid-copper conductors with 600-V rated, 75 deg C, color-coded insulation.

1. Low-Voltage Circuits: No. 16 AWG, minimum.
2. Line-Voltage Circuits: No. 12 AWG, minimum.
1.2

2.13 Station Smoke and Carbon Monoxide Detectors:

1. Nonsystem smoke detectors shall be listed as compatible with the fire-alarm equipment installed or shall have a contact closure interface listed for the connected load.
2. Nonsystem smoke detectors shall meet the monitoring for integrity requirements in NFPA 72
3. Comply with UL 217; suitable for NFPA 101, residential occupancies; operating at 120-V ac with 9-V dc battery as the secondary power source. Provide with "low" or "missing" battery chirping-sound device.
4. Auxiliary Relays: One Form C, rated at 0.5 A.

5. Audible Notification Appliance: Piezoelectric sounder rated at 90 dBA at 10 feet (3 m) according to UL 464.
6. Visible Notification Appliance: 177-cd strobe.
7. Heat sensor, 135 deg F (57 deg C) combination rate-of-rise and fixed temperature.
8. Test Switch: Push to test; simulates smoke at rated obscuration.
9. Tandem Connection: Allow tandem connection of number of indicated detectors; alarm on one detector shall actuate notification on all connected detectors.
10. Plug-in Arrangement: Detector and associated electronic components shall be mounted in a plug-in module that connects to a fixed base. Provide terminals in the fixed base for connection to building wiring.
11. Self-Restoring: Detectors shall not require resetting or readjustment after actuation to restore them to normal operation.
12. Integral Visual-Indicating Light: LED type, indicating detector has operated and power-on status.
13. Detector shall send trouble alarm when nearing end-of-life, power supply problems, or internal faults.
14. Comply with UL 2075

PART 3 - EXECUTION

3.1 EQUIPMENT INSTALLATION

A. HVAC: Locate detectors not closer than 3 feet (1 m) from air-supply diffuser or return-air opening.

B. Duct Smoke Detectors: Comply with NFPA 72 and NFPA 90A. Install sampling tubes so they extend the full width of the duct.

C. Heat Detectors in Elevator Shafts: Coordinate temperature rating and location with sprinkler rating and location.

D. Audible Alarm-Indicating Devices: Install per NFPA 72. Install bells and horns on flush-mounted back boxes with the device-operating mechanism concealed behind a grille.

E. Visible Alarm-Indicating Devices: Install per NFPA 72.

F. FACP: Surface mount with tops of cabinets not more than 72 inches (1830 mm) above the finished floor.

G. Annunciator: Install with top of panel not more than 72 inches (1830 mm) above the finished floor.

H. The contractor shall provide the following spare devices at a location determined by the engineer or fire marshal prior to final approval of shop drawings. Contractor shall be responsible for all conduit, wire, battery, cards etc. needed to install these spare devices. Devices not used shall be delivered to the owner as spare. Devices: 6 - horn/strobes (any candela), 4 - pull stations, 4 - smoke detectors, and 4 - control modules.

3.2 WIRING INSTALLATION

A. Install wiring according to the following:
   1. NECA 1.
   2. TIA/EIA 568-A.

B. Wiring Method:

   1. Cables and raceways used for fire alarm circuits, and equipment control wiring associated with the fire alarm system, may not contain any other wire or cable. Cable installed in plenum ceiling spaces shall be plenum rated. Fire alarm cable installed in walls, exposed areas or in inaccessible spaces shall be in conduit. All cable and conduit shall be concealed where possible.
   2. Signaling Line Circuits: Power-limited fire alarm cables shall not be installed in the same cable or raceway as signaling line circuits.

C. Wiring within Enclosures: Separate power-limited and non-power-limited conductors as recommended by manufacturer. Install conductors parallel with or at right angles to sides and back of the enclosure. Bundle, lace, and train conductors to terminal points with no excess. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with the fire alarm system to terminal blocks. Mark each terminal according to the system's wiring diagrams. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.

D. Cable Taps: Use numbered terminal strips in junction, pull, and outlet boxes, cabinets, or equipment enclosures where circuit connections are made.

E. Color-Coding: Color-code fire alarm conductors differently from the normal building power wiring. Use one color-code for alarm circuit wiring and a different color-code for supervisory circuits. Color-code audible alarm-indicating circuits differently from alarm-initiating circuits. Use different colors for visible alarm-indicating devices. Paint fire alarm system junction boxes and covers red.

F. Risers: Install at least two vertical cable risers to serve the fire alarm system. Separate risers in close proximity to each other with a minimum 1-hour-rated wall, so the loss of one riser does not prevent the receipt or transmission of signals from other floors or zones.

G. Wiring to Remote Alarm Transmitting Device: 1-inch (25-mm) conduit between the FACP and the transmitter. Install number of conductors and electrical supervision for connecting wiring as needed to suit monitoring function.

3.3 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals according to "Basic Electrical Materials and Methods Electrical Identification."

B. Install instructions frame in a location visible from the FACP.

C. Paint power-supply disconnect switch red and label "FIRE ALARM CIRCUIT CONTROL."

3.4 GROUNDING

A. Ground the FACP and associated circuits; comply with IEEE 1100. Install a ground wire from main service ground to the FACP.

3.5 FIELD QUALITY CONTROL

A. Perform the following field tests and inspections and prepare test reports:

1. Before requesting final approval of the installation, submit a written statement using the form for Record of Completion shown in NFPA 72.
2. Perform each electrical test and visual and mechanical inspection listed in NFPA 72. Certify compliance with test parameters.
3. Visual Inspection: Conduct a visual inspection before any testing. Use as-built drawings and system documentation for the inspection. Identify improperly located, damaged, or nonfunctional equipment, and correct before beginning tests.
4. Testing: Follow procedure and record results complying with requirements in NFPA 72.

   a Detectors that are outside their marked sensitivity range shall be replaced.

5. Test and Inspection Records: Prepare according to NFPA 72, including demonstration of sequences of operation by using the matrix-style form in Appendix A in NFPA 70.

3.6 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain the fire alarm system, appliances, and devices. Provide a minimum of 2 hours of training to the Owner’s Representative.

M & E Consulting, Inc.
1304 Bertrand Drive, Suite F-7
Lafayette, LA 70506
Ph: (337)234-7474
cad@meconsulting.com

CADD/Electronic File Transfer to Contractor for M&E Drawings.

Dear Contractor:

At your request, we will provide electronic files for your convenience and use in the preparation of shop drawings related to _____ , subject to the following terms and conditions: **(Name of project)**

Our electronic files are compatible with **Auto Cad (latest version)**. We make no representation as to the compatibility of these files with your hardware or your software beyond the specified release of the referenced specifications.

Data contained on these electronic files are part of our instruments of service and shall not be used by you or anyone else receiving these data through or from for any purpose other than as a convenience in the preparation of shop drawings for the referenced project. Any other use or reuse by you or by others will be at your sole risk and without liability or legal exposure to us. You agree to make no claim and hereby waive, to the fullest extent permitted by law, any claim or cause of action of any nature against us, our officers, directors, employees, agents or sub-consultants that may arise out of or in connection with your use of the electronic files.

Furthermore, you shall, to the fullest extent permitted by law, indemnify and hold us harmless against all damages, liabilities or costs, including reasonable attorneys' fees and defense costs, arising out of or resulting from your use of these electronic files.

These electronic files are not construction documents. Differences may exist between these electronic files and corresponding hard-copy construction documents. We make no representation regarding the accuracy or completeness of the electronic files you receive. In the event that a conflict arises between the signed or sealed hard-copy construction documents shall govern. You are responsible for determining if any conflict exists. By your use of these electronic files, you are not relieved of your duty to fully comply with the contract documents, including, and without limitation, the need to check, confirm and coordinate all dimensions and details, take field measurements, verify field conditions and coordinate your work with that of other contractors for the project.

Because information presented on the electronic files can be modified, unintentionally or otherwise, we reserve the right to remove all indicia of ownership and/or involvement form each electronic display.

We will furnish you electronic files of the following drawing sheets:
(PLEASE INDICATE DRAWINGS NEEDED):

_____ _____
_____ _____

Under no circumstances shall delivery of the electronic files for use by you be deemed a sale by us, and we make no warranties, either express or implied, of merchantability and fitness for any particular purpose. In no event shall we be liable for any loss of profit or any consequential damages as a result of your use or reuse of these electronic files.

_____ _____

(Date) **(Contractor name and firm name)**

_____ _____

(e-mail address) **(Contractor signature)**

Please complete this form completely and email to cad@meconsulting.com .

END OF SECTION 28 31 11

SECTION 312513 - TEMPORARY EROSION AND SEDIMENTATION CONTROL

PART 1 GENERAL

1.1 SUMMARY

A. The work specified in this Section consists of designing, providing, maintaining and removing temporary erosion and sedimentation controls as necessary.

B. Temporary erosion controls include, but are not limited to, grassing, mulching, setting, watering, and reseeding onsite surfaces and spoil and borrow area surfaces and providing interceptor ditches at ends of berms and at those locations which will ensure that erosion during construction will be either eliminated or maintained within acceptable limits as established by the Owner.

C. Temporary sedimentation controls include, but are not limited to, silt dams, traps, barriers, and appurtenances at the foot of sloped surfaces which will ensure that sedimentation pollution will be either eliminated or maintained within acceptable limits as established by the Owner.

D. Contractor is responsible for providing effective temporary erosion and sediment control measures during construction or until final controls become effective.

E. It shall be the responsibility of the Contractor to attain all permits and associated documentation necessary to provide a Stormwater Pollution Prevention Plan for the construction site as required by the Louisiana Department of Environmental Quality.

1.2 REFERENCE DOCUMENTS

A. Applicable State of Louisiana or City Building Code and Standard Building Code.

PART 2 PRODUCTS

2.1 EROSION CONTROL

A. Netting — fabricated of material acceptable to the Owner.

B. Straw mulch shall be utilized on all newly graded areas to protect areas against washouts and erosion. Straw mulch shall be comprised of threshed straw of oats, wheat, barley, or rye that is free from noxious weeds, mold or other objectionable material. The straw mulch shall contain at least 50 percent by weight of material to be 10-in, or longer. Straw shall be in an air-dry condition and suitable for placement with blower equipment.

2.2 SEDIMENTATION CONTROL

A. Bales - clean, seed-free cereal-hay type.

B. Netting - fabricated of material acceptable to the Owner.

C. Filter stone - crushed stone conforming to State D.O.T.D. Specifications.

D. Concrete block - hollow, non-load-bearing type.

E. Concrete - exterior grade not less than one inch thick.

2.3 SILT FENCE

A. Steel posts shall be a minimum of 5-ft in. length, 2-1/2-in, by 2-1/2-in, by 1/4in. angle post with self-fastening tabs and a 5-in, by 4in. (nominal) steel anchor plate at bottom.

B. Welded wire fabric shall be 4-in, by 4-in, mesh of 12 gauge by 12 gauge steel wire.

C. Silt fence fabric shall be a woven, polypropylene, ultraviolet resistant material such as Mirafi 100X as manufactured by Mirafi, Inc., Charlotte, NC or equal.

D. Tie wires for securing silt fence fabric to wire mesh shall be light gauge metal clips (hog rings), or 1/32-in, diameter soft aluminum wire.

E. Prefabricated commercial silt fence may be substituted for built-in-field fence. Prefabricated silt fence shall be “Envirofence” as manufactured by Mirafi Inc., Charlotte, NC or equal.

PART 3 EXECUTION

3.1 EROSION CONTROL

A. Minimum procedures for grassing are:
1. Scarify slopes to a depth of not less than six inches and remove large clods, rock, stumps, roots larger than 2-inch in diameter and debris.
2. Sow seed within twenty-four (24) hours after the ground is scarified with either mechanical seed drills or rotary hand seeders.
3. Apply mulch loosely and to a thickness of between 3/4-inch and 1-1/2-inches.
4. Apply netting over mulched areas on sloped surfaces.
5. Roll and water seeded areas in a manner which will encourage sprouting of seeds and growing of grass. Reseed areas which exhibit unsatisfactory growth. Backfill and seed eroded areas.

3.2 SEDIMENTATION CONTROL

A. Install and maintain silt dams, traps, barriers, and appurtenances as shown on the approved descriptions and working drawings. Hay bales which deteriorate and filter stone which is dislodged shall be replaced.

B. Silt Fence Installation
1. Silt Fences shall be positioned as necessary to prevent off site movement of sediment produced by construction activities as directed by the Engineer.
2. Dig trench 6-in wide and 6-in deep along proposed fence lines.
3. Drive metal-stakes, 8-ft on center (maximum) at back edge of trenches. Stakes shall be driven 2-ft (minimum) into ground.

4. Hang 4 by 4 woven wire mesh on posts, setting bottom of wire in bottom of trench. Secure wire to posts with self-fastening tabs.
5. Hang filter fabric on wire carrying to bottom of trench with about 4-in, of fabric laid across bottom of trench. Stretch fabric taut along fence length and secure with tie wires 12-in. O.C. both ways.
6. Backfill trench with excavated material and tamp.
7. Install pre-fabricated silt fence according to manufacturer's instructions.

C. Staging areas and access ways shall be surfaced with a minimum depth of 4-in, crushed stone.

3.3 MAINTENANCE AND INSPECTIONS

A. Inspections:
1. Make a visual inspection of all sedimentation control devices once per week and promptly after every rainstorm. If such inspection reveals that additional measures are needed to prevent movement of sediment to offsite areas, promptly install additional devices as needed. Sediment controls in need of maintenance shall be repaired promptly.

B. Device Maintenance:
1. Silt Fences:
   a. Remove accumulated sediment once it builds up to one-half of the height of the fabric.
   b. Replace damaged fabric or patch with a 2-ft minimum overlap.
   c. Make other repairs as necessary to ensure that the fence is filtering all runoff directed to the fence.
2. Add crushed stone to access ways and staging area as necessary to maintain a firm surface free of ruts and mud holes.

3.4 PERFORMANCE

A. Should any of the temporary erosion and sediment control measures employed by the Contractor fail to produce results which comply with the requirements of the State of Louisiana and the Owner, Contractor shall immediately take whatever steps are necessary to correct the deficiency at his own expense.

END OF SECTION

SECTION 321216 - ASPHALT PAVING

PART 1 GENERAL

1.1 SUMMARY

A. Scope of Work
   1. Furnish all labor, materials and equipment required to mix, spread, compact and finish bituminous pavements for binder and wearing courses on roads, parking lots and other areas in conformance with the lines, grades and thicknesses shown on the Drawings and as specified herein.

B. Related Sections
   1. Section 32 11 23 – Aggregate Surface and Base Courses.

1.2 REFERENCES

A. American Association of State Highway and Transportation Officials:
   1. AASHTO M17 - Standard Specification for Mineral Filler for Bituminous Paving Mixtures.
   2. AASHTO M29 - Standard Specification for Fine Aggregate for Bituminous Paving Mixtures.
   3. AASHTO M140 - Standard Specification for Emulsified Asphalt.
   4. AASHTO M324 - Standard Specification for Joint and Crack Sealants, Hot Applied, for Concrete and Asphalt Pavements.

B. Louisiana Department of Transportation and Development:
   1. LDOTD Standard Specifications – Louisiana Standard Specifications for Roads and Bridges, 1992 Edition.

C. ASTM International:
   1. ASTM D242 - Standard Specification for Mineral Filler For Bituminous Paving Mixtures.
   2. ASTM D692 - Standard Specification for Coarse Aggregate for Bituminous Paving Mixtures.
   3. ASTM D946 - Standard Specification for Penetration-Graded Asphalt Cement for Use in Pavement Construction.
   4. ASTM D977 - Standard Specification for Emulsified Asphalt.
   5. ASTM D1073 - Standard Specification for Fine Aggregate for Bituminous Paving Mixtures.
   6. ASTM D1188 - Standard Test Method for Bulk Specific Gravity and Density of Compacted Bituminous Mixtures Using Coated Samples
   7. ASTM D2027 - Standard Specification for Cutback Asphalt (Medium-Curing Type).
   8. ASTM D2726 - Standard Test Method for Bulk Specific Gravity and Density of Non-Absorptive Compacted Bituminous Mixtures.
   9. ASTM D3381 - Standard Specification for Viscosity-Graded Asphalt Cement for Use in Pavement Construction.

10. ASTM D3515 - Standard Specification for Hot-Mixed, Hot-Laid Bituminous Paving Mixtures.
11. ASTM D3549 - Standard Test Method for Thickness or Height of Compacted Bituminous Paving Mixture Specimens.
12. ASTM D6690 - Standard Specification for Joint and Crack Sealants, Hot Applied, for Concrete and Asphalt Pavements.

1.3 SUBMITTALS

A. Product Data:
1. Submit product information for asphalt and aggregate materials with certificates signed by supplier and Contractor certifying that materials comply with the requirements herein.
2. Prior to construction of asphalt paving, submit mix design to the Engineer for review and approval.

1.4 QUALITY ASSURANCE

A. The asphalt mixing plant shall be certified by Louisiana Department of Transportation and Development.

B. Obtain materials from same source throughout.

C. Perform work in accordance with requirements of Louisiana Standard Specifications for Roads and Bridges, 1992 Edition, hereinafter referred to as “LDOTD Standard Specifications”.

1.5 ENVIRONMENTAL REQUIREMENTS

A. Do not place asphalt mixture when ambient air or base surface temperature is less than 50 degrees F for wearing courses or 40 degrees F for binder course, or surface is wet or frozen.

PART 2 PRODUCTS

2.1 ASPHALT MATERIALS

A. All asphalt materials, including but not limited to, asphalt cement, primer, tack coat shall be in accordance with LDOTD Standard Specifications.

2.2 AGGREGATE MATERIALS

A. All aggregate materials, including coarse aggregate, fine aggregate and mineral filler shall be in accordance with LDOTD Standard Specifications.

2.3 MIXES

A. Use dry material to avoid foaming. Mix uniformly.

B. Asphalt Paving Mixtures: Designed in accordance with LDOTD Standard Specifications.
   1. Binder Course: Type 3.
   2. Wearing Course: Type 3.

2.4 EQUIPMENT

A. Maintain paving equipment in satisfactory operating condition and correct breakdowns in a timely manner so as to not delay progress of paving operation.

2.5 SOURCE QUALITY CONTROL

A. Submit proposed mix design of each class of mix for review prior to beginning of Work.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify utilities indicated under paving are installed with excavations and trenches backfilled and compacted.

B. Verify compacted base course is ready to support paving and imposed loads.
   1. Proof roll base course as necessary to identify soft spots.
   2. Remove soft or yielding base course and replace acceptable material.

C. Verify gradients and elevations of base are correct.

D. Verify gutter drainage grilles and frames and manhole frames are installed in correct position and elevation.

3.2 BASE COURSE

A. Aggregate Base Course: Install as specified in Section 32 11 23.

B. Cement Stabilized Base Course: Install as specified in Section 32 11 33.

3.3 EXISTING WORK

A. Saw cut and notch existing paving as indicted on Drawings.

B. Clean existing paving to remove foreign material, excess joint sealant and crack filler from paving surface.

C. Repair surface defects in existing paving to provide uniform surface to receive new paving.

3.4 PRIME COAT

A. Apply prime coat to all base material surfaces in accordance with LDOTD Standard Specifications.

B. Make necessary precautions to protect adjacent areas from overspray.

3.5 TACK COAT

A. Apply tack coat in accordance with LDOTD Standard Specifications.

B. Apply tack coat on asphalt and concrete surfaces at uniform rate.

C. Apply tack coat to contact surfaces of curbs, gutters and other adjacent structures.

D. Coat surfaces of manhole and catch basin frames with oil to prevent bond with asphalt paving. Do not tack coat these surfaces.

3.6 ASPHALT PAVING PLACEMENT

A. Place asphalt mixture on completed base, spread and strike off.

B. To the extent possible, pavement shall be spread by a finishing machine. Inaccessible or irregular areas may be placed by hand methods to the required depth with hot shovels and rakes.

C. Successive lifts of asphalt in parking areas shall be applied in transverse directions with the surface course being placed in the direction of surface water runoff. Paving strips shall not be less than 10 feet in width.

D. Joints between old and new pavements or between successive days of paving shall be made in a manner that will provide a continuous bond between adjoining paving. Construction joints shall have the same texture, density and smoothness as other sections of paving. Clean contact surfaces of all joints and apply tack coat.

E. Single Course Asphalt Paving
1. Install Work in accordance LDOTD Standard Specifications.
2. Place asphalt wearing course to the thickness indicated on the Drawings within 24 hours of applying primer or tack coat.
3. Compact paving by rolling to specified density. Do not displace or extrude paving from position. Hand compact in areas inaccessible to rolling equipment.
4. Perform rolling with consecutive passes to achieve even and smooth finish without roller marks.

F. Multiple Course Asphalt Paving
1. Place asphalt binder course(s) to the thickness(es) indicated on the Drawings within 24hours of applying primer or tack coat.
2. Place wearing course to the thickness indicated on the Drawings within 24 hours of placing and compacting final binder course if possible. When binder course is

placed more than 24 hours before placing wearing course, clean surface and apply tack coat before placing wearing course.

3. Compact each course by rolling to specified density. Do not displace or extrude paving from position. Hand compact in areas inaccessible to rolling equipment.
4. Perform rolling with consecutive passes to achieve even and smooth finish, without roller marks.

G. Rolling and Compaction
1. After spreading, the mixture shall be compacted with rollers such that the required density and surface are uniformly attained while the mixture is in a workable condition.
2. Areas of paving which are inaccessible to rollers shall be compacted to the required density with hand or mechanical tampers.
3. After rolling, the pavement shall have a uniform, tightly-knit surface free of cracks, tears or other deficiencies.

3.7 ERECTION TOLERANCES

A. Flatness of finished paving surface shall have a maximum variation of 1/4 inch measured with 10 foot straight edge both parallel and perpendicular to the paved centerline.

B. The compacted thickness of the finished pavement section shall be within 1/4 inch of the specified thickness. Areas of deficient thickness shall receive a tack coat and 1” overlay or shall be removed and replaced at the required thickness at the discretion of the Owner and at no additional cost.

3.8 FIELD QUALITY CONTROL

A. An independent testing laboratory, selected and paid by the Owner, shall take samples and perform tests, including mat density tests, in accordance with LDOTD Standard Specifications.

B. Asphalt Paving Mix Temperature: Measure temperature at time of placement.

C. Asphalt Paving Thickness: ASTM D3549; test one core sample from every 1000 square yards compacted paving with a minimum of two cores being required.

D. Asphalt Paving Density: ASTM D1188 or ASTM D2726; test one core sample from every 1000 square yards compacted paving with a minimum of two cores being required.

E. All coring holes shall be filled with full-depth asphalt or concrete.

3.9 PROTECTION OF FINISHED WORK

A. Immediately after placement, protect paving from mechanical injury for 12 hours or until surface temperature is less than 140 degrees F.

END OF SECTION

SECTION 321613 - CONCRETE CURBS AND SIDEWALKS

PART 1 GENERAL

1.1 SUMMARY

A. Scope of Work:
   1. This section includes all materials, equipment, labor and incidentals to provide cast-in-place concrete curb and sidewalks to the lines, grades, thicknesses and strengths indicated in the plans as required to complete the project. Formwork, reinforcement, jointing, accessories, finishing and curing are all included in this section.

B. Related Sections:
   1. Section 32 05 23 – Cement & Concrete for Exterior Improvements.

1.2 REFERENCES

A. American Concrete Institute (ACI):
   1. ACI 116R – Cement and Concrete Terminology
   2. ACI 117 – Standard Specifications for Tolerances for Concrete Construction and Materials.
   3. ACI 221.1 – Standard Practice for Selecting Proportions for Normal, Heavyweight and Mass Concrete.
   4. ACI 211.2 – Standard Practice for Selecting Proportions for Structural Lightweight Concrete.
   5. ACI 301 – Standard Specifications for Structural Concrete.
   6. ACI 302.1R – Guide for Concrete Floor and Slab Construction.
   7. ACI 303.1 – Standard Specification for Cast-In-Place Architectural Concrete.
   8. ACI 304R – Guide for Measuring, Mixing, Transporting, and Placing Concrete.
   9. ACI 304.2R – Placing Concrete by Pumping Methods.
   10. ACI 305R – Hot Weather Concreting.
   11. ACI 306.1 – Standard Specification for Cold Weather Concreting.
   12. ACI 308 – Standard Practice for Curing Concrete.
   13. ACI 309R – Guide for Consolidation of Concrete.
   14. ACI 315 – Details and Detailing of Concrete Reinforcement.
   15. ACI 318 – Building Code Requirements for Structural Concrete.
   16. ACI 347 – Formwork for Concrete.
   17. ACI 502.4 – Standard Specification for Repairing Concrete with Epoxy Mortars.

B. American Society for Testing and Materials (ASTM):
   1. ASTM A185 – Specification for Steel Welded Wire Fabric, Plain, for Concrete Reinforcement.
   2. ASTM A615 – Specification for Deformed and Plain Billet-Steel Bars for Concrete Reinforcement.
   3. ASTM C31 – Standard Practice for Making and Curing Concrete Test Specimens in the Field.

4. ASTM C33 – Specification for Concrete Aggregates.
5. ASTM C39 – Test Method for Compressive Strength of Cylindrical Concrete Specimens.
6. ASTM C40 – Test Method for Organic Impurities in Fine Aggregates for Concrete.
7. ASTM C42 – Test Method for Obtaining and Testing Drilled Cores and Sawed Beams of Concrete.
8. ASTM C94 – Specification for Ready-Mixed Concrete.
9. ASTM C114 – Test Methods for Chemical Analysis of Hydraulic Cement.
10. ASTM C117 – Test Method for materials finer than No. 200 Sieve in Mineral Aggregates by Washing.
11. ASTM C123 – Test Method for Lightweight Particles in Aggregate.
12. ASTM C127 – Test Method for Density, Relative Density (Specific Gravity), and Absorption of Coarse Aggregate.
13. ASTM C128 – Test Method for Density, Relative Density (Specific Gravity), and Absorption of Fine Aggregate.
14. ASTM C136 – Test Method for Sieve Analysis of Fine and Coarse Aggregates.
15. ASTM C142 – Test Method for Clay Lumps and Friable Particles in Aggregates.
16. ASTM C143 – Test Method for Slump of Hydraulic Cement Concrete.
17. ASTM C150 – Specification for Portland Cement.
18. ASTM C171 – Specification for Sheet Materials for Curing Concrete.
19. ASTM C172 – Standard Practice for Sampling Freshly Mixed Concrete.
20. ASTM C309 – Specification for Liquid Membrane-Forming Compounds for Curing Concrete.
21. ASTM C330 – Specification for Lightweight Aggregates for Structural Concrete.
22. ASTM C470 – Specification for Molds for Forming Concrete Test Cylinders Vertically.
23. ASTM C494 – Specification for Chemical Admixtures for Concrete.
24. ASTM C618 – Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use as a Mineral Admixture in Portland Cement Concrete.
25. ASTM C979 – Specification for Pigments for Integrally Colored Concrete.
26. ASTM C1017 – Specification for Chemical Admixtures for Use in Producing Flowing Concrete.
27. ASTM D994 – Specification for Preformed Expansion Joint Filler for Concrete (Bituminous Type).
28. ASTM D1190 – Specification for Concrete Joint Sealer, Hot-Applied Elastic Type.
29. ASTM D1751 – Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types).
30. ASTM D3405 – Specification for Joint Sealant, Hot-Applied, for Concrete and Asphalt Pavements.
31. ASTM D3406 – Specification for Joint Sealant, Hot-Applied, Elastomeric-Type, for Portland Cement Concrete Pavements.
32. ASTM E329 – Specification for Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction.

C. American Welding Society (AWS):
1. AWS D1.4 – Structural Welding Code – Reinforcing Steel.

D. Concrete Reinforcing Steel Institute (CRSI):
   1. CRSI Manual of Standard Practice
   2. CRSI Publication – Placing Reinforcing Bars

E. Where reference is made to one of the above standards, the revision in effect at the time of bid opening shall apply.

PART 2 PRODUCTS

2.1 PORTLAND CEMENT CONCRETE MATERIALS

A. All concrete materials including aggregates, reinforcement, admixtures, formwork, tools and equipment shall be in accordance with the requirements of Section 32 05 23.

2.2 CONCRETE MIX

A. Concrete mix for curbs and sidewalks shall be Class A (4,000 psi) in accordance with Section 32 05 23.

PART 3 EXECUTION

3.1 GENERAL

A. In addition to this section, requirements for formwork erection, reinforcement placement, concrete placement, form removal, joint sealing, finishing and curing are as specified in Section 32 05 23.

3.2 SUBGRADE PREPARATION

A. The subgrade shall be excavated or filled to the required lines and grades. All soft, yielding or otherwise unsuitable material shall be removed and replaced. Filled sections shall be compacted to ninety-five percent of the maximum standard Proctor density (ASTM D698) with compaction extending a minimum of six inches beyond form lines.

B. Remove loose material from compacted subgrade to provide a uniformly smooth surface immediately prior to placement of concrete.

3.3 INSTALLATION

A. The concrete shall be placed either by an approved slip form/extrusion machine, by the formed method or by a combination of these methods.

B. Formed Method:
   1. Forms shall be of metal or other suitable material that is straight and free from warp, having sufficient strength to resist the pressure of the concrete without displacement and sufficient tightness to prevent leakage of concrete mixture. Flexible or rigid forms of proper curvature may be used for curved sections.

2. Forms shall extend for the full depth of the required concrete section. All forms shall be set to the required lines and grades and rigidly braced and staked so that they remain in both horizontal and vertical alignment until their removal. Forms shall be cleaned and coated with an approved form-release agent before concrete is placed against them.
3. Install a sufficient quantity of forms to allow continuance of work and so that forms remain in place a minimum of 24 hours after placement of concrete.
4. Reusable forms shall be cleaned after each use.

C. Machine Placement:
1. The slip form/extrusion machine shall be so designed to place, spread, consolidate, screed and finish the concrete in one complete pass in such a manner that a minimum amount of hand finishing will be necessary to provide a dense and homogenous concrete section.
2. The machine shall shape, vibrate and/or extrude the concrete for the full width and depth of the section being placed. It shall be operated with as nearly a continuous forward movement as possible.
3. All operations of mixing, delivery and spreading concrete shall be so coordinated as to provide uniform progress with stopping and starting of the machine held to a minimum.

3.4 JOINTING

A. Contraction Joints:
1. Contraction and construction joints shall be placed at the standard spacing of ten feet in curb and gutter sections. For sidewalk sections, refer to the Drawings for joint spacing requirements.
2. Transverse weakened-plane contraction joints shall be constructed at right angles to the curb line. Joint depth shall average at least one-fourth of the cross-section of the concrete.
3. Contraction joints may be sawed, hand-formed for made by one-eighth inch thick division plates in the formwork. Sawing shall be done early after the concrete has set to prevent the formation of uncontrolled cracking. The joints may be hand-formed by using a thin metal blade to impress a plane of weakness into the plastic concrete.

B. Expansion Joints:
1. Expansion joints shall be constructed at right angles to the curb line at immovable structures, at points of curvature for short radius curves and at a standard spacing of sixty feet in curb and gutter or sidewalk sections unless otherwise specified in the Drawings.
2. Expansion joint filler shall conform to the requirements of ASTM D994 and shall consist of a 3/4 inch thick pre-formed material cut to the exact cross-section of the curb and gutter section.
3. Expansion joints in a slip-formed section shall be constructed with an appropriate hand tool by raking through the partially set concrete for the full depth and width of the section. After joint filler is placed, open areas adjacent to the joint shall be filled with concrete and then troweled and edged.

C. Curbs, combination curbs and gutters and sidewalks constructed adjacent to existing concrete shall have the same type of joints as in the existing concrete with similar spacing, however, contraction joints spacing shall not exceed ten feet.

D. Finish, protect and cure concrete in accordance with Section 32 05 23.

3.5 BACKFILLING

A. After the concrete has set sufficiently, the spaces in front and back of the completed section shall be filled to the required elevations with suitable material which shall be compacted and neatly graded.

3.6 CLEANING AND ADJUSTING

A. Sweep concrete surface and wash free of stains, discolorations, dirt and other foreign material just prior to final inspection.

B. Protect concrete from damage until acceptance of work. Exclude traffic from concrete for a minimum of 14 days after placement.

C. Remove and replace any sections of concrete damaged prior to final acceptance.

END OF SECTION

SECTION 326113 - MISCELLANEOUS WORK AND CLEANUP

PART 1 GENERAL

1.1 SCOPE OF WORK

A. Furnish all labor, materials, equipment and incidentals required to do the miscellaneous work not specified in other sections but obviously necessary for the proper completion of the work as shown on the Drawings.

B. When applicable the Contractor shall perform the work in accordance with other sections of this Specification. When no applicable specification exists the Contractor shall perform the work in accordance with the best modern practice and/or as directed by the Engineer.

C. The work of this Section includes, but is not limited to, the following:
1. Protection and/or removal and reinstallation of signs, lampposts and mailboxes.
2. Crossing and relocating existing utilities.
3. Restoring of roadways and pavement.
4. Protection and bracing of utility poles.
5. Restoring easement and right-of-ways.
6. Temporary facilities.
7. Cleaning up.
8. Incidental work.

D. The Contractor’s bid price shall include costs associated with this Section. The work specified herein is not shown on the Contract Drawings. It shall be the Contractor’s responsibility to develop his/her costs for this work based on site/field investigations prior to the bid.

PART 2 PRODUCTS

2.1 MATERIALS

A. Materials required for this Section shall be the same quality of materials that are to be restored. Where possible, the Contractor may re-use existing materials that are removed and acceptable for reuse.

PART 3 EXECUTION

3.1 RESTORATION AND REPLACEMENT OF SIGNS, LAMPPOSTS AND MAILBOXES

A. Existing signs, lampposts and mailboxes which may be damaged by the Contractor or removed by the Contractor during the course of installing the new pipelines shall be reinstalled in a vertical position at the same location from which they were removed. Damaged items shall be replaced with an item equal to or better than the damaged items. A concrete anchor shall be provided as necessary, at no additional cost, to ensure a rigid

alignment. Care shall be exercised in the reinstallation of all items to prevent damage to the newly installed pipelines.

3.2 CROSSING AND RELOCATING EXISTING UTILITIES

A. The Contractor shall furnish all labor, materials, equipment, and incidentals required in crossing and/or relocating culverts; water courses, including brooks and drainage ditches; storm drains; sewers; water mains; and other utilities and obstructions including, but not limited to, electric, telephone and gas services. This work shall include, but is not limited to, the following: bracing, hand excavation and backfill, sheeting and shoring, dewatering, compaction, restoration, location and protection of existing utilities, erosion and sedimentation control, traffic control, clean-up, and all else incidental thereto for which separate payment is not provided under other items in the Bid Form.

B. In locations where existing utilities cannot be crossed without interfering with the construction of the work as shown on the Drawings, the Contractor shall remove and relocate the utility as directed by the Engineer or cooperate with the utility companies concerned if they relocate their own utility.

C. At pipe crossings and where designated by the Engineer, the Contractor shall furnish and place compacted granular bedding material so that the existing utility or pipe is firmly supported for its entire exposed length. The bedding shall extend to the mid- diameter of the pipe crossed.

3.3 RESTORATION OF ROADWAYS AND PAVEMENT

A. The Contractor shall repair and/or replace existing roadways disturbed by the construction. Paved drives shall be repaved to the limits and thicknesses existing prior to construction. Gravel drives shall be replaced and regraded to the limits and thicknesses existing prior to construction.

3.4 PROTECTION AND BRACING OF UTILITY POLES

A. The Contractor shall be responsible for making all arrangements with the proper utility companies for the bracing and protection of all utility poles that may be damaged or endangered by the Contractors operations. Work under this item shall include the related removal and reinstallation of guy wires, or support poles whether shown on the Drawings or not.

3.5 RESTORING EASEMENTS AND RIGHT-OF-WAYS

A. The Contractor shall be responsible for all damage to private property due to his operations. The Contractor shall protect from injury all walls, fences, cultivated shrubbery and vegetables, fruit trees, pavement, underground facilities, such as water pipe, or other utilities which may be encountered along the route. If removal and replacement are required, it shall be done in a workmanlike manner so that replacement is equivalent to that which existed prior to construction.

B. Existing lawn and sod surfaces damaged by construction shall be regraded and reseeded or sodded as directed. These areas shall be maintained until all work under this Contract

has been completed and accepted. Any additional work required to restore property to the original condition shall be performed by the Contractor.

C. Existing trees, shrubs, plants, and bushes outside of easements shall be fully protected during construction.

3.6 TEMPORARY FACILITIES

A. The Contractor shall furnish, install, maintain and remove all temporary facilities required for the proper completion of the Contract as shown on the Drawings and as specified herein.

3.7 CLEANING UP

A. The Contractor shall remove all construction material, excess excavation, buildings, equipment and other debris remaining on the job as a result of construction operations and shall restore the site of the work to a neat and orderly condition.

3.8 INCIDENTAL WORK

A. The Contractor shall perform all incidental work not otherwise specified, but obviously necessary, for the proper completion of the Contract as shown on the Drawings and as specified herein.

END OF SECTION

SECTION 329200 – TURF AND GRASSES

PART 1 GENERAL

1.1 SCOPE OF WORK

A. Seeding, sodding and lawn restoration.

B. Restoration work to provide the quality of landscape equal to or better than that which existed before initiation of the Project.

1.2 PROTECTION

A. Only vehicles and equipment necessary to perform the Work shall be permitted on lawn areas.

1.3 SUBMITTALS

A. Certificates of Conformance or Compliance
   1. Sod and seed blend.
   2. Fertilizer: Bag label with guaranteed analysis.
   3. Seeding method to be used with list of equipment.

1.4 FINAL ACCEPTANCE

A. Final inspection and acceptance will be at the end of the turf establishment period. Acceptance shall be based upon a satisfactory stand of turf defined as 95 percent ground cover of species established.

B. Reestablish turf in areas that do not have 95 percent ground cover of the established species. Repair rejected areas of turf within acceptable planting dates as directed by Owner's Representative.

PART 2 PRODUCTS

2.1 MATERIALS

A. Topsoil for landscaped, sodded or seeded areas shall be provided in accordance with LDOTD Standard Specifications for Roads and Bridges, 2006 Edition, Section 715, Topsoil.

B. Sod shall be furnished and installed in designated areas in accordance with LDOTD Standard Specifications for Roads and Bridges, 2006 Edition, Section 714, Sodding.

C. Seeding mixtures shall be in accordance with LDOTD Standard Specifications for Roads and Bridges, 2006 Edition, Section 717, Seeding.

D. Mulch shall be furnished and installed on seeded areas in accordance with LDOTD Standard Specifications for Roads and Bridges, 2006 Edition, Section 716, Vegetative and Fiber Mulch.

E. Fertilizer shall be in accordance with LDOTD Standard Specifications for Roads and Bridges, 2006 Edition, Section 718, Fertilizer and Agricultural Lime.

F. Water will be furnished by Owner. Contractor shall furnish all hoses, meters, back flow preventers, and any other connections necessary to perform watering needs.

PART 3 EXECUTION

3.1 PREPARATION

A. Topsoil depth shall be a minimum of 6 inches. Topsoil shall not be used while in a frozen or muddy condition. The Contractor shall dispose of surplus materials.

B. Scarify compacted areas to a depth of 6 inches. Scarify compacted subsoil before topsoil is added. Work the soil down to pea sized particles and form an appropriate grade that will allow sod to be just below flush with paved areas or as required for seeded areas.

C. Roll the area with an appropriately sized roller used in landscaping to firm the turf bed, then relevel to the appropriate grade.

D. Debris and stones over a maximum of 5/8 inch in any dimension shall be removed from surfaces designated as lawn areas.

E. Prepared surfaces shall be protected from compaction or damage by vehicular or pedestrian traffic and surface erosion.

3.2 SOD INSTALLATION

A. At a minimum, sod shall be installed for a width of 5 feet along the entire perimeter of new buildings and pavement areas and on all slopes of 4:1 or greater.

B. Sod shall be properly moist at the time of cutting and shall be laid within 24 hours of cutting to prevent excessive heat buildup.

C. Lay sod with the ends staggered by a minimum of 1 foot. Adjust the sod so the seams are firmly butted together and curled edges are laid flat.

D. Water thoroughly until subsoil is wet and whenever sod shows signs of drying or wilting. Sprinklers or nozzle hoses are acceptable. Continue watering until the Project is accepted.

E. Fertilize immediately prior to or immediately after the sodding operation.

F. Timing of the Work shall be done at typically accepted times in spring or fall when temperatures are mild and establishment can be completed.

G. Maintain lawn for 30 days after installation, including watering, weeding, re-sodding, mowing, trimming, and edging. Mow grass at regular intervals to maintain at a maximum height of 2.5 inches. Do not cut off more than 1/3 of the height at any one mowing.

H. Damage resulting from erosion, washouts, drought, diseases, or other causes shall be repaired by filling with topsoil, tamping, fertilizing, and sodding by the Contractor at no additional compensation. Sod operations shall be repeated until a satisfactory uniform stand of grass is obtained as determined by the Owner.

3.3 SEEDING OPERATION

A. Seed beds shall be prepared by disking, harrowing or other approved methods.

B. Rake seed for good soil contact.

C. Water with sprinklers whenever soil surface is dry and until small puddles just begin to form. Open ended hoses will not be accepted. Continue proper watering schedule until the Project is accepted.

D. Fertilize immediately prior to or immediately after seeding.

E. Install vegetative or fiber mulch on all seeded areas.

F. Maintain lawn for 30 days after installation, including watering, weeding, reseeding, mowing, trimming, and edging. Mow grass at regular intervals to maintain at a maximum height of 2.5 inches. Do not cut off more than 1/3 of the height at any one mowing.

G. Damage resulting from erosion, washouts, drought, diseases, or other causes shall be repaired by filling with topsoil, tamping, fertilizing, and seeding by the Contractor at no additional compensation. Seed operations shall be repeated until a satisfactory uniform stand of grass is obtained as determined by the Owner.

END OF SECTION

SECTION 331113 - PUBLIC WATER UTILITY DISTRIBUTION PIPING

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Water piping.
2. Tapping sleeves and valves.
3. Valves.
4. Meters.
5. Air release valves.
6. Precast concrete vaults and meter boxes.
7. Bedding and backfill materials.

B. Related Sections:
1. Section 32 05 23 – Cement and Concrete for Exterior Improvements.
2. Section 33 12 16 – Water Utility Distribution Valves.
3. Section 33 12 43 – Water Utility Granular Activated Carbon Absorption Units.

1.2 REFERENCES

A. American Association of State Highway and Transportation Officials:
1. AASHTO T180 - Standard Specification for Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and a 457-mm (18-in.) Drop.

B. American Society of Mechanical Engineers:
1. ASME B16.1 - Cast Iron Pipe Flanges and Flanged Fittings.

C. ASTM International:
1. ASTM A36/A36M - Standard Specification for Carbon Structural Steel.
2. ASTM A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
3. ASTM A307 - Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength.
4. ASTM D698 - Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft3 (600 kN-m/m3)).
5. ASTM D1557 - Standard Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort (6,000 ft-lbf/ft3 (2,700 kN-m/m3)).
6. ASTM D1784 - Standard Specification for Rigid Poly (Vinyl Chloride) (PVC) Compounds and Chlorinated Poly (Vinyl Chloride) (CPVC) Compounds.
7. ASTM D2241 - Standard Specification for Poly (Vinyl Chloride) (PVC) Pressure-Rated Pipe (SDR Series).
8. ASTM D2922 - Standard Test Method for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth).
9. ASTM D3017 - Standard Test Method for Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth).

10. ASTM D3139 - Standard Specification for Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals.
11. ASTM F477 - Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe.

D. American Water Works Association:
1. AWWA C104 - ANSI Standard for Cement Mortar Lining for Ductile-Iron Pipe and Fittings for Water.
2. AWWA C105 - ANSI Standard for Polyethylene Encasement for Ductile-Iron Pipe Systems.
3. AWWA C110 - ANSI Standard for Ductile-Iron and Gray-Iron Fittings, 3 In. Through 48 In. (76 mm Through 1,219 mm), for Water.
4. AWWA C111 - ANSI Standard for Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings.
5. AWWA C115 - ANSI Standard for Flanged Ductile-Iron Pipe with Ductile-Iron or Gray-Iron Threaded Flanges.
6. AWWA C150 – ANSI Standard for Thickness Design of Ductile-Iron Pipe.
7. AWWA C151 - ANSI Standard for Ductile-Iron Pipe, Centrifugally Cast, for Water or Other Liquids.
8. AWWA C153 - ANSI Standard for Ductile-Iron Compact Fittings for Water Service.
9. AWWA C200 - Steel Water Pipe 6 In. (150 mm) and Larger.
10. AWWA C203 - Coal-Tar Protective Coatings and Linings for Steel Water Pipelines - Enamel and Tape - Hot Applied.
11. AWWA C205 - Cement-Mortar Protective Lining and Coating for Steel Water Pipe - 4 In. and Larger - Shop Applied.
12. AWWA C206 - Field Welding of Steel Water Pipe.
13. AWWA C207 - Steel Pipe Flanges for Waterworks Service - Sizes 4 In. Through 144 In. (100 mm Through 3,600 mm).
14. AWWA C208 - Dimensions for Fabricated Steel Water Pipe Fittings.
15. AWWA C213 - Fusion-Bonded Epoxy Coating for the Interior and Exterior of Steel Water Pipelines.
16. AWWA C300 - Reinforced Concrete Pressure Pipe, Steel-Cylinder Type.
17. AWWA C301 - Prestressed Concrete Pressure Pipe, Steel-Cylinder Type.
18. AWWA C500 - Gate Valves for Water and Sewage Systems.
19. AWWA C600 - Installation of Ductile-Iron Water Mains and Their Appurtenances.
20. AWWA C605 - Water Treatment - Underground Installation of Polyvinyl Chloride PVC Pressure Pipe and Fittings for Water.
21. AWWA C606 - Grooved and Shouldered Joints.
22. AWWA C700 - Cold-Water Meters - Displacement Type, Bronze Main Case.
23. AWWA C701 - Cold-Water Meters - Turbine Type, for Customer Service.
24. AWWA C702 - Cold-Water Meters - Compound Type.
25. AWWA C706 - Direct-Reading, Remote-Registration Systems for Cold-Water Meters.
26. AWWA C900 - Polyvinyl Chloride (PVC) Pressure Pipe, and Fabricated Fittings, 4 In. through 12 In. (100 mm Through 300 mm), for Water Distribution.

27. AWWA C905 - Polyvinyl Chloride (PVC) Pressure Pipe and Fabricated Fittings, 14 In. Through 36 In. (350 mm Through 1,200 mm), for Water Transmission and Distribution.
28. AWWA M6 - Water Meters - Selection, Installation, Testing, and Maintenance.

E. Manufacturer's Standardization Society of the Valve and Fittings Industry:
1. MSS SP-60 - Connecting Flange Joint between Tapping Sleeves and Tapping Valves.

F. National Fire Protection Agency:
1. NFPA 24 - Standard for the Installation of Private Fire Service Mains and Their Appurtenances.

1.3 SUBMITTALS

A. Contractor is required to submit six (6) copies of product data for review and approval. The Engineer shall promptly review this data, and return two (2) copies to the Contractor as accepted, or with requested modifications. Contractor to submit data on pipe materials, pipe fittings, valves, meter assemblies, and all accessories.

1.4 RECORD DRAWINGS

A. The Contractor shall furnish an As-Built drawing showing the actual locations of piping mains, valves, connections, fire hydrants, service assemblies, etc.

PART 2 PRODUCTS

2.1 GENERAL

A. All water main piping and fittings shall be of the types specified herein and shall be NSF approved.

B. All materials used to convey water for public consumption shall be "lead free" as defined in the Louisiana Department of Health and Hospitals' Fact Sheet included at the end of this section.

2.2 WATER PIPING

A. Ductile Iron Pipe
1. Ductile Iron Pipe shall comply with AWWA C150/A21.50, AWWA C151/A21.51 AWWA C111/A21.11, latest revisions. Pipe shall be minimum Class 50 for an internal working pressure of 250 psi with 100 psi surge allowance plus a safety factor of 2.0.
2. Thickness of ductile iron pipe shall be in accordance with laying condition "Type 2" with a minimum of 5 feet of cover, AWWA C150/A21.50. Thickness design will also be based on a minimum working pressure of 250 psi. Surface loading shall be AASHTO H-20 Truck.

3. Buried piping shall be Push-on or Mechanical Joint, with factory installed rubber gasket conforming to AWWA C111/A21.11, latest revisions.
4. Piping above ground shall be Flanged Joint. Flanged shall comply with AWWA C115/A21.15, latest revision. Pipe barrel shall be designed in accordance with AWWA C151/A21.51, latest revision and nominal thickness of pipe shall be at least Class 53. All flanges shall be ductile iron and rated for a working pressure of 250 psi. Flanged joints shall not be used for underground installations except within structures.
5. All ductile iron pipe shall be asphaltic coated outside and cement-mortar lined inside with seal coat of bituminous material all in accordance with AWWA C151/A21.51 and AWWA C104/A21.4 respectively.
6. Fittings shall be cast of gray iron or ductile iron conforming to AWWA C110/A21.10 or AWWA C153/A21.53. Cast iron fittings shall be asphaltic coated outside and cement-mortar lined inside with a seal coat of bituminous material conforming to AWWA C104/A21.4, latest revision. Joints for cast iron fittings shall be mechanical joint conforming to AWWA C153/A21.53 for 3" through 16" and AWWA C111/A21.11 for 18" through 24". Fittings shall have "O" ring seals.
7. Where indicated on the drawings or otherwise required by the Contract Documents, pipe joints may require additional thrust restraint by incorporating mechanical glands in accordance with pipe manufacturer's installation recommendations. Restrained joints shall meet requirements of AWWA C151, AWWA C110 and AWWA C111 standards. Joint design shall utilize a high strength ductile iron or structural steel gland assembled on the pipe along with retainer lugs, conforming to ASTM A536 strength requirements, latest revision. Stainless steel or corrosive resistant high-strength low-alloy nuts, bolts and rods shall complete the restrained joint assembly, delivering a full circumferential contact and support of the pipe wall. The mechanical joint restraining gland shall have a pressure rating equal to that of the pipe on which it is used. All bends and tie-ins shall require mechanical restraints, including thrust blocking.
8. Where indicated on the drawings or otherwise required by the Contract Documents, special external corrosion protection shall be provided for all ductile iron pipe and fittings. External corrosion protection shall be accomplished by complete encasement of the pipe with 8 mil thick polyethylene immediately before installing the pipe. Polyethylene encasement material shall be in accordance with requirements of AWWA C105/A21.5. The polyethylene encasement shall provide a "loose" wrap with no tears, rips or other perforations of the material.

B. Polyvinyl Chloride (PVC) Pipe – C900
1. C900 PVC pipe shall be the gasket joint bell type, meeting the requirements of AWWA C900 for sizes 4" to 12" diameter or AWWA C905 for sizes 14" to 48" diameter. Unless otherwise specified on the Drawings, Pipe shall be Pressure Class 165 (DR 25) with cast iron pipe equivalent OD.
2. Joints for PVC pipe shall be gasketed, push-on type conforming to the requirements of ASTM D3139 with joint gaskets complying with ASTM F477. Joints between pipe and metal fittings shall be compression type mechanical joints conforming with the requirements of ASTM D3139 and AWWA

C111/A21.11 with joint gaskets complying with AWWA C111/A21.11. Pipe and fittings shall be assembled with a non-toxic lubricant NSF tested, and certified suitable for potable water distribution products. Provisions shall be made for contraction and expansion at each joint. Integral bells or affixed couplings shall be tested with the pipe.

3. All fittings, tees, bends, crosses and specials used in connection with PVC pipe shall be of the same material and minimum thickness as specified for iron pipe. The fittings shall be made specifically for the pipe utilized, and only standard manufactured fittings will be acceptable. Special adaptors required to transition from PVC pipe to another type of pipe or to a valve or other appurtenance shall be of the type as recommended by the PVC pipe manufacturer. Only standard manufacturer adaptors will be acceptable.
4. Mechanical restraints for PVC pipe shall consist of the same physical properties as those described for ductile iron pipe with the exception of the circumferential contact support being designed for AWWA C900 pipe. Restraints shall be Uni-Flange 1300, Megalug 1100 PV or approved equal.
5. All PVC pipe shall have a 10 gauge insulated solid copper tracer wire installed in the trench with the pipe to facilitate locating the pipe with an electronic pipe locator. This wire is to be taped on top of the pipe at 10-foot intervals.

C. Polyvinyl Chloride (PVC) Pipe – Pressure-Rated

1. Pressure-Rated PVC pipe shall be the gasket joint bell type, meeting the requirements of ASTM D2241 and/or ASTM D3139. Unless otherwise specified on the Drawings, Pipe shall be Class 160 (SDR 26), except that PVC water mains located under roads or installed by jack & bore methods shall be Class 200 (SDR 21).
2. Joints for PVC pipe shall be factory installed rubber gasket seal joints conforming to ASTM F477 requirements. Solvent-cement type joints are not acceptable. Pipe and fittings shall be assembled with a non-toxic lubricant NSF tested, and certified suitable for potable water distribution products. Provisions shall be made for contraction and expansion at each joint. Integral bells or affixed couplings shall be tested with the pipe.
3. All fittings, tees, bends, crosses and specials used in connection with PVC pipe shall be of the same material and minimum thickness as specified for iron pipe. The fittings shall be made specifically for the pipe utilized, and only standard manufactured fittings will be acceptable. Special adaptors required to transition from PVC pipe to another type of pipe or to a valve or other appurtenance shall be of the type as recommended by the PVC pipe manufacturer. Only standard manufacturer adaptors will be acceptable.
4. Mechanical restraints for PVC pipe shall consist of the same physical properties as those described for ductile iron pipe with the exception of the circumferential contact support being designed for ASTM D2241 pipe. Restraints shall be Uni-Flange 1300, Megalug 1100 PV or approved equal.
5. All PVC pipe shall have a 10 gauge insulated solid copper tracer wire installed in the trench with the pipe to facilitate locating the pipe with an electronic pipe locator. This wire is to be taped on top of the pipe at 10-foot intervals.

D. High Density Polyethylene Pipe (HDPE)

1. HDPE pipe shall be extra-high molecular weight high density polyethylene 4710 and shall conform in all respects to AWWA C901/C906 and ASTM F714 and shall meet the quality standard of the National Sanitation Foundation Standard 61 and bear its seal of approval as safe for potable water. HDPE pipe shall be Class 200 (SDR 11), Ductile Iron Pipe size. Piping shall be Design-Flow HDPE pipe, as manufactured by Independent Pipe Products, Inc., or approved equal. The minimum opening in the pipe shall be of equal or greater size as connecting pipe. No restriction of flow will be allowed.
2. All HDPE water pipe shall be connected together using the heat fusion butt-weld method. All joints shall be leak-tight and fully restrained.
3. All fittings for HDPE pipe shall be as specified for iron pipe and shall include stainless steel inserts. All fittings shall be compatible with the pipe on which they are installed and only standard manufactured fittings will be acceptable. Fittings shall be Tyler/Union or approved equal.
4. All HDPE pipe shall have a 10 gauge insulated solid copper tracer wire installed in the trench with the pipe to facilitate locating the pipe with an electronic pipe locator. This wire is to be taped on top of the pipe at 10-foot intervals.

2.3 TAPPING SLEEVES AND VALVES

A. Tapping Sleeves:
1. All tapping sleeves shall be cast iron or ductile iron sleeves meeting the requirements of AWWA C110/A21.10, in two sections, the halves to be bolted together along the centerline of the pipe.
2. Mechanical joint ends shall conform to AWWA C111/A21.11.
3. Flanged ends shall conform to AWWA C110/A21.10, Class 250 lb.
4. Bolts and nuts will be of a high strength low alloy corrosion resistant steel conforming to ASTM A325 (Type 3). All mechanical joint glands shall be cast iron.
5. Branch outlet or taping sleeve shall be flanged, with a machined projection or recess to mate with tapping valve inlet to assure correct alignment.

B. Tapping Valves:
1. Tapping valves shall conform to the requirements of AWWA C500 with the following exceptions:
   a. Tapping valves shall have oversize seat rings to permit entry of standard tapping machine cutters.
   b. In the open position, valve gates shall be clear of the ports, to that cutter will pass through without making contact with the gates.
   c. Valves shall have an inlet flange conforming to ASA B 16.1, Class 125, with a machined recess to mate the tapping sleeve outlet flange to assure correct alignment.
   d. Valves shall have a standard mechanical joint outlet end and shall fit any standard tapping machine.

2.4 VALVES

A. Valves: Conform to Section 33 12 16.

2.5 BEDDING AND BACKFILL MATERIALS

A. Bedding materials shall be installed as indicated on the Drawings using select material. Select material shall be defined as fine granular material, or native soil, consisting of sand, sandy loam or loam free of excessive clay (less than 5 percent). When wet, the material shall not form mud or muck.

B. Haunching backfill is defined as backfill material placed from the bottom of pipe to the pipe springline. Haunching backfill shall consist of approved native soil or fine granular backfill, and shall be tamped to provide the lower part of the pipe with support as indicated on the Drawings.

C. Initial backfill is defined as backfill material placed to a point 12” above the top of the pipe. Initial backfill may consist of finely divided native material stockpiled from the excavation, if approved by the engineer, or fine granular material. Initial backfill shall be compacted to 95% maximum density, as defined by the Standard Proctor test.

D. Final backfill is defined as backfill material placed from a point 12” above the top of the pipe to existing grade, sub-grade, or base as required. Final backfill may consist of native material, if approved by the engineer, or select material. The degree of backfilling compaction density required shall be governed by the location of the water main.
   1. Whenever trenches fall under known structural pavements (streets, drives, or walkways), the trench shall be compacted to 95% maximum density, as defined by the Standard Proctor test.
   2. Otherwise, the trench shall be compacted to 90% maximum density, or to the insitu density of the surrounding soil.

PART 3 EXECUTION

3.1 EXAMINATION

A. Contractor shall carefully examine the project site and verify existing conditions before starting work.

B. Contractor shall verify that existing utility water main size, location, and depth are as indicated on Drawings.

C. All pipe, fittings, and accessories delivered to the job site shall be carefully examined by both the Contractor and the Engineer or his representative. This inspection does not exempt the Contractor from supplying the materials specified by the Contract. All materials found to have flaws, cracks, or other defects, whether before or after installation, shall be rejected by the Engineer and will be repaired or replaced by the Contractor as directed by the Engineer, at no additional cost.

3.2 PREPARATION

A. Pre-Construction Site Photos:

1. Take photographs along centerline of proposed pipe trench; minimum one photograph for each 200 feet of pipe trench.
2. Show mail boxes, curbing, lawns, driveways, signs, culverts, and other existing site features.
3. Include project description, date taken and sequential number on back of each photograph.

B. Cut pipe ends square, ream pipe and tube ends to full pipe diameter, remove burrs. Use only equipment specifically designed for pipe cutting. The use of chisels or hand saws will not be permitted. Grind edges smooth with beveled end for push-on connections.

C. Remove scale and dirt on inside and outside before assembly.

D. Prepare pipe connections to equipment with flanges or unions.

3.3 SURFACE PREPARATION, PRIMING AND PAINTING

A. All exposed metal piping, valves, fittings, etc. which have not received a suitable system of paints from the factory shall be cleaned, primed and painted as specified in this section.

B. All metal surfaces to be painted shall be prepared by sandblasting or other methods to provide a surface suitable for paint adherence.

C. All above ground metal piping and fittings, after cleaning, shall be primed and painted with a four- coat Alkyd paint system to a total dry film thickness of 5 mils. Immediately after surface preparation, each surface shall be primed with one coat of red lead iron oxide alkyd linseed oil paint conforming to Federal Specifications TT-P-86a to a minimum dry film thickness of 1 mil. Any primer surface damaged after priming operations and prior to application of the paint system shall be re-cleaned and re-primed as specified above. The initial three coats of paint shall be modified in color to contrast with successive coats. All painting shall be done in accordance with SSPC Paint Applications Specifications No. 1 – Latest Revision and in accordance with the manufacturer's suggested application procedures.

D. All below ground metal piping and fittings shall be painted with two coats of a coal tar-epoxy paint. Each coat shall have a dry film thickness of 6 – 8 mils for a total dry film thickness of 12 – 16 mils. The limits of the coal tar epoxy application shall be all piping or fittings below, or in contact with, the ground surface to a point 12" above finish grade.

3.4 EXCAVATION AND BEDDING

A. Excavate pipe trench in accordance with the Drawings. Excavated trench shall be of sufficient width to allow proper handling of the pipe and thorough compaction of backfill around the pipe.

B. Dewater excavations to maintain dry conditions and preserve final grades at bottom of excavation.

C. Stones found in the excavated trench shall be removed for a depth of at least six inches below the bottom of the pipe.

D. Place bedding material as required.

E. The subgrade and/or bedding material shall be accurately shaped and trimmed to support the pipe barrel. Each pipe section, when in place, shall have a uniform bearing on the supporting soil for the full length of the pipe barrel.

3.5 INSTALLATION - PIPE

A. Install ductile iron pipe in accordance with AWWA C600.

B. Install PVC pipe in accordance with AWWA C605.

C. Unless otherwise indicated on the Drawings, water pipe shall be installed to clear all utility lines and shall have a minimum of 36 inches of cover.

D. Proper equipment shall be used for lowering sections of pipe into trenches. Under no circumstances shall pipe be laid in water and no pipe shall be laid when trench conditions or weather are unsuitable for work. Full responsibility for the diversion of drainage and for dewatering of trenches during construction shall be borne by the Contractor.

E. All dirt and foreign matter shall be removed from the inside of pipe and fittings before they are lowered into the trench. Pipe and fittings shall be kept clean during and after laying. Care shall be taken to keep dirt out of the jointing space.

F. At the end of each day's work, and when pipe laying is discontinued for any appreciable period, open ends of pipe shall be closed with a cast plug or cap securely in place in all openings and at the end of the line.

G. Pipe shall be supported to proper line and grade and secured against upheaval or floating during the placement of bedding.

H. All bends and tie-in assemblies shall require restraint by thrust blocking. Additional restraining devices shall be required as indicated in the Drawings.

I. All pipe and fittings shall be lowered carefully into the trench in such manner as to prevent damage to pipe, fittings, or linings. Neither pipe nor fittings shall be dropped or dumped into the trench.

J. Cutting of pipe, when needed, shall be done in a neat and workmanlike manner without damage to pipe or pipe lining.

K. Unless otherwise directed by the Engineer, pipe shall be laid with bell ends facing the direction of laying. For lines on a appreciable slope, bells shall, at the direction of the Engineer, face upgrade. Wherever necessary to deflect pipe from a straight line in either the horizontal or vertical plan, to avoid any obstructions, or for other acceptable reasons, the degree of deflection at any joint shall not be greater than that recommended by the

pipe manufacturer. Any necessary deflections greater than that recommended shall require fittings.

L. Separation of Water Mains and Sewer Lines

1. Water mains shall be generally laid at least ten (10) feet horizontally from any existing or proposed sewer line. The distance shall be measured from edge to edge. In cases where it is not practical to maintain a ten (10) foot separation, the Engineer, with approval of the Louisiana Department of Health and Human Resources, may allow water main to be installed closer to a sewer line provided that:
   a. Water and sewer mains are laid in separate trenches not less than six (6) feet apart (face to face), or
   b. The water main is laid on an undisturbed earth shelf located on one side of the sewer line at such an elevation that the bottom of the water main is at least 18 inches above the top of the sewer line.
2. Water mains crossing sewers shall be laid to provide a minimum vertical distance of 18 inches between the outside of the water main and the outside of the sewer. This shall be the case where the water main is either above or below the sewer. At crossings, one full length of water pipe shall be located so both joints will be as far from the sewer as possible. Special structural support for the water and sewer pipes, if required, shall be installed by the Contractor at no direct pay.

M. Install valves in accordance with Section 33 12 16.

3.6 THRUST RESTRAINT

A. Class R concrete, as defined in Section 32 05 23, shall be placed at all valves, tees, bends, caps, dead-end, plugs, etc. as detailed in the Drawings. Concrete thrust block shall be placed against undisturbed earth, and shall be located so pipe fittings and joints will be accessible for repair.

B. Additional thrust restraint devices shall be installed as indicated on the Drawings.

3.7 HYDROSTATIC TESTING

A. All hydrostatic testing shall be done in accordance with the manufacturer's specifications, or in accordance with AWWA C600 or AWWA C605, and in accordance with this specification, whichever is more stringent. The contractor shall furnish gages, meters, water and all other material, tools, labor equipment and other necessary assistance of conducting the tests. The Engineer shall be notified at least 48 hours in advance of the hydrostatic test.

B. The pipeline shall be tested with a pressure of 150 psi, maintained over a continuous four (4) hour period. After a successful four (4) hour pressure test has been achieved, a two (2) hour leak test shall be run at the same 150 pound pressure. If the test indicates a leakage in excess of ten (10) gallons per inch of internal pipe diameter per mile of pipeline per 24 hours, the Contractor will be required to find and fix the leak. All known leaks shall be stopped, regardless of this test requirement. The cost of finding and repairing any leak shall be at the Contractor's expense.

C. The Contractor may elect to pressure test against existing valves. However, the Owner does not guarantee the water tightness of existing valves. Should a new water main be tested against an existing valve and the test fails, the contractor must then install proper blocking and retest the system as provided herein, at his expense.

3.8 DISINFECTION OF POTABLE WATER PIPING SYSTEM

A. All new water lines including appurtenances shall be disinfected following the acceptance of the hydrostatic test in accordance with AWWA C651. Mains shall be thoroughly flushed before introduction of the disinfectant.

B. All new mains and repaired portions of, or extensions to, existing mains shall be thoroughly disinfected by the use of chlorine or chlorine compounds before being placed in use. The rate of application of chlorine shall be in such proportion to the rate of water entering the pipe or other appurtenances that the chlorine dose applied to the water shall be at least 50 mg/L. Chlorinated water shall be retained long enough to destroy non-spore-forming bacteria. The period shall be at least three hours and preferably longer, as may be directed. After the chlorine treated water has been retained for the required time, the chlorine residual at pipe extremities and at other representative points shall be at least 5 mg/L. If the residual is less than 5 mg/L, the disinfection procedure shall be repeated until a 5 mg/L residual is obtained, as required above.

C. While the disinfectant is being applied to any section of the system, the water will be allowed to escape at all extremities of this section until the presence of chlorine is evident by measuring with an orthotolidin test kit furnished by the contractor. If bacteriological tests indicate insufficient disinfection at the completion of the test and flushing of the system, the procedure shall be repeated on that part of the system at no additional compensation. The cost of disinfection shall be included in the bid price.

D. The Contractor shall take whatever steps necessary to prevent the backflow of the strong chlorine solution into any existing water distribution system.

E. Water from new systems, or from new parts of existing systems, shall not be furnished for consumer's use until tests performed by a laboratory which is certified by the state health officer have shown the new system or new part of the existing system to be free from contamination by Coliform bacteria (following EPA approved procedures prescribed in *Standard Methods for the Examination of Water and Wastewater*, Nineteenth Edition). Samples shall not be collected from the new facilities until such new facilities have been disinfected as prescribed in Paragraph B above, and the chlorinated water thoroughly flushed from the system.

END OF SECTION

DEPARTMENT OF HEALTH AND HOSPITALS

FACTS

Louisiana Lead Reduction

State of Louisiana Safe Drinking Water Program

Low lead requirements in plumbing and potable water distribution systems:

Concentrations of lead found in drinking water do not typically derive from natural sources. Instead, the most common cause of lead concentrations in potable water is contamination from the gradual corrosion of water supply pipes and plumbing fixtures as well as the solder, or flux, used for installation and repair. Most current regulatory efforts to control lead in drinking water focus primarily on reducing the lead content of these system components.

On June 29, 2011, Gov. Bobby Jindal signed Louisiana House Bill 471 and enacted Act Number 362. This Act takes effect January 1, 2013, and prohibits the use, installation, repair, introduction into commerce, or sale of pipes, fittings, fixtures, solder, or flux that are not "lead free" when used for conveying water for human consumption.

The Department of Health and Hospitals (DHH) has prepared this fact sheet to help clarify how Act 362 redefines "lead-free" and how these new, lowered lead limits will affect various components used in the construction of new and existing plumbing and water distribution projects. In addition, this fact sheet will describe the key components of implementation including code development, applicable performance and material standards, enforcement and exceptions.

Reduced Lead Requirements of Act 362 (effective January 1, 2013):

Under Act 362, the lead content of pipes, fittings and fixtures will be reduced from not more than 8.0 percent lead to not more than a weighted average of 0.25 percent lead when used with respect to the wetted surfaces of pipes, pipe fittings, plumbing fittings and fixtures.

All pipe, plumbing fittings and fixtures, solder or flux used in the installation or repair of any public water system or any plumbing in a facility providing water for human consumption must meet the new low lead requirements, except when necessary for the repair of leaded joints of cast iron pipes.

EXCEPTIONS: The following materials are not required to meet the reduced lead requirements of Act 362:

- Pipes, pipe fittings, plumbing fittings or fixtures, including backflow preventers, which are used exclusively for non-potable services such as manufacturing, fire sprinkler system, industrial processing, irrigation, outdoor watering or any other uses where the water is not anticipated to be used for human consumption; or
- Toilets, bidets, urinals, fill valves, flushometer valves, tub fillers, shower valves, showers, safety shower flushes, service saddles or water distribution main gate valves that are two inches in diameter or larger.
- Materials purchased or acquired by a public water system prior to January 1, 2013, can continue to be utilized until January 1, 2014.

In addition to the installation requirements, no person shall introduce into commerce any pipe, pipe or plumbing fitting or fixture intended to convey or dispense water for human consumption through drinking or cooking that is not lead-free, including kitchen faucets, bathroom faucets or any other end-use devices intended to convey or dispense water for human consumption through drinking or cooking.

Louisiana Administrative Code (LAC) Updates:

These new low-lead requirements will be published in Parts XII (Water Supplies) and XIV (Plumbing)

OVER

of LAC Title 51 (Sanitary Code). Under Parts XII and XIV, all applicable potable water piping, fixtures, pipe related products and materials that join or seal pipes shall be evaluated and listed as conforming with NSF/ANSI 372-Drinking Water System Components, Lead Content or shall be certified to be lead-free by an independent American National Standards Institute (ANSI)-accredited third party testing laboratory, inspection agency or other organization concerned with product evaluation.

Enforcement:

The enforcement of the lead reduction law will be handled during plan reviews, permit inspections, surveys, complaints, etc. For plumbing-related violations, the enforcement will typically be handled at the local level in accordance with their ordinances, laws or other regulations. When handled at the state level, the enforcement process will be in accordance with Part I of LAC Title 51.

Potential Health Effects of Lead Exposure:

- Lead is a neuro-toxic metal that accumulates in both soft tissue and bones. Even low-level exposure can lead to a range of adverse health effects, including brain, nervous system and blood disorders.
- Children and Infants— Exposure can result in delays in physical or mental development, reduced intelligence, learning disabilities, attention deficit disorder, behavioral problems, stunted growth, impaired hearing and kidney damage.
- Adults— Exposure can result in kidney problems, high blood pressure, nerve disorders, fertility problems, muscle and joint pain, irritability, memory and concentration problems. Pregnant women can pass lead contained in their bodies to their fetuses.

Highlighted Facts:

- Act 362 Becomes Effective January 1, 2013.
- Prohibits the use, installation or repair, introduction into commerce, or selling of pipes, fittings, fixtures, solder, or flux that is not “lead-free” when used for conveying water for human consumption.
- Pipes, fittings and fixtures that are used exclusively for non-potable services are not required to meet the reduced lead requirements of Act 362.
- Materials purchased or acquired by a public water system prior to January 1, 2013 can continue to be utilized until January 1, 2014.
- All applicable piping, fixtures, pipe-related products and materials that join or seal pipes shall be evaluated and listed as conforming with NSF/ANSI 372-Drinking Water System Components, Lead Content or shall be certified to be lead free by an independent ANSI-accredited third party testing laboratory.

State of Louisiana
Safe Drinking Water Program
Department of Health and Hospitals
Office of Public Health

628 N. 4th Street
Baton Rouge, LA 70802
Phone: 225-342-7499
Fax: 225-342-7303
www.dhh.la.gov/SafeDrinkingWater

SECTION 331216 - WATER UTILITY DISTRIBUTION VALVES

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Resilient wedge gate valves.
2. Valve boxes.

B. Related Sections:
1. Section 03 30 00 - Cast-In-Place Concrete.
2. Section 31 23 17 - Trenching Excavation and Backfill.
3. Section 33 11 13 - Public Water Utility Distribution Piping.

1.2 REFERENCES

A. American Water Works Association:
1. AWWA C500 - Metal-Seated Gate Valves for Water Supply Service.
2. AWWA C515 – Reduced Wall, Resilient-Seated Gate Valves for Water Supply Service.
3. AWWA C550 - Protecting Epoxy Interior Coating for Valves and Hydrants.
4. AWWA C600 - Installation of Ductile-Iron Water Mains and Their Appurtenances.

B. National Sanitation Foundation:
1. NSF 61 - Drinking Water System Components - Health Effects

1.3 SUBMITTALS

A. Contractor is required to submit six (6) copies of product data for review and approval. The Engineer shall promptly review this data, and return two (2) copies to the Contractor as accepted, or with requested modifications. Contractor to submit data on pipe materials, pipe fittings, valves, meter assemblies, and all accessories.

1.4 DELIVERY, STORAGE AND HANDLING

A. Section 01 60 00 - Product Requirements: Requirements for transporting, handling, storing and protecting products.

B. Prepare valves and accessories for shipment according to AWWA Standards and seal valve and ends to prevent entry of foreign matter into product body.

C. Store products in areas protected from weather, moisture, or possible damage; do not store products directly on ground; handle products to prevent damage to interior or exterior surfaces.

PART 2 PRODUCTS

2.1 RESILIENT WEDGE GATE VALVES – STANDARD TYPE

A. Manufacturers:
1. M & H 7000 Series
2. Mueller A-2360 series.
3. American Darling 2500 series.
4. Clow F-6100 series.
5. Substitutions: Section 01 60 00 - Product Requirements.

B. All gate valves shall be resilient wedge type meeting the requirements of AWWA C-515 except as amended herein. All gate valves shall be provided with “O” ring seals. AWWA C-515 gate valves shall be provided with bronze stem nut and wedge lugs guided within the valve body with machined guides. Gate valves shall open counterclockwise and shall have a working pressure rating of 250 PSI. Gate valves shall have mechanical joint ends for below ground installations and flanged ends for above ground installations.

C. Gate valves 3” or smaller shall be iron body with bronze trim. Valves shall be of the mechanical joint or threaded end type.

2.2 RESILIENT WEDGE GATE VALVES – INSERTION TYPE

A. Manufacturer:
1. Hydra-Stop Insta-Valve 250 Patriot Series.

B. Insertion valve shall be an all stainless steel body resilient wedge gate valve designed for permanent use in potable water. Valve design shall allow the valve to be installed into an existing pressurized pipeline while maintaining constant pressure and service without system shutdown. No restraining devices, restraining fasteners or transition gaskets shall be required for installation or operation of the valve.

C. Traditional line tapping methods shall be used for the installation of all insertion valves to allow removal of a single coupon for system evaluation. Reaming the pipe, complete removal of a section of pipe or milling a slot in the pipe shall be prohibited.

D. All insertion valves shall be installed by companies trained and authorized by the approved valve manufacturer.

E. Valve Body and Bonnet Construction:
1. Insertion valves shall have a stainless steel body, carbon steel epoxy coated bonnet and a reinforced composite polymer valve cartridge to provide corrosion resistance, strength and a pressure rating that meets or exceeds the requirements of resilient seated gate valves.
2. Insertion valves must be capable of working on Cast Iron or Ductile Iron Class A, B, C and D, IPS PVC, C900 and C909 PVC, Steel and AC pipe diameters without changing either top or bottom portion of split valve body or using a transition gasket.

3. Insertion valves must provide a solid support of the host pipe through the entire laying length of the valve body. No gaps or space between the valve body and host pipe shall be accepted.
4. Insertion valves shall be rated for 250 psig maximum working pressure and the pressure rating must be permanently marked into the valve body.
5. Insertion valves must be hydrostatically pressure tested to 1.25 times the system operating pressure (minimum) or 1.5 times the insertion valve's 250 psig maximum pressure rating. The test shall be sustained for a minimum of 15 minutes prior to tapping the host pipe. If the insertion valve body is moved, the pressure test must be completed again before the host pipe is tapped.

F. Resilient Wedge Gate Assembly:
1. Insertion valves shall have an EPDM molded resilient wedge seal affixed into a reinforced composite polymer valve cartridge. The entire assembly shall be inert and impervious to corrosion.
2. The valve cartridge shall be engineered to come into contact with the interior of the host pipe and an engineered sealing surface in the valve body to create a seal. The resilient wedge shall be reinforced where the wedge contacts the host pipe.
3. Pressure equalization on the downstream or upstream side of the closed wedge shall not be necessary to open the valve.
4. The wedge shall be symmetrical and seal equally well with flow in either direction.
5. The resilient wedge must ride inside a minimum of four body channels to maintain wedge alignment throughout its travel and to achieve maximum fluid control.
6. Insertion valves shall have a full size, full port flow way that is unobstructed and free of depressions.

G. Insertion valves shall utilize four O-Rings to seal between valve body to valve bonnet and valve stem. O-Rings shall be located so as to ensure the 250 psig pressure worthiness and prevent ground water and/or foreign materials from entering the valve.

H. Valve Stem:
1. Insertion valves shall be NRS (non-rising stem) and shall operate with standard turns 3 turns per diameter inch to open or close.
2. Insertion valves shall be operated by a 2" square nut, opening left.
3. The valve stem shall be made of stainless steel.
4. The valve stem shall be able to withstand torque of 700 ft. lbs. without compromising operation.
5. The NRS stem shall have an integral stem collar manufactured of no lead bronze. The stem shall be affixed into the valve cartridge to maintain stem alignment, low torque and continuous operation of the valve.

2.3 ECCENTRIC PLUG VALVES

A. Eccentric plug valves shall be of the tightly closing, resilient faced, non-lubricating variety as manufactured by Clow, or approved equal. Valves shall be of eccentric design such that the valve's pressure member (plug) rises off the body seat contact area immediately upon shaft rotation during the opening movement. Valves shall be drop-

tight at the rated pressure (175 psi through 12", 150 psi 14" and above) and shall be satisfactory for applications involving throttling service as well as frequent or infrequent on-off service. The valve closing member should rotate approximately 90 degrees from the full-open to full-closed position and vice-versa.

B. The valve body shall be constructed of cast iron (semi-steel) conforming to ASTM A126, Class B. Body ends shall be:
   1. Flanged with dimensions, facing and drilling in full conformance with ANSI B16.1, Class 125. This includes flange thickness.
   2. Mechanical Joint to meet the requirements of AWWA C111/ANSI A21.11.
   3. Grooved Ends to meet the requirements of AWWA C606.

C. Eccentric plug valves shall have a rectangular shaped port. Port areas for 3" – 20" valves shall be a minimum 80% of full pipe area. Port area for 24" valve shall be a minimum 70% of full pipe area.

D. Valve seat surface shall be welded-in overlay, cylindrically shaped of not less than 90% pure nickel. Seat area shall be raised, with raised area completely covered with weld to ensure proper seat contact. The machined seat area shall be a minimum of .125" thick and .500" wide.

E. The valve plug shall be constructed of cast iron (semi-steel) conforming to ASTM A126, Class B. The plug shall have a cylindrical seating surface that is offset from the center of the plug shafts. The plug shafts shall be integral. The entire plug shall be 100% encapsulated with Buna-N rubber in all valve sizes. The rubber compound shall be approximately 70 (Shore A) durometer hardness. The rubber to metal bond must withstand 75 lbs. pull under test procedure ASTM D-429-73 Method B.

F. Shaft bearings, upper and lower, shall be sleeve type metal bearings, sintered, oil impregnated and permanently lubricated Type 316 stainless steel. Thrust bearings shall be Nylatron.

G. Plug valve shaft seals shall be of the multiple V-ring type (Chevron) and shall be adjustable. All packing shall be replaceable without removing the bonnet or actuator and while the valve is in service. Shaft seals shall be made of Buna-N.

H. Each valve shall be given a test against the seat at the full rated working pressure and a hydrostatic shell test at twice the rated working pressure. Certified copies of individual tests shall be submitted when requested. Certified copies of proof-of-design tests shall be submitted upon request.

I. Manual valves shall have lever or worm gear type actuators with handwheels. Lever actuators shall be furnished on valves 6" and smaller. Worm gear type actuators shall be furnished on valves 8" and larger.

2.4 BUTTERFLY VALVES

A. All butterfly valves shall be of the rubber-seated, tight-closing type. They shall meet or exceed AWWA Standard C-504. All valves shall be Clow Valve Style 4500 butterfly valves, or approved equal.

B. All valves must use full AWWA C-504 Class 150B valve shaft diameter, and full Class 150B underground-service-operator torque rating throughout entire travel, to provide capability for operation in emergency service. All valves shall be NSF approved.

C. Valve body shall be high-strength cast iron ASTM A126 Class B with 18-8 type 304 stainless steel body seat. Valve vane shall be high-strength cast iron ASTM A48 Class 40, having rubber seat mechanically secured with an integral 18-8 stainless steel clamp ring and 18-8 stainless steel self-locked screws.

D. For valves 4”-12” the valve shaft shall be one piece, extending full size through the entire valve. Valve shaft shall be 304 stainless steel. Packing shall be 0-ring cartridge designed for permanent duty in underground service. For 14” and larger valve shaft shall be 18-8 stainless steel stub shaft design keyed to the vane with stainless steel torque plugs.

E. Valve ends shall be one of the following type as indicated in the construction plans:
   1. Wafer Type Body: Suitable for installation between 125# or 150# ASA flanges.
   2. Flanged: Short body valves per Table 2 of AWWA C504. Flanges shall be 125# ANSI.
   3. Mechanical Joint: Both ends of valve shall be “MJ” per AWWA C111. “MJ” accessories (bolts, glands, gaskets) must be supplied by valve manufacturer.

F. Valve operator shall be of the traveling-nut type, sealed, gasketed, and lubricated for underground service. It shall be capable of withstanding an overload input torque of 450 ft. pounds at full-open or full-closed position without damage to the valve or valve operator. It shall be designed for submergence in water to 25 ft head pressure for up to 72 hours.

G. Valve shall be capable of easy closure by one man using standard valve key even under emergency line-break conditions. Operators shall come with easy external adjustment.

H. All manual operators for service other than underground shall have position indicator and shall be totally enclosed and permanently lubricated. All valves shall open left (clockwise to close). In any event, a maximum pull of 80 pounds on the lever shall produce full output torque through entire travel. Operator shall accept 300 pounds pull on lever at full-open and full-closed positions without damage to the valve or operator. Operators shall be of the traveling nut type.

I. Cylinder operator shall be of the base mounted configuration. Cylinder barrel shall be on molybdenum-disulfide lined glass fiber reinforced epoxy tubing, to provide a corrosion-free, self-lubricated high strength barrel. Rod seal shall be urethane, molybdenum-disulfide filled, to provide a self-lubricated, long life seal.

J. Piston rod shall be of hard chromium plated 18-8 stainless steel, and shall be top and bottom guided in a heavy cast iron mechanism housing for positive alignment. Guiding shall be accomplished by bronze bearings at ends of housing straddling all side loads improved in operation. Entire operator including piston rod shall be fully enclosed.

2.5 CHECK VALVES

A. All check valves shall be of the cushioned swing type as manufactured by Mueller, or approved equal. Valves shall be furnished with an external lever and weight unless otherwise specified. Swing check valves shall be constructed with heavy cast iron or cast steel body with a bronze or stainless steel seat ring, a non-corrosive shaft for attachment of the weight and lever, complete non-corrosive cushion chamber, and shall allow for removal of all internal parts without removing the valve body from the line.

B. The cushion chamber shall be attached to the side of the valve body externally and so constructed with a piston operating in a chamber that will effectively permit the valve to be operated without any hammering action. The cushioning shall be by air, and the cushioning chamber shall be so arranged that the closing speed will be adjustable to meet the service requirements.

C. The valve disc shall be of cast iron or cast steel and shall be suspended from a non-corrosive shaft which will pass through a stuffing box and be connected to the cushion chamber on the outside of the valve.

2.6 COMBINATION AIR AND VACUUM RELEASE VALVES

A. All combination air and vacuum release valves shall be guaranteed not to blow shut under normal operating conditions with air flowing into the pipeline or being exhausted from the pipeline via the valve.

B. Valves 2 inches and smaller shall be combination air and vacuum release valves and shall be Crispin Type R or approved equal.

C. Valves 3 inches and larger shall be dual air and vacuum release valves and shall include a small orifice valve for exhausting small quantities of entrained air and a large orifice for inducting as well as exhausting large quantities of air. The combination air/vacuum and pressure release valve shall be Crispin US Series Universal valve or approved equal.

2.7 VALVE BOXES

A. Valve boxes shall be made of cast iron and shall be of the heavy roadway type with an inside diameter of not less than 5 inches.

B. The top section of the valve box shall be adjustable for elevation and shall be of the three-piece screw type.

C. The base shall be sufficiently large so that it will not come in contact with the valve or pipe at any point.

D. The valve box cover shall be cast iron with the designation “water” embossed on the top side and shall be of the bolt-down type.

E. The top of the valve box shall be installed flush with the ground and shall be supported by a 2’ x 2’ x 6” poured in place concrete foundation reinforced with 6”x6”x10 ga. welded wire fabric as shown on the Drawings. Precast concrete pads will not be allowed unless prior approval is received from the owner.

2.8 ACCESSORIES

A. Concrete for Thrust Restraints: Type R Concrete as specified in Section 03 30 00.

PART 3 EXECUTION

3.1 EXAMINATION

A. Section 01 30 00 - Administrative Requirements: Verification of existing conditions before starting work.

B. Determine exact location and size of valves from Drawings; obtain clarification and directions from Architect/Engineer prior to execution of work.

C. Verify invert elevations prior to excavation and installation of valves.

3.2 PREPARATION

A. Identify required lines, levels, contours and datum locations.

B. Locate, identify, and protect utilities to remain from damage.

C. Do not interrupt existing utilities without permission and without making arrangements to provide temporary utility services.
1. Notify Engineer not less than three working days in advance of proposed utility interruption.
2. Do not proceed without written permission from the Engineer.

D. Perform trench excavation, backfilling and compaction in accordance with Section 31 23 17.

3.3 INSTALLATION

A. Install valves in conjunction with pipe laying; set valves plumb.

B. Provide buried valves with valve boxes installed flush with finished grade.

3.4 THRUST RESTRAINT

A. Class R concrete, as defined in Section 03 30 00, shall be placed at all valves, tees, bends, caps, dead-end, plugs, etc. as detailed in the Drawings. Concrete thrust block shall be placed against undisturbed earth, and shall be located so pipe fittings and joints will be accessible for repair.

B. Additional thrust restraint devices shall be installed as indicated on the Drawings.

3.5 DISINFECTION OF POTABLE WATER PIPING SYSTEM

A. Flush and disinfect system in accordance with Section 33 11 13.

3.6 HYDROSTATIC TESTING

A. Pressure test system to in accordance with Section 33 11 13.

END OF SECTION

SECTION 333100 - SANITARY UTILITY SEWERAGE PIPING

PART 1 GENERAL

1.1 SUMMARY

A. Scope of Work:
   1. Furnish all labor, materials, equipment and incidentals required to install and test sewer pipe and fittings, complete as shown on the Drawings and as specified herein.

B. Related Sections:
   1. Section 31 23 17 – Trenching Excavation & Backfill.
   2. Section 33 05 13 – Precast Concrete Manholes and Structures.

1.2 REFERENCES

A. ASTM International:
   1. ASTM A74 - Standard Specification for Cast Iron Soil Pipe and Fittings.
   2. ASTM A746 - Standard Specification for Ductile Iron Gravity Sewer Pipe.
   3. ASTM C564 - Standard Specification for Rubber Gaskets for Cast Iron Soil Pipe and Fittings.
   4. ASTM D698 - Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft3 (600 kN-m/m3)).
   5. ASTM D 1784 - Standard Specification for Rigid Poly Vinyl Chloride (PVC) Compounds and Chlorinated Poly Vinyl Chloride (CPVC) Compounds.
   6. ASTM D2321 - Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications.
   7. ASTM D2729 - Standard Specification for Poly (Vinyl Chloride) (PVC) Sewer Pipe and Fittings.
   8. ASTM D2922 - Standard Test Method for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth).
   9. ASTM D3017 - Standard Test Method for Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth).
   10. ASTM D3034 - Standard Specification for Type PSM Poly (Vinyl Chloride) (PVC) Sewer Pipe and Fittings.
   11. ASTM F477 - Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe.
   12. ASTM F789 - Standard Specification for Type PS-46 and Type PS-115 Poly Vinyl Chloride (PVC) Plastic Gravity Flow Sewer Pipe and Fittings.
   13. ASTM F794 - Standard Specification for Poly Vinyl Chloride (PVC) Profile Gravity Sewer Pipe and Fittings Based on Controlled Inside Diameter.

B. National Sanitation Foundation (NSF)
   1. NSF 14 - Plastic Piping Components and Related Materials.

C. Where reference is made to one of the above standards, the revision in effect at the time of bid opening shall apply.

1.3 DEFINITIONS

A. Bedding: Fill placed under, beside and directly over pipe, prior to subsequent backfill operations.

1.4 SUBMITTALS

A. Product Data: Submit data indicating pipe material used and pipe accessories.

B. Manufacturer's Installation Instructions: Indicate special procedures required to install Products specified.

C. Manufacturer's Certificate: Certify products meet or exceed specified requirements.

1.5 CLOSEOUT SUBMITTALS

A. Project Record Documents: Provide an as-built drawing indicating location of pipe runs, connections, manholes, cleanouts, and invert elevations.

1.6 QUALITY ASSURANCE

A. All pipe and fittings shall be furnished by manufacturers who are fully experienced, reputable and qualified in the manufacture of the pipe to be furnished. The pipe shall be designed, constructed and installed in accordance with the best practices and methods and shall comply with this Section.

B. All pipe and fittings shall be from a single manufacturer. The supplier shall be responsible for the provisions of all test requirements specified in the referenced Standards, as applicable. In addition, all pipe to be installed under this Contract may be inspected at the plant for compliance with the requirements specified herein by an independent testing laboratory provided by the Owner. The Contractor shall require the manufacturers cooperation in these inspections. The cost of plant inspection of all pipe approved for this Contract, plus the cost of inspection of a reasonable amount of disapproved pipe, will be borne by the Owner.

C. Inspections of the pipe may also be made by the Engineer or other representatives of the Owner after delivery. The pipe shall be subject to rejection at any time on account of failure to meet any of the requirements specified herein, even though sample pipes may have been accepted as satisfactory at the place of manufacture. Pipe rejected after delivery shall be marked for identification and shall be removed from the job at once.

1.7 DELIVERY, STORAGE AND HANDLING

A. Care shall be taken in shipping, handling and laying to avoid damaging the pipe and fittings. Extra care will be necessary, during cold weather construction. Any pipe damaged in shipment shall be replaced as directed by the Engineer.

B. Any pipe or fitting showing a crack or which has received a blow that may have caused an incipient fracture, even though no such fracture can be seen, shall be marked as rejected and removed at once from the work.

C. While stored, pipe shall be adequately supported from below at not more than 3-ft intervals to prevent deformation. Pipe shall not be stacked higher than 6-ft. Pipe and fittings shall be stored in a manner which will keep them at ambient outdoor temperatures. Temporary shading as required to meet this requirement shall be provided. Simple covering of the pipe and fittings which allows temperature buildup when exposed to direct sunlight will not be permitted.

1.8 FIELD MEASUREMENTS

A. Verify field measurements and elevations are as indicated in the construction drawings.

B. Notify engineer of any discrepancies or variations from plan dimensions and elevations.

PART 2 PRODUCTS

2.1 SANITARY SEWAGE PIPE

A. Cast Iron Pipe: All cast iron pipe shall conform to the requirements of ASTM A74, Extra Heavy type, inside nominal diameter as indicated in the Drawings, bell and spigot ends.
1. Fittings: Cast iron.
2. Joints: ASTM C564, rubber gasket joint devices.

B. Ductile Iron Pipe: All ductile iron pipe shall conform to the requirements of ASTM A746, Extra Heavy type, inside nominal diameter as indicated in the Drawings, bell and spigot ends.
1. Fittings: Ductile iron.
2. Joints: AWWA C111, rubber gasket joint devices.

C. Polyvinyl Chloride (PVC) Pipe:
1. PVC gravity pipe and fittings shall be Type PSM, SDR 35 with full diameter dimensions and shall conform to ASTM D3034, or Type PS-46 conforming to ASTM F789. Straight pipe shall be furnished in lengths of not more than 13-ft and wyes shall be furnished in lengths of not more than 3-ft. Saddle wyes will not be allowed.
2. PVC pipe and fittings shall have bell and spigot push-on joints. The bell shall consist of an integral wall section with a solid cross-section elastomeric gasket securely locked in place to prevent displacement during assembly. Elastomeric gaskets shall conform to ASTM F477 and ASTM D3212.
3. All fittings and accessories for sewers shall be have bell and/or spigot configurations compatible with the pipe.
4. Each length of pipe and each fitting shall be marked with the name of the manufacturer, nominal size and SDR designation. All gaskets shall be marked with the name of the manufacturer, size and proper insertion direction.

2.2 MANHOLES

A. All manholes shall be in accordance with Section 33 05 13 – Precast Concrete Manholes and Structures.

2.3 BEDDING AND COVER MATERIALS

A. Bedding, Cover and Backfill shall be as specified in Section 31 23 17 – Trenching Excavation and Backfill.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify trench is ready to receive work and excavations, dimensions, and elevations are as indicated on drawings.

3.2 PREPARATION

A. Correct over excavation with fine aggregate.

B. Remove large stones or other hard matter which could damage pipe or impede consistent backfilling or compaction.

3.3 BEDDING

A. Excavate pipe trench in accordance with Section 31 23 17.

B. Place bedding material at trench bottom, level materials in continuous layer not exceeding 6 inches.

C. Maintain optimum moisture content of bedding material to attain required compaction density.

3.4 INSTALLATION - PIPE

A. No single piece of pipe shall be laid unless it is generally straight. The centerline of the pipe shall not deviate from a straight line drawn between the centers of the openings at the ends of the pipe by more than 1/16-in per foot of length. If a piece of pipe fails to meet this requirement check for straightness, it shall be rejected and removed from the site. Laying instructions of the manufacturer shall be explicitly followed.

B. If any defective pipe is discovered after it has been installed, it shall be removed and replaced with a sound pipe in a satisfactory manner at no additional cost to the Owner. All pipe and fittings shall be thoroughly cleaned before installation, shall be kept clean until they are used in the work and when laid, shall conform to the lines and grades required.

C. PVC pipe and fittings shall be installed in accordance with requirements of the manufacturer, ASTM D2321 or as otherwise specified herein. As soon as the excavation is complete to normal grade of the bottom of the trench, bedding material shall be placed, compacted and graded to provide firm, uniform and continuous support for the pipe. Bell holes shall be excavated so that only the barrel of the pipe bears upon the bedding. The pipe shall be laid accurately to the lines and grades indicated on the Drawings. Blocking under the pipe will not be permitted. Horizontal and vertical final position tolerance shall be plus or minus 0.02 feet.

D. All pipe shall be sound and clean before installation. When installation is not in progress, including lunchtime, the open ends of the pipe shall be closed by watertight plug or other approved means. Good alignment shall be preserved during installation. The deflection at joints shall not exceed that recommended by manufacturer. Fittings, in addition to those shown on the plans, shall be provided, if required, in crossing utilities which may be encountered upon opening the trench.

E. When cutting pipe is required, the cutting shall be done by machine, leaving a smooth cut at right angles to the axis of the pipe. Cut ends of pipe to be used with a bell shall be beveled to conform to the manufactured spigot end.

F. The Engineer may examine each bell and spigot end to determine whether any preformed joint has been damaged prior to installation. Any pipe having defective joint surfaces shall be rejected, marked as such, and immediately removed from the job site.

G. Each length of the pipe shall be shoved home against the pipe previously laid and held securely until enough backfill has been placed to hold the pipe in place. Joints shall not be “pulled” or “cramped”.

H. Before any joint is made, the pipe shall be checked to assure that a close joint with the next adjoining pipe has been maintained and that the inverts are matched and conform to the required grade. The pipe shall not be driven down to grade by striking it.

I. Precautions shall be taken to prevent flotation of the pipe in the trench.

J. When moveable trench bracing such as trench boxes, moveable sheeting, shoring or plates are used to support the sides of the trench, care shall be taken in placing and moving the boxes or supporting bracing to prevent movement of the pipe, or disturbance of the pipe bedding and the screened gravel backfill. Trench boxes, moveable sheeting, shoring or plates shall not be allowed to extend below mid-diameter of the pipe. As trench boxes, moveable sheeting, shoring or plates are moved, screened gravel shall be placed to fill any voids created and the screened gravel and backfill shall be recompacted to provide uniform side support for the pipe.

K. Lay pipe to slope gradients noted on drawings; with maximum variation from indicated slope of 1/8 inch in 10 feet.

L. Install bedding at sides and over top of pipe to minimum compacted thickness of 12 inches.

M. Refer to Section 31 23 17 for backfilling and compacting requirements. Do not displace or damage pipe when compacting.

3.5 INSTALLATION – JOINTING METHODS

A. Sewer pipe and fittings shall be jointed in accordance with the recommendations of the latest ASTM Standards and detailed instructions of the manufacturer.

B. All manhole connections shall be as shown on the Drawings except that concrete and mortared connections shall be equipped with an integral 0-ring or other sealant such that a positive watertight seal is established. The Contractor shall be responsible for repairing all damage to manholes where pipe connections are made.

3.6 INSTALLATION – WYE BRANCHES, CHIMNEYS AND STUBS

A. All fittings shall be furnished by the same manufacturer that furnishes the pipe.

B. Wye branches shall be furnished and installed and capped in locations directed by the Engineer. Each wye branch shall be provided with an end cap and shall be backed with a piece of wood (2-in by 4-in) that extends to a point 3-ft below the finished ground surface.

C. Chimneys shall be installed according to the detail on the Drawings at locations to be determined by the Engineer.

D. Ample time shall be given to the Engineer to obtain the exact location of each wye branch and chimney before it is covered up. Wye branches and chimneys, which are covered before the Engineer has had time to obtain their location, shall be exposed so that location measurements can be taken.

E. Manhole drops shall be installed as shown on the Drawings or directed by the Engineer.

F. Pipe stubs for manhole connections shall not exceed 3.25-ft in length unless directed otherwise by the Engineer. Install caps where required.

3.7 INSTALLATION – SERVICE CONNECTIONS

A. Service connections shall be installed at a minimum slope of 1 percent at the locations and to the limits as shown on the Drawings. The end shall be capped and backed with a 2-in by 4-in wood post extending to 3-ft below the finished ground surface.

B. Service connections shall be 6-in diameter unless otherwise shown on the Drawings.

C. Service connections shall include cleanout as detailed in the Drawings.

3.8 INSTALLATION - MANHOLES

A. Install manholes in accordance with Section 33 05 13 – Precast Concrete Manholes and Structures.

3.9 FIELD QUALITY CONTROL

A. Leakage Tests
   1. Prior to final inspection of the project, the Contractor shall, at his own expense, conduct a water leakage test for the entire collection and disposal system. The leakage outward or inward (exfiltration or infiltration) shall not exceed 100 gallons per inch of pipe diameter per mile per day for any section of the system.
   2. A low pressure air test may be conducted in lieu of the above water test with prior approval of the Engineer. The low pressure air test shall consist of pressurizing each segment of sewer main to 4 psi for 5 minutes. No loss of air pressure is allowed.
   3. All tests shall be conducted under the direct supervision of the Engineer or his representative. The Contractor shall provide 48 hours notice to the Engineer prior to conducting these tests.

B. Allowable Deflection Test
   1. Pipe deflection measured not less than 90 days after the backfill has been completed as specified shall not exceed *5* percent. Deflection shall be computed by multiplying the amount of deflection (nominal diameter less minimum diameter when measured) by 100 and dividing by the nominal diameter of the pipe.
   2. Deflection shall be measured with a rigid mandrel (Go/No-Go) device cylindrical in shape and constructed with a minimum of 9 or 10 evenly spaced arms or prongs. Drawings of the mandrel with complete dimensions shall be submitted to the Engineer for each diameter of pipe to be tested. The mandrel shall be hand pulled through all sewer lines.

C. Any section of sewer not passing the mandrel shall be uncovered at no additional cost to the Owner and the bedding and backfill replaced to prevent excessive deflection. Repaired pipe shall be retested.

D. When tests indicate Work does not meet specified requirements, remove work, replace and retest.

3.10 PROTECTION OF FINISHED WORK

A. Protect pipe and aggregate cover from damage or displacement until backfilling operation is in progress.

END OF SECTION

SECTION 334000 - STORM DRAINAGE UTILITIES

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Storm drainage piping.
2. Accessories.
3. Underground pipe markers.
4. Catch basins and plant area drains.
5. Cleanouts.
6. Bedding and cover materials.

B. Related Sections:
1. Section 32 05 23 – Cement & Concrete for Exterior Improvements
2. Section 31 23 17 – Trenching Excavation & Backfill

1.2 REFERENCES

A. American Association of State Highway and Transportation Officials:
1. AASHTO HB - Standard Specifications for Highway Bridges.
2. AASHTO M36 - Standard Specification for Corrugated Steel Pipe, Metallic-Coated, for Sewers and Drains.
3. AASHTO M190 - Standard Specification for Bituminous-Coated Corrugated Metal Culvert Pipe and Pipe Arches.
4. AASHTO M198 - Standard Specification for Joints for Concrete Pipe, Manholes, and Precast Box Sections Using Preformed Flexible Joint Sealants.
5. AASHTO M218 - Standard Specification for Steel Sheet, Zinc-Coated (Galvanized), for Corrugated Steel Pipe.
6. AASHTO M245 - Standard Specification for Corrugated Steel Pipe, Polymer-Precoated, for Sewers and Drains.
7. AASHTO M246 - Standard Specification for Steel Sheet, Metallic-Coated and Polymer-Precoated, for Corrugated Steel Pipe.
8. AASHTO M315 - Standard Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets.
9. AASHTO T180 - Standard Specification for Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and a 457-mm (18-in.) Drop.

B. ASTM International:
1. ASTM A742 - Standard Specification for Steel Sheet, Metallic-Coated and Polymer-Precoated for Corrugated Steel Pipe.
2. ASTM A760 - Standard Specification for Corrugated Steel Pipe, Metallic-Coated for Sewers and Drains.
3. ASTM A762 - Standard Specification for Corrugated Steel Pipe, Polymer-Precoated for Sewers and Drains.
4. ASTM A798 - Standard Practice for Installing Factory-Made Corrugated Steel Pipe for Sewers and Other Applications.

5. ASTM A849 - Standard Specification for Post-Applied Coatings, Pavings, and Linings for Corrugated Steel Sewer and Drainage Pipe.
6. ASTM A929 - Standard Specification for Steel Sheet, Metallic-Coated by the Hot-Dip Process for Corrugated Steel Pipe.
7. ASTM C76 - Standard Specification for Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe.
8. ASTM C443 - Standard Specification for Joints for Circular Concrete Sewer and Culvert Pipe, Using Rubber Gaskets.
9. ASTM C506 - Standard Specification for Reinforced Concrete Arch Culvert, Storm Drain, and Sewer Pipe.
10. ASTM C990 - Standard Specification for Joints for Concrete Pipe, Manholes, and Precast Box Sections Using Preformed Flexible Joint Sealants.
11. ASTM D698 - Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft3 (600 kN-m/m3)).
12. ASTM D1784 - Standard Specification for Rigid Poly (Vinyl Chloride) (PVC) Compounds and Chlorinated Poly (Vinyl Chloride) (CPVC) Compounds.
13. ASTM D2321 - Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications.
14. ASTM D2412 - Standard Test Method for Determination of External Loading Characteristics of Plastic Pipe by Parallel-Plate Loading.
15. ASTM D3034 - Standard Specification for Type PSM Poly (Vinyl Chloride) (PVC) Sewer Pipe and Fittings.
16. ASTM D3212 - Standard Specification for Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals.
17. ASTM D3350 - Standard Specification for Polyethylene Plastic Pipe and Fittings Materials.
18. ASTM F477 - Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe.
19. ASTM F794 - Standard Specification for Poly (Vinyl Chloride) (PVC) Profile Gravity Sewer Pipe and Fittings Based on Controlled Inside Diameter.
20. ASTM F949 - Standard Specification for Poly (Vinyl Chloride) (PVC) Corrugated Sewer Pipe with a Smooth Interior and Fittings.
21. ASTM F2306 - Standard Specification for 12 to 60 inch Annular Corrugated Profile-Wall Polyethylene (PE) Pipe and Fittings for Gravity-Flow Storm Sewer and Subsurface Drainage Applications.
22. ASTM F2648 - Standard Specification for 12 to 60 inch Annular Corrugated Profile Wall Polyethylene (PE) Pipe and Fittings for Land Drainage Applications.

C. National Corrugated Steel Pipe Association (NCSPA)

1.3 SUBMITTALS

A. Product Data: Submit data indicating pipe and pipe accessories.

B. Manufacturer's Installation Instructions: Submit special procedures required to install Products specified.

C. Manufacturer's Certificate: Certify Products meet or exceed specified requirements.

1.4 QUALITY ASSURANCE

A. Perform Work in accordance with Louisiana Standard Specifications for Roads and Bridges, Latest Edition.

PART 2 PRODUCTS

2.1 STORM DRAINAGE PIPING

A. Reinforced Concrete Pipe and Pipe Arch (RCP & RCPA): Circular pipe shall comply with the requirements of ASTM C76, Class III, wall thickness "B" unless otherwise noted on the Drawings. Arch pipe shall comply with the requirements of ASTM C506. The joint design for reinforced concrete pipe shall be bell and spigot or tongue and grove. Pipe joints shall incorporate preformed flexible joint sealant in accordance with the requirements of AASHTO M198/ASTM C990 or rubber gaskets in accordance with the requirements of AASHTO M315/ASTM C443. Joint sealants/gaskets shall be installed in strict accordance with the pipe manufacturer's recommendations. All concrete pipe joints shall be wrapped with filter fabric.

B. High-Density Polyethylene Pipe (HDPE): Pipe shall comply with the requirements of ASTM F2648 and shall have a smooth interior and annular exterior corrugations. Joints shall be watertight in accordance with ASTM D3212 with gaskets meeting the requirements of ASTM F477. Gaskets shall be installed by the manufacturer and covered with a removable, protective wrap to ensure gasket is free from debris. Pipe shall have a reinforced bell with a polymer composite band. HDPE fittings shall comply with the requirements of ASTM F2306. Material for pipe production shall be an engineered compound of virgin and recycled high-density polyethylene conforming with the minimum requirements of cell classification 435420C as defined by ASTM D3350.

C. Corrugated Metal Pipe and Pipe Arch (CMP & CMPA): Pipe shall be either bituminous coated steel pipe in accordance with AASHTO M36/ASTM A760 or polymer coated steel pipe in accordance with AASHTO M245/ASTM A762. Bituminous coating shall conform to the applicable requirements of AASHTO M190/ASTM A849. Polymer coated steel coils shall conform to the requirements of AASHTO M246/ASTM A742. Polymer coating shall be "Trenchcoat" by Dow Chemical, or approved equal. Pipe gauge shall be 14 minimum. Coupling bands for joining metal conduit shall comply with AASHTO M36/ASTM A760 and shall be fabricated from metal sheets of the same material and shall have the same thickness and coating as the conduit. All metal pipe joints shall be wrapped with filter fabric.

D. Ribbed Polyvinyl Chloride Pipe (RPVCP): PVC corrugated pipe and fittings with a smooth interior shall conform to the requirements of ASTM F949, Series 46 with UV inhibitors. Pipe and fittings shall be homogeneous throughout and free from visible cracks, holes, foreign inclusions or other injurious defects. Pipe shall be manufactured to 46 PSI stiffness when tested in accordance with ASTM D2412. The pipe shall be made of PVC compound having a minimum cell classification of 12454 as defined in ASTM D1784. To insure compatibility, the pipe manufacturer shall provide all fittings. All joints shall be made with integrally-formed bell and spigot gasketed connections. Gaskets shall meet the requirements of ASTM F477.

E. Polyvinyl Chloride Pipe (PVC): Pipe and fittings shall be Type PSM, SDR 35 with full diameter dimensions and shall conform to ASTM D3034. Pipe and fittings shall have bell and spigot push-on joints. The bell shall consist of an integral wall section with a solid cross-section elastomeric gasket securely locked in place to prevent displacement during assembly. Joints shall conform to the requirements of ASTM D3212 with gaskets conforming to ASTM F477.

F. Corrugated Polypropylene Pipe (CPP):
1. Pipe shall be smooth interior and annular exterior corrugated polypropylene (PP) pipe meeting the requirements of ASTM F2764, ASTM F2881 or AAHSHTO M330 Type S (double-wall) or Type D (triple-wall).
2. Material for pipe and fitting production shall be an impact modified copolymer meeting requirements of ASTM F2764, ASTM F2881 and AASHTO M330.
3. The following shall be clearly marked on both the interior and exterior surface of the pipe:
    1) ASTM Specifications: ASTM F2764, ASTM F2881 or AASHTO M330, as appropriate.
    2) Class, size and wall.
    3) Date of manufacture.
    4) Name or trademark of manufacturer.
    5) Diameter of Pipe. The diameter indicating in the construction drawings shall mean the inside diameter of the pipe.
4. Water tight joints shall be bell and spigot meeting the watertight requirements of ASTM D3212. Gaskets shall comply with the requirements of ASTM F477. Gaskets shall be installed by the pipe manufacturer and covered with a removable wrap to ensure the gasket is free from debris. A joint lubricant supplied by the manufacturer shall be used on the gasket and bell during assembly.
5. Fittings shall conform to ASTM F2764, ASTM F2881 or AASHTO M330, with the exception of meeting the watertight joint performance requirements of ASTM D3212. Gasketed bell and spigot connections shall utilize a spun-on, welded or integral bell and spigot with gaskets meeting ASTM F477.

2.2 CATCH BASINS, AREA DRAINS AND JUNCTION BOXES

A. Catch basin lid and frame shall be cast iron or galvanized steel construction per details included in the Drawings.

B. Cast-in-place concrete, Class M as specified in Section 32 05 23.

2.3 BEDDING AND COVER MATERIALS

A. Bedding: If required, as specified in Section 31 23 17.

B. Soil Backfill from Above Pipe to Finish Grade: As specified in Section 31 23 17.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify trench cut and excavation base is ready to receive work and excavations, dimensions, and elevations are as indicated on Drawings.

3.2 PREPARATION

A. Hand trim excavations to required elevations. Correct over excavation with fine aggregate.

B. Remove large stones or other hard matter which could damage piping or impede consistent backfilling or compaction.

3.3 BEDDING

A. Excavate pipe trench in accordance with Section 31 23 17 for work of this Section. Hand trim excavation for accurate placement of pipe to elevations indicated.

B. Place bedding material, if required, at trench bottom, level materials in continuous layer not exceeding 6 inches compacted depth.

C. Maintain optimum moisture content of bedding material to attain required compaction density.

D. Remove large stones or other hard matter which could damage piping or impede consistent backfilling and/or compaction.

3.4 INSTALLATION - PIPE

A. Install pipe, fittings, and accessories in accordance with ASTM D2321, ASTM A798 or manufacturer’s recommendations. Seal joints watertight.

B. Place pipe on bedding, if required, in accordance with Section 31 23 17.

C. Lay pipe to slope gradients noted on Drawings.

D. Pipe shall be laid with bell ends facing in the direction of laying and shall progress uphill.

E. Where ground water occurs, pumping shall continue until backfilling has progressed to a sufficient height to prevent flotation of pipe. Water shall be disposed of in such a manner as to cause no property damage or be a hazard to public health.

F. Refer to Section 31 23 17 for trenching, backfilling and compacting requirements. Do not displace or damage pipe when compacting.

G. Wrap pipe joints with a minimum 24 inch wide strip of filter fabric. Lap ends of fabric a minimum of 12” and securely band fabric to pipe at each end.

3.5 INSTALLATION - CATCH BASINS, AREA DRAINS AND JUNCTION BOXES

A. Form bottom of excavation clean and smooth to correct elevation.

B. Form and place cast-in-place concrete base pad, with provision for storm sewer pipe to be placed at proper elevations.

C. Establish elevations and pipe inverts for inlets and outlets as indicated on Drawings.

D. Form and construct cast-in-place concrete walls with sleeves at proper elevations to accept required storm sewer pipe.

E. Mount lid and frame and form/construct cast-in-place concrete top to proper elevation to ensure positive drainage as indicated on Drawings.

F. Grout all interior surfaces of structure as required to provide a watertight installation.

3.6 FIELD QUALITY CONTROL

A. Request inspection prior to placing backfill cover over pipe.

B. Compaction Testing: In accordance with ASTM D698.

C. When tests indicate work does not meet specified requirements, remove work, replace and retest.

3.7 PROTECTION OF FINISHED WORK

A. Protect pipe from damage or displacement until backfilling operation is complete.
   1. Take care not to damage or displace installed pipe and joints during construction of pipe supports, backfilling, testing, and other operations.
   2. Repair or replace pipe that is damaged or displaced from construction operations.

END OF SECTION