



- DETAIL No. 1
SIDEWALK DRAIN CHANNEL
- NOTES:
1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DISTURBED AREAS.
 2. THIS SHEET SHALL BE USED IN CONJUNCTION WITH A STORMWATER POLLUTION PREVENTION PLAN PREPARED FOR THE SITE. (SWPP BY OTHERS)
 3. THE CONTRACTOR SHALL STABILIZE SILT FENCE WITH WELDED WIRE FABRIC AS DEEMED NECESSARY BY THE ENGINEER AT NO DIRECT PAY.
 4. THE LIMITS OF CONSTRUCTION SHALL BE LIMED, FERTILIZED & SEEDED WITHIN 14 DAYS OF ANY WORK STOPAGE OR UPON CONTRACT COMPLETION. SEEDING SHALL MEET REQUIREMENT OF LSSRB LATEST EDITION FOR TIME OF YEAR.
 5. THE CONTRACTOR SHALL USE ANY EROSION CONTROL MEANS NECESSARY TO PREVENT SILT FROM LEAVING SITE OR ENTERING DRAINS.
 6. SILT FENCE WILL BE USED AS DIRECTED BY THE ENGINEER AND CHECK DAMS AS SHOWN ON THIS SHEET SHOULD NOT BE CONSIDERED FINAL PLACEMENT OR FINAL QUANTITY. MORE SILT FENCE AND CHECK DAMS MAY BE REQUIRED FOR EROSION CONTROL.
 7. ALL AREAS OUTSIDE OF PAVING THAT ARE DISTURBED SHALL BE GRADED SUCH THAT A MINIMUM OF 3 INCHES OF TOPSOIL MAKE UP THE FINAL GRADE.
 8. AFTER ALL GRASS HAS BEEN FULLY ESTABLISHED THE CONTRACTOR SHALL PAINT ALL FIELD LINES SHOWN ON THIS SHEET WITH WHITE PAINT.

- DRAIN ARROW
- 68.4 EXISTING SURFACE GRADES
- × 69.0 PROPOSED SURFACE GRADES

1439 Centre Ct., Ste 401
Alexandria, LA 71301
Ph: 318.445.3151
Fx: 318.445.3988
Em: adg@adgllc.net

Fontenot & Associates, LLC
2025 Jackson Street
Alexandria, LA 71301
Office: 318.427.7808
CONSULTANT (IF APPLICABLE)

PHASE 2 - RENOVATIONS TO
CARTER C. RAYMOND
JUNIOR HIGH SCHOOL
2510 SAINT CHARLES AVE, LECOMPTE, LA 71346

PROJECT NO: SCF
DRAWN: SCF
CHECKED: SCF
DATE: 08.15.25
LAST REV: 08.15.25

C-103