

**DATE:** November 14, 2025

**MEMO TO:** All Plan Holders on Record

**FROM:** Ashe Broussard Weinzettle Architects LLP

**Project:** Tioga Elementary School Addition to Gymnasium  
Rapides Parish School Board – RPSB Bid 11-25-07  
Tioga Elementary School  
Architect Project Number: 2023.11.3.3

**RE:** Addendum Number One (1)

The following additions, deletions, changes, supplemental information or clarifications are hereby made part of the Contract Documents for the above referenced project:

1. SPECIFICATIONS, Section 0965 00, Resilient Flooring
  - a. 2.1.A: Approved equals to Tarkett Omni sport:
    - a. Mondo, Advance
    - b. Ecore, Baller
2. SPECIFICATIONS, add the following sections
  - a. 32 92 19, Sodding
  - b. 31 25 13, Erosion Control Devices
  - c. 31 05 15, Soils for Earthwork
  - d. 31 20 00, Earth Moving - Building Area Only (Structural)
  - e. 31 22 13, Rough Grading
  - f. 31 23 17, Trenching, Bedding and Backfill for Drainage and Utilities
3. All areas of the site disturbed by construction activities shall be sodded, as per specification.
4. Re: SPECIFICATIONS, Supplemental Conditions:
  - a. 3.7.2 – change “State” to RPSB”.
5. Re: SPECIFICATIONS, Section 01 23 00, Base Bid and Alternate.
  - a. 1.2.A – Change to read “All work indicated for construction of “Tioga Elementary School Addition to Gymnasium””.
6. Re: SPECIFICATIONS, Section 01 40 00, Quality Requirements:
  - a. 1.7.B Mock-up Required:
    - i. Change B to C.
    - ii. Delete line “a. Exterior Windows...” entirely
7. Accompanying this addendum is soils investigation report which is hereby made part of the project Specifications as “Appendix A”.
8. Re: SPECIFICATIONS, Section 06 20 00, Finish Carpentry:
  - a. 2.2.B: add at the end of the sentence “or BIRCH at Contractor option.”
9. Re: SPECIFICATIONS, Section 7 27 26, Fluid Applied Membrane Air Barriers:
  - a. 2.1.A: add “4. StoGuard by StoCorporation”.

- a. 1.2.A.1: add to end of sentence "...to match existing at Gym Building."
- 11. Re: SPECIFICATIONS, 08 14 00, Wood Doors:
  - a. 2.1.B: revise to read "...type to be STAIN GRADE MAPLE OR BIRCH or equal."
- 12. Provide and install one (1) fire extinguisher and cabinet, as per Specifications, in location as directed by Architect.
- 13. Re: DRAWINGS:
  - a. A2.0, 1/A2.0, STORAGE 100 – change keynote 89 to 31.
  - b. A2.2
    - i. 9/A2.2 – delete keynote 118  
-change keynote 74 to 31 in two (2) locations
    - ii. 10/A2.2 – change keynote 74 to 31.
  - c. A2.3, Keynotes
    - i. Add keynote "54 – TPO membrane roofing system on coverboard. ADD. ALT."
    - ii. Add keynote numbers 62 and 63 after 61 in the note column.
  - d. A4.0
    - i. 1/A4.0 – add keynote 80 at water fountain
    - ii. 4/A4.0 – change keynote 3 to 39.
    - iii. 5/A4.0 – change keynote 23 to 22.  
-change keynote 7 to 19.
  - e. A5.0
    - i. 2/A5.0 – change keynotes 133 to 104 in two (2) locations  
-change keynote 104 to 133.
    - ii. 3/A5.0 – change keynote 109 to 108.  
-change keynote 30 to 112.
    - iii. 4/A5.0 – change keynotes 29 to 35 at soldier courses, two (2) locations.
    - iv. Keynotes – revise as follows:
      - 1. 104 – add "18ga." before "anchor".
      - 2. 112 – add "wall girt, see STRUCTURAL".
      - 3. 133 – add "Zee-closure, typical to roofing system."
      - 4. 30 – change to read "Roof purlins, see STRUCTURAL..."
  - f. A5.1
    - i. 1/A5.1 – change keynote 83 to 93.
    - ii. 2/A5.1 – change keynote 81 to 108.
    - iii. 3/A5.1 – change keynote 18 to 16.

End of Addendum Number One (1)