



- ### MECHANICAL KEYED NOTES
- NEW 2X2 CEILING SUPPLY DIFFUSER. PROVIDE NEW SPIN-COLLAR, HARD ROUND DUCTWORK AND FLEX DUCTWORK. BALANCE TO CFM INDICATED. REFER TO SCHEDULE.
 - NEW 2X2 CEILING SUPPLY DIFFUSER. PROVIDE NEW SPIN-COLLAR, HARD ROUND DUCTWORK, DIFFUSER TO HAVE BALANCE AT FACE CAPABILITIES. DO NOT INSTALL FLEX DUCTWORK ABOVE HARD CEILING. PROVIDE GYPSBOARD MOUNTING KIT WHEN LOCATED IN GYPSBOARD CEILING. BALANCE TO CFM INDICATED. REFER TO SCHEDULE.
 - NEW 141 CEILING SUPPLY DIFFUSER. PROVIDE NEW SPIN-COLLAR, HARD ROUND DUCTWORK, DIFFUSER TO HAVE BALANCE AT FACE CAPABILITIES. DO NOT INSTALL FLEX DUCTWORK ABOVE HARD CEILING. PROVIDE GYPSBOARD MOUNTING KIT WHEN LOCATED IN GYPSBOARD CEILING. BALANCE TO CFM INDICATED. REFER TO SCHEDULE.
 - NEW 2X2 CEILING RETURN/TRANSFER GRILLE. PROVIDE GYPSBOARD MOUNTING KIT WHEN LOCATED IN GYPSBOARD CEILING. PROVIDE RETURN/ROUND BOOT ON GRILLE FACING AWAY FROM FPB'S AND OTHER TRANSFER DUCTS WHERE INDICATED. REFER TO SCHEDULE.
 - NEW SIDE WALL SUPPLY AIR DRUM STYLE DIFFUSER WITH SUPPLY DUCTWORK BEHIND. PROVIDE NEW SPIN-IN ALL DRUM DIFFUSERS TO BE LOCATED AT SIMILAR HEIGHT ON WALL. MOUNT ALL DRUM DIFFUSERS AS HIGH AS POSSIBLE. OPPOSED BLADE DAMPER TO BE ACCESSIBLE THROUGH FACE OF REGISTER. DRUM DIFFUSERS TO BE PROVIDED WITH ADJUSTABLE AIR VANES. COORDINATE LOCATION WITH ARCHITECT. REFER TO SCHEDULE.
 - NEW SIDE RETURN AIR GRILLE WITH RETURN AIR BOOT BEHIND. ALL SIDE WALL GRILLES TO BE LOCATED AT SIMILAR HEIGHT ON WALL. MOUNT ALL SIDE WALL GRILLES AS HIGH AS POSSIBLE. COORDINATE LOCATION WITH ARCHITECT. REFER TO SCHEDULE.
 - NEW THERMOSTAT/SENSOR. PROVIDE NEW CONTROL WIRING. FIELD VERIFY EXACT FINAL LOCATION WITH ARCHITECT PRIOR TO INSTALLATION TO AVOID CONFLICT WITH SHELVING, FURNITURE, ETC.
 - NEW COOLING/HEATING FAN POWERED BOX. PROVIDE NEW DDC SENSOR/T-STAT. REFER TO SCHEDULE AND DETAIL FOR MORE INFORMATION. MAINTAIN CLEARANCE FOR MAINTENANCE AROUND BOX.
 - NEW COOLING ONLY VAV BOX. PROVIDE NEW DDC SENSOR/T-STAT. REFER TO SCHEDULE AND DETAIL FOR MORE INFORMATION. MAINTAIN CLEARANCE FOR MAINTENANCE AROUND BOX.
 - NEW INDOOR WALL MOUNTED EVAPORATOR UNIT. COORDINATE FINAL LOCATION IN THE FIELD. REFER TO MECHANICAL HYDRONIC/REFRIGERANT PIPING PLANS FOR PIPE ROUTING. MAINTAIN MAINTENANCE ACCESS CLEARANCES FOR UNIT. ROUTE UNITS FULL SIZED CONDENSATE DRAIN LINE TO NEW INSULATED HUB DRAIN, MOP SINK, MECHANICAL ROOM FLOOR DRAIN OR OTHER CODE APPROVED LOCATION. PROVIDE WITH INTEGRAL CONDENSATE PUMP. PROVIDE WITH FACTORY PROGRAMMABLE THERMOSTAT.
 - PROVIDE AND INSTALL NEW CEILING EXHAUST FAN. PROVIDE FAN WITH BACKDRAFT DAMPER. REFER TO SCHEDULE.
 - PROVIDE AND INSTALL NEW HOT WATER COIL. REFER TO SCHEDULE AND DETAIL. FIELD VERIFY ALL SIZES. COIL TO BE INSTALLED TO MATCH DUCTWORK SIZES. REFER TO MECHANICAL HYDRONIC PLAN FOR MORE INFORMATION.
 - NEW WALL MOUNTED ALUMINUM LOUVER SIMILAR TO GREENHECK MODEL ESD-435DE OR APPROVED EQUAL TO BE INSTALLED AND USED FOR OUTSIDE AIR. PAINT TO MATCH EXTERIOR WALL COLOR OR OTHER COLOR AS REQUIRED BY THE ARCHITECT. PROVIDE AND TRANSITION NEW CONNECTION TO NEW OUTSIDE AIR SUPPLY FAN AS SHOWN. PROVIDE BIRDSCREEN AT LOUVER. PROVIDE PLENUM DUCTWORK BEHIND LOUVER TO BE SAME SIZE AS LOUVER. COORDINATE EXACT LOUVER LOCATION AND ALL WORK WITH ARCHITECT PRIOR TO INSTALL.
 - NEW WALL MOUNTED ALUMINUM LOUVER SIMILAR TO GREENHECK MODEL ESD-435DE OR APPROVED EQUAL TO BE INSTALLED AND USED FOR EXHAUST AIR. PAINT TO MATCH EXTERIOR WALL COLOR OR OTHER COLOR AS REQUIRED BY THE ARCHITECT. PROVIDE AND TRANSITION NEW CONNECTION TO NEW EXHAUST FANS AS SHOWN. PROVIDE BIRDSCREEN AT LOUVER. PROVIDE PLENUM DUCTWORK BEHIND LOUVER TO BE SAME SIZE AS LOUVER. COORDINATE EXACT LOUVER LOCATION AND ALL WORK WITH ARCHITECT PRIOR TO INSTALL.
 - NEW TRANSFER AIR DUCT BOOT ACROSS WALL TO DECK. MINIMUM SIZE OF 24" BY 12" UNLESS OTHERWISE INDICATED ON PLAN. REFER TO DETAILS.
 - PROVIDE NEW MOTORIZED OUTSIDE AIR DAMPER. DAMPER TO BE INTERLOCKED WITH ASSOCIATED FOCUS OPERATION. DAMPER TO BE CLOSED WHEN UNIT IS "OFF". FIELD VERIFY EXACT LOCATION.
 - PROVIDE AND INSTALL NEW COMBINATION FIRE/SMOKE DAMPER AS SHOWN. PROVIDE NEW DUCT SEALING AND FIRE CAULK/SEAL AROUND NEW DUCT. REFER TO DETAIL. FIELD VERIFY ALL SIZES. ALL FIRE DAMPERS INSTALLED IN NEW DUCTS TO MATCH NEW DUCTWORK SIZES.
 - PROVIDE AND INSTALL NEW FIRE DAMPER AS SHOWN. PROVIDE NEW DUCT SEALING AND FIRE CAULK/SEAL AROUND NEW DUCT. REFER TO DETAIL. FIELD VERIFY ALL SIZES. ALL FIRE DAMPERS INSTALLED IN NEW DUCTS TO MATCH NEW DUCTWORK SIZES.
 - PROVIDE AND INSTALL NEW EXTERIOR DRYER VENT CAP. COORDINATE EXACT FINAL LOCATION IN THE FIELD. COORDINATE PAINTING/FINISH WITH ARCHITECT PRIOR TO INSTALLATION.
 - OUTSIDE AIR DUCT RISER UP THROUGH FLOOR AND LEVELS ABOVE TO ROOF INTAKE HOOD. REFER TO MECHANICAL PLANS FOR CONTINUATION.
 - KITCHEN EXHAUST DUCTWORK DOWN THROUGH FLOORS TO KITCHEN DRAIN ROOM TO SERVE KITCHEN HOOD. REFER TO MECHANICAL PLANS FOR CONTINUATION.
 - REFER TO ENLARGED MECHANICAL ROOM PLAN FOR ALL MECHANICAL KEYED NOTES AND INFORMATION.
 - PROVIDE AND INSTALL NEW DRYER BOOSTER FAN SIMILAR TO FANTECH DBF OR APPROVED EQUAL INSTALLED IN DRYER EXHAUST DUCT. PROVIDE TRANSITION(S) AND TURN(S) AS REQUIRED TO INSTALL IN DUCT. FAN TO BE INTERLOCKED WITH ASSOCIATED DRYER. MAINTAIN MANUFACTURERS RECOMMENDED CLEARANCE AROUND UNIT.
 - PROVIDE AND INSTALL 18 GAUGE DUCT FOR MEDIUM PRESSURE DUCTWORK WHERE INDICATED.
 - PROVIDE AND INSTALL NEW 2X2 ACCESS PANEL WRAP FOR MECHANICAL UNIT MAINTENANCE. COORDINATE IN FIELD EXACT FINAL LOCATION.

- ### MECHANICAL GENERAL NOTES
- ALL DUCT SIZES SHOWN ARE INSIDE CLEAR. INCREASE ACCORDINGLY WHERE INTERIOR LINER IS SHOWN OR SPECIFIED.
 - COORDINATE IN THE FIELD THE EXACT LOCATION OF ALL CEILING MOUNTED GRILLES AND DIFFUSERS WITH LIGHT FIXTURES AND (ARCHITECT'S) REFLECTED CEILING PLAN.
 - CONTRACTOR TO PROPERLY SEAL ALL NEW OR MODIFIED DUCTWORK.
 - SHOP PRIME ALL MISCELLANEOUS INTERIOR BRACKETS AND HANGERS UNLESS GALVANIZED OR STAINLESS STEEL. ALL EXTERIOR BRACKETS, CLAMPS, AND HANGERS SHALL BE HOT DIPPED GALVANIZED. COAT ALL CUT ENDS AND WELDS WITH "ZINC" COLO GALVANIZING COMPOUND.
 - FIELD COORDINATE WITH STRUCTURAL. OFFSET AND TRANSITION DUCTWORK AS REQUIRED.
 - THESE CONSTRUCTION DRAWINGS ARE DIAGNOSTIC, AND DO NOT NECESSARILY REFLECT ACTUAL DIMENSIONS. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY ALL DIMENSIONS AND COORDINATE PLACEMENT OF ALL EQUIPMENT AND ROUTING OF ALL PIPING AND/OR DUCT SYSTEMS.
 - ALL CONSTRUCTION IS TO CONFORM TO MORE STRINGENT OF PLAN, SPECIFICATION REQUIREMENTS AND LOCAL CODES. CONFORM TO SMACNA HVAC CONSTRUCTION STANDARDS AS A MINIMUM WHERE NO OTHER SPECIFICATIONS OR CODE REQUIREMENTS APPLY.
 - RETURN AIR IS THROUGH AIR GRILLES AND BACK THROUGH RETURN AIR OPENINGS TO THE MECHANICAL ROOM. CONTRACTOR TO MAINTAIN RETURN AIR PATH. PROVIDE OPENINGS OR RETURN AIR BOOTS AS REQUIRED.
 - ALL DUCTWORK 15 FEET DOWNSTREAM OF AHU'S AND 10 FEET DOWNSTREAM OF FPB'S TO BE PROVIDED WITH KNAUF PERFORMANCE+ INTERNAL LINER OR APPROVED EQUAL.
 - ALL TRANSFER AIR DUCTS/BOOTS TO BE PROVIDED WITH INTERNAL LINING.
 - PROVIDE RETURN AIR BOOTS ON ALL RETURN GRILLES FOR OFFICES, CONFERENCE ROOMS, ETC ON 4TH FLOOR.

1 SECOND FLOOR MECHANICAL PLAN
Scale: 1/8" = 1'-0"

ASHE BROUSSARD I WEINZETTLE ARCHITECTS

TIPTON ASSOCIATES

CONSULTANTS:
MonsieurBuller & Associates, LLC
CABDO Landscape Architecture, LLC
S&S O'Brien
Mechanical Engineering
Structural
Electrical
Specialty Architecture

ISSUE FOR BID

LOUISIANA STATE UNIVERSITY OF ALEXANDRIA
DOWNTOWN HEALTH SERVICES CENTER
800 JACKSON ST.
ALEXANDRIA, LA 71301

PROJECT # 2450-70798 WBS: F:19002488
ARCH PROJECT # 2023.20 / 1531.00-23
SITE ID: NEW SITE CODE: 4-40423
DATE OCTOBER 10, 2023
Ashe Broussard Weinzettl Architects, LLP
Tipton Associates APAC, A Joint Venture
301 Jackson Street, Suite 205
Alexandria, LA 71301
NO. REVISION DATE

STATE OF LOUISIANA
DOUGLAS CORREY, JR.
Professional Engineer
10/10/2025

SECOND FLOOR MECHANICAL PLAN

M102