



CENTRALBIDDING
FROM CENTRAL AUCTION HOUSE

**Contract No. 4 Manifest-Rhinehart Water Well Site Improvements &
Booster Stations 2, 3, and 4 Improvements**
LAGC Plan Room - North

Project documents obtained from www.CentralBidding.com
13-Feb-2026 08:50:10 AM

SPECIFICATIONS, CONTRACT DOCUMENTS

AND

CONSTRUCTION DRAWINGS

NEBO WATER SYSTEM, INC.

CONSOLIDATION WITH THE
MANIFEST-RHINEHART WATER SYSTEM, INC.


CONTRACT 4
MANIFEST-RHINEHART WATER WELL SITE IMPROVEMENTS &
BOOSTER STATIONS 2, 3, AND 4 IMPROVEMENTS

ADDENDUM NO. 1

DATE ISSUED: WEDNESDAY, FEBRUARY 4, 2026 @ 3:00 P.M.

BID DATE: WEDNESDAY, FEBRUARY 18, 2026 @ 10:00 A.M.

PAN AMERICAN ENGINEERS, LLC
1717 JACKSON STREET
ALEXANDRIA, LOUISIANA 71301



Thomas C. David, Jr. 2-4-26

This addendum shall be part of the Contract Documents as provided in Instructions to Bidders.

This addendum is issued for the purpose of modifying and/or clarifying the Specifications and/or Drawings and is to be construed as being as much a part of the original Contract Documents as though originally contained herein.

Acknowledge receipt of the addendum by inserting its number on Page 1 of the Bid Form. Failure to do so may subject the Bidder to disqualifications.

NEBO WATER SYSTEM, INC.
CONTRACT 4
MANIFEST-RHINEHART WATER WELL SITE IMPROVEMENTS &
BOOSTER STATIONS 2, 3, AND 4 IMPROVEMENTS
ADDENDUM NO. 1

SPECIFICATIONS AND CONTRACT DOCUMENTS

ITEM 1 SECTION 13900 - GROUND STORAGE TANKS

- The following tank manufacturer is approved:
 - Superior Tank Company, Inc.
1700 Bamore Road
Rosenberg, Texas 77471
832-223-9416 (office)
Attention: Hailey Day, Sales Coordinator
hailey.day@superiortank.com
www.superiortank.com

ITEM 2 SECTION 15120 - MECHANICAL PIPING, VALVES AND APPURTENANCES

- Paragraph 2.1.C: Delete this paragraph in its entirety and replace it with the following:

Fittings for PVC Pipe: Fittings that are three (3) inches in diameter or larger shall be mechanical joint S.S.B., unless otherwise shown on the Drawings, and shall be made of ductile cast iron with a pressure rating of 350 psi, and cement lined and asphalt coated. All fittings shall meet or exceed ANSI/AWWA C153/A21.53 and ANSI/AWWA C111/A21.11 specifications. ~~All DIMJ fittings shall be of domestic manufacture. (Made in USA).~~ All follower glands shall be mechanical joint restraint devices as specified under "Mechanical Joint Restraint Devices" of these Specifications. Fittings two (2) inches and smaller, unless otherwise shown on the Drawings, shall be PVC (DR 21) gasketed fittings manufactured by the Harrington Corporation of Lynchburg, Virginia or approved equal.
- Paragraph 2.2.C: Delete this paragraph in its entirety and replace it with the following:

Fittings: Ductile iron fittings used underground shall be mechanical joint unless otherwise shown on the Drawings in accordance with ANSI/AWWA C153/A21.53 and ANSI/AWWA C111/A21.11 specifications. Fittings shall have a pressure rating of 350 psi. ~~All DIMJ fittings shall be of domestic manufacture. (Made in USA).~~ All follower glands shall be mechanical joint restraint devices as specified under "Mechanical Joint Restraint Devices" of these Specifications. The fittings shall be cement lined and seal coated on the inside according to AWWA C104 with an NSF approved seal coat, and seal coated on the outside with one (1) mil thick asphaltic coating in accordance with AWWA C151.