






- 1 PROVIDE AND INSTALL NEW VERTICAL AIR CONDITIONING UNIT ON FLOOR IN THIS VICINITY. PROVIDE 24" HIGH (MINIMUM) PAINTED ANGLE IRON FRAME AND RUBBER ISOLATION PADS BELOW AIR CONDITIONING UNIT IN DRAIN PAN WITH FLOAT SWITCH. SEE MECHANICAL SPECIFICATIONS. CONNECT RETURN AIR DUCT TO INDOOR AIR CONDITIONING UNIT FULL SIZE. RUN INSULATED CONDENSATE DRAIN LINE FULL SIZE FROM AIR CONDITIONING UNIT TO FLOOR DRAIN AND TERMINATE. PROVIDE 2" AIR GAP BETWEEN DRAIN LINE AND FLOOR DRAIN. REFER TO PLUMBING PLAN FOR LOCATION OF FLOOR DRAIN.
- 2 PROVIDE AND INSTALL A MANUAL BALANCING DAMPER AND 120-160 ELECTRICAL SERVICE MOTORIZED DAMPER IN OUTSIDE AIR DUCT IN THIS VICINITY. INTERLOCK MOTORIZED DAMPER WITH RESPECTIVE INDOOR AIR CONDITIONING UNIT HEAT STRIP AND OUTDOOR CONDENSING UNIT COMPRESSOR TO OPEN WHEN UNIT HEAT STRIP OR COMPRESSOR ARE ON AND CLOSE WHEN UNIT HEAT STRIP OR COMPRESSOR ARE OFF. PROVIDE ALL RELAYS, WIRING, ETC. REQUIRED FOR PROPER INSTALLATION AND OPERATION. CONNECT OUTSIDE AIR DUCT TO RETURN AIR DUCT AS SHOWN. INSULATE MOTORIZED DAMPER SAME AS DUCT FOR NOISE.
- 3 AIR CONDITIONING UNIT ON WALL. VERIFY EXACT LOCATION AND ELEVATION WITH ARCHITECT PRIOR TO INSTALLATION.
- 4 PROVIDE AND INSTALL A MANUAL VOLUME BALANCING DAMPER IN DUCTWORK IN THIS VICINITY.
- 5 PROVIDE AND INSTALL A HEAVY GAUGE EXTRUDED ALUMINUM MALL LOUVER WITH BIRDSCREEN AT SIZE INDICATED, DRIP CAP, EXTENDED SILL, AND ANODIZED FINISH (COLOR BY ARCHITECT). LOUVER SHALL BE GREENECKE EVH-SOLD HIGH VELOCITY, WIND DRIVEN, RAIN DRAINABLE STATIONARY LOUVER OR APPROVED EQUAL WITH BACKDRAFT DAMPER. CONNECT DUCTWORK FULL SIZE TO LOUVER. REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOUVER LOCATIONS AND ELEVATIONS PRIOR TO INSTALLATION.
- 6 PROVIDE AND INSTALL T-DAY PROGRAMMABLE THERMOSTAT ON MALL IN THIS VICINITY. COORDINATE EXACT THERMOSTAT LOCATION AND ELEVATION IN FIELD WITH ARCHITECT PRIOR TO INSTALLATION. PROVIDE ALL WIRING, CONDUIT, ETC. REQUIRED FOR PROPER OPERATION.
- 7 PROVIDE AND INSTALL CEILING MOUNTED EXHAUST FAN IN THIS VICINITY. PROVIDE ALL WIRING, CONTROLS, DUCTWORK, ETC. REQUIRED FOR PROPER INSTALLATION AND OPERATION. PROVIDE AND INSTALL EXHAUST FAN SENSOR (GELING TYPE WITH 15 MINUTE TIMER) FOR ON/OFF CONTROL OF EXHAUST FAN. SENSOR SHALL BE PROVIDED BY MECHANICAL CONTRACTOR AND INSTALLED BY ELECTRICAL CONTRACTOR. COORDINATE LOCATION OF FAN AND MOTION SENSOR WITH ARCHITECTURAL CEILING PLAN, LIGHTS, AND ALL OTHER CEILING DEVICES. COLOR OF MOTION SENSOR TO MATCH COLOR OF LIGHT SWITCH COVERS.
- 8 UNDERCUT DOOR 3/4" FOR TRANSFER AIR.
- 9 PROVIDE INSULATED RETURN AIR FLENUM FULL SIZE OF GRILLE WITH ROUND DUCT CONNECTION FOR CONNECTION OF RETURN AIR DUCT.
- 10 PROVIDE AND INSTALL A MANUAL DAMPER AT DUCT TAP SPIN FITTING AND BALANCE TO CFM INDICATED AT DIFFUSER. DUCT TAPS SHALL BE A MINIMUM OF 12" FROM END OF SUPPLY AIR DUCT (TYPICAL).
- 11 OFFSET 4" DUCT DOWN IN THIS VICINITY. REFER TO SHEET M100 FOR CONTINUATION.

- A. ALL WORK SHALL COMPLY WITH LOCAL, STATE, AND FEDERAL CODES TO THE SATISFACTION OF CODE AUTHORITIES HAVING JURISDICTION.
- B. ALL WORK SHALL COMPLY WITH THE REQUIREMENTS OF NFPA 90A & 101, THE CLEAN AIR ACT AND THE AMERICANS WITH DISABILITIES ACT.
- C. COORDINATE ALL CEILING DEVICES, DUCTWORK, ETC. WITH LIGHTING, STRUCTURE, ETC. THROUGH GENERAL CONTRACTOR. REFER TO ALL DRAWINGS (STRUCTURAL, PLUMBING, ELECTRICAL, ARCHITECTURAL, ETC.). NOTIFY ARCHITECT/ENGINEER CONCERNING ANY CONFLICTS NOTED PRIOR TO BIDS FOR CLARIFICATION TO THE SATISFACTION OF THE BIDDER. REFER TO SPECIFICATIONS SECTION 15000 FOR REQUIREMENTS. REFER TO LATEST ARCHITECTURAL REFLECTED CEILING PLAN. COORDINATE ALL CEILING DEVICE LOCATIONS WITH CEILING GRID.
- D. ALL SUPPLY, EXHAUST, RETURN AND FRESH AIR DUCTWORK SHALL BE EXTERNALLY INSULATED. DUCT SIZES SHOWN ARE CLEAR METAL TO METAL. WRAP DUCTWORK EXTERNALLY.
- E. HARDCAST ALL DUCTWORK JOINTS FOR AIRTIGHT SYSTEM. REFER TO DETAILS FOR DUCTWORK TAP, SPLITTER, BRANCH CONFIGURATION, ETC. INSTALL IN ACCORDANCE WITH SMACNA RECOMMENDATIONS AND INSTALLATION GUIDELINES.
- F. THE EXISTING BUILDING WILL BE OCCUPIED DURING CONSTRUCTION DURING NORMAL BUSINESS HOURS, WHICH ARE 7:30 AM TO 5:00 PM ON MONDAY THRU THURSDAY AND 7:30 AM TO NOON ON FRIDAY. ADDITIONALLY, THERE ARE REGULARLY SCHEDULED MEETING IN THE EVENINGS.
- G. PROGRAMMABLE THERMOSTAT SHALL REMAIN IN FAN "AUTO" MODE.

 <p>ADG ENGINEERING</p>	<p>ASSOCIATED DESIGN GROUP, INC. 3909 W Congress Street, Suite 201 Lafayette, Louisiana 70506 Phone: (337) 234-5710 Email: adginc@adginc.org</p>										
<p>Project No. <u>25097</u></p>											
	<p>APPENDUM NO. 4</p>										
	<p>REVISIONS/SUBMISSIONS</p>										
<p style="text-align: right;">05/14/2026</p> <p style="text-align: right;">DATE</p>											
 <p>411 ARGENEAUX ROAD CARENCRO LOUISIANA 70520 337.846.6645 email: lynn@lynnguidryarchitect.com</p>											
<p>CARENCRO CITY HALL EXPANSION 2026</p>											
<p>210 EAST ST. PETER STREET CARENCRO, LOUISIANA</p>											
<p>Drawing Title</p> <p style="text-align: center; font-size: 1.5em;">HVAC PLANS</p>											
	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 33%; padding: 5px;"> Designed <div style="text-align: center; font-size: 1.2em;">DEP</div> </td> <td style="width: 33%; padding: 5px;"> Project No. <div style="text-align: center; font-size: 1.2em;">2024.006</div> </td> </tr> <tr> <td style="padding: 5px;"> Drawn <div style="text-align: center; font-size: 1.2em;">RW</div> </td> <td style="padding: 5px;"> Scale <div style="text-align: center; font-size: 1.2em;">AS NOTED</div> </td> </tr> <tr> <td style="padding: 5px;"> Checked <div style="text-align: center; font-size: 1.2em;">RCC</div> </td> <td style="padding: 5px;"> Drawing No. <div style="text-align: center; font-size: 2em;">M. O R I</div> </td> </tr> <tr> <td style="padding: 5px;"> Reviewed <div style="text-align: center; font-size: 1.2em;">RCC</div> </td> <td style="padding: 5px;"> <div style="text-align: center; font-size: 1.5em;"> <u>73</u> of <u>83</u> </div> </td> </tr> <tr> <td style="padding: 5px;"> Date <div style="text-align: center; font-size: 1.2em;">FEB. 10, 2026</div> </td> <td></td> </tr> </table>	Designed <div style="text-align: center; font-size: 1.2em;">DEP</div>	Project No. <div style="text-align: center; font-size: 1.2em;">2024.006</div>	Drawn <div style="text-align: center; font-size: 1.2em;">RW</div>	Scale <div style="text-align: center; font-size: 1.2em;">AS NOTED</div>	Checked <div style="text-align: center; font-size: 1.2em;">RCC</div>	Drawing No. <div style="text-align: center; font-size: 2em;">M. O R I</div>	Reviewed <div style="text-align: center; font-size: 1.2em;">RCC</div>	<div style="text-align: center; font-size: 1.5em;"> <u>73</u> of <u>83</u> </div>	Date <div style="text-align: center; font-size: 1.2em;">FEB. 10, 2026</div>	
Designed <div style="text-align: center; font-size: 1.2em;">DEP</div>	Project No. <div style="text-align: center; font-size: 1.2em;">2024.006</div>										
Drawn <div style="text-align: center; font-size: 1.2em;">RW</div>	Scale <div style="text-align: center; font-size: 1.2em;">AS NOTED</div>										
Checked <div style="text-align: center; font-size: 1.2em;">RCC</div>	Drawing No. <div style="text-align: center; font-size: 2em;">M. O R I</div>										
Reviewed <div style="text-align: center; font-size: 1.2em;">RCC</div>	<div style="text-align: center; font-size: 1.5em;"> <u>73</u> of <u>83</u> </div>										
Date <div style="text-align: center; font-size: 1.2em;">FEB. 10, 2026</div>											