



HVAC GENERAL
DEMOLITION NOTES

- A. REMOVE EXISTING MECHANICAL EQUIPMENT OR DUCTWORK AS INDICATED. OWNER SHALL HAVE FIRST RIGHT OF REFUSAL ON REMOVED EQUIPMENT. IF REFUSED BY OWNER, REMOVE FROM SITE AND DISPOSE OF LEGALLY.
- B. CONTRACTOR SHALL VISIT SITE AND REVIEW ALL ARCH/ENGINEERING DRAWINGS TO DETERMINE THE SCOPE OF DEMOLITION WORK. COORDINATE ALL WORK WITH AND THROUGH GENERAL CONTRACTOR AND OWNER TO DETERMINE WHEN SERVICES CAN GO OFFLINE.
- C. PRIOR TO DISCONNECTING AND REMOVING OF ANY SERVICES IN THE DESIGNATED AREAS SHOWN, THE CONTRACTOR MUST ENSURE THAT THE SERVICES REMOVED DO NOT EFFECT THE NORMAL OPERATION OF AREAS OUTSIDE THE CONSTRUCTION AREA. ALLOWANCE MUST BE MADE FOR ANY RE-ROUTING/TEMPORARY CONNECTIONS AS NECESSARY BEFORE THE WORKS COMMENCE.
- D. CONTRACTOR SHALL CAP ALL OPEN ENDS OF DUCT THAT ARE TO REMAIN THROUGHOUT CONSTRUCTION TO PREVENT DUST FROM ENTERING DUCT.

HVAC DEMOLITION KEYNOTES

- △ REMOVE EXISTING CONDENSING UNIT ON ROOF IN THIS VICINITY. REMOVE ALL ASSOCIATED CONTROLS, WIRING, PIPING, ETC.



ASSOCIATED DESIGN GROUP, INC.
3909 W Congress Street, Suite 201
Lafayette, Louisiana 70506
Phone: (337) 234-5710
Email: adginc@adginc.org
Project No. 25097

△	ADDENDUM NO. 4	05.14.2026
NO.	REVISIONS/SUBMISSIONS	DATE

Lynn Guidry
ARCHITECT

411 ARCENEAUX ROAD CARENCRO LOUISIANA 70520
337.846.6645 email: lynn@lynnguidryarchitect.com

CARENCRO
CITY HALL
EXPANSION
2026



210 EAST ST. PETER STREET CARENCRO, LOUISIANA

Drawing Title
HVAC ROOF PLANS



Designed DEP	Project No. 2024.006
Drawn RW	Scale AS NOTED
Checked RCC	Drawing No. M.190RI
Reviewed RCC	Date FEB. 10, 2026
	74 of 83