

- ELECTRICAL KEYNOTES:**
1. CONNECT NEW LIGHT FIXTURES TO EXISTING LIGHT CIRCUIT SERVING THIS SPACE. LIGHTING CONTROL SHALL REMAIN UNCHANGED.
 2. CONNECT LIGHTING IN THIS SPACE TO CIRCUIT INDICATED.
 3. CONNECT EXTERIOR LIGHTING TO CIRCUIT CI-28 AND WIRE THROUGH PHOTOCELL.
 4. LIGHTING FIXTURE LAYOUT SHALL MATCH IN THE UPPER AND LOWER CABINETS OF THIS FURNITURE UNIT. VERIFY WITH ARCHITECT/ENGINEER PRIOR TO ROUGH-IN. REFERENCE ARCHITECTURAL DRAWINGS. FIXTURES IN LOWER CABINET UNIT SHALL BE SURFACE MOUNTED.
 5. DIMMER SWITCH SHALL CONTROL FOR ADJACENT DISPLAY LIGHTING.
- ELECTRICAL NOTES**
- A. CONTRACTOR SHALL REFER TO ALL OTHER PORTIONS OF THE CONTRACT DOCUMENTS (PLANS, SPECIFICATIONS, ADDENDA, ARCHITECTURAL SUPPLEMENTAL INSTRUCTIONS AND ANY APPROVED CHANGE ORDERS) AND PROVIDE ALL LIGHT FIXTURES, OUTLETS, TELE/DATA OUTLETS, SPEAKERS, AND ASSOCIATED CIRCUITRY AS IF ORIGINALLY INCLUDED ON THE ELECTRICAL PLANS. IF THERE ARE ANY DISCREPANCIES, CONTRACTOR SHALL NOTIFY ARCHITECT/ENGINEER IN WRITING PRIOR TO ORDERING EQUIPMENT, ROUGH-IN FOR EQUIPMENT AND/OR INSTALLATION OF EQUIPMENT. PRIOR TO ROUGH-IN OF EQUIPMENT, CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING COPIES OF APPROVED SHOP DRAWINGS OF SUCH EQUIPMENT AND REVIEWING SAID SUBMITTALS TO ENSURE COMPATIBILITY WITH THE ELECTRICAL SYSTEM. CONTRACTOR SHALL IMMEDIATELY NOTIFY ARCHITECT/ENGINEER IN WRITING OF ANY DISCREPANCIES BETWEEN THE REQUIRED ROUGH-IN REQUIREMENTS AND THE ELECTRICAL SYSTEM.
 - B. VERIFY EXACT MOUNTING HEIGHT OF ALL WALL MOUNTED FIXTURES WITH ARCHITECT/OWNER PRIOR TO ROUGH-IN.
 - C. REFER TO ARCHITECTURAL REFLECTED CEILINGS FOR ALL CEILING MOUNTED DEVICES.
 - D. CONTRACTOR SHALL PROPERLY SEAL PENETRATIONS TO RATED ASSEMBLIES AND ALL EXTERIOR WALLS TO PROPERLY MAINTAIN RATING & ASSEMBLIES BUILDING ENVELOPE.
 - E. CIRCUITS SHALL HAVE DEDICATED NEUTRALS. NEUTRALS SHALL NOT BE SHARED.
 - F. AS A MINIMUM ALL ELECTRICAL WORK SHALL COMPLY WITH THE 2020 EDITION OF THE NATIONAL ELECTRICAL CODE.
 - G. REFER TO ELECTRICAL DIVISION SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
 - H. VERIFY REQUIREMENTS FOR ALL OWNER FURNISHED EQUIPMENT PRIOR TO ROUGH-IN.
 - I. ALL EXIT SIGNS SHALL BE 'UNSWITCHED'.
 - J. EXTERIOR LIGHTING CONTROLLED VIA PHOTOCELL.
 - K. SUBSCRIPTS AT LIGHT FIXTURE DESIGNATIONS DENOTE SWITCHING SCHEME.
 - L. CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS OF THE INTERNATIONAL ENERGY CODE (IECC) 2021 RESIDENTIAL AND COMMERCIAL BUILDING ENERGY CODE FOR LIGHTING AND CONTROLS.

ADG ENGINEERING

ASSOCIATED DESIGN GROUP, INC.
3909 W Congress Street, Suite 201
Lafayette, Louisiana 70506
Phone: (337) 234-5710
Email: adginc@adginc.org

Project No. 25097

ADDENDUM NO. 4	05.14.2026
NO. REVISIONS/SUBMISSIONS	DATE

Lynn Guidry
ARCHITECT

411 ARCEAUX ROAD CARENCRO LOUISIANA 70520
337.846.6645 email: lynn@lynnguidryarchitect.com


CARENCRO
CITY HALL
EXPANSION
2026



210 EAST ST. PETER STREET CARENCRO, LOUISIANA

Drawing Title
ELECTRICAL LIGHTING PLANS

Designed PM, CM	Project No. 2024.006
Drawn GW	Scale AS NOTED
Checked DS	Drawing No. E.100R1
Reviewed	Date FEB. 10, 2026



ADDENDUM
5-14-26

